

PAKISTAN AIRPORTS AUTHORITY
(Engineering Services E/M, BKIAP)

BOQ

ESTABLISHMENT OF NEW EARTHING PITS IN PLACE OF OLD / DETERIORATED EARTHING PITS FOR CRITICAL OPERATIONAL INSTALLATIONS AT CHERAT APPROACH, SAIDU SHARIF AIRPORT & BKIAP PESHAWAR

S.No.	Item Description	Qty.	Rate		Unit	Amount Rs.
			Figere	Words		
1	Providing and fixing Earthing Set at saidu sharif airport and cherat approach ,with 2' x 2' x 1/4" copper plate burried in the ground at a depth of 12 feet or less if water comes out from the ground level (with salt and charcoal, or Earthing chemical powder etc.) making the pit 12 feet deep by excavation of all type of soil (including soft or hard rock) i/c fixing of 8 SWG copper wire in 1/2" G.I conduit, complete in all respect as required.(AR)	09 Jobs			per Job	
2	Providing and fixing 1-1/2" x 1/3" thick copper strip with suitable saddle at 12" intervals complete as required.	441 RM			per RM	
3	Providing and installation of copper earthing rod at BKIAP peshawar, of 10 feet length and 1" dia in soil at a depth of 120 feet or less if water comes out from the ground with sufficient quantity of salt, charcoal and earthing chemical powder etc after making 4" bore in the soil, fixing of 6 SWG copper wire in 3/4" G.I conduit terminating at surface level, complete in all respect as required.	12 Jobs			per Job	
					Total (Rs.)	
					Millions	

Contractor

Divisional Engineer ES (E&M)
PAA BKIAP Peshawar

S.No.	Item Description	Qty.	Rate	Unit	Amount
-------	------------------	------	------	------	--------