

Sr. #	Description	Unit	Qty	Rate	Amount
1.a	Excavation dressed section, to in rock designed grades profiles, and excavated material disposed off within lead of 50 m and lift upto 1.5 m. (b) Medium hard rock requiring occasional blasting.	Cum	1649.994	1186	1956893
1.b	Excavation in shingle or gravel formation and rock not required ballasting undressed lead upto 50 Mtr in dry soil. (P 2-1/4)	Cum	14849.947	713	10588012
2	Providing sub-base course of pit run gravel (granular material) i/c placing mixing compacting to required density (90-95%) (P 14-2/9)	Cum	358.042	5101	1826374
3.a	Ratio 1:4:8 (P 5-1/2-d) (Cement concrete plain including placing , compacting, finishing and curing complete (including screening and washing of stone))	Cum	291.627	7710	2248447
3.b	Ratio 1:2:4 (P 5-1/2 b) (Cement concrete plain including placing , compacting, finishing and curing complete (including screening and washing of stone))	Cum	528.539	10274	5430211
4	Erection and removal of centering for RCC work or plain cement concrete work in vertical (5-5/21-ii)	Sqm	318.050	1015	322821
5	Reinforced cement concrete 1:2:4 in roof slab, beams, columns lintal etc i/c all labour material all kind forms mould lifting, mixing, compacting, finishing and curring complete (P 5-2/3 i)	Cum	1418.016	23193	32888048
6	Supplying and fabrication of intermediate grade deformed reinforcement (40,000 Psi 276 Mpa yield) for RCC slabs, beams, columns and pile caps, including cutting, bending, laying in position i/c cost of binding wire (P 5-3/6-9)	Kg	134711.534	270	36372111
7	Brick work in foundation and plinth in cement and mortar Ratio 1:5 (P 6-1/1)	Cum	179.569	12667	2274597
8	Pacca brick work other than building i/c striking of joints upto 3meter height in 1:5 cement sand mortar (P 6-1/4-ii)	Cum	131.624	13163	1732570
9	Bricks work in ground floor (including striking of joints) in cement sand mortar Ratio 1:5 (P 6-1/2-ii)	Cum	157.414	13507	2126189
10	Cement plaster (1:4) upto 1st floor height 13mm (10-1/5-b)	Sqm	2602.797	372	968240
11	Providing fixing 90-Lbs M.s Rail i/c anchor of MS flat 40x6mm long 610mm spacing complete in all respect as per drawing (P 23-12/75-a).	Mtr.	20.760	6925	143763
12	Damp proof course with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture 40mm (P 6-4/25-a)	Sqm	34.075	878	29918
13	P/F G.I 700mm long 50x50x6mm anngle iron post for barbid wire fence duly fixed in position	No.	51	2924	149124
14	Vertical damp proof course of 20mm thick cement plaster 1:2 with bitumen at 1 kg per sqm (P 6-4/26)	Sqm	131.301	742	97425
15.a	Providing, lowering & laying into trenches & jointing cement concrete reinforced pipeline to correct alignment & grade including cutting of pipes where necessary cost o jointing material & testing with internal diameter. (P 13-8/23-b & e) 150mm dia	Mtr.	20.000	1332	26640
15.b	225mm dia	Mtr.	98.000	1720	168560
16	Filling watering and ramming earth under floors with surplus earth from foundation (P 2-5/25).	Cum	9899.964	196	1940393
17	Filling, watering , ramming earth under floor with new earth (excavation from outside) lead upto 30m and left upto 1.50m (P 2-5/26).	Cum	1225.695	357	437573
18	Earth work compaction (soft, ordinary or hard soil) (a) laying earth in 150mm layers/leveling, dressing and watering for compaction etc. complete (P 2-3/15-a)	Cum	1225.695	67	82122
19	Carriage of 3.00 cum/5m tons of all material like earth, stone spawal stone, slabs etc. by means of truck or any other means owned by the contractor lead upto 3 K.M (for removing of surplus earth from grid area to disposal point) (P1-1/1).	Cons:	7825.671	278	2175537
20	Supplying and filling sand under floor and plugging into wells (P 6-4/24)	Cum	88.352	1838	162391
21	Providing and fixng platform of 40x5mm GI strp flat and batton or GI tee iron 50x100x5mm, 1.75m long fixed in position complete in all respects as per drawing No.PDW/TB-626. (P 20-7/72)	Sqm	126.000	34862	4392612

Sr. #	Description	Unit	Qty	Rate	Amount
22	Providing and fixing M.S dowel bar of 15mm dia 1.25m long including PVC/wooden sleeves complete as per drawing No.PDW/TV-420 (P 20-7/71).	No.	342.000	436	149112
23	Expansion joints (P 14-5/32).	Mtr.	213.000	1322	281586
24	Mosaci flooring consisting of mosaic topping of one part of cement to two parts of marble chips laid over 25mm thick flooring off 1:2:4 cement concrete including rubbing & polishing complete b) 13mm with grey cement. (P 9-3/14b)	Sqm	476.425	1985	945703
25	Mosaic dado or skirting with one part of cement & 2 parts of marble chips laid over 13mm thick cement plaster 1:3 complete with finishing and polishing b) 13mm with grey cement (P 9-5/27-b)	Sqm	26.271	1805	47419
26	Providing and laying 40mm thick Jambo Lawn sheets on roof (20-23/183-a)	Sqm	684.351	1360	930718
27	Placing polythene sheet 0.2mm thick (P8-5/26).	Sqm	684.35	541	370234
28	Brick tiles 225 x 113 x 38mm laid over 100mm earth & 25mm mud plaster grouted with cement sand 1:3 on top of RCC roof slab provided with .75 kg bitumen coating sand blinded. (P 8-1/2)	Sqm	684.351	1257	860229
29	Providing and fixing 04-rows barbed wire fencing around switch yard of G.I barbed wire 14SWG 2 ply 4 points fixed on G.I angle iron 50 x 50 x 6mm posts complete (excluding cost of angle iron post) (P 20-9/81)	Mtr.	134.563	395	53152
30	Providing and fixing steel door with grill work on outer face of the door as per approved design of Engineer Incharge (P 20-3/29)	Sqm	6.688	18632	124602
31	Providing and fixing aluminum natural anodized openable hinged window without glazing (P 20-5/46)	Sqm	63.180	9497	600020
32	Providing and fixing aluminum natural anodized openable hinged doors without glazed (P20-5/47)	Sqm	25.650	10387	266426
33	Providing and fixing aluminum natural anodized fly screen shutter (P 20-5/48)	Sqm	63.180	3336	210768
34	Glazing with plate glass 6mm thick using PVC gasket (P 11-7/41)	Sqm	88.830	2255	200312
35	P/F Aluminum door lock single action natural anodized (P 20-5/52)	No.	10	4532	45320
36	Providing, preparing surface and applying 3 coats of approved type plastic emulsion paint to plastered surface as per manufacturer	Sqm	1362.457	629	856985
37	Shoe bands for Long bend size 100 mm (4") pipe i/c fixing (P 23-5/22(ii))	Dzn	1.00	19944	19944
38	Glazed tiles dado 6mm thick jointed in white cement & laid over 1:2 cement sand mortar 20mm thick including finishing (P 9-5/26-a)	Sqm	35.922	3537	127056
39	Topping of cement concrete (1:2:4) including surface finishing and dividing into panels 75mm thick (P 9-2/9-d)	Sqm	20.000	1072	21440
40.a	20mm dia (P 13-12/36-b) (Providing, laying, jointing & testing heavy water or steam quality G.I or W.I pipes & specials inside building and trenches with internal diameter.)	Mtr.	50.000	557	27850
40.b	13mm dia (P 13-12/36-a) (Providing, laying, jointing & testing heavy water or steam quality G.I or W.I pipes & specials inside building and trenches with internal diameter.)	Mtr.	50.000	401	20050
41	White glazed earthen ware water closet squatting type domestic Indian pattern of best quality (P 13-18/63).	No.	1.000	4898	4898
42	White glazed earthen ware wash hand basin domestic of supreme quality. 65 cm (P 13-18/64-a)	No.	1.000	2618	2618
43	White glazed earthen ware pedestal for wash hand basin of supreme quality. (P 13-19/65).	No.	1.000	2112	2112
44	Low level flushing cistern 13.5 liters capacity best quality white glazed. (P 13-19/70-a).	No.	1.000	3496	3496
45	Looking glass 550mm x 400mm size 1st quality (without frame) Pak made (P 13-20/77-a).	No.	1.000	1224	1224
46	C.P Pillar cocks 13mm dia (P 13-20/80).	No.	1.000	850	850
47	C.P bib tap 13mm dia (P 13-20/82-a).	No.	1.000	820	820
48	C.P waste coupling 40mm dia (P 13-20/84-b).	No.	1.000	858	858

Sr. #	Description	Unit	Qty	Rate	Amount
49	C.I brackets for wash basins (P 13-21/91-a).	No.	2.000	406	812
50	C.I man hole covers having following diameter with frames: 450mm dia (P 13-24/116-b).	No.	4.000	1780	7120
51	Connection 13mm dia BCP (P 13-21/92-b).	No.	2.000	383	766
52	PVC flushing bend 32mm dia (P 13-21/87).	No.	1.000	173	173
53	13mm dia C.P stop cocks (P 13-20/81-a).	No.	1.000	763	763
54	20mm dia pillar cocks (P 13-20/80-b).	No.	1.000	112	112
55	S-trap 102mm diameter China-ware (Pakistan made) (P 13-23/107).	No.	1.000	516	516
56	P/F M.S plate 14 SWG 600mm square trench cover in control room (P 20-8/73)).	Mtr.	17.080	10021	171159
57	Providing and fixing hard brass or gun metal peet valves heavy pattern with hand wheel on G.I or W.I pipe lines laid in the ground or inside buildings for diameter of 20mm dia (P 13-15/46-b).	No.	2.000	1082	2164
58	Providing and fixing 15mm dia bar fan clamps suitable for RCC roof slab (P 20-7/64)	No.	15.000	355	5325
59	Vinyl floor tiles laid with adhesive 300x300x5mm size on firm foundation. (P 9-5/28)	Sqm	20.345	1827	37170
60	Supplying and spreading of crushed stone/water born gravel of 75mm size.	Cum	820.710	2925	2400575
61.a	Providing and fixing cable tray M.S aple iron inculding i/c anchor bolts fixing in cable trenches. Three way(P20-7/66).	No.	185	5225	966625
61.b	One way (P 20-7/66).	No.	150	1817	272550
62	Boring for tubewells in all water bearing soils from ground level 60 to 90 meter depth including sinking & with-drawing of casing pipe with internal diameter 150mm (P 13-2/3-c)	Mtr.	120.000	7100	852000
63	Wiring main with 2-1/1.78 (7/.029) PVC insulated wire 19.1mm 16 SWG (1.62 mm) thick steel conduit fitted on surface including accessories. ((P 21-5/3)	Mtr.	480.000	356	170880
64	Wiring main with 2-1/7/0.85 (7/.036) PVC insulated wire in 19.1mm 16 SWG (1.62mm) thick steel conduit fitted on surface including accessories. (P 21-6/4)	Mtr.	900.000	408	367200
65	Wiring main with 2-1/7/1.35 (7/.052) PVC insulated wire in 25.4mm 16 SWG (1.62mm) thick steel conduit fitted on surface including accessories. (P 21-6/6)	Mtr.	440.000	639	281160
66	Wiring for light or fan points with 1/1.13mm (3.029) PVC insulated wire in 19.1mm dia 16 SWG (1.62mm) thick steel conduit on suface complete with switch, holder/ceiling rose and plastic plate for switch, regulator/dimmer upto 10 meter. (P 21-1/1)	No.	80	2921	233680
67	Wiring 2 pin plug control point with 1/1.13 (3.029) PVC insulated wire on switch board includin plug & switch (P 21-2/9)	No.	5.000	323	1615
68	Wiring 3/5 pin 5 Amp wall socket point with 1/1.13 (3.029) PVC insulated conductor and 2.5mm PVC insulated 19.1mm dia 16 S.W.G (1.62mm) on surface complete with switch socket combined (concealed) (P 21-2/8)	No.	5.000	3392	16960
69	Providing and fixing flush type 3 pin 15 Amp S.P plug socket swith (combined) as replacement complete with board (P 21-25/22).	No.	7.000	306	2142
70	Providing and erection of ceiling fan best quality including wiring down rod with insulated wire (3/.029) PVC wire framed with regulator canopy laying rock at complete etc.c) 56 sweep (P 21-29/11-c)	No.	15.000	6654	99810
71	Providing and erection of butterfly shutter for 457mm (18") sweep exhaust fan complete (P 21-30/18)	No.	12.000	323	3876
72	Supply and erection of 457mm (18") sweep including wiring with (3.029) PVC wiring fixing complete etc. as required (P 21-30/12)	No.	12.000	5197	62364
73	Providing/laying and connecting hard drawn bare copper wire 3.2 mm (14SWG) as earth continuity conductor with any given main or submain in all system of wiring ((P 21-21/155).	Sqm	60.000	24	1440

Sr. #	Description	Unit	Qty	Rate	Amount
74	Soap dishes chromium plated ((P 13-19/73-b).	No.	1.000	3148	3148
75	Glass shelves 600mm x 125mm size C.P brackets with C.P. railing.(P 13-20/79)	No.	1	565	565
76	Chromium plated shower 13mm complete with C.P arm, 2 No.. C.P stop cock, 01 No. C.P bib cock & 01 No. C.P shower. (P 13-22/97).	No.	1.000	5371	5371
77	Termite proofing with approved chemical C.H.B (P 2-7/37) pre-construction	Sqm	357.000	225	80325
78	Cutting holes 230mm square through stone, brick or concrete block masonry in cement walls for pipes and making good to original condition a) upto 455mm thickness. (P 13-14/40-a)	No.	22.000	784	17248
79	Leveling and dressing and making lawns (P 20-18/123)	Sqm	10619.701	76	807097
80	Preparing surface and painting of door and window any type i/c edges 03 coats ((P 12-3/5-c).	Sqm	15.500	685	10618
81	Floor trap100mm x 50mm (including 50mm concrete chamber all around) with C.P grating (P 13-23/108-b)	No.	2.000	797	1594
82	Gully trap 100mm diameter of cement concrete (including 305mm x 305mm masonry chamber and C.I grating 150mm x 150mm) (P 13-23/109)	No.	1.000	3862	3862
83	Providing, lowering & laying into trenches, jointing and testing PVC class 'D' pipe line with specials interial dia (P 13-7/21-b & c) 75mm	Mtr	30.000	2365	70950
i.	100mm dia	Mtr	76.400	2462	188097
84	P/F open shuttering and timbering and removing of timbering after complion of job.(2-4/19)	Sqm	481.20	311	149653
85	A.C. PIPE 150mm (6") dia. Absestos(22-1/1,2)	Mtr	3208.00	1610	5164880
86	Providing and fixing of distribution board three phase 60 Amps 400 Volts 3 way per phase with 01 i/c circuit breaker 30 Amp tp and outgoing breaker 6.30 Amps complete with N Link in wall recessed (for street lights) (P 21-33/17)	No.	2	26381	52762
87	P/F of Distribution board Single phase 60 Amps 250 volts 8 way per phase with 01 No.incoming circuit breaker 60 Amps 250 Volts of outgoing breaker SP 6.3 Amps complete with volt meter,selector switch and phase indicator lights and Nlink on given board (for tube well) (P 21-33/16)	No.	1	19116	19116
88	Providing and fixing on prepared board iron-clad bus bar with 4 copper strips of 100 Amps in 19 mm x 4 mm section with chamber of overall size 609 mm x 336 mm (P 21-35/32)	No.	3	8387	25161
89	Providing and fixing T.P./C change-over swith 500 volts 15 Amps on a prepared board (P 21-35/29)	No.	6	2787	16722
90	Wiring main with 4-1/1.78 (7/.029) PVC insulated wire 660 volts grade in 25mm G.I pipe on surface. (P 21-13/75)	Mtr	248	684	169632
91	Wiring main with 4-1/7/0.85 (7/.036) PVC insulated wire 660 volts grade in 25mm G.I pipe on surface (P 21-14/76)	Mtr	382	755	288410
92	Wiring main with 4-1/7/1.04 (7/.044) PVC insulated wire 660 volts grade in 25mm G.I pipe on surface (P 21-14/77)	Mtr	133	843	112119
93	Fabrication, erection, fixing and installation of car shed of 3 ply fiber glass in steel structure made of 18 gauge square tube 32x32mm sid bracing for sheet with MS flat 25x3mm and 75mm dia 16 gauge vertical post complete in respect (P 20-24/188)	Sqm	75	6892	516900
94	P/F Aluminum door closer (single action) natural anodiozed (P20-5/53)	No.	10	7151	71510
95	P/F water geyser 114 Ltr.(25 Gallons)capacity.(P20-19/145)	No.	1	19333	19333
96	Glass Strip for dividing the flooring into Panels.(P9-6/31b)	Mtr.	1616	176	284416
97	Weather shield paint three coats on new cement plaster surface. (P 10-3/24)	Mtr.	277.700	359	99694
98	Providing and laying Tuff tile over 100 mm thick sand complete. (P 9-6/30)	Sqm	405.000	1244	503820
99	Preparing surface and rock wall finishing.	Sqm	1549.426	1216	1884102
100	Making and fixing grating Size in opening including fixing 1.524m x at site with flat iron 2.439m 50x10mm and 20mm (5' x 8') square bars at 100mm center to center.	Sqm	116.750	9519	1111343

Sr. #	Description	Unit	Qty	Rate	Amount
101	P/F GI earth strip 30x 3mm for switch yard fencing famre with allied bolt nuts etc. as per drawing no.PDW/TS-786 (P 20-9/85)	No	45.000	519	23355
102	P/F S/Y/Fence frame of G.I angle iron with wire netting complete as per drawing.	Sqm	163.125	4,300	701,438
103	P/F Switch yard fence gate of 1 ½ of G.I pipe fenching of G.I wire No.8 mesh 2x2" complete with rali/wheel fabrication, welding and erection in position as per drawing.	No.	1	120,000	120,000
104	P/F of M.S channels 40x70mm & 305mm long i/c grouting anchor bolts (N.S)	No.	90.000	180	16,200
105	Applying 03 coats of chlorinated acid resisting paint any color on plaster surface.	Sqm	84.800	160	13,568
106	P/F of fluorescent tube light approved 1x40 watts with startar-choke-patti etc complete)	No.	50.000	700	35,000
107	S/E of double cone bracket with water tight reflector	No.	5.000	134	672
108	RCC pre-stressed pr-cost trench cover at factory site.	Sqm	264.310	2,500	660,775
109	Providing fixing erection graden light switch yard poles 14feet height different size of G.I pole 4 inch dia 8feet long, 3 inch dia 4 feet long and 2 inch dia 2feet long, duly fabricated welded cutting, finishing and painting complete foundation	No.	18	20,000	360,000
110	Providing and fixing in position 30 Amp 500 watts 3 phase 4 pin power socket outlet wather proof (CEC make)	No.	4	6,265	25,060
111	P/Fixing AC flood light fitting alongwith 100watt best quality fittings complete in all respect.	No.	8	20,000	160,000
112	P/Fixing DC flood light fitting alongwith 500watt incandescent lamp according to Philips category No.QKE-500 watts (.DC flood lighth) fitting complete in all respect.	No.	2	20,000	40,000
113	Post top lantern 4250mm high with mercury lamp 250volt 125 Watts (HPL-125) ratting according to Phillips at No.H/SPQ-545.	No.	22	18,000	396,000
114	Earthing Pits arrangement or Pit Bore for Power Transformers & 11kV Incoming Panel complete including Copper Plate size 2`x2`x	Job	4	140,000	560,000
115	Providing/fixing louvers of aluminum anodized on windows of control room i/c complete fittings.	Sqm	15.12	7,000	105,840
116	Providing and fixing 1.5 ton A.C split unit (invertors)(Gree make) complete in all respect.	No.	3	175,000	525,000
117	Providing/installation of 1 H.P motor complete in all respect for draw pit for disposal of water.	Job	1	50,000	50,000
119	From boring to under ground water (Providing/laying installation of water pump to lift the water to CHB roof or head tank on roofing the source complete in all respects along with wire lead connect plug brackets etc.)	Job	1	75,000	75,000
120	from under ground water tank to overhead water tank on roofing CHB.	Job	1	75,000	75,000
121	Providing of Fire Fighting Equipments (02 No. Chemical foam 10 gallons trolley mounted with equivalent number of re-fills, 04 Set Sand container with shovel (45 gallons), 06 Set Six fire buckets with stand consisting 4-stand & 24 buckets, 05 No.Chemical foam (02 gallons) with equivalent number of re-fills (10 liters), 02 No. CO2 trolley mounted twin cylinder of 20Kg each) as per standard specification of WAPDA/IESCO	Job	1	300,000	300,000
122	Providing of Furniture (06 No. office chair, 01 No. office table, 01 No. side rack, 01 No. steel amirah, 01 No. wall clock, 01 No. stool & 01 No. notice board) as per standard specification of WAPDA/IESCO.	Job	1	190,000	190,000

Sr. #	Description	Unit	Qty	Rate	Amount
123	Providing of Wiring Material for 02 No.Power Transformers,02 No.Line Bay & Allied Equipments (160 No. copper stud for earth conductor, 285 No. thimble for 95mm sq, 30 Kg galvanized nuts & bolts off sizes, 24 No. thimble for 10mm, 24 No. PG connector for copper conductor 95mm sq, 20 Kg rough cloth, 36 No. PVC tape (RYB), 600 Doz. cable marking lead (A-Z)(0-9), 15 Pkt. cable ties 8", 400 Rft PVC pipe size 2"dia, 200 Rft PVC pipe size 1.25" dia,150 Rft PVC pipe size 3"dia, 200 Rft PVC pipe size 4"dia, 30 No. cable glands brass size 35mm, 40 No. cable glands brass size 25mm, 06 No. cable glands brass size 170mm, 01 No. PT Box complete, 25 Mtr. battery copper lead 120mm, 02 No. 110V DC Hooter, 02 No. 220V AC Hooter, 12 No. thimble copper 40mm) as per standard specification of WAPDA/IESCO.	Job	1	655,000	655,000
124	Providing of Grid T&P (01 No. Blower China, 01 No. screw wrench 10", 01 No. screw wrench 8", 01 No. plier size 8", 01 No. wire cutter 6", 01 No. nozzle plier, 01 No. drill machine 1/2 H.P, 01 set box spanner set, 01 set screw driver set, 01 set D spanner set, 01 No. avo meter, 01 set ring spanner set & 01 No. first aid box with material) as per standard specification of WAPDA/IESCO.	Job	1	165,000	165,000
125	Providing of wooden pallets (sheesham,kikar) size 800x800x130mm for loading/unloading of power transformers.	No.	20	7,500	150,000
126	Providing of (sheshem,partel) Wooden Sleeper size 10"x10"x5" for loading/unloading of power transformers.	No.	8	22,000	176,000
127	Providing of Tents size 16`x18` as per IESCO specification.	No.	8	35,000	280,000
128	Providing/installation of Lightening protection with copper strip size 20x2mm along with 20mm dia copper rod on the top of parapet wall of control house building & link the same with earthing mesh at four points complete as per drawing.	Job	1	300,000	300,000
129	Fixing of earthrod upto 10ft depth for earthing mash in switch yard	No.	80	1,200	96,000
130	P/F M.S sheet Sign Board 6' X 4' according IESCO requirement.	Job	1	100,000	100,000
131	P./F 5 ply 250 Gaylon fiber water tank on RCC roof slab complete.	job	1	50,000	50,000
132	Providing 1No.mobile Android for Grid Staff. 6 Ram 128 Gb Rom (Samsung).	No.	1	70,000	70,000
133	Providing/fixing of steel stairs with accessories complete in all respect for access to Roof Slab as per IESCO specifications	job	1	120,000	120,000
134	Providing/laying paint markings with allied accessories for the safety zone along the route on the control house building floor.	job	1	50,000	50,000
135	providing & fixing of L.C.D 44" INCH ,CCTV Camera (08No) along with all accesoreis complete in all respect. (TCL)	job	1	200,000	200,000
136	01 No. Laptop Hp/Dell core i7, Ram 8GB hard disk SSD 500 Gb with all accessories for PD Gsc IESCO.	job	1	250,000	250,000
138	Water quality monitoring/management/testing/analysis (Before Mobilization, During works execution & After completion) Parameters, PH, Electric Conductivity, color, taste, odor, turbidity, TDS, TSS, Total hardness, chloride (Cl), Arsenic, Cadmium, Sulphate, Copper (Cu), Sodium (Na), Calcium (Ca), Mangnaseium, Potassium, Nickle, Lead (Pb), Carbonate, Bicarbonate, Iron (Fe), Nitrate, Zinc (Zn), Aluminium (Al), Flouride (F), Chromium (Cr), Manganese (Mn) Total Coliform, E Coliform, E coli, Fecal Coliform	Quarterly	4	25,000	100,000
139	Air quality monoriting/testing (Before Mobilization During works execution & After completion)Parameters, Ambient, Air, Work Site, PM2.5, PM10, Dust, Lead, Sox, Nox, CO	Quarterly	4	30,000	120,000
140	Noise monitoring/analysis/measurement/management (One job/month) Parameteres Offices/Control room, Working Site area	Quarterly	4	2,000	8,000

Sr. #	Description	Unit	Qty	Rate	Amount
141	Other environmental & social mitigation measures (Demarcation of work area, SSEMP, First Aid Box, Fire Fighting Equipments, Proper Storage of Oil and Lubricant, Awareness Proper Storage of Oil and Lubricants, Awareness Panaflexes (size 4x6 feet) minimum 15 No.	Job	1	250,000	250,000
142	Soild waste & waste water management, safe storage/placement of raw materials.	Job	1	25,000	25,000
143	Tree Planatation (5'-7' Height) Local/Indiginous fruit trees.	No.	350	250	87,500
Total					140,039,186
%age Above/ below					
Total					
Please add 16% PST as Provincial Sales Tax as statutory charges					
Grand Total					
The above same BOQ must be signed and stamp by the bidder & should not be altered otherwise the bid will be rejected:_____					