

Construction of New Air traffic Control Tower (ATCT), Fire Station and Allied Facilities at Skardu International Airport, Skardu

**Schedule of Daywork Rates
Labour**

Item No.	Description	Nominal Quantity	Unit	Rate (USD)	Rate (PKR)	Extended Amount (PKR)
D101	Project Manager	10	Day	Not Applicable		
D102	Site Engineer	10	Day	Not Applicable		
D103	Surveyor	30	Day	Not Applicable		
D104	Foreman / General Foreman	30	Day	Not Applicable		
D105	Charge Hand / Supervisor	30	Day	Not Applicable		
D106	Skilled Mason	50	Day	Not Applicable		
D107	Carpenter	20	Day	Not Applicable		
D108	Steel Fixer	50	Day	Not Applicable		
D109	Electrician	30	Day	Not Applicable		
D110	Plumber	20	Day	Not Applicable		
D111	HVAC Technician	20	Day	Not Applicable		
D112	Welder	40	Day	Not Applicable		
D113	Painter	10	Day	Not Applicable		
D114	Tile Setter	20	Day	Not Applicable		
D115	Machine Operator	10	Day	Not Applicable		
D116	Driver	40	Day	Not Applicable		
D117	Skilled Labour	50	Day	Not Applicable		
D118	Semi-Skilled Labour	50	Day	Not Applicable		
D119	Unskilled Labour	100	Day	Not Applicable		
D120	Watchman / Security Guard	100	Day	Not Applicable		
D121	Cleaner / Helper	100	Day	Not Applicable		
	Subtotal					0.00
D122	Allow Fifteen Percent (15%) of Subtotal for Contractor's overheads, profit, taxes, supervision, administrative costs and all other indirect costs, in accordance with Paragraph 3(b) of the Daywork Procedure.				15% of Subtotal	0.00
	Total for Daywork - Labour (Carried forward to Daywork Summary)					0.00

Notes

1. Labour rates shall be deemed to include all wages, salaries, overtime (where applicable), statutory benefits, social security contributions, EOBI contributions, leave pay, insurance, transportation, accommodation, supervision, small tools, personal protective equipment (PPE), compliance with labour laws, and all other direct and indirect costs necessary for the execution of the Daywork.
2. Measurement and payment shall be in accordance with Sub-Clause 13.3 [Variation Procedure] and the Daywork Schedule contained in the Bill of Quantities.
3. Only labour actually employed on Daywork and authorized in writing by the Engineer shall be measured and paid.
4. No payment shall be made for idle time, standby time, inefficiencies, or labour not actually engaged in the authorized Daywork unless otherwise directed in writing by the Engineer.

Construction of New Air traffic Control Tower (ATCT), Fire Station and Allied Facilities at Skardu International Airport, Skardu
Schedule of Daywork Rates

Materials

Item No.	Description	Nominal Quantity	Unit	Rate (USD)	Rate (PKR)	Extended Amount (PKR)
D201	Ordinary Portland Cement (OPC), Type-I, 50 kg bag, ASTM C150 or equivalent	100	bag	Not Applicable		
D202	Coarse Sand (River/Pit), Zone-II grading, free from silt & organic matter	50	m3	Not Applicable		
D203	Coarse Aggregate, crushed stone, 3/4" (20mm) nominal size	50	m3	Not Applicable		
D204	Deformed Reinforcement Steel Bars, Grade 60 (Fy = 60,000 psi), assorted dia. 10mm-25mm	1000	kg	Not Applicable		
D205	Structural Steel Sections (I-Beam / Channel / Angle), Grade A36 or equivalent, assorted sizes	1000	kg	Not Applicable		
D206	Solid Concrete Blocks, 150mm x 200mm x 400mm (6"x8"x16"), min. compressive strength 1,500 psi	500	no.	Not Applicable		
D207	Burnt Clay Bricks (1st Class), standard size 230mm x 115mm x 75mm (9"x4.5"x3"), min. crushing strength 1,500 psi	500	no.	Not Applicable		
D208	Shuttering Plywood, 18mm thick, 1220mm x 2440mm (4'x8') sheet, film-faced	50	sheet	Not Applicable		
D209	Timber (Deodar/Kail), sawn, assorted sections, for formwork/scaffolding	100	cft	Not Applicable		
D210	Binding Wire, GI, 16 SWG	50	kg	Not Applicable		
D211	PVC Conduit Pipe, 3/4" (20mm) dia, heavy gauge, for electrical wiring	500	rft	Not Applicable		
D212	Copper Conductor Cable, PVC insulated, single core, assorted sizes 2.5mm2	1000	rft	Not Applicable		
D213	uPVC Water Supply Pipe, Class-C / Schedule-40, dia 1", threaded/solvent-weld	300	rft	Not Applicable		
D214	uPVC Sewerage Pipe, dia 4", solvent-weld joint	300	rft	Not Applicable		
D215	Waterproofing Membrane, APP/SBS modified bitumen, 3mm thick, torch-applied	200	m2	Not Applicable		
D216	Ceramic / Vitrified Floor Tiles, 600mm x 600mm, Grade-A, matt/glossy finish	200	m2	Not Applicable		
D217	Weather-shield Emulsion Paint, exterior grade	200	ltr	Not Applicable		
D218	Welding Electrodes, E6013/E7018, 3.15mm dia	50	kg	Not Applicable		
D219	Nails, Screws & Assorted Fasteners, GI/MS, various sizes 1"-4"	20	kg	Not Applicable		
D220	Non-Shrink Cementitious Grout, high strength (min. 50 MPa @ 28 days), pre-mixed	100	kg	Not Applicable		
D221	Silicone Sealant, weatherproof grade, 300ml cartridge	50	no.	Not Applicable		
	Subtotal					0.00
D222	Allow Fifteen Percent (15%) of Subtotal for Contractor's overheads, supervision, handling, storage, wastage, profit, taxes and all incidental costs in accordance with Paragraph 4(b).				15% of Subtotal	0.00
	Total for Daywork: Materials (carried forward to Daywork Summary)					0.00

Notes:

1. Nominal Quantities are Employer-inserted assumed quantities, provided solely to enable comparison of bidders' rates at tender stage. They do not constitute a guarantee of actual daywork quantities to be instructed during execution.
2. All items are stated in measurable units (weight, volume, length, area, or count) to enable verification of quantities actually consumed on Site as a basis for payment. No item is priced on a lump-sum or "lot" basis, since a lump-sum quantity cannot be physically checked against work done and is a common source of daywork payment disputes.
3. Sizes, grades, and specifications stated against each item are indicative, for the purpose of rate comparability at tender stage. Where a conflict arises between this Schedule and the Technical Specifications or BOQ for the same material, the Technical Specifications/BOQ shall govern.
4. This Schedule is to be read together with the Schedule of Daywork Rates: Labour and the Schedule of Daywork Rates: Contractor's Equipment, and the Daywork Summary, forming part of the Bill of Quantities.

Construction of New Air traffic Control Tower (ATCT), Fire Station and Allied Facilities at Skardu International Airport, Skardu

Schedule of Daywork Rates

Equipment

Item No.	Description	Nominal Quantity (hours)	Unit	Basic Hourly Rental Rate (USD)	Basic Hourly Rental Rate (PKR)	Extended Amount (PKR)
D301	Concrete Mixer, drum type, 10/7 cft capacity, diesel/electric driven	100	Hour	Not Applicable		
D302	Concrete Vibrator, needle type, 40mm-60mm poker dia, petrol/electric driven	100	Hour	Not Applicable		
D303	Diesel Generator Set, 125 kVA, silent/canopied type, with ATS panel	200	Hour	Not Applicable		
D304	Diesel Generator Set, 30 kVA, silent/canopied type	100	Hour	Not Applicable		
D305	Excavator / Backhoe Loader, bucket capacity 0.9-1.2 m3, engine power 90-100 HP	100	Hour	Not Applicable		
D306	Wheel Loader, bucket capacity 1.5-2.0 m3, engine power 120-150 HP	50	Hour	Not Applicable		
D307	Dump Truck, 10-wheeler, payload capacity 12-16 tons (8-10 m3)	100	Hour	Not Applicable		
D308	Water Bowser / Tanker, capacity 5,000-6,000 litres, truck-mounted	80	Hour	Not Applicable		
D309	Mobile Crane, hydraulic, telescopic boom, 25-ton lifting capacity	60	Hour	Not Applicable		
D310	Tower Crane, max. lifting capacity 6-8 tons, jib length 40-50m	100	Hour	Not Applicable		
D311	Man / Material Hoist, single cage, capacity 1,000-1,200 kg	100	Hour	Not Applicable		
D312	Plate Compactor, plate size approx. 500mm x 400mm, centrifugal force 15-20 kN	50	Hour	Not Applicable		
D313	Road Roller (vibratory), single drum, 8-10 ton static weight	40	Hour	Not Applicable		
D314	Welding Machine, arc/MIG type, 300-400 amp, diesel/electric driven	80	Hour	Not Applicable		
D315	Air Compressor, diesel/electric driven, capacity 150-185 CFM	60	Hour	Not Applicable		
D316	Concrete Pump, boom/trailer mounted, output capacity 30-40 m3/hr	40	Hour	Not Applicable		
D317	Concrete Batching Plant, capacity 30-40 m3/hr, with weigh-batcher	40	Hour	Not Applicable		
D318	Total Station (electronic), with operator, accuracy +/- (2mm + 2ppm)	40	Hour	Not Applicable		
D319	Mobile Lighting Tower, 4 x 1000W metal halide, telescopic mast, diesel-genset mounted	60	Hour	Not Applicable		
	Subtotal					0.00
D320	Allow Fifteen Percent (15%) of Subtotal for Contractor's overheads, supervision, mobilisation, demobilisation, fuel, lubricants, maintenance, insurance, operator management, profit, taxes and all incidental costs in accordance with the Contract Data.				15% of Subtotal	0.00
	Total for Daywork: Contractor's Equipment (carried forward to Daywork Summary)					0.00

Notes:

- Nominal Quantities (hours) are Employer-inserted assumed quantities, provided solely to enable comparison of bidders' rates at tender stage. They do not constitute a guarantee of actual daywork hours to be instructed during execution.
- Capacities and specifications stated against each item are indicative minimums, for the purpose of rate comparability at tender stage. The Contractor shall deploy equipment of at least the stated capacity, in good working order, suitable for the intended task and Site conditions.
- A "Subtotal" row has been added before Item D322 for consistency with Schedules 1 (Labour) and 2 (Materials), since the overhead/profit percentage at D322 is expressed as a percentage "of Subtotal." The source Preamble text did not show this row explicitly — please confirm this reflects the intended calculation basis.
- This Schedule is to be read together with the Schedule of Daywork Rates: Labour and the Schedule of Daywork Rates: Materials, and the Daywork Summary, forming part of the Bill of Quantities.

**Construction of New Airtraffic Control Tower (ATCT), Fire Station and Allied Facilities at Skardu
International Airport, Skardu**

Daywork Summary

Description	Amount (PKR)
1. Total for Daywork: Labour	0.00
2. Total for Daywork: Materials	0.00
3. Total for Daywork: Contractor's Equipment	0.00
Total for Daywork (Provisional Sum) (carried forward to Grand Summary)	0.00