

AVIATION COMPLEX AT BLUE AREA, ISLAMABAD

BILL NO. 10.B: STORM DRAINAGE

BILL OF QUANTITIES

Item No.	Item Description	Unit	Qty	Unit Rate (Rs.)	Total Amount (Rs.)
(i)	(ii)	(iii)	(iv)	(v)	(vi)

GENERAL NOTE

Supply, installation, testing and commissioning of the following items of work, including all labour, tools, plant, accessories, etc. required for completion of each item as per specifications and as approved by the Engineer.

Ref Specs: 0120,0150,1100,1200,1510,1520,1530,2650

A.EARTH WORK

- | | | | |
|---|--|-----|-------|
| 1 | Structural and trench excavation in common soil/material wet or dry including disposal of surplus excavated material at designated locations as directed by the Engineer. | Cft | 1,176 |
| 2 | Compacted Backfilling with Common material as shown on drawings or as directed by the Engineer. | Cft | 53 |
| 3 | Formation of embankment from road Way excavation material including hauling up-to any lead and lift, placing in layers, compaction upto 95% modified AASHTO dry density, dressing top and side slopes as per specifications and drawings or as directed by the Engineer. | Cft | 1,000 |

B. CONCRETE WORK

- | | | | |
|---|---|-----|-------|
| 4 | Provide and laying Class 'E' (1:4:8) concrete in foundations including placing compacting, finishing and curing complete (including screening and washing of aggregates) as shown on drawings or as directed by the Engineer. | Cft | 228 |
| 5 | Providing and laying RCC with 3000 psi compressive cylindrical strength all as specified in drain bed, wall and slabs etc., of any thickness, using Crushed stone, including use and waste of form work (steel) and finishing surface.. | Cft | 1,050 |
| 6 | Supply and fix, bars round, using deformed bars Grade-40 incl cutting, bending, binding and placing reinforcement in position. | Kg | 2,380 |

Total Amount (Rs.) = _____