

AVIATION COMPLEX AT BLUE AREA, ISLAMABAD

BILL NO. 7: ESCALATOR WORKS

BILL OF QUANTITIES

Item No.	Item Description	Unit	Qty	Unit Rate (Rs.)	Total Amount (Rs.)
(i)	(ii)	(iii)	(iv)	(v)	(vi)
Escalators					
Ref Specs: Escalator-SP, 9200					
Escalator-01	Supply, installation, testing & commissioning of Indoor Escalators able to move 6000 persons/hr complying all EN-115 standards minimum but not limited to VVVF controller, tempered glass balustrade, handrail, intermediate support not required, floor cover switch, float switch, antistatic brushes, handrail entrance protection, step anti upthrust protection, communication/interface card with software to integrate with BMS including relevant electrical works, one (01) year manufacturer warranty, One (01) years of defect liability period, FAT for two (02) persons complete in all respect as per specification including all taxes & duties.(complete in all respect) ES-1= 4.267 meter approx.	Each	8		
Escalator-02	Relevant civil & allied works including but not limited to cutting, patching, H/I beams (supply & installation), dismantling and revamping of floor/surrounding effected areas and all works required for necessary adjustments during installation of new equipment complete in all respects. All taxes, levies & duties shall be included.	Lot	1		
Escalator-03	Electrical & ancillary works for escalators including cables and other essential accessories etc. complete in all respects. All taxes, levies & duties shall be included.	Lot	1		
Escalator-04	Third party validation for testing & commissioning of escalators in Pakistan.	Each	8		
				Total Amount (Rs.)	<u> </u>