

PRICE SCHEDULE

PROCUREMENT OF 06 KVA UPS WITH 4x230AH BATTERY BACKUP FOR DIFFERENT LOCATIONS OF NBP PAKISTAN.

S. No.	Description	Quantity (a)	Unit (b)	Unit Rate (c) (Pak Rupees)	Total (a x c) (Pak Rupees)
1.	UPS Supply, Installation, testing and commissioning of 06 KVA UPS. Technology: True on Line (Double Conversion). Pure sine wave, Input voltage: 165-275VAC, Input Frequency: 46-56Hz, Out Put voltage: 220/230VAC, Output frequency: 50Hz, Transfer time: 0ms, Power factor: 0.7, Model No: _____ Brand Name: _____ UPS Power Rating: _____ Name of Manufacturer: _____ Country of Origin: _____	15	Nos.		
2.	BATTERIES Supply, Installation, testing and commissioning of Batteries for above UPS. Rating: 12V, 4x230Ah, Dry Sealed Lead Acid Maintenance Free. Battery Rating: _____ Model No: _____ Brand Name: _____ Name of Manufacturer: _____ Country of Origin: _____	15	Nos.		

Continued

PRICE SCHEDULE

**PROCUREMENT OF 06 KVA UPS WITH 4x230 AH BATTERY BACKUP FOR DIFFERENT LOCATIONS OF NBP
PAKISTAN.**

S. No.	Description	Quantity (a)	Unit (b)	Unit Rate (c) (Pak Rupees)	Total (a x c) (Pak Rupees)
3.	MAIN POWER CABLING Supply, Laying and connection of Cu/PVC/PVC Cables (Pakistan/Fast or Equivalent Make), 6mm ² , 3-core.	15	Jobs		
4.	MINIATURE CIRCUIT BREAKER (MCB) Supply, Installation and connection of miniature circuit breaker of 16A, Make: Scheinder, Terasaki, ABB or equivalent.	15	Nos.		

Continued

Amount in Words

(Rs. _____)

- The quoted rates / amount shall be inclusive of all applicable Federal/Provincial Govt. Taxes/Duties and charges for inland transportation and other related services etc.
- The material upon delivery at the site should be got verified from the Bank Engineer, prior to its installation at site. Otherwise, Bank Engineer reserves the right to replace the same without incurring any liability or payment of any charges to the bidder.