

Annexure 7: Delivery Schedule

Subject of Procurement: _____

Procurement Reference Number: _____

Name of Bidder: _____

S #	Item Name	UoM	Preferred No. of Units per Pack	Packing Unit	Qty Req.	Exstock quantities for immediate delivery	Earliest delivery period (Weeks)	Last delivery period (weeks)
1.	1000KVA Transformer 03-Phase step down pole mounted with, copper winding and warranty. Testing certificate as per IESCO/WAPDA. Placement of transformer 2 feet from floor/ground as per transformer size. Type 11kv/415; Branded (IESCO/WAPDA/PEC Approved).	No.	01	No.	01			Delivery Time along with installation etc with in 30 Days
2.	Industrial Protection Panel compatible with 11kv 630-amp VCB TP, with two outgoing circuit for two different transformer 1000KVA and 400KVA (IESCO/WAPDA /PEC Approved).	No.	01	No.	01			Delivery Time along with installation etc with in 30 Days
3.	Single core 120 mm 15kv XPLE copper 52 meter, from HT metering panel to protection cable	Meter	01	Meter	52			Delivery Time along with installation etc with in 30 Days

4.	Earth cable 1-core 25 sqmm bare copper conductor for Protection Panel, Transformer and HT Panel	Meter	01	Meter	43			Delivery Time along with installation etc with in 30 Days
5.	Earth connectivity cable 1-core 25 sq mm yellow green Insulated	Meter	01	Meter	45			Delivery Time along with installation etc with in 30 Days
6.	Supply of 11KV termination Kit heat shrink type for the following equipment. 1, Wapda metering panel. 2, Transformer protection panel. 3.1000 KVA transformer	Set	HT Termination kit	Set	04			Delivery Time along with installation etc with in 30 Days
7.	Earth upto ECP	Job	01	Job	01			Delivery Time along with installation etc with in 30 Days
8.	Execution of all the jobs from serial 1 to 7, including the supply, installation, testing, and commissioning of the 1000 KVA transformer and 11KV transformer protection panel, laying & termination of power cables, construction of three earthing pits 30 feet deep with GI	Job	01	Job	01			Delivery Time along with installation etc with in 30 Days

	Pipes and earthing chemical; earthing of the transformer, HT Panel, protection panel, and associated cables; submission of electrical drawings to the end user; and provision of one day of onsite operational training to the end user.							
--	--	--	--	--	--	--	--	--

The Delivery Schedule is authorised by:

Signature: _____

Name: _____

Position: _____

Date: _____

(DD/MM/YY)

Authorized for and on behalf of:

Company: _____

Stamp or seal: