

Schedule of Requirements

The Schedule of requirements provides a summary list of requirements under the tender as shown below, for specifications, see under the Specifications and Compliance sheet.

S #	Item Name	Measuring Unit	No. of Units per Pack	Packing Unit	Qty
1.	1000KVA Transformer 03-Phase step down pole mounted with, copper winding and warranty. Testing certificate as per IESCO/WAPDA. Placement of transformer 2 feet from floor/ground as per transformer size. Type 11KV/415; Branded (IESCO/WAPDA/PEC Approved).	No.	01	No.	01
2.	Industrial Protection Panel compatible with 11kv 630-amp VCB TP, with two outgoing circuit for two different transformer 1000KVA and 400KVA (IESCO/WAPDA /PEC Approved).	No.	01	No.	01
3.	Single core 120 mm 15kv XPLE 52 meter, from HT metering panel to protection cable	Meter	01	Meter	52
4.	Earth cable 1-core 25 sqmm bare copper conductor for Protection Panel, Transformer and HT Panel	Meter	01	Meter	43
5.	Earth connectivity cable 1-core 25 sq mm yellow green Insulated	Meter	01	Meter	45
6.	Supply of 11KV termination Kit heat shrink type for the following equipment. 1, Wapda metering panel. 2, Transformer protection panel. 3.1000 KVA transformer	Set	HT Termination kit	Set	04
7.	Earthing upto ECP	Job	01	Job	01
8.	Execution of all work listed in serial 01 to 07 including the supply installation, testing, commissioning of the 1000 KVA transformer & 11KV protection panel, laying & termination of power cables, construction of three earthing pits – 30 feets deep with GI pipe and earthing chemical, earthing of the transformer, HT panel, protection panel, and associated cable. Submission of the electrical drawing to the end user, and provision of one day of onsite operational training to the end user.	Job	01	Job	01

Schedule of requirements Authorized by:

Signature: _____ Name: _____

Position: _____ Date: _____
(DD/MM/YY)

Authorized for and on behalf of:

Company: _____

Stamp or seal: