

Sr NO	Description	Unit	Qty	Rate		Amount
1	Removing cement plaster	Sqm	256	46	WCSR item	11716
2	Dismantling brick work in cement mortar	Cum	16	1588	WCSR item	25965
3	Excavation in open cutting for sewer and manholes as shown in drawings, dressing to correct section and dimension according to template and levels and removing surface water in all types of soil shingle, gravel and rock 0 - 2.0m	Cum	69	328	WCSR item	22666
4a	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate) Ratio 1:4:8	Cum	123	7710	WCSR item	949332
4b	Ratio 1:2:4	Cum	10	10274	WCSR item	100128
5	R.C.C work using coarse sand except the cost of steel reinforcement and its labour for bending and binding. This rate also include all kind of forms moulds lifting shuttering, curing, rendering and finishing the exposed surface (including screening the washing of shingle). In-situ in roof slabs, beams, columns, rafts, lintels and other structural members complete in all respect 1:2:4	Cum	6	23193	WCSR item	127996
6	Supplying and fabrication of intermediate grade deformed reinforcement for R.C.C in slabs, beams, columns and pile caps, including cutting, bending laying in position including cost of binding wire 60,000PSI yield.	kg	884	287	WCSR item	253502
7	Bricks work other than building including striking of joints up to 3.0m height in cement sand mortar 1:5	Cum	40	13163	WCSR item	521160
8	Cement plaster 13mm ratio 1:4	Sqm	560	372	WCSR item	208237
9	Filling watering and ramming earth under floors with surplus earth from foundation	Cum	24	196	WCSR item	4747
10	Filling watering and ramming earth under floors with new earth (excavation from outside) lead upto 30m and lift upto 1.5m	Cum	341	357	WCSR item	121813
11	Carriage of 3.0 Cum or 5 metric tons of all material like earth, silt, sand, stone aggregate spawl, coal, lime, surkhi. Steel girders, M.S sheets, M.S Bars etc or 4.25 Cum of timber or 3.75 metric tons of fuel wood by truck or any other means 5 Km.	Cum	341	336	WCSR item	114565
12	Weather shield paint Three Coats on new Surface	Sqm	700	359	WCSR item	251226
13	Distempering Two coat over and cluding cost of priming coat.	Sqm	82	156	WCSR item	12796
14	Scraping ordinary distemper and paints	Sqm	350	86	WCSR item	30153
15	Providing laying into trenches, jointing and testing PVC class 'B' pipe line with special for internal 75mm	Mtr	10	1083	WCSR item	10825
16	Providing laying into trenches, jointing and testing PVC class 'B' pipe line with special for internal 100mm	Mtr	5	1657	WCSR item	8284
17	Painting new surface preparing surface and painting of guard bars, gates of iron bars, gratings railings, (including standards braces etc) and similar open work	Sqm	60	281	WCSR item	16996
18	Providing & Fixing grating angle iron frame with 10mm Sq iron bar at 75mm center to center as per approved design of engineer	Sqm	60	5494	WCSR item	331904
19	Providing lowering and laying into trenches and jointing cement concrete reinforced pipeline to correct alignment and grade including cutting of pipes where necessary cost of jointing material and testing with internal diameter. 225mm	Mtr	50	1720	WCSR item	86002
20	Fabrication, erection, fixing and installation of car shed of 3 ply fiber glass sheet with steel structure made of 18 guage square tube 32x32mm side bracing for sheet with MS flat 25x3mm and 75mm 16 guage vertical post complete in all respect.	Sqm	8	6892	WCSR item	57649
21	Dismantling Brick and Tuff tile flooring	Sqm	1119	97	WCSR item	108280
22	Earthwork compaction (soft, ordinary or hard soil) compaction by roller ordinary soil	Cum	341	86	WCSR item	29236
23	Providing and laying Tuff tile over 100mm thick sand complete	Sqm	1119	151	WCSR item	168850
24	Supply and filling sand under floors or plugging in wells.	Cum	113	1837	WCSR item	206802
25	Flooring comprising of first class Granite glazed tiles with 13mm thick white bond cement	Sqm	19	3557	WCSR item	66114
26	Flooring comprising of glazed tiles 6mm thick laid in white cement mortar 1:2 over 20mm thick cement mortar 1:2 complete coloured	Sqm	4	3713	WCSR item	15530
27	Wiring light or fan point with 1/1.13 (3.029) PVC insulated wire in 19.1mm, 1.50mm thick PVC conduit recessed in the wall or column complete with switch plastic plate ceiling rose/batten holder	No	2	2312	WCSR item	4624
28	Providing and fixing flush type 3 pin 15 Amps S.P Plug-socket, switch (combined) as replacement on board already exist	No	1	511	WCSR item	511

29	Wiring mains with 2-1/1.78 (7/.029) PVC insulated wire in 19.1mm PVC conduit recessed in the wall as required.	Mtr	50	183	WCSR item	9169
30	Wiring mains with 2-1/1.78 (7/.029) PVC insulated wire in 19.1mm PVC conduit recessed in the wall as required.	No	1	4000	Market rate	4000
	Total					3880773
	%age Above/ below					
	Total					
	Please add 16% PST as Provincial Sales Tax as statutory charges					
	Grand Total					

Note: BOQ must be signed stamp by the bidder: _____