



REAL ESTATE DIVISION

Principal Office,

STATE LIFE BUILDING NO.09,

DR. ZIAUDDIN AHMED ROAD,

KARACHI - 75530

PABX No : 021-99202800-9

D.H (R.E) : 021-99204520

Email : dbred@statelife.com.pk

Website : www.statelife.com.pk

TENDER FOR REHABILITATION OF ELECTRICAL INFRASTRUCTURE OF DB ROOMS GROUND, MEZZANINE, 4TH TO 8TH FLOOR (BOTH SIDE) AT STATE LIFE BUILDING NO. 2, WALLACE ROAD, KARACHI.

INVITATION OF TENDER

TENDER NO. RE/EL/EW/DBR/4002/2026

State Life Insurance Corporation of Pakistan invites sealed bids through EPADS from Firms registered with Income Tax and Sales Tax Departments and are on active Taxpayers List of the Federal Board of Revenue. Tender for Rehabilitation of electrical infrastructure of DB rooms ground, mezzanine, 4th to 8th floor (both side) at state life building no. 2, Wallace road, Karachi.

2. Tender must be supported with bid security as shown in the bidding documents in Shape of pay order in the name of State Life Insurance Corporation of Pakistan.
3. Tender documents will be received only from those firms who are registered with PPRA for e-procurement on EPADS V.2.0 System for tendering in State Life Insurance Corporation of Pakistan through their email addresses which were provided by them to PPRA at the time of their registration.
4. Filled tender must be submitted through email address on **02-09-2026** till 11:00 AM sharp. Bids will be opened the same day at 11:30 A.M. Single stage single envelope procedure of PPRA will be followed.
5. This advertisement is also available on PPRA website at www.ppra.org.pk and SLIC Website www.Statelife.com.pk

Assistant Manager (Elect.) RE
4th floor Annex building, State Life
Building No. 9,
Dr. Ziauddin Ahmed Road,
Karachi.



STATE LIFE
INSURANCE CORPORATION OF PAKISTAN

REAL ESTATE DIVISION

Principal Office,

STATE LIFE BUILDING NO.09,

DR. ZIAUDDIN AHMED ROAD,

KARACHI - 75530

PABX No : 021-99202800-9

D.H (R.E) : 021-99204520

Email : dbred@statelife.com.pk

Website : www.statelife.com.pk

Dated: _____

M/s. _____

**SUB: TENDER FOR REHABILITATION OF ELECTRICAL INFRASTRUCTURE OF DB ROOMS
GROUND, MEZZANINE, 4TH TO 8TH FLOOR (BOTH SIDE) AT STATE LIFE BUILDING
NO. 2, WALLACE ROAD, KARACHI.**

Enclosed, please find herewith Tender Documents for the subject work as per single stage single envelope procedure of PPRA Rules. Please submit the same duly filled and completed in all respects on EPADS latest by **02-09-2026** at 11:00 a.m.

You are requested to submit tender through e-procurement system of PPRA (EPADS) by the stipulated date. For further details, you may contact the undersigned before the opening of the Tender for any query.

The Corporation reserves the right to reject any or all Tenders as per provisions of PPRA Rules.

WALEED NASIM
A.M (Elect.) RE

Encl: As above.

STATE LIFE INSURANCE CORPORATION OF PAKISTAN
REAL ESTATE DIVISION

TENDER FOR REHABILITATION OF ELECTRICAL INFRASTRUCTURE OF DB ROOMS GROUND, MEZZANINE, 4TH TO 8TH FLOOR (BOTH SIDE) AT STATE LIFE BUILDING NO. 2, WALLACE ROAD, KARACHI.

TENDER NO. RE/EL/EW/DBR/4002/2026

FINANCIAL BID DOCUMENTS

REAL ESTATE DIVISION
4th floor Annex building, State
Life Building #. 9, Dr. Ziauddin
Ahmed Road, Karachi

MANDATORY CRITERIA

TENDER FOR REHABILITATION OF ELECTRICAL INFRASTRUCTURE OF DB ROOMS GROUND, MEZZANINE, 4TH TO 8TH FLOOR (BOTH SIDE) AT STATE LIFE BUILDING NO. 2, WALLACE ROAD, KARACHI.

TENDER NO. RE/EL/EW/DBR/4002/2026

MANDATORY

- i.** Electrical Contractor License from Electric Inspector Govt. of Sindh (attached copy).
- ii.** NTN Certificate (Please attach copy).
- iii.** **SRB** Certificate (Please attach copy).
- iv.** **Related work experience letters of last Five (05) Years** (Please attach copy)
- iv.** Affidavit on stamp paper that the firm/company is not blacklisted by any Govt./Semi Govt./MNCs & Private Organization.

SEAL & SIGNATURE OF ELECTRICAL CONTRACTOR

TENDER FOR REHABILITATION OF ELECTRICAL INFRASTRUCTURE OF DB ROOMS GROUND, MEZZANINE, 4TH TO 8TH FLOOR (BOTH SIDE) AT STATE LIFE BUILDING NO. 2, WALLACE ROAD, KARACHI.

TENDER NO. RE/EL/EW/DBR/4002/2026

1. GENERAL TERMS:

- 1.1. Tender is invited for rehabilitation of Electrical infrastructure of DB Rooms Ground, Mezzanine, 4th to 8th Floor (Both Side) at state life Building No. 02, Wallace Road, Karachi.
- 1.2. Tender shall be submitted through e-procurement system of PPRA (EPADS V.2.0). Scanned copy of Tender documents (all papers) must be signed and stamped to signify the acceptance of tender's conditions before submitting the tender on EPADS.
- 1.3. Technical services and operating conditions for achieving the performance shall be the responsibility of the Tenderer.
- 1.4. Tender without Bid Security will be rejected.
- 1.5. Manual submission of tender will not be accepted. Original pay order must be reached to Real Estate Division, Principle office, 4th Floor Annexe Building, State Life Building No. 09, Dr. Zia Uddin Ahmed Road Karachi before the time of opening of tender. However, scanned copy will be uploaded on e-pad while submitting the tender.
- 1.6. Any conditional Tender will not be accepted and will be liable to rejection.
- 1.7. Contractor has to clean the site in every respect from unused material, debris and tools on completion of work.
- 1.8. All the works to be carried out as per IEEE Code & Standard and tender specifications under the direct supervision of Electrical Section (Real Estate) Principal Office, Karachi.
- 1.9. Payment to be made as per actual work done/after completion of work.
- 1.10. State Life Insurance Corporation of Pakistan will not be responsible for any loss to life or theft of tool / equipment or consumable material and will not accept any claim, liabilities or compensation.

2. PRE-BID VISIT:

Tenderers are requested to visit the site before submission of Tenders/Bids and ensure that their offers are complete in all respect and that all terms & conditions mentioned in this document shall be strictly complied with. Tenderer must ensure/study the specification, schedules and B.O.Q as are attached with offer to avoid any debate/discussion/dispute during/after execution of work.

No TA/DA will be given to Tenderers for Pre-Bid Visit.

3. PRICES AND ESCALATION:

Quoted price shall be inclusive all applicable Taxes GST, SST, Transportation, Insurance, octari, loading, unloading, lifting and fixing of equipment at Site, as specified in the Tender.

SEAL & SIGNATURE OF ELECTRICAL CONTRACTOR

2. No price escalation claim will be entertained in any reason due to change in Taxes, Levy, Wages, Currencies fluctuation or any other change announced by the Central Government / Provincial Government or any local Authority
4. **MODE OF PAYMENT:**
- i. 95% payment of bill will be made after completion of job.
 - ii. 05% Retention Money will be deducted from bill & released after defect liability (i.e., One (01) year) completion of work.
5. **DEFECT LIABILITY PERIOD:**
- i. Defect liability period shall be started after completion of work for One (01) Year.
 - ii. The Contractor will replace the components if not found according to specification or found defective due to faulty design material or workmanship or being non-genuine.
6. **LIQUIDATED DAMAGES:**
- Failure to execute the work within the stipulated time will render contractor liable to payment of liquidated damages at the rate of 0.3% of contract price per day or part thereof, of delay subject to max. to 10% of Contract amount.
7. **SIGNING OF CONTRACT AGREEMENT:**
- i. Upon acceptance of the tender the supplier shall execute with the State Life Insurance Corporation of Pakistan a proper agreement on judicial stamp paper of containing certain terms and conditions in the form prescribed by the State Life Insurance Corporation of Pakistan within Seven (07) days from the acceptance of Letter of Award.
 - ii. The contract shall be Governed and interpreted in all respects in accordance with the Law of Pakistan.
 - iii. State Life Insurance Corporation of Pakistan reserves the right to reject any or all offers, as per provisions of PPRA Rules.
8. **COMPLETION OF WORK (RISK & COST)**
- If due to any reason, contractor is unable to complete the work in given time on performing poorly for which L.D has been imposed on him, State Life can terminate the contract with him and get the remaining work executed through other contractor at his risk & cost. The cost so incurred will be deducted from his bills or recovered from him through other/ legal means.
9. **TERMINATION:**
- State Life employer shall have the right to terminate the contract wholly by given a notice to the contractor upon failure of Contractual obligations.

SEAL & SIGNATURE OF ELECTRICAL CONTRACTOR

FOR REHABILITATION OF ELECTRICAL INFRASTRUCTURE OF DB ROOMS GROUND, MEZZANINE, 4TH TO 8TH FLOOR (BOTH SIDE) AT STATE LIFE BUILDING NO. 2, WALLACE ROAD, KARACHI.

TENDER NO. RE/EL/EW/DBR/4002/2026

SPECIAL CONDITIONS

1.	Bid Security	Rs. <u>30,000/-</u> in the form of pay order by schedule bank in favour of M/s. "State Life Insurance Corporation of Pakistan
2.	Release of Bid Security	a. To unsuccessful Tenderer after award of work. b. To successful Tenderer upon submission of performance bond
3.	Forfeiture of Bid Security	a. If the bid is withdrawn after opening. b. If the bidder does not accept letter of award or refuse of enter in contract.
4.	Date and time of opening of Tender	a. Submission of bid on e-pads is <u>02-09-2026</u> at <u>11:00 AM.</u> b. Opening of bid on e-pads is <u>02-09-2026</u> at <u>11:30 AM.</u>
4.	Date of Commencement of Work	Three (03) days from the date of award of work.
5.	Time of Completion	Thirty (30) Days from the date of commencement of work
6.	Liquidated Damages	0.3% of the contract price per day (maximum 10% of contract amount)
7.	Maintenance Period	One (01) Year from date of certificate of completion of works.
8.	Bid/Tender validity period	Three (03) Months
9.	Method of Payment	i. 95% payment will be made after satisfactory completion of job ii. 05% Retention Money will be deducted from bill.
10.	Retention Money	05% (Five percent) of the certified amount
11.	Release of retention money	Upon completion of maintenance period
12.	Payment of income tax	All prevailing government taxes (federal & provincial) including income tax, GST, super tax, sales tax, S.S.T, etc. payable by the contractor should be included in the quoted prices of each item in the bill of quantity. (No Additional payment shall be entertained)
13.	Black Listed	As per blacklisting policy of State Life.

SEAL & SIGNATURE OF ELECTRICAL CONTRACTOR

BILL OF QUANTITIES
Tender No. RE/EL/EW/DBR/4002/2026

**TENDER FOR REHABILITATION OF ELECTRICAL INFRASTRUCTURE OF D.B ROOMS OF GROUND,
MAZZANINE, 4TH TO 8TH Floor (BOTH SIDE) AT STATE LIFE BUILDING – 2, WALLACE ROAD,
KARACHI.**

Sr.#.	Description	Unit	Quantity	Rate	Amount
1	POWER CABLE WORKS: Supply, laying, installation, termination, testing and commissioning of 50mm ² 4core PVC / PVC power cable copper conductor 300/500volts Fast/Pakistan cable/ Universal/equivalent or approved by SLIC representative, from 4th floor to 7th floor (both side) run in through existing cable route as per site required. The cable should be terminated at both ends with tin coated copper lugs and cable should be properly clamped or tie on both sides, complete works in all respect	Mtrs.	40		
2	POWER CABLE WORKS (7th to 8th Floor) Bank side Supply, laying, installation, termination, testing and commissioning of 25mm ² 4core PVC / PVC power cable copper conductor 300/500volts Fast/Pakistan cable/ Universal/equivalent or approved by SLIC representative, from 7th floor to 8th floor (Bank side) run in through existing cable route as per site required. The cable should be terminated at both ends with tin coated copper lugs and cable should be properly clamped or tie on both sides, complete works in all respect	Mtrs.	15		
3	EARTH CABLE WORKS: (Both side) Supply, laying, installation, termination, testing and commissioning of 16mm ² single core PVC / PVC power cable copper conductor 300/500volts Pakistan cable/Pioneer/ Universal/equivalent or approved by SLIC representative, from 4th floor to 7th floor (both side) run in through cable tray/PVC conduit as per site required. The cable should be terminated at both ends with tin coated copper lugs and cable should be properly clamped or tie on both sides, complete works in all respect	Mtrs	40		
4	EARTH CABLE WORKS: (Bank side) Supply, laying, installation, termination, testing and commissioning of 10mm ² single core PVC / PVC power cable copper conductor 300/500voltsPakistancable/ Pioneer/Universal/equivalent or approved by SLIC representative, from 7th floor to 8th floor (Bank side) run in through cable tray/PVC conduit as per site required. The cable should be terminated at both ends with tin coated copper lugs and cable should be properly clamped or tie on both sides, complete works in all respect.	Mtrs.	10		

SEAL & SIGNATURE OF THE CONTACTOR

BILL OF QUANTITIES
Tender No. RE/EL/EW/DBR/4002/2026

**TENDER FOR REHABILITATION OF ELECTRICAL INFRASTRUCTURE OF D.B ROOMS OF GROUND,
MAZZANINE, 4TH TO 8TH Floor (BOTH SIDE) AT STATE LIFE BUILDING – 2, WALLACE ROAD,
KARACHI.**

Sr.#.	Description	Unit	Quantity	Rate	Amount
5	<u>DISTRIBUTION BOARD: (Bank side 8th floor)</u> Following LT distribution boards of size 18" x 24" gauge 16 including, recessed/surface mounted including all accessories, to be installed at 8 th floor related civil works etc. complete in all respects. Four (04)Nos. Bus bars of 18-inch length each to be installed in the DB for all three phases and neutral and suitable for connection of up to 25 sq.mm cable. The amperage of bus bar will be 150 Amp. Incoming TP 100 Amp breaker of make Schneider/ABB/Terasaki or equivalent 01No. Busbar 4 pole 200 amp of make 01 No.	No.	1		
6	<u>DISTRIBUTION BOARD: (7th floor both side)</u> Following LT distribution boards of size 24" x 36" gauge 16 including, recessed/surface mounted including all accessories, to be installed at 7 th floor(both side) related civil works etc. complete in all respects. Four (04)Nos. Bus bars of 18-inch length each to be installed in the DB for all three phases and neutral and suitable for connection of up to 50 sq.mm cable. The amperage of bus bar will be 200 Amp. Incoming TP 150 Amp breaker of make Schneider/ ABB/Terasaki or equivalent 01No. Busbar 4 pole 200 amp of make 01No. Out going TP 100 amp of make Schneider/ABB/Terasaki or equivalent 03 Nos.	Nos.	2		
7	<u>CIRCUIT BREAKER:</u> Supply and fixing of circuit breaker 100 amp with metal box back box on outgoing of each energy meter of make (Schneider/ABB/Terasaki or equivalent) or approved by SLIC representative, complete in all respect.	Nos.	8		
8	<u>CIRCUIT BREAKER</u> Providing and fixing of 150 amps main TP circuit breaker of make (Schneider/ABB/Terasaki or equivalent) or approved by SLIC representative in already installed DB at 4 th floor (Both side) complete works in all respect.	Nos.	2		
9	<u>SINGLE PHASE METER (8TH FLOOR) BANK SIDE:</u> Supply & installation of single phase digital meter as per KE Spec. of digital type along with board and all the accessories required as per site requirement.	No.	01		

SEAL & SIGNATURE OF THE CONTACTOR

BILL OF QUANTITIES**Tender No. RE/EL/EW/DBR/4002/2026****TENDER FOR REHABILITATION OF ELECTRICAL INFRASTRUCTURE OF D.B ROOMS OF GROUND,
MAZZANINE, 4TH TO 8TH Floor (BOTH SIDE) AT STATE LIFE BUILDING – 2, WALLACE ROAD,
KARACHI.**

Sr.#.	<u>Description</u>	Unit	Quantity	Rate	Amount
10	<u>THREE PHASE METER:</u> Supply & installation of three phase digital meter as per KE Spec. of digital type along with board and all accessories required as per site requirement.	Nos.	8		
11	<u>LYING OF POWER CABLE WORKS:</u> Laying, installation, termination, testing and commissioning of 25mm² 4core PVC/PVC power cable copper conductor 300/500 volts Fast/Pakistan cable/Uniersal/equivalent or approved by SLIC representative, from DB at Ground, 1 st , 5 th , 7 th & 8 th Floor to energy meters installed at both side run in through existing cable route as per the site requirement (cable will be provided by SLIC). The cable should be terminated at both ends with tin coated copper lugs and cable should be properly clamped or tie on both sides, complete in all respect.	Mtr	25		

SEAL & SIGNATURE OF THE CONTACTOR



Construction Site HSE Inspection

Project / Building Name

Date:

YES

NO

NA

1. GENERAL SITE SAFETY

I	Adequate signage is displayed for safety procedures and hazards			
II	The site has a designated first aid station and emergency medical procedures.			
III	Fire extinguishers and other firefighting equipment are strategically placed.			

OBSERVATIONS

2. PERSONAL PROTECTIVE EQUIPMENT (PPE) Depend on type of activity

I	Workers are wearing appropriate PPE as required by their tasks			
II	PPE is in good condition and properly fitted for each worker			
III	Additional specialized PPE (e.g., fall protection, respiratory protection) is provided where needed			
IV	Adequate supplies of PPE are available for all workers			

OBSERVATIONS

3. WORKSITE HOUSEKEEPING

I	Work areas and access routes are clear of debris and hazards			
II	Are signs posted to warn of wet floors			
III	Waste and construction materials are properly disposed of or stored.			
IV	Tools and equipment are stored securely when not in use.			
V	Hazardous substances are stored and labeled correctly.			
VI	Care Related to floor Mopping			

OBSERVATIONS

--

4. SCAFFOLDINGS AND LADDERS

I	Scaffoldings are erected and used according to safety standards.			
II	Ladders are in good condition and used safely with appropriate access			
III	Proper fall protection measures are in place for elevated work.			
IV	Scaffoldings and ladders are inspected regularly for defects.			

OBSERVATIONS

--

5. ELECTRICAL SAFETY

I	Electrical installations comply with safety regulations and codes			
II	Electrical panels and circuits are properly labeled and accessible			
III	Power tools and electrical equipment have grounded plugs.			
IV	Workers are trained in electrical safety and lockout / tag out procedures			

OBSERVATIONS**6. MATERIAL HANDLING**

I	Safe lifting and material handling practices are observed			
II	Mechanical lifting equipment is inspected and certified			
III	Workers are trained in material handling safety techniques			
IV	Heavy materials are securely stacked and stored to prevent collapse			

OBSERVATIONS**7. HAZARDOUS SUBSTANCES**

I	Chemicals are properly labeled, stored, and handled		
II	Material Safety Data Sheets (MSDS) are available for hazardous substances		
III	Workers are informed about the hazards and safe handling of chemicals		
IV	Spill kits and emergency response procedures are in place		

OBSERVATIONS**8. EMERGENCY PREPAREDNESS**

I	Emergency response plans are posted, and workers are familiar with them.		
II	Evacuation routes and assembly points are clearly marked.		
III	First aid kits and medical emergency procedures are accessible		
IV	Workers are trained in emergency response and evacuation procedures		

OBSERVATIONS

9. WORKSITE TRAFFIC MANAGEMENT

I	Traffic routes are clearly marked and separate from work areas		
II	Adequate traffic signs and barriers are in place to control vehicle movement.		
III	Workers and vehicle operators are trained in traffic safety rules		
IV	High-visibility clothing is worn by workers in traffic areas		

OBSERVATIONS

--

10.Waste Disposal

I	Ensure there are adequate numbers of containers?		
II	Ensure there are separate and approved containers for toxic and flammable waste?		
III	Ensure waste containers located where the waste is produced?		
IV	Ensure waste containers are emptied regularly?		

OBSERVATIONS

--

11. HSE TRAINING AND COMPETENCY

I	Workers receive HSE induction and specific job training		
II	Competency assessments are conducted for specialized tasks		
III	Records of training and competency assessments are maintained		
IV	Workers are periodically retrained on HSE topics.		

OBSERVATIONS

--