

Sr. #	Description	Unit	Qty	Rate		Amount
1 (a)	Part-A (Tower Foundations) Installation of foundation of following type towers including but not limited to excavation in various soil as well in rock i/c dewatering, stub setting, leveling etc. providing slope protection where necessary i/c fixing of grounding sets as per specification i/c carriage of stub, grounding set from department store, installation of grounding sets Conventional Foundation Tower type ZM1 foundation 20 ^o drawing No.PDW/TC-198	Footing	144	75000	Market items	10800000
1 (b)	Tower type ZM30 foundation 20 ^o drawing No.PDW/TC-199	Footing	48	95000	Market items	4560000
1 (c)	Tower type ZM60 foundation 20 ^o drawing No.PDW/TC-200	Footing	28	115000	Market items	3220000
1 (d)	Tower type EA foundation type A-1 drawing No.PDW/TC-244	Footing	20	195000	Market items	3900000
1 (e)	Tower type ED foundation type D-1 drawing No.PDW/TC-245	Footing	16	215000	Market items	3440000
1 (f)	Tower type EG foundation type G-1 drawing No.PDW/TC-246	Footing	16	255000	Market items	4080000
1-ii (a)	Semi sub merged foundations Tower type ZM1 foundation 10 ^o drawing No.PDW/TC-440	Footing	4	215000	Market items	860000
1-ii (b)	Tower type ZM30 foundation 10 ^o drawing No.PDW/TC-441	Footing	4	255000	Market items	1020000
1-ii (c)	Tower type ZM60 foundation 10 ^o drawing No.PDW/TC-442	Footing	4	295000	Market items	1180000
2 (a) (i)	Part-B Erection of Towers Transport from IESCO Regional Store to site of work & Install 132KV Steel Tubular Poles with all accessories in accordance with requirements of Contract Documents/ Drawings with all accessories including U-Bolts/ V-Shackles, Number Plates, Danger signs, Phase Plates & Anti-climbing device alongwith Barbed Wire etc. including electric welding of nuts, bolts & washers upto 06meter height of towers.Suspension Tower Type ZM - 1 Basic Body (without stubs)	No.	37	120000	Market items	4440000
2 (a) (ii)	3.0 m Leg Extension	Set.	19	6500	Market items	123500
2 (a) (iii)	6.0 m Leg Extension	Set.	2	8500	Market items	17000
2 (b) (i)	Medium Angle Tower Type ZM - 30 Basic Body (without stubs)	No.	13	150000	Market items	1950000
2 (b) (ii)	3.0 m Single Leg Extension	Set.	5	8500	Market items	42500
2 (c) (i)	Heavy Angle/Deadend Tower Type ZM-60 Basic Body (without stubs)	No.	8	175000	Market items	1400000
2 (c) (ii)	3.0 m Leg Extension	Set.	3	8500	Market items	25500
2 (d) (i)	220kV Tower Type EA Basic Body (without stubs)	No.	5	200000	Market items	1000000
2 (d) (ii)	2.0 m Leg Extension	No.	12	8000	Market items	96000
2 (d) (iii)	6.0 m Leg Extension	No.	4	12000	Market items	48000
2 (d) (iv)	8.0 m Leg Extension	No.	4	18000	Market items	72000
2 (e) (i)	Basic Body (without stubs)	No.	4	250000	Market items	1000000
2 (e) (ii)	2.0 m Leg Extension	No.	16	15000	Market items	240000
2 (f) (i)	220kV Tower Type EG Basic Body (without stubs)	No.	4	295000	Market items	1180000
2 (f) (ii)	2.0 m Leg Extension	No.	16	25000	Market items	400000

3-i	Part-C:- (Stringing of Conductor, Shield wire and Installation of Insulators,Fittings & Dampers etc. i/c Transportation etc) Stringing / Sagging (Double Circuit) 06 No. Conductor type greely including installation of Insulators, Stock Bridge Dampers, Assemblies, Hardwares, Midspan Joints, Deadend Clamps Repair Sleeves etc including transportation from IESCO regional store to site of work.	Km	18.4	450000	Market items	8280000
3-ii	Stringing 1 No. Glavanized Steel Wire 9mm dia, Standard including installation of	Km	18.4	250000	Market items	4600000
4	Part D (Mitigation Measures for Environmental Management & Monitoring Plan (EMMP). Water quality monitoring/management analysis (Before Mobilization & After completion) Provision of clean drinking water at site.	Job	4	20000	Market items	80000
5	Air Quality Monitoring	Job	4	25000	Market items	100000
6	Noise Quality Monitoring	Job	4	1500	Market items	6000
7	Waste Water Quality Monitoring.	Job	4	20000	Market items	80000
8	Other environmental & Social mitigation measurs (Demarcation of work area, SSEMP, First Aid Box, Fire Fighting Equipments, Proper Storage of Oil & Lubricants, Awareness Pan flexes (size 4x6 feet) minimu 15 Nos).	Job	1	250000	Market items	250000
9	Site restoration (complete in all respects).	No.	71	8500	Market items	603500
	Total					59094000
	%age Above/ below					
	Total					
	Please add 16% PST as Provincial Sales Tax as statutory charges					
	Grand Total					
	The above same BOQ must be signed and stamp by the bidder & should not be altered otherwise the bid will be rejected:_____					