

Ref. No.	Description	Unit	Qty	Rate	Amount
1	Supply and installation of single phase 220/240 V, 50C/S Split Inverter (Hot & Cool) Reversible AC unit wall mounted capacity 12000 BTU (1 Ton), comprises of evaporating & condensing units with rotary/ reciprocating compressor along with 22 gauge 10 Rft. Copper pipe and insulation with PVC duct, hole sealing with white cement & L-type power quoted angle iron frame size 1-1/2" x 1-1/2" x 1/8" thick, handling charges, (loading, unloading, transportation etc.)i/c evacuation, nitrogen pressure, testing gas charging with standard suction and discharge pressure and amperes, control wiring, rawal bolts, drain piping, testing commissioning complete in all respect. The specifications of quoted AC must be filled in Evaluation Criteria-1 for scrutiny. Compressor warranty- 03yrs(T3 Rating) Refrigerant R410.	Nos.	7		
2	Supply, Laying and connecting Copper Piping of 22 Gauge (Muller Brand or Equivalent) with Aero flex Insulation and Three Core – 110/.076 Control Wire (Pakistan/Pioneer Cable or Equivalent); including all necessary fittings and accessories; as per site requirement	Rft	500		