

Sr. #	Description	Unit	Qty	Rate		Amount
1	Excavation in foundation of building, bridges and other structures including dag belling, dressing, refilling with excavated material including watering, ramming lead upto 31meter and lift upto 1.5meter in hard or soft soil (P 2-5/22-c)	Cum	87.232		WCSR Items	
2	Supply and spreading of crushed stone/water born gravel 20mm size (P 7 5/28).	Cum	573.238		WCSR Items	
3	Refilling excavated stuff in trenches in 150mm layer i/c watering ramming compaction (P 2-3/13)	Cum	69.786		WCSR Items	
4	Leveling, dressing and making lawns (P 20-18/123)	Sqm	2700.000		WCSR Items	
5	Earthing pit arrangement for Power Transformers & 11kV incoming panels complete including copper plate size 2'x2' x 1/2" & other material depth upto 20'.	Job	4		Market items	
6	Providing and fixing 1.5 ton A.C split unit (invertors) complete in all respect.	No.	3		Market items	
7	Providing/fixing of steel stairs with accessories complete in all respect for access to ground floor and 1st floor of control house building.	Job	1		Market items	
8	Providing of Fire Fighting Equipments (02 No. Chemical foam 10 gallons trolley mounted with equivalent number of re-fills, 04 Set Sand container with shovel (45 gallons), 06 Set Six fire buckets with stand consisting 4-stand & 24 buckets, 05 No.Chemical foam (02 gallons) with equivalent number of re-fills (10 liters), 02 No. CO2 trolley mounted twin cylinder of 20Kg each) as per standard specification of WAPDA/IESCO	Job	1		Market items	
9	Providing of Furniture (12 No. office chair, 02 No. office table, 02 No. side rack, 02 No. steel amirah, 02 No. wall clock, 02 No. stool & 02 No. notice board) as per standard specification of WAPDA/IESCO.	Job	1		Market items	
10	Providing of Grid T&P (01 No. Blower China, 01 No. screw wranch 10", 01 No. screw wranch 8", 01 No. plier size 8", 01 No. wire cutter 6", 01 No. pipe plier, 01 No. drill machine 1/2 H.P., 01 set box spanner set, 01 set	Job	1		Market items	
11	Providing of Wiring Material for Power Transformers & Allied Equipments (150 No. copper stud for earth conductor, 285 No. thimble for 95mm sq, 30 Kg galvanized nuts & bolts off sizes, 24 No. thimble for 10mm, 24 No. PG connector for copper conductor 95mm sq, 15 Kg rough cloth, 36 No. PVC tape (RYB), 600 Doz. cable marking lead (A-Z)(0-9), 15 Pkt. cable ties 8", 120 Rft PVC pipe size 2"dia, 300 Rft PVC pipe size 1.25" dia, 50 Rft PVC pipe size 4"dia, 90 No. cable glands brass size 35mm, 150 No. cable glands brass size 25mm, 06 No. cable glands brass size 170mm, 01 No. PT Box complete, 25 Mtr. battery copper lead 120mm, 02 No. 110V DC Hooter, 02 No. 220V AC Hooter, 12 No. thimble copper 40mm) & 250 No. copper earthing lugs along with nuts, bolts, spring & plain washers for 95mm sq conductor. as per standard specification of WAPDA/IESCO. as per standard specification of WAPDA/IESCO.	Job	1		Market items	
12	Hikvision Bullet Camera 2MP having 1080P resolution, 1p-66 weatherproof, 20M night vision, DVR 2MP 1080P recording, 04 channles, 500GB HDD storage, installation, testing and commissioning, Branded Power Supply Adopter, BNC and DC Cable, CCTV Wiring Fee-100FT with 44 inch LCD (Samsung).	Job	1		Market items	
13	Providing/installation of Lightening protection with 360meter copper strip size 20x5mm along with 26 No. 1.5m long 16mm dia copper shielding rod with base clamp including 150 No. fixing clamps on the top of parapet wall of control house building & link the same with earthing mesh at four points complete as per drawing.	Job	1		Market items	
	Total					
	%age Above/ below					
	Total					
	Please add 16% PST as Provincial Sales Tax as statutory charges					
	Grand Total					

The above same BOQ must be signed and stamp by the bidder & should not be altered otherwise the bid will be rejected:_____