

Sr. #	Description	Unit	Qty	Rate	Amount
1a	Installation of foundation of following type towers including but not limited to excavation in various soil as well in rock i/c dewatering, stub setting, leveling etc. providing slope protection where necessary i/c fixing of grounding sets as per specification i/c carriage of stub, grounding set from department store, installation of grounding sets.Tower type ZM1 foundation 20° drawing No.PDW/TC-198	Footing	8		Market Rate
1b	Tower type ZM30 foundation 20° drawing No.PDW/TC-199	Footing	8		Market Rate
1c	Tower type ZM60 foundation 20° drawing No.PDW/TC-200	Footing	4		Market Rate
1d	Tower type EA	Footing	4		Market Rate
1e	Tower type ED	Footing	8		Market Rate
1f	Tower type EG	Footing	4.000		Market Rate
2a (i)	Transport from IESCO Regional Store to site of work & Install 132KV Steel Tubular Poles with all accessories in accordance with requirements of Contract Documents/ Drawings with all accessories including U-Bolts/ V-Shackles, Number Plates, Danger signs, Phase Plates & Anti-climbing device alongwith Barbed Wire etc. including electric welding of nuts, bolts & washers of tower upto 06-meter height of towersSuspension Tower Type ZM - 1Basic Body (without stubs)	No.	2.000		Market Rate
2a(ii)	6.0 m Leg Extension	No.	8.000		Market Rate
2b(i)	Medium Angle Tower Type ZM - 30 Basic Body (without stubs)	No.	2		Market Rate
2b (ii)	3.0 m Leg Extension	No.	8		Market Rate
2c(i)	Heavy Angle Tower Type ZM - 60 Basic Body (without stubs)	No.	1		Market Rate
2c(ii)	3.0 m Leg Extension	No.	4		Market Rate
2d(i)	220kV Tower Type EA Basic Body (without stubs)	No.	1		Market Rate
2d(ii)	8.0 m Leg Extension	No.	4		Market Rate
2e(i)	220kV Tower Type ED Basic Body (without stubs)	No.	2		Market Rate
2e(ii)	8.0 m Leg Extension	No.	8		Market Rate
2f(i)	220kV Tower Type EG Basic Body (without stubs)	No.	1		Market Rate
2f(ii)	8.0 m Leg Extension	No.	4		Market Rate
3	Destringing/restringing / Sagging (Double Circuit) 06 No. Conductor type Rail including installation of Insulators, Stock Bridge Dampers, Assemblies, Hardwares, Midspan Joints, Deadend Clamps Repair Sleeves etc including transportation from IESCO regional store to site of work.	Km	0.7		Market Rate
4	Destringing/restringing / Sagging (Single Circuit) 03 No. Conductor type Lynx including installation of Insulators, Stock Bridge Dampers, Assemblies, Hardwares, Midspan Joints, Deadend Clamps Repair Sleeves etc including transportation from IESCO regional store to site of work.	Km	0.2		Market Rate
5	Destringing/restringing 01 No. Glavanized Steel Wire 9mm dia, Standard including installation of Stock Bridge Dampers, Assemblies, Hardwares, Midspan Joints, Deadend Clamps etc including transportation from IESCO regional store to site of work.	Km	0.900		Market Rate
6	Providing of N2 RTK Palm Base Receiver along with Jupiter Laser GNSS Rover Receiver by SINO GNSS with complete accessories (One Base & Two Rover with Two Data Controller)	Job	1.000		Market Rate
7	Water quality monitoring/management analysis (Before Mobilization & After completion) Provision of clean drinking water at site.	Job	1.000		Market Rate
8	Other environmental & Social mitigation measures (Demarcation of work area, SSEMP, First Aid Box, Fire Fighting Equipments, Proper Storage of Oil & Lubricants, Awareness Panels flexes (size 4x6 feet) minimum 15 Nos).	Job	1.000		Market Rate
9	Site restoration (complete in all respects).	No.	9.000		Market Rate
10	Dismantling of existing towers alongwith hardware and returned to store.	Kg.	45346.000		Market Rate
11	Dismantling of existing conductor (Rail) along with suspension/tension assembly, Stock Bridge Dampers & returned to store. (ACSR Rail length 0.3Km) Total Weight of Scrap	Kg	2880.360		Market Rate

Sr. #	Description	Unit	Qty	Rate		Amount
12	Dismantling of existing earth wire along with suspension/tension assembly, Stock Bridge Dampers & returned to store. (length 0.300Km) Total Weight of Scrap	Kg	105		Market Rate	
	Total					
	%age Above/ below					
	Total					
	Please add 15% FST as statutory charges					
	Grand Total					

The above same BOQ must be signed and stamp by the bidder & should not be altered otherwise the bid will be rejected:_____