

Sr. #	Description	Unit	Qty	Rate		Amount
1a	Ex. in foundation of building, bridges and other structures i/c dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 30 mtr and lift upto 1.50m In Hard Soil	Cum	1223.6263		2-5-22a.	
1b	Cutting hard rock such as granite, ballast, hard lime stone or sand- stone etc. with chisels and hammers for small foundations	Cum	135.95848		2-5-23.	
3a	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate) Ratio 1:4:8	Cum	125.51107		5-1-2d	
3b	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate) Ratio 1:2:4	Cum	8.7105497		5-1-2b	
4	R.C.C work using coarse sand except the cost of steel reinforcement and its labour for bending and binding. This rate also include all kind of forms moulds lifting shuttering, curing, rendering and finishing the exposed surface (including screening the washing of shingle). In-situ in roof slabs, beams, columns, rafts, lintels and other structural members complete in all respect 1:2:4	Cum	930.129		5-1-3a	
5	Supplying and fabrication of intermediate grade deformed reinforcement for R.C.C in slabs, beams, columns and pile caps, including cutting, bending laying in position including cost of binding wire 40,000PSI yield.	kg	93146.610		5-3-6b	
6	Bricks work other than building including striking of joints utp 3.0m height in cement sand mortar 1:5	Cum	195.020		6-1-4 d	
7	Cement plaster 13mm ratio 1:4	Sqm	1929		10-1-5b	
8	Providing and fixing Razor barbed wire fencing having 460mm ring at 150mm centre to centre hanging on 10mm dia MS bar with 40x40x5mm angle iron post of 1.0m height complete.	Mtr	451.83		20-23-186.	
9	Filling watering and ramming earth under floors with surplus earth from foundation	Cum	407.87543		2-5-25.	
10	Filling watering and ramming earth under floors with new earth (excavation from outside) lead upto 30m and lift upto 1.5m	Cum	2824.7128		2-5-26.	
11	Carriage of 3.0 Cum or 5 metric tons of all material like earth, silt, sand, stone aggregate spawl, coal, lime, surkhi. Steel girders, M.S sheets, M.S Bars etc or 4.25 Cum of timber or 3.75 metric tons of fuel wood by truck or any other means 5 Km.	Cum	2824.7128		1-1-1	
12	Weather shield paint Three Coats on new Surface	Sqm	2638.7473		10-3-24.	
13A	Providing laying into trenches, jointing and testing PVC class 'B' pipe line with special for internal 75mm	Mtr	283.84639		13-7-20a.	
13B	Providing laying into trenches, jointing and testing PVC class 'B' pipe line with special for internal 100mm	Mtr	6.0957025		13-7-20b.	
14	Making and fixing steel grated door with 2.0mm thick sheeting including angle iron frame 50x50x10mm and 20mm square bars 100mm center to center with locking arrangement	Sqm	27.689033		20-3-27.	
15	Painting new surface preparing surface and painting of guard bars, gates of iron bars, gratings railings, (including standards braces etc) and similar open work	Sqm	55.378067		12-3-5d.i+ii	
16	Making and Fixing grating in opening including fixing at site with flat iron 50x10mm and 20mm square bars at 100mm centre to centre	Sqm	275.55019		20-3-28.	

Sr. #	Description	Unit	Qty	Rate		Amount
17	Wiring light or fan point with 1/1.13 (3.029) PVC insulated wire in 19.1mm, 1.50mm thick PVC conduit recessed in the wall or column complete with switch plastic plate ceiling rose/batten holder	No	12.000		21-4-26.	
18	Wiring mains with 2-1/1.13 (3/029) PVC insulated wire in 19.1mm PVC Conduit recessed in the wall as required	Mtr	200.000		21-15-93.	
19	Wiring mains with 2-1/1.78 (7/029) PVC insulated wire in 19.1mm PVC conduit recessed in the wall as required.	Mtr	400.000		21-15-95.	
20	Providing lowering and laying into trenches and jointing cement concrete reinforced pipeline to correct alignment and grade including cutting of pipes where necessary cost of jointing material and testing with internal diameter.150mm	Mtr	20.000		13-8-23b.	
21	P/F Gate Lamp best Quality Complete In all respect	No	6.000		Market Rate	
22	P/F LED Flood Light 50W Osaka or phillips	No	10.000		Market Rate	
	Total					
	%age Above/ below					
	Total					
	Please add 15% FST as statutory charges					
	Grand Total					

The above same BOQ must be signed and stamp by the bidder & should not be altered otherwise the bid will be rejected:_____