

Name of Work	Construction of Jeepable Road at Azad Khel Abad Tehsil Bataira District Kohistan Contract Package No PIDCL/KPK/SAP/2024-25-R/12/14/20						
Bill of Quantities/Cost Estimate							
S.No.	Schedule Ref	Item of Work	Quantity		Rate	Unit	Amount
	1	SH:I EARTH WORK					
1	03-03-b	Excavate Unsuitable Hard Rock Material	48,800	cft	30,191.17	1000cft	1473329.10
2	03-66-d	Roadway Excavation in Surplus / Unsuitable Rock (Soft) Material	24,960	cft	24058.32	1000cft	600495.67
3	03-66-a	Roadway Excavation in Surplus / Unsuitable Common Material (gravelly soil)	57,000	cft	20,550.68	1000cft	1171388.76
					Total		3245213.52
	2	SH:II RETAINING WALL					
1	03-25-d	Excavation in foundation of building, bridges etc complete : in shingle/gravel	200	cft	13760.97	1000cft	2752.19
2	06-05-i	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	50	cft	34944.55	%cft	17472.28
3	08-01-d-03	Random rubble masonry in foundn. & plinth in cement, sand mortar : Ratio 1:6	420	Cft	32486.06	%Cft	136441.45
4	06-05-f MRS-2025	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4)	10	Cft	48238.48	%Cft	4823.85
					Total(B)		161489.77
					TOTAL (A+B)		3406703.29