

Sr. #	Description	Unit	Qty	Rate		Amount
A-1(a)	Installation of foundation of following type towers including but not limited to excavation in various soil as well in rock i/c dewatering, stub setting, leveling etc. providing slope protection where necessary i/c fixing of grounding sets as per specification i/c carriage of stub, grounding set from department store, installation of grounding sets. Tower type ZM1 foundation 20° drawing No.PDW/TC-198	Footing	20.000		Market items	
b	Tower type ZM1 foundation 10° drawing No.PDW/TC-440	Footing	4.000		Market items	
B(a)	Transport from IESCO regional store to work sites and & Install 220/132 kV double circuit towers with all accessories in accordance with requirements of Contract Documents/ Drawings with all accessories including U-Bolts/ V-Shackles, Number plates, Danger signs, Phase plates & Anti-climbing device alongwith barbed wire etc & Electric Welding of towers Suspension Tower Type ZM - 1					
(i)	Basic Body (without stubs)	No.	6		Market items	
(ii)	3.0 m Leg Extension	No.	8		Market items	
C-1	Stringing / Sagging (Double Circuit) 03 No. conductors type ACCC Greely including installation of Disc Insulators,Suspension/Tension fitting,stock bridge dampers,midspan joints, repair sleeves etc including transportation from IESCO regional store to work sites.	Km	13.040		Market items	
C-2	Stringing of 1 No. Glavanized Steel Wire 9mm dia, including installation of Stock Bridge Dampers,Suspension/Tension Fitting, Midspan Joints, Repair Sleeves etc alongwith transportation from	Km	1.200		Market items	
D-1	Dismantling of existing Tower ZM-1 tower without stubs & cleats and returned to store in weight	Kg	3016.000		Market items	
D-2	Dismantling of existing lynx conductor along with allied accessories & returned to store in (ACSR Scrap) weightage	km	29645.136		Market items	
E-1	Water quality monitoring/management analysis (Before Mobilization & After completion) Provision of clean drinking water at site.	Job	4.000		Market items	
E-2	Air quality Monitoring	Job	4.000		Market items	
E-3	Noise Quality Monitoring	Job	4.000		Market items	
E-4	Waste water Monitoring	Job	4.000		Market items	
E-5	Other environmental & Social mitigation measurs (Demarcation of work area, SSEMP, First Aid Box, Fire Fighting Equipments, Proper Storage of Oil & Lubricants,PPEs	Job	1.000		Market items	
E-6	Site restoration (complete in all respects).	No.	55.000		Market items	
	Total					
	%age Above/ below					
	Total					
	Please add 16% PST as Provincial Sales Tax as statutory charges					
	Grand Total					

The above same BOQ must be signed and stamp by the bidder & should not be altered otherwise the bid will be rejected:_____