

Sr. #	Description	Unit	Qty	Rate		Amount
1	Excavation in shingle or gravel formation and rock not required ballasting undressed lead upto 50 Mtr in dry soil. (P 2-1/4-c)	72.000	Cum		WCSR items	
2	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate) without shuttering. (P 5-1/2-d). Ratio 1:4:8	6.221	Cum		WCSR items	
3	Supplying and fabrication of intermediate grade deformed reinforcement (40,000 Psi 276 Mpa yield) for RCC slabs, beams, columns and pile caps, including cutting, bending, laying in position i/c cost of binding wire (P 5-3/6-9)	176.447	Kg		WCSR items	
4	Reinforced cement concrete work using coarse sand except the cost of steel reinforcement and its labour for bending and binding. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing, rendering and finishing the exposed surface (including screening and wahsing of shingle) a) In-situ in roof slabs, beams, columns, rafts, lintals and other structural members complete in all respect Ratio 1:2:4 (P 5-2/3a-i)	0.000	Cum		WCSR items	
5	Refilling excavated stuff in trenches in 150mm layer i/c watering ramming compaction (P 2-3/13)	2.262	Cum		WCSR items	
6	Coursed Rubble, masonry including hammer dressing.in Cement sand mortor ratio 1:4 (P7-2/4-b)	38.484	Cum		WCSR items	
7	Dumping shingle spawls and boulders including carriage of material within 90 m.	27.000	Cum		WCSR items	
	Total					
	%age Above/ below					
	Total					
	Please add 15% FST as statutory charges					
	Grand Total					

The above same BOQ must be signed and stamp by the bidder & should not be altered otherwise the bid will be rejected:_____