

Standard Bidding Document

NCB-302 Procurement of Fan with motor for 40 MVA T/F, Fan with motor for 20/26 MVA T/F , Fan with motor for 10/13 MVA T/F, Fan with motor for 21/30 MVA T/F (132/66)(Estimated cost amounting to Rs. 6,166,623) including GST & all other taxes
(Goods)

National

Single Stage-One Envelope



October 13, 2026

*IESCO-PMU (Islamabad Electric Supply company (IESCO)), Director procurement
Office of Director (Procurement) Project Management Unit (PMU) Near 132kV Rawal Grid Station, Club Road,
Kashmir Chowk Islamabad Capital Territory
Phone: +92-319-599-2205, Email: Iescopmu@iesco.com.pk*

Table of Contents

REQUEST FOR BIDS	1
Instructions to Bidders	3
Bid Data Sheet	24
Bids Data Sheet (BDS)	25
Eligibility Criteria	30
Evaluation Criteria	31
Items/Lots	33
Related Services of Goods:	35
Items/Lot Specification	36
Price Schedule	38
General Conditions of Contract	40
Special Conditions of Contract	51
Bid Securing Declaration	58
Contract Form	60
Integrity Pact	63
Performance Guarantee Form	65
Annexure	68
Manufacturer experience annex	69
Production capacity annex	69
Bidder information form	69
Bidder JV form	69

Deviation from contractual provision	69
Deviation technical provision	69
Qualification information	70
Manufacturer authorization	70
Manufacturer information form	70
Production capacity of manufacturer	70
Letter of bid	70
IESCO blacklisting policy	71
Correction of defect in warranty period	71
Type test requirement	71
Payment terms	71
SPECS	71
Price schedule NCB-302 EXW	72
Price schedule NCB-302 DDP	72
Procurement Forms	73
Past Experience and Completed Contracts	1
Historical Contract Non-Performance, and Pending Litigation and Litigation History	1
Current Contracts and Their Progress	1
Financial Capacity and Net Worth Evaluation Form	1
Average Annual Turnover	1
Additional Forms and Documents	77

REQUEST FOR BIDS

PROCUREMENT OF GOODS

1. The **IESCO-PMU (Islamabad Electric Supply company (IESCO))** has reserved Funds for the procurement planned for FY **2026-27**. The **IESCO-PMU (Islamabad Electric Supply company (IESCO))** intends to apply part of the proceeds of this Fund to cover eligible payments under the contract for the "**NCB-302 Procurement of Fan with motor for 40 MVA T/F, Fan with motor for 20/26 MVA T/F , Fan with motor for 10/13 MVA T/F, Fan with motor for 21/30 MVA T/F (132/66)(Estimated cost amounting to Rs. 6,166,623) including GST & all other taxes**" with the reference of "**P111373**"
2. The **IESCO-PMU (Islamabad Electric Supply company (IESCO))** invites sealed Bids from eligible Bidders for procurement of goods described in the bidding documents on **EPADS v2.0**.
3. **Single Stage-One Envelope** will be used by adopting **Least Cost Based Selection (LCBS)** Technique for the subject procurement, in line with the Public Procurement Rules, 2026 and any Regulations, Regulatory Guides, Procurement Guidelines or Instructions issued by the Authority from time to time.
4. All Bids must be accompanied by a Bid Security amount described in Bid Security Section in Bidding Document in the form of **Call at Deposit, Bank Guarantee, Demand Draft** or all bids must be accompanied by bid securing declaration in the format specified in the Bidding documents
5. E-Bidding documents, containing detailed terms & conditions, specifications and requirements etc. are available on **e-Pak Acquisition and Disposal System (EPADS)** at **<https://epads.gov.pk/opportunities/federal/procurements/111373>** for all the interested bidders registered on **EPADS v2.0**. Bidders are required to get themselves registered on **EPADS v2.0** to participate in Bidding process.
6. The e-bids, prepared in accordance with the instructions in the e-Bidding Documents, must be submitted through **EPADS v2.0** on or before **Monday,**

October 26, 2026 11:00 AM. E-bids will be opened using **EPADS v2.0** on the same day at **Monday, October 26, 2026 11:30 AM.** Manual submission of Bids shall not be entertained. Those vendors who have not yet registered on the new version of **EPADS v2.0**, may register themselves on <https://vendors.epads.gov.pk/>. A tutorial to explain the registration process is available at <https://www.youtube.com/watch?v=MNW6T38v7tc>

In terms of Rule 65 of Public Procurement Rules, 2026 Grievance Redressal Committee (GRC) is notified for the subject procurement and notification copy is available on the procuring agency's website and on Authority's website at (www.ppra.gov.pk).

IESCO-PMU (Islamabad Electric Supply company (IESCO)), Director procurement
Office of Director (Procurement) Project Management Unit (PMU) Near 132kV
Rawal Grid Station, Club Road, Kashmir Chowk Islamabad Capital Territory
+92-319-599-2205
iescopmu@iesco.com.pk



Instructions to Bidders

A. Introduction

1.Scope of Bids

1.1 The Procuring Agency (PA), as indicated in the **Bids Data Sheet (BDS)** invites Bids **through EPADS v2.0** for the provision of Goods as specified in the BDS and **in Section V - Evaluation Criteria, Specifications & Schedule of Requirements**. The name, identification, and number of items/deliverables are provided in the **BDS**. The successful Bidders will be expected to provide the goods within the specified period and timeline(s) as stated in the **BDS**.

2. Source of Funds

2.1 Source of funds is referred in Clause-2 I of Invitation for Bids.

3. Eligible Bidders

3.1 A Bidder may be natural person, company or firm or public or semi-public agency of Pakistan or any foreign country, or any combination of them with a formal existing agreement (on Judicial Papers) in the form of a joint venture, consortium, or association. In the case of a joint venture, consortium, or association, all members shall be jointly and severally liable for the execution of the Contract in accordance with the terms and conditions of the Contract. The joint venture, consortium, or association shall nominate a Lead Member as nominated in the BDS, who shall have the authority to conduct all business for and on behalf of any and all the members of the joint venture, consortium, or association during the Bidding process, and in case of award of contract, during the execution of the contract.

Verifiable copy of the agreement that forms a joint venture, consortium or association shall be required to be submitted as part of the Bid.

The appointment of Lead Member in the joint venture, consortium, or association shall be confirmed by submission of a valid Power of Attorney to the Procuring Agency.

Any bid submitted by the joint venture, consortium or association shall indicate the part of proposed contract to be performed by each party and each party shall be evaluated (or post qualified if required) with respect to its contribution only, and the responsibilities of each party shall not be substantially altered without prior written approval of the Procuring Agency and in line with any

instructions issued by the Authority.

(The limit on the number of members of JV or Consortium or Association may be prescribed in BDS, in accordance with the guidelines issued by the PPRA).

3.2 The invitation for Bids is open to all prospective suppliers, manufacturers, or authorized agents / dealers subject to any provisions of incorporation or licensing by the respective national incorporating agency or statutory body established for that particular trade or business. Procuring agencies shall specify the registration/licensing requirements for the foreign bidders keeping in view the requirement of that business.

3.3 A Bidder shall not have a conflict of interest. All Bidders found to have a conflict of interest shall be disqualified. A Bidder may be considered to have a conflict of interest with one or more parties in this Bidding process, if they:

1. are associated or have been associated in the past, directly or indirectly with a firm or any of its affiliates which have been engaged by the Procuring Agency to provide consulting services for the preparation of the design, specifications and other documents to be used for the procurement of the Goods to be purchased under this Invitation for Bids.
2. have controlling shareholders in common; or
3. receive or have received any direct or indirect subsidy from any of them; or
4. have the same legal representative for purposes of this Bid; or
5. have a relationship with each other, directly or through common third parties, that puts them in a position to have access to information about or influence on the Bids of another Bidder, or influence the decisions of the Procuring Agency regarding this Bidding process; or
6. Submit more than one Bid in this Bidding process.

3.4 A Bidder may be ineligible if –

1. he is declared bankrupt or, in the case of company or firm, insolvent;
2. payments in favor of the Bidder is suspended in accordance with the judgment of a court of law other than a judgment declaring bankruptcy and resulting (in accordance with the national laws) in the total or partial loss of the right to administer and dispose of its property;

3. the Bidder is convicted, by a final judgment, of any offence involving professional conduct;

4. the Bidder is blacklisted locally or by international organizations and hence debarred due to involvement in corrupt and fraudulent practices, or submission of false or misleading information or performance failure or involved in disrupting procurement process or due to breach of bid Securing Declaration.

3.5 As and when required, bidders shall provide to the Procuring Agency evidence of their eligibility, proof of compliance with the necessary legal requirements to carry out the contract effectively.

3.6 Bidders shall submit Bids relating to the nature, conditions and modalities of sub-contracting wherever the sub-contracting of any elements of the contract amounting to more than ten (10) percent of the Bid price is envisaged.

4. Eligible Goods and Related Services

4.1 All goods and related services to be supplied under the contract shall have their origin in eligible source countries, and all expenditures made under the contract will be limited to such goods and services. For purpose of this Bid, ineligible countries are the countries declared ineligible by the Federal Government.

5. One Bid per Bidder

5.1 A bidder shall submit only one Bid, in the same bidding process, either individually as a Bidder or as a member in a joint venture or any similar arrangement.

5.2 The Bidder shall not engage a subcontractor for any portion of the contract if the value of such subcontracting exceeds thirty percent (30%) of the total contract amount.

6. Cost of Bidding

6.1 Any cost incurred by the bidder relating to the preparation and submission of its Bid shall be borne by the bidder, and the Procuring Agency shall in no case be responsible or liable for those costs, regardless of the conduct or outcome of the bidding process.

B. Bidding Documents

7. Contents of Bidding Document

7.1 The Goods required, Bidding procedures, and terms and conditions of the contract are prescribed in the Bidding Documents. In addition to the Invitation for Bids, the Bidding documents which should be read in conjunction with any addenda issued in accordance with **ITB 10.1** include:

Section I -Invitation to Bids

Section II Instructions to Bidders (ITB)

Section III Bid Data Sheet (BDS)

Section IV Evaluation Criteria, Specifications, Schedule of Requirements

Section V Bid Forms

Section VI General Conditions of Contract (GCC)

Section VII Special Conditions of Contract (SCC)

Section VIII Contract Forms

Section IX Integrity Pact

Section X Declaration of Beneficial Ownership Information.

7.2 The Bidder is expected to examine all instructions, forms, terms and specifications in the Bidding documents. Failure to furnish all the information required in the Bidding documents through EPADS v2.0 will be at the Bidder's risk and may result in the rejection of its Bids.

8. Clarification of Bidding documents

8.1 A prospective Bidder requiring any clarification of the Bidding documents may notify the Procuring Agency through EPADS v2.0.

8.2 The Procuring Agency will within two (02) working days after receiving the request for clarification, respond to any request for clarification through EPADS v2.0 provided that such request is received not later than three (03) days, prior to the deadline for the submission of Bids as prescribed in **ITB 22**

8.3 The Procuring Agency's response will be forwarded to all identified Prospective Bidders through EPADS v2.0, including a description of the inquiry,

but without identifying its source.

8.4 Should the Procuring Agency deem it necessary to amend the Bidding document as a result of a clarification, it shall do so following the procedure under **ITB 9**.

8.5 If indicated **in the BDS**, the Bidder's designated representative is invited at the Bidder's cost to attend a pre-Bid meeting at the place, date and time mentioned **in the BDS**. During this pre-Bid meeting, prospective Bidders may request clarification of the schedule of requirement, the Evaluation Criteria or any other aspects of the Bidding document.

8.6 Minutes of the pre-Bid meeting, if applicable, including the text of the questions asked by Bidders, including those during the meeting (without identifying the source) and the responses given, together with any responses prepared after the meeting will be uploaded on EPADS v2.0. Any modification to the Bidding documents that may become necessary as a result of the pre-Bid meeting shall be made by the Procuring Agency exclusively through the use of an Addendum pursuant to ITB 9. Non-attendance at the pre-Bid meeting will not be a cause for disqualification of a Bidder.

9. Amendment of Bidding documents

9.1 Before the deadline for submission of Bids, the Procuring Agency for any reason, whether at its own initiative or in response to a clarification requested by a prospective Bidder or Pre-Bid meeting may modify the Bidding documents by issuing addenda through EPADS v2.0.

9.2 The Procuring Agency shall promptly publish the addendum through EPADS v2.0.

Any addendum issued including the notice of any extension of the deadline shall also be communicated through EPADS v2.0 to all the bidders who have already submitted their bids. Such bidders shall have the right to withdraw their already submitted bid and re-submit the revised bid prior to the original or extended bid submission deadline.

9.3 To give prospective Bidders reasonable time in which to take an addendum/corrigendum into account in preparing their Bids, the Procuring Agency may, at its discretion, extend the deadline for the submission of Bids through EPADS v2.0:

Provided that the Procuring Agency shall extend the deadline for submission of Bids, if such an addendum is issued within last three (03) days of the Bids submission deadline.

C. Preparation of Bids

10. Language of Bid

10.1 The Bid prepared by the bidder, as well as all correspondence and documents relating to the Bids exchanged by the Bidder and the Procuring Agency shall be written in the English language unless otherwise specified in the BDS. Supporting documents and printed literature furnished by the Bidder may be in another language provided they are accompanied by an accurate translation of the relevant pages in the English language unless otherwise specified in the **BDS**, in which case, for purposes of interpretation of the Bidder, the translation shall govern.

11. Documents and samples Constituting the Bid

11.1 The Bid prepared by the Bidder shall constitute the documents required in the **BDS**.

Details of sample(s) where applicable and requested in the BDS.

Documentary evidence established in accordance with ITB 13 that the Bidder is eligible and/or qualified for the subject bidding process;

Documentary evidence established in accordance with **ITB 03** that the Bidder has been authorized by the manufacturer to deliver the goods into Pakistan, where required and where the supplier is not the manufacturer of those goods;

Documentary evidence established in accordance with ITB 12 that the goods and related services to be supplied by the Bidder are eligible goods and services, and conform to the Bidding Documents;

Bid security or Bid Securing Declaration furnished in accordance with **ITB ---**.

12. Documents Establishing Eligibility of the Goods and Conformity to Bidding documents

12.1 To establish the conformity of the bidder to the Bidding document, the Bidder shall furnish as part of its Bids the documentary evidence that Goods

provided conform to the technical specifications and standards.

13. Documents Establishing Eligibility and Qualification of the Bidder

13.1 Pursuant to **ITB 10**, the Bidder shall furnish, as part of its Bid, all those documents establishing the Bidder's eligibility to participate in the Bidding process and/or its qualification to perform the contract if its Bid is accepted.

14. Form of Bid

14.1 The Bidder shall fill the Form of Bid furnished in the Bidding document. The Bid Form must be completed without any alterations to its format and no substitute shall be accepted.

15. Bid Prices

15.1 The Bid Prices quoted by the Bidder in the Form of Bid and in the Price Schedules shall conform to the requirements specified below or exclusively mentioned hereafter in the Bidding documents.

15.2 All items in the Schedule of Requirement must be listed and priced separately in the Price Schedule(s). If a Price Schedule shows items listed but not priced and neither explicitly denied, their prices shall be construed to be included in the prices of other items.

15.3 In the event that any item(s) in the Price Schedule are not quoted, and such omission is determined by the Procuring Agency not to materially affect the responsiveness of the Bid, the Procuring Agency may, for the sole purpose of bid evaluation and comparison, assign a price to the unquoted item(s) in accordance with the following methodology:

(a) The assigned price shall be the average of the prices quoted for the same item(s) by all substantially responsive bidders; or

(b) In cases where no comparable quotations are available, the Procuring Agency shall apply the corresponding item price from its duly approved cost estimate for evaluation purposes.

The prices so assigned shall be utilized exclusively for bid evaluation and comparison, and shall not, under any circumstances, be incorporated into or form part of the Contract Price.

15.4 The Bid price to be quoted in the Form of Bid in accordance with **ITB 13.1** shall be the total price of the Bid.

15.5 The Bidder shall indicate on the appropriate Price Schedule, the unit prices (where applicable) and total Bid price of the Goods it proposes to provide under the contract.

15.6 Prices quoted by the Bidder shall be fixed during the Bidder's performance of the contract and not subject to variation on any account. A Bid submitted with an adjustable price will be treated as non-responsive and shall be rejected.

16. Bids Currencies

16.1 Prices shall be quoted in Pakistani Rupees unless otherwise specified in the BDS in accordance with Rule 42 (2) of the Public Procurement Rules, 2026.

17. Bids Validity Period

17.1 Such extensions may be more than one time but the total period of such extension shall not exceed the original bid validity period.

17.2 Bids shall remain valid for the period specified in the **BDS** after the Bid submission deadline prescribed by the Procuring Agency. A Bid valid for a shorter period shall be rejected by the Procuring Agency as non-responsive. The period of Bid validity will be determined from the complementary Bid securing instrument, i.e. the expiry period of Bid Security or Bids Securing Declaration as the case may be.

The procuring agency shall ordinarily be under an obligation to process and evaluate the bid and to issue letter of award within the stipulated bid validity period.

17.3 Under exceptional circumstances, prior to the expiration of the initial Bid validity period, the Procuring Agency may request the Bidders' consent to an extension of the period of validity of their Bids through EPADS v2.0. The Bid Security provided under **ITB 17** shall also be suitably extended. A Bidder may refuse the request without forfeiting its Bid security or causing to be executed its Bid Securing Declaration. A Bidder agreeing to the request will not be required nor permitted to modify its Bid, but will be required to extend the validity of its Bid Security or Bid Securing Declaration for the period of the extension.

18. Bid Security or Bid Securing Declaration

18.1 The Bidder shall furnish as part of its Bid, a Bid Security in accordance with Rule 36 of the Public Procurement Rules, 2026.

18.2 The original Bid Security shall be enclosed within the sealed envelope and to be submitted physically before closing time for submission of bids. Whereas, scanned copy of bid security shall be uploaded electronically through EPADS v2.0 before closing hours for submission of bids.

18.3 The Bidder who failed to submit the original Bids security before the submission deadline shall be disqualified straightaway.

18.4 The Bid Security or Bid Securing Declaration is required to protect the Procuring Agency against the risk of Bidder's conduct which would warrant the security's forfeiture, pursuant to **ITB 18.7**.

18.5 The Bid Security shall be denominated in the local currency or in another freely convertible currency, and it shall be in the form specified in the BDS which shall be in any of the following:

- a) a bank guarantee, a bank draft, an irrevocable letter of credit issued by a Scheduled bank in the form provided in the Bidding Documents or another form acceptable to the Procuring Agency;
- b) a cashier's or certified cheque; or
- c) another security if indicated in the BDS.

The Bid Security shall be valid for twenty-eight (28) days beyond the end of the validity of the Bid. This shall also apply if the period for Bid Validity is extended. In either case, the form must include the complete name of the Bidder.

18.6 The Bid Security shall be payable promptly upon written demand by the Procuring Agency in case any of the conditions listed in **ITB 18.7** are invoked.

18.7 Unsuccessful Bidders' Bid Security will be discharged or returned as promptly as possible, however in no case later than thirty (30) days after the expiration of the period of Bid Validity prescribed by the procuring agency pursuant to **ITB 17**. The Procuring Agency shall make no claim to the amount of the Bid Security, and shall promptly return the Bid Security documents, after whichever of the following that occurs earliest:

- a. the expiry of the Bid Security;

- b. the entry into force of a procurement contract and the provision of a Performance Guarantee, for the performance of the contract if such a guarantee, is required by the Bid documents;
- c. the rejection by the Procuring Agency of all Bids;
- d. cancellation of procurement proceedings.
- e. the withdrawal of the Bid prior to the deadline for the submission of Bids, unless the Bid document stipulates that no such withdrawal is permitted.

18.8 The successful Bidder's Bid Security will be discharged upon the Bidder signing the contract, or furnishing the Performance Guarantee.

18.9 The Bid Security may be forfeited or the Bid Securing Declaration executed:

- a. if a Bidder:
- b. withdraws its Bid during the period of Bid Validity as specified by the Procuring Agency, and referred by the Bidder on the Form of Bids except as provided for in **ITB 16.2**; or
- c. does not accept the correction of errors; or
- d. in the case of a successful Bidder, if the Bidder fails:
- e. to sign the contract; or
- f. to furnish Performance Guarantee.

19. Withdrawal, Substitution, and Modification of Bid

19.1 Before Bid submission deadline, any Bidder may withdraw, substitute, or modify its Bid after it has been submitted through EPADS v2.0.

20. Format and Signing of Bid

20.1 The Bidder shall prepare and submit Bids with due diligence after carefully reading all the terms and condition before bid submission deadline through EPADS v2.0.

D. Submission of Bids

21. Submission of Bids through EPADS v2.0 before bid submission deadline.

21.1 The Technical and Financial Bids, shall be submitted electronically through EPADS, before bid submission deadline. The bid submission option shall be automatically disabled once the deadline is over.

22. Deadline for Submission of Bids

22.1 Bids shall be received by the Procuring Agency through EPADS v2.0 before bid submission deadline.

22.2 The Procuring Agency may, under exceptional circumstances, extend the deadline for the submission of Bids, after recording reasons in writing and in an equal opportunity manner.

In such case, all rights and obligations of the Procuring Agency and the Bidders that were previously governed by the original deadline shall thereafter be subject to the revised deadline.

E. Opening and Evaluation of Bids

23. Opening of Bids

23.1 The respective Bid Evaluation Committee of the Procuring Agency shall open all Bids through the EPADS v2.0, on the date and time specified in the Bid Data Sheet (BDS).

23.2 The respective Bid Evaluation Committee **shall generate minutes through EPADS v2.0 containing brief details of bid opening process.** The record of the Bid opening shall include, as a minimum: the name of the Bidder, the Bid price if applicable, and the presence or absence of a Bid Security or Bid Securing Declaration.

23.3 The procuring agency shall live broadcast the opening of bids on national media or on their website or digital channels, if the volume of procurement exceeds five hundred million rupees in case of goods and services and one thousand million rupees in case of works.

23.4 In case the date of opening of bid has been declared as public holiday or the procuring agency fails to open bid due to any EPADS v2.0 related issues, the submission and opening of bids shall be shifted to the next working day at the same time.

23.5 In case of Single Stage One Envelope Procedure, the Bidders names, the Bid prices, the total amount of each Bid and, the presence or absence of Bid Security, Bid Securing Declaration and such other details as the Procuring Agency may consider appropriate, will be announced by the Bid respective Evaluation Committee.

23.6 No bid will be rejected at the time of bid opening except for bids whose original bid security has not been provided to the procuring agency before bid submission deadline.

24. Clarification of Bids

24.1 To assist in the examination, evaluation and comparison of Bids of the Bidders, the respective Bid Evaluation Committee may, ask any Bidder for a clarification of its Bid including breakdown of prices.

24.2 The request for clarification and the response shall be sought through EPADS v2.0 before **three days prior to the deadline for submission of bids.** No change in the prices or substance of the Bids shall be sought, offered, or permitted.

24.3 The alteration or modification in the bids which in any way affect the following parameters will be considered as a change in the substance of a Bid:

1. evaluation & qualification criteria;
2. required scope of work or specifications;
3. all securities requirements;
4. tax requirements;
5. terms and conditions of Bidding documents.
6. change in the ranking of the Bidder

24.4 From the time of bid(s) opening to the time of Contract award if any Bidder wishes to contact the Procuring Agency on any matter related to the Bids it should do so through **EPADS v2.0**.

25. Preliminary Examination of Bids

25.1 Prior to the detailed evaluation of Bids, the respective Bid Evaluation Committee will determine whether each Bid:

1. meets the eligibility criteria defined in **ITB 3**;
2. has been prepared as per the format and contents defined by the Procuring Agency in the Bidding documents;
3. is accompanied by the required securities; and
4. is substantially responsive to the requirements of the Bidding documents.

25.2 The respective Bid Evaluation Committee's determination of a Bid's responsiveness will be based on the contents of the Bid itself.

25.3 A substantially responsive Bid is one which conforms to all the terms, conditions, and specifications of the Bidding documents, without material deviation or reservation. A material deviation or reservation is one that: -

1. affects in any substantial way the scope, quality, or performance of the Goods;
2. limits in any substantial way, inconsistent with the Bidding documents, the Procuring Agency's rights or the Bidders obligations under the Contract; or
3. if rectified, would affect unfairly the competitive position of other Bidders presenting substantially responsive Bids.

25.4 If a Bid is not substantially responsive, it will be rejected by the respective Bid Evaluation Committee and may not subsequently be evaluated for complete technical responsiveness.

26. Examination of Terms and Conditions; Technical Evaluation

26.1 The respective Bid Evaluation Committee shall examine the Bids to confirm that all terms and conditions specified in the **GCC** and the **SCC** have been accepted by the Bidder without any material deviation or reservation.

26.2 The respective Bid Evaluation Committee shall evaluate the technical aspects of the Bids submitted, to confirm that all requirements specified in Schedule of Requirements and Technical Specifications of the Bidding documents have been met without material deviation or reservation.

26.3 If after the examination of the terms and conditions and the technical evaluation, the respective Bid Evaluation Committee determines that the Bid is not substantially responsive in accordance with **ITB**, it shall reject the Bid.

27. Correction of Errors

27.1 Bids determined to be substantially responsive will be checked for any arithmetic errors. Errors will be corrected as follows: -

1. if there is a discrepancy between unit price and the total price that is obtained by multiplying the unit price and quantity, the unit price shall prevail, and the total price shall be corrected, unless in the opinion of the respective Evaluation Committee there is an obvious misplacement of the decimal point in the unit price, in which the total price as quoted shall govern and the unit price shall be corrected;
2. if there is an error in a total corresponding to the addition or subtraction of sub-totals, the sub-totals shall prevail and the total shall be corrected; and
3. where there is a discrepancy between the amounts in figures and in words, the amount in words will govern.
4. Where there is discrepancy between grand total of price schedule and amount mentioned on the Form of Bid, the amount referred in Price Schedule shall be treated as correct subject to elimination of other errors.

27.2 The amount stated in the Bid will be adjusted by the respective Bid Evaluation Committee in accordance with the above procedure for the correction of errors and, with the concurrence of the Bidder, shall be considered as binding upon the Bidder. If the Bidder does not accept the corrected amount, its Bid will then be rejected, and the Bid Security may be forfeited or the Bids Securing Declaration may be executed.

28. Conversion to Single Currency

28.1 For the purposes of comparison of bids quoted in different currencies, the price shall be converted into a single currency in accordance with Rule 42(2) of Public Procurement Rules, 2026.

29. Evaluation of Bids

29.1 The Bids, quotations, or proposals shall be evaluated by the respective evaluation committees as per evaluation criteria prescribed in the Bidding Documents in accordance with Rule 11, 12 and 13 of the Public Procurement Rules, 2026.

29.2 While evaluating the bids, the procuring agency shall consider the following:

- i. Bids will be evaluated on lump sum bid basis or items wise or Lot wise (contracts), as specified in the BDS; and the Bid Price;
- ii. correction of arithmetic errors in accordance with ITB 27;

30. Domestic Preference

30.1 The respective Bid Evaluation Committee shall evaluate and compare bids, allow for preference to domestic bidders, while competing with the international bidders in accordance with the policies of the Federal Government.

The percentage of preference, to be accorded shall be clearly mentioned in the bidding documents under the bid evaluation criteria.

31. Determination of Successful Bid

31.1 Selection technique will be adopted for determining the Successful Bid in accordance with the criteria referred in the BDS or prescribed in the separate section titled as Evaluation Criteria.

31.2 Least Cost Based Selection (LCBS)

After meeting the requirements of eligibility, qualification and substantial responsiveness, the bid in compliance with all the mandatory (technical) specifications/requirements and/or requisite quality threshold (if any), and having lowest evaluated cost (or financial proposal) shall be considered Successful Bid.

31.3 Quality and Cost Based Selection (QCBS)

In such combination, there shall be some specific weightage of both the technical features and financial aspects of the proposal. The financial marks shall be awarded on the basis of inverse proportion calculations. The successful bid shall be declared, on the basis of combined evaluation.

31.4 Quality Based Selection (QBS)

After meeting the requirements of eligibility, qualification and substantial responsiveness the bid in compliance with all the mandatory (technical) specifications/requirements and attaining highest marks in the Technical Evaluation considering all other qualitative and/or quantitative parameters (or point rated criteria) for technical proposal(s) such as working methodology, implementation plan, resource allocation, additional functionalities, risk

management approach, knowledge transfer techniques, post implementation methodology etc. shall be treated as highest ranked bid. Later on, the financial proposal of highest ranked bidder shall be opened, however, in case of failure to proceed further with such a bidder, the procuring agency may resort to second highest bidder and so on.

31.5 The Procuring Agency may adopt the Quality & Cost Based Selection Technique due to the following two reasons:

1. Where the Procuring Agency knows about the main features, usage and output of the products; however not clear about the complete features, technical specifications and functionalities of the goods to be procured and requires the bidders to submit their proposals defining those features, specifications and functionalities; or
2. Where the Procuring Agency, in addition to the mandatory requirements and mandatory technical specifications, requires parameters specified in Evaluation Criteria to be evaluated while determining the quality of the goods.

31.6 In such cases, the Procuring Agency may allocate certain weightage to these factors as a part of Evaluation Criteria, and may determine the ranking of the bidders on the basis of combined evaluation in accordance with provisions of Rule 2(1)(xxviii) of the Public Procurement Rules, 2026.

32. Abnormally Low Financial Bids

32.1 An abnormally low bid is a bid that, in light of the Procuring Agency's cost estimate, market conditions, or other received bids, appears to be unrealistically low and may not be sustainable for successful contract execution.

32.2 Where the Bid price is considered to be abnormally low, the Procuring Agency shall perform price analysis either during determination of Successful Bids or as a part of the post-qualification process.

32.3 The Procuring Agency may reject an Abnormally low financial bid in accordance with Rule 43 of the Public Procurement Rules, 2026.

32.4 In order to identify the Abnormally Low Bids (ALB) following approaches can be considered to minimize the scope of subjectivity:

1. Comparing the Bid price with the cost estimate;

2. Comparing the Bid price with the Bid(s) offered by other Bidders submitting substantially responsive Bids; and

3. Comparing the Bids price with prices paid in similar contracts in the recent past either government- or development partner-funded.

32.5 The respective Bid Evaluation Committee will determine to its satisfaction whether the Bidder that is selected as having submitted the successful bid is qualified to perform the contract satisfactorily.

32.6 The determination will take into account the Bidder's financial, technical, and production capabilities. It will be based upon an examination of the documentary evidence of the Bidder's qualifications submitted by the Bidder, as well as such other information as the Procuring Agency deems necessary and appropriate. Factors not included in these Bidding documents shall not be used in the evaluation of the Bidders' qualifications.

32.7 Respective Bid Evaluation Committee may seek "Certificate for Independent Price Determination" from the Bidder and the results of reference checks may be used in determining an award of contract.

Explanation: The Certificate shall be furnished by the Bidder. The Bidder shall certify that the price is determined keeping in view of all the essential aspects such as raw material, its processing, value addition, optimization of resources due to economy of scale, transportation, insurance and margin of profit etc.

32.8 An affirmative determination will be a prerequisite for award of the contract to the Bidder. A negative determination will result in rejection of the Bidder's Bid, in which event the respective Bid Evaluation Committee will proceed to the next ranked Bidder to make a similar determination of that Bidder's capabilities to perform satisfactorily.

F. Award of Contract

33. Criteria of Award

33.1 The Procuring Agency will award the Contract to the Bidder whose Bids has been determined to be substantially responsive to the Bidding documents and who has been declared as Successful Bidder.

34. Negotiations

34.1 In accordance with Rule 52A of Public Procurement Rules, 2026, without changing the cost and scope of work or services, the procuring agency may

negotiate with the successful bidder (with a view to streamline the work or task execution, at the time of contract finalization) on methodology, work plan, staffing and special conditions of the contract.

There shall be no limitation on the successful bidder offering voluntary reduction in bid price without affecting the quality or scope of the procurement.

35. Procuring Agency's Right to reject all bids

35.1 The Procuring Agency reserves the right to reject all bids or proposals at any time prior to the issuance of the Letter of Award, without incurring any liability, in accordance with Rule 45 of the Public Procurement Rules, 2026.

36. Cancellation of Procurement

36.1 The procuring agency reserves the right to cancel the procurement proceedings in accordance with Rule 46 of the Public Procurement Rules, 2026.

37. Procuring Agency's Right to Vary Quantities at the Time of Award

37.1 The Procuring Agency reserves the right at the time of contract award to increase or decrease the **quantity of** Goods originally specified in these Bidding documents provided this does not exceed **by** 15%, without any change in unit price or other terms and conditions of the Bids and Bidding documents.

38. Notification of Award

38.1 Prior to the award of contract, the procuring agency shall announce and publish the result of bid evaluation on EPADS v2.0 in accordance with Rule 48 of the Public Procurement Rules, 2026.

The Bidder whose Bids has been accepted will be notified of the award by the Procuring Agency prior to expiration of the Bids/Bid Validity period. The Letter of Award will state the sum that the Procuring Agency will pay the successful Bidder in consideration for the delivery of Goods as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price).

38.2 The Letter of award will constitute the formation of the Contract, subject to the Bidder furnishing the Performance Guarantee and signing of the contract.

39. Signing of Contract

39.1 Promptly after issuance of Letter of award, Procuring Agency shall send the successful Bidder the draft Contract, incorporating all terms and conditions as agreed by the parties to the contract.

39.2 Immediately after the Redressal of grievance by the GRC (if any), and **after fulfillment of all conditions precedent** of the Contract Form, the successful Bidder and the Procuring Agency shall sign the Contract.

40. Corrupt & Fraudulent Practices

40.1 Procuring Agencies (including beneficiaries of Government funded projects and procurement) as well as Bidders/Contractors under Government financed contracts, observe the highest standard of ethics during the procurement and execution of such contracts, and will avoid engaging in any corrupt and fraudulent practices.

F. Grievance Redressal & Complaint Review Mechanism

41. Constitution of Grievance Redressal Committee

41.1 The Grievance Redressal Committee shall address the grievance, if any submitted by any party, including the bidder, in accordance with Rule 65 of the Public Procurement Rules, 2026 read with Redressal of Grievances Regulations, 2021.

In case if any party or the bidder is not satisfied with the decision of the GRC or if it fails to decide within ten days, the bidder or the party may file an appeal before the Appellate Committee of the Authority in accordance with Rule 65(7) of the Public Procurement Rules, 2026 to be read with Redressal of Grievances Regulations, 2021.

G. Mechanism of Blacklisting

42. Mechanism of Blacklisting

42.1 The Procuring Agency shall initiate blacklisting proceedings against any bidder, supplier, or contractor in accordance with the Rule 25 of the Public Procurement Rules, 2026.

42.2 The blacklisted/debarred bidder may file the review petition before the Authority in accordance with Rule 25 (6) of the Public Procurement Rules, 2026 to be read with Procedure of filing and disposal of Review Petitions Regulations, 2021.

43. Contract Management

43.1 For each procurement, the Procuring Agency shall designate a Contract Manager, who shall be duly responsible for the efficient management and administration of the contract in strict compliance with the provisions set forth under Rules 58, 59, and 60 of the Public Procurement Rules, 2026.

44. Inspection of goods and evaluation of services.


44.1 The Inspection Committee or the Firm shall have the right to conduct inspections of the goods in accordance with Rule 61 of the Public Procurement Rules, 2026.

45. Socio-economic development.

45.1 In accordance with Rule 63 of the Public Procurement Rules, 2026, preference may be granted to small and medium enterprises and marginalized groups in accordance with the policies notified by the Federal Government.

46. Environmental objectives

46.1 As per Rule 64 of the Public Procurement Rules, 2026, the procuring agency may seek to procure goods with a reduced environmental impact throughout their life cycle when compared to goods services with the same primary function that may otherwise be procured.



Bid Data Sheet

Bids Data Sheet (BDS)

The following specific data for the procurement of Goods to be procured shall complement, supplement, or amend the provisions in the Instructions to Bidders (ITB). Whenever there is a conflict, the provisions herein shall prevail over those in ITB.

BDS Clause Number

ITB Number

Amendments of, and Supplements to, Clauses in the Instruction to Bidders

A. Introduction

BDS Clause Number 1

ITB Number 1.1

Name of Procuring Agency: **IESCO-PMU (Islamabad Electric Supply company (IESCO))**

The subject of procurement is: **NCB-302 Procurement of Fan with motor for 40 MVA T/F, Fan with motor for 20/26 MVA T/F , Fan with motor for 10/13 MVA T/F, Fan with motor for 21/30 MVA T/F (132/66)(Estimated cost amounting to Rs. 6,166,623) including GST & all other taxes**

Period for Provision of Goods:

Extension Period (if applicable):

Expected commencement date: **Monday, November 30, 2026**

BDS Clause Number 2

ITB Number 2.1

Source of funds [Enter source of funds]

Financial year for the operations of the Procuring Agency: **2026-27**

Name and identification number of the Contract: **P111373**

Identification Number:

BDS Clause Number 3

ITB Clause Number 3.1

Eligible Bidder [Enter eligibility of bidder]

JV/Consortium or Association Allowed: **Yes**

Number of JV/Consortium Members: **2**

see section of eligibility criteria.

B. Bidding Documents

BDS Clause Number 4

ITB Clause Number 4.1

Eligible goods and related services [Enter requirements for eligible goods and related services, if any]

ITB Number 8.1

The Bidders may seek clarifications through **EPADS v2.0** : Clarification Date: Friday, October 23, 2026

ITB Number 8.2

The Bidders may seek clarifications through **EPADS v2.0** : Clarification Date: Friday, October 23, 2026

ITB Number 8.3

The Bidders may seek clarifications through **EPADS v2.0** : Clarification Date: Friday, October 23, 2026

ITB Number 8.5

Pre-bid meeting will be/will not be held [Tick the appropriate] If yes write down the time, and date of the pre-Bid meeting:

[The meeting should take place not later than one weeks before the deadline for Bid submission.]

C. Preparation of Bids

BDS Clause Number 5

ITB Number 10.1

The Language of all correspondences and documents related to the Bids shall be in: **English**

List of documents required along with the bid:

1. i. Joint venture Agreement if any on non-judicial stamp paper for particular tender
- ii. No Deviation certificates from Commercial terms and technical specification
- iii. Firms Engineers and professionals Information
- iv. Income tax returns for last three years
- v. Audited Financial Reports of last three years
- vi. Confirm and valid Bank Credit line (latest) (if any) required to establish cash flow or financial resources.

BDS Clause Number 6

ITB Number 11.1

Documents required / not required with bid submission [enter list of documents] Samples required / not required with the bid [Enter the names and number of samples]

Items/Lots and their related documents:

See section items and Lots

BDS Clause Number 7

ITB Number 12.1

Items / Lots Specifications:

see section of items specifications.

BDS Clause Number 8

ITB Number 15.6

The price shall be **Fixed**.

BDS Clause Number 9

ITB Number 16.1

Currency of the Bids shall be : **PKR**

BDS Clause Number 10

ITB Number 17.1

The Bids/Bid Validity period shall be: **90 Days**

BDS Clause Number 11

ITB Number 18.1

The amount of Bid Security shall be as defined in Bid Security Section for items and lots given in **BDS 6**

Instrument of Bid Security shall be in the Name of : **Chief Engineer (Development) PMU IESCO Islamabad**

The Bid Security shall be in the form of: **Call at Deposit, Bank Guarantee, Demand Draft**

ITB Number 18.2

The address for submission of original bid security is [Insert the address for bid security submission]

D. Submission of Bids

BDS Clause Number 12

ITB Number 20.1

Bid shall be submitted online on EPADS v2.0 whereas hard copy of the bid security should be submitted to the following;

Office of Director (Procurement) Project Management Unit (PMU) Near 132kV Rawal Grid Station, Club Road, Kashmir Chowk Islamabad Capital Territory before bid submission deadline.

Bids that are not submitted on EPADS v2.0 shall be disqualified.

The deadline for Bids submission is: **Monday, October 26, 2026 11:00 AM**

Day : **Monday**

Date: **Monday, October 26, 2026**

Time : **11:30 AM**

E. Opening and Evaluation of Bids

BDS Clause Number 13

ITB Number 23.1

The Bids opening shall take place on **EPADS v2.0**.

Day : **Monday**

Date: **Monday, October 26, 2026**

Time : **11:30 AM**

ITB Number 29.2

The procuring agency shall consider the following:

lump sum bid basis; or

items wise; or

Lot wise (contracts),

ITB Number 30.1

BDS Clause Number 14

ITB Number 31.1

Domestic Preference [applicable / not applicable]

ITB Number 31.2

Selection technique adopted will be:

The Procuring Agency shall use any of the following evaluation techniques for determination of successful bid.

Least Cost Base Selection (LCBS)

Quality and Cost Based Selection (QCBS)

Quality Based Selection (QBS)

[Insert the Evaluation Technique]

Selection technique adopted will be: **Least Cost Based Selection (LCBS)**
see Evaluation Criteria

F. Review of Procurement Decisions

BDS Clause Number 15

ITB Number 41.1

Grievance against this procurement shall be submitted online on EPADS v2.0.

Arbitrator shall be appointed by mutual consent of the both parties.

ITB Number 42.2

The Address of PPRA Grievance Redressal Appellate Committee to submit a copy of grievance:

Grievance Redressal Appellate Committee,
Public Procurement Regulatory Authority
1st Floor, G-5/2, Islamabad, Pakistan
Tel: +92-51-9202254

Eligibility Criteria

Required Registration
NADRA CITIZENSHIP (CNIC/NICOP)
FBR (NTN)
FBR (GSTN)

Eligibility Criteria	Document
The amount of performance security (or guarantee), as a percentage of the Contract Price, shall be Ten (10%) percent of the Contract Price in favor of chief engineer (Development) IESCO from Schedule Bank of Pakistan having rating A+ in shape of Bank Guarantee. Contractor will provide performance Guarantee at time of acceptance of Notification of Award	Yes
Bid Declaration Form not applicable	No
Bid security must be submitted in an acceptable form in the amount fixed in PKR valid for 28 days beyond bid validity period in favor of Chief Engineer (Development), IESCO, Islamabad	Yes
The bidder shall include all applicable taxes, duties, levies and GST etc. as per PPRA EPADS v2.0 in the bid price. Any applicable tax or duty not included in the quoted price shall be deducted from the bidder's payments as per applicable Government rules and SOPs. No additional payment shall be made on this account. Moreover, any excuse of bidder for not adding the taxes amount in the bid price shall not be accepted.	Yes
Price schedule attached as annexure shall be considered for bid price being mandatory to be filled for responsiveness	Yes

Evaluation Criteria


Eligible bidder(s) with substantially responsive bid(s) offering **Least Cost Based Selection (LCBS)** shall be consider for the award of contract(s).

Least Cost Based Selection (LCBS)

Weightage

Technical Evaluation %	
100	
Technical Marks	100
Passing Marks	100
Technical Evaluation Criteria	
Bidder or its manufacturer or Joint Venture (JV) must have successfully completed at least two (02) contracts of similar complexity involving same or higher-rated material/equipment during the last Ten (10) years. The aggregate value of both contracts shall be equal to or greater thanRs. 5 M but none of the contract value should be less than 30% of aggregate value.(Rs. 1.5M) (Quantitative)(Doc Required)	30
Manufacturer shall demonstrate at least five years experience in designing and manufacturing of similar nature/complex involving same or higher rated equipment/material. Two (02) years satisfactory operation performance of same or high rated equipment (Quantitative)(Doc Required)	30
Manufacturer will indicate its manufacturing / production capacity which shall be double the total sum of orders already in hand, expected orders in pipe line and this order (if placed by the bidder) (Quantitative)(Doc Required)	10

Bidder's Net Worth for last year calculated as difference b/w total assets & total liabilities should be positive. however bidder's net worth shall be equal to or greater than 40% of Rs. 5M (2M) (Quantitative)(Doc Required)	10
Minimum average annual turnover of PKR calculated as total revenue of the Bidder over the last three Years shall be equal to or greater than Rs.7M (Quantitative)(Doc Required)	10
Specify proposed sources of financing, working capital and lines of credit available to meet the cash flow demands shall be equal to or greater than Rs.5M (Quantitative)(Doc Required)	10



Items/Lots

Lot Title : 1

Bid Security : 184999 PKR

Item	UNSPSC	Delivery Schedule	Quantity	Manufacturer / Dealer Authorization	Warranty
Procurement of Fan with motor for 40 MVA T/F,	Fan	Address: IESCO Regional Store New Wah Schedule: (120 Days (EXW Basis) for local / 210 Days (DDP Basis) for foreign) After signing of contract Quantity: 9/Qty	9 / Qty	Manufacturer Authorization form	730 Days
Fan with motor for 20/26 MVA T/F ,	Fan	Address: IESCO Regional Store New Wah Schedule: (120 Days (EXW Basis) for local / 210 Days (DDP Basis) for foreign) After signing of contract Quantity: 12/Qty	12 / Qty	Manufacturer Authorization form	730 Days
Fan with motor for 10/13 MVA T/F,	Fan	Address: IESCO Regional Store New Wah Schedule: (120 Days (EXW Basis) for local / 210 Days (DDP Basis) for foreign) After signing of contract Quantity: 14/Qty	14 / Qty	Manufacturer Authorization form	730 Days

Item	UNSPSC	Delivery Schedule	Quantity	Manufacturer / Dealer Authorization	Warranty
Fan with motor for 21/30 MVA T/F (132/66)	Fan	Address: IESCO Regional Store New Wah Schedule: (120 Days (EXW Basis) for local / 210 Days (DDP Basis) for foreign) After signing of contract Quantity: 3/Qty	3 / Qty	Manufacturer Authorization form	730 Days



Related Services of Goods:

No



Items/Lot Specification

Lot Title : 1

Item: Procurement of Fan with motor for 40 MVA T/F,

UNSPSC: Fan

Specifications / Requirements:

P:46:2022

Item: Fan with motor for 20/26 MVA T/F ,

UNSPSC: Fan

Specifications / Requirements:

P:46:2022

Item: Fan with motor for 10/13 MVA T/F,

UNSPSC: Fan

Specifications / Requirements:


P:46:2022

Item: Fan with motor for 21/30 MVA T/F (132/66)

UNSPSC: Fan

Specifications / Requirements:

P:46:2022



Price Schedule

For Individual Items

#	Item Title	Quantity	Unit Price (PKR)	Total Price (PKR)	Delivery Location	Delivery Period / Year	Country of Origin
1							
2							

For Lots

#	Lot Title	Total Lot Price (PKR)	Country of Origin
1	[Lot 1 Title]		





General Conditions of Contract

A. General

1. Definitions

1.1 Unless the context otherwise requires, the following terms whenever used in this Contract shall have the same meaning and shall be interpreted as indicated

- a. “Applicable Law” means the laws and any other instruments having the force of law in the Government’s Country, or in such other country as may be specified in the Special Conditions of the Contract (SC), as they may be issued and in force from time to time;
- b. The “Arbitrator” is the person appointed with mutual consent of both the parties, to resolve contractual disputes as provided for in the General Conditions of the Contract GCC Clause 35 hereunder.
- c. “Authority” means Public Procurement Regulatory Authority.
- d. The “Commencement Date” is the date when the Supplier shall commence execution of the contract as specified in the SCC.
- e. “Completion date” means the date of completion of the Contract by the Bidder as certified by the Procuring Agency.
- f. “Procuring Agency” means:-
 - a. any Ministry, Division, Department or any Office of the Government;
 - b. any authority, corporation, body or organization established by or under a Law or which is owned or controlled by the Government;
- g. “The Contract” means an agreement enforceable by law;
- h. “The Contract Price” means the price payable to the Bidder under the Contract for the full and proper performance of its contractual obligations;
- i. “Ancillary Services” means those services ancillary to the provision of Goods, such as transportation and insurance, and any other incidental services, such as installation, commissioning, provision of technical assistance, training, and other such obligations of the Bidder covered under the Contract;
- j. “GCC” means the General Conditions of Contract contained in this section;
- k. “SCC” means the Special Conditions of Contract by which the GCC may be amended or supplemented;
- l. “Day” means calendar day unless indicated otherwise.
- m. “Defective Goods” are those goods which are below standards, requirements or specifications stated by the Contract.
- n. “Delivery” means the transfer of the goods from the supplier equipment, machinery, and /or other materials which the Supplier is required to supply to the Procuring Agency under Contract.

o. "Effective Date" means the date on which this Contract comes into force and effect.

p. "Force Majeure" means an unforeseeable event which is beyond reasonable control of either Party and which makes a Party's performance of its obligations under the Contract impossible or so impractical as to be considered impossible under the circumstances.

For the purposes of this Contract, "Force Majeure" means an event which is beyond the reasonable control of a Party, is not foreseeable, is unavoidable, and its origin is not due to negligence or lack of care on the part of a Party, and which makes a Party's performance of its obligations hereunder impossible or so impractical as reasonably to be considered impossible in the circumstances. and includes, but is not limited to, war, riots, civil disorder, earthquake, fire, explosion, storm, flood, epidemics, or other adverse weather conditions, strikes, lockouts or other industrial action (except where such strikes, lockouts or other industrial action are within the power of the Party invoking Force Majeure to prevent), confiscation or any other action by Government agencies.

q. "The Bidder" means the individual or corporate body whose Bids to provide the Goods has been accepted by the Procuring Agency;

r. "The Project Site," where applicable, means the place or places named in Bids Data Sheet and technical Specifications;

s. "Government" means the Government of Pakistan;

t. "Subcontractor" means any entity to which the Bidder subcontracts any part of the Goods.

u. "The Services" means the work to be performed by the Bidder pursuant to this Contract and as prescribed in the Specifications and Schedule of Activities included in the Bidder's Bids;

v. "Party" means the Procuring Agency or the Bidder, as the case may be, and "Parties" means both of them;

w. "Foreign Currency" means any currency other than the currency of the country of the Procuring Agency;

x. "Completion Date" means the date of completion of the contract by the Bidder as certified by the Procuring Agency;

y. "In Writing" means communicated in written form with proof of receipt;

z. "Local Currency" means the currency of Pakistan;

a. "Origin" means the place where the Goods were mined, grown, or produced or from which the Services are supplied. Goods are produced when, through manufacturing, processing, or substantial and major assembly of components, a commercially recognized new produce results that is substantially different in basic characteristics or in purpose or utility from its components.

b. "Specification" means the Specification of the Goods and performance of incidental services in accordance with the relevant standards included in the Contract and any modification or addition made or approved by the Procuring Agency.

c. "Procuring Agency" means: -

any Ministry, Division, Department or any Office of the Federal Government;

any authority, corporation, body or organization established by or under a Federal Law or which is owned or controlled by the Federal Government;

2. Application and Interpretation

2.1 These General Conditions shall apply to the extent that they are not superseded by provisions of other parts of the Contract.

2.2 In interpreting these Conditions of Contract headings and marginal notes are used for convenience only and shall not affect their interpretations unless specifically stated; references to singular include the plural and vice versa; and masculine include the feminine. Words have their ordinary meaning under the language of the Contract unless specifically defined.

3. Applicable Law

3.1 The contract shall be governed and interpreted in accordance with the laws of Pakistan, unless otherwise specified in SCC.

4. Governing Language

4.1 The Contract as well as all correspondence and documents relating to the Contract exchanged between the Bidder and the Procuring Agency, shall be written in the **English language** unless otherwise stated in the **SCC**. Supporting documents and printed literature that are part of the Contract may be in another language provided these are accompanied by an accurate translation of the relevant passages in English, in which case, for purposes of interpretation of the Contract, this translation shall govern.

5. Notices

5.1 Any notice, request, or consent made pursuant to this Contract shall be in writing and shall be deemed to have been made when delivered in person to an authorized representative of the Party to whom the communication is addressed, or when sent by registered mail, telex, telegram, or facsimile to such Party at the address specified in the **SCC**.

6. Standard

6.1 The Goods supplied under this Contract shall conform to the standards mentioned in the Technical Specifications, and, when no applicable standard is mentioned, the American Standards (such as ACI, IEEE, ASME, etc.) or the Pakistani standards such as PSQCA Such standards shall be the latest issued by the concerned institution.

7. Delivery/Location

7.1 The Goods shall be delivered to such locations as the Procuring Agency may approve and as specified in SCC.

8. Authorized Representatives / Authority of Member in charge

8.1 Any action required or permitted to be taken, and any document required or permitted to be executed, under this Contract by the Procuring Agency or the Bidder may be taken or executed by the officials specified in the **SCC**.

B. Commencement, Completion, Modification, and Termination of Contract

8. Effectiveness of Contract

8.1 This Contract shall come into effect on the date the Contract is signed by both parties and such other later date as may be stated in the SCC.

9. Commencement of the Contract

9.1 The Bidder shall confirm availability of Key Experts and begin carrying out the Services not later than the number of days after the Effective Date specified in the SCC.

10. Program

10.1 Before commencement of the Contract, the Bidder shall submit to the Procuring Agency for approval a Program showing the general methods, arrangements, order and timing for all activities. The Services shall be carried out in accordance with the approved Program as updated.

11. Starting Date/Expiration Date

11.1 The Bidder shall start carrying out the Services Five (05) days after the date the Contract becomes effective, or at such other date as may be specified in the SCC.

11.2 Unless terminated earlier pursuant to Clause **GCC 16** hereof, this Contract shall expire at the end of such time period after the Effective Date as specified in the SCC.

12. Entire Agreement

12.1 This Contract contains all covenants, stipulations and provisions agreed by the Parties. No agent or representative of either Party has authority to make, and the Parties shall not be bound by or be liable for, any statement, representation, promise or agreement not set forth herein.

13. Modification

13.1 Any modification or variation of the terms and conditions of this Contract, including any modification or variation of the scope, may only be made by written agreement between the Parties. However, each Party shall give due consideration to any Bids for modification or variation made by the other Party.

13.2 In cases of any modifications or variations, the prior written consent of the Procuring Agency is required.

14. Force Majeure

14.1 Definition

For the purposes of this Contract, “Force Majeure” means an event which is beyond the reasonable control of a Party and which makes a Party’s performance of its obligations under the Contract impossible or so impractical as to be considered impossible under the circumstances.

14.2 No Breach of Contract

The failure of a Party to fulfill any of its obligations under the contract shall not be considered to be a breach of, or default under, this Contract in so far as such inability arises from an event of Force Majeure, provided that the Party affected by such an event (a) has taken all reasonable precautions, due care and reasonable alternative measures in order to carry out the terms and conditions of this Contract, and (b) has informed the other Party as soon as possible about the occurrence of such an event.

14.3 Extension of Time

Any period within which a Party shall, pursuant to this Contract, complete any action or task, shall be extended for a period equal to the time during which such Party was unable to perform such action as a result of Force Majeure. However, such period shall not exceed sixty (60) days.

14.4 Payments

During the period of their inability to perform the Services as a result of an event of Force Majeure, the Bidder shall be entitled to continue to be paid under the terms of this Contract, as well as to be reimbursed for additional costs reasonably and necessarily incurred by them during such period for the purposes of the Services and in reactivating the Service after the end of such period.

15. Termination

15.1 By the Procuring Agency

The Procuring Agency may terminate this Contract in case of the occurrence of any of the events specified in paragraphs (a) through (e) of this Clause. In such an occurrence the Procuring Agency shall give at least thirty (30) calendar days' written notice of termination to the Bidder in case of the events referred to in (a) through (d); at least sixty (60) calendar days' written notice in case of the event referred to in (e);

- a. If the Bidder fails to remedy a failure in the performance of its obligations hereunder, as specified in a notice of suspension;
- b. If the Bidder becomes (or, if the Bidder consists of more than one entity, if any of its members becomes) insolvent or bankrupt or enter into any agreements with their creditors for relief of debt or take advantage of any law for the benefit of debtors or go into liquidation or receivership whether compulsory or voluntary;
- c. If the Bidder fails to comply with any final decision reached as a result of arbitration proceedings;
- d. If, as the result of Force Majeure, the Bidder is unable to perform a material portion of the Services for a period of not less than sixty (60) calendar days;
- e. If the Procuring Agency, in its sole discretion and for any reason whatsoever, decides to terminate this Contract;

15.2 By the Bidder

The Bidder may terminate this Contract, by not less than thirty (30) calendar days' written notice to the Procuring Agency, in case of the occurrence of any of the events specified in paragraphs (a) through (d) of this Clause.

- a. If the Procuring Agency fails to pay any money due to the Bidder pursuant to this Contract and not subject to dispute within forty-five (45) calendar days after receiving written notice from the Bidder that such payment is overdue.
- b. If, as the result of Force Majeure, the Bidder is unable to perform a material portion of the Services for a period of not less than sixty (60) calendar days.
- c. If the Procuring Agency fails to comply with any final decision reached as a result of arbitration.
- d. If the Procuring Agency is in material breach of its obligations pursuant to this Contract and has not remedied the same within forty-five (45) days (or such longer period as the Bidder may have subsequently approved in writing) following the receipt by the Procuring Agency of the Bidder's notice specifying such breach.

C. Obligations of the Bidder

16. General

16.1 Standard of Performance

1. The Bidder shall deliver the product and carry out the Services with all due diligence, efficiency and economy, in accordance with generally accepted professional standards and practices, and shall observe sound management practices, and employ appropriate technology and safe and effective equipment, machinery, materials and methods. The Bidder shall always act, in respect of any matter relating to this Contract or to the Services, as a faithful adviser to the Procuring Agency, and shall at all times support and safeguard the Procuring Agency's legitimate interests in any dealings with the third parties.

16.2 Law Applicable to Goods

The Bidder shall deliver the goods in accordance with the Contract and in accordance with the Law of Pakistan and shall take all practicable steps to ensure that any of its Experts and Sub-Bidders, comply with the Applicable Law.

17. Conflict of Interests

17.1 Bidder Not to Benefit from Commissions and Discounts.

The remuneration of the Bidder shall constitute the Bidder's sole remuneration in connection with this Contract or the Services, and the Bidder shall not accept for their own benefit any trade commission, discount, or similar payment in connection with activities pursuant to this Contract or to the Services or in the discharge of their obligations under the Contract, and the Bidder shall use their best efforts to ensure that the Personnel, any Subcontractors, and agents of either of them similarly shall not receive any such additional remuneration.

17.2 Bidder and Affiliates Not to be Otherwise Interested in Project

The Bidder agree that, during the term of this Contract and after its termination, the Bidder and its affiliates, as well as any Subcontractor and any of its affiliates, shall be disqualified from providing Goods for any project resulting from or closely related to the Services.

17.3 Prohibition of Conflicting Activities

Neither the Bidder nor its Subcontractors nor the Personnel shall engage, either directly or indirectly, in any of the following activities:

- a. during the term of this Contract, any business or professional activities in the Government's country which would conflict with the activities assigned to them under this Contract;
- b. during the term of this Contract, neither the Bidder nor their Subcontractors shall hire public employees in active duty or on any type of leave, to perform any activity under this Contract;

18. Confidentiality

18.1 Except with the prior written consent of the Procuring Agency, the Bidder and the Experts shall not at any time communicate to any person or entity any confidential information acquired in the course of the contract.

19. Insurance to be Taken Out by the Bidder

19.1 The Bidder(a) shall take out and maintain, and shall cause any Subcontractors to take out and maintain, at its (or the Subcontractors', as the case may be) own cost but on terms and conditions approved by the Procuring Agency, insurance against the risks, loss or damage, and for the coverage, as shall be specified in the SCC; and (b) at the Procuring Agency's request, shall provide evidence to the Procuring Agency showing

that such insurance has been taken out and maintained and that the current premiums have been paid.

20. Bidder's Actions Requiring Procuring Agency's Prior Approval

20.1 The Bidder shall obtain the Procuring Agency's prior approval in writing before taking any of the following actions:

- (a) appointing such members of the Personnel not provided by the Bidder;
- (b) changing the Program of activities; and
- (c) any other action that may be specified in the SCC.

21. Reporting Obligations

21.1 The Bidder shall submit to the Procuring Agency the reports and documents in the numbers, and within the periods as prescribed by the Procuring Agency.

22. Liquidated Damages

22.1 If the Supplier fails to deliver any or all of the Goods or to perform the Services within the period(s) specified in the Contract, the Procuring Agency shall, without prejudice to its other remedies under the Contract, deduct from the Contract Price, as liquidated damages, a sum equivalent to the percentage specified in **SCC** of the delivered price of the delayed Goods or unperformed Services for each week or part thereof of delay until actual delivery or performance, up to a maximum deduction of the performance security (or guarantee) specified in **SCC**. Once the said maximum is reached, the Procuring Agency may consider termination of the Contract pursuant to **GCC Clause 16**.

22.2 Correction for Over-payment

If the Intended Completion Date is extended after liquidated damages have been paid, the Procuring Agency shall correct any overpayment of liquidated damages by the Bidder by adjusting the next payment certificate. The Bidder shall be paid interest on the overpayment, calculated from the date of payment to the date of repayment, at the rates specified in SCC.

22.3 Lack of performance penalty

If the Bidder has not corrected a Defect within the time specified in the Procuring Agency's notice, a penalty for Lack of performance will be paid by the Bidder. The amount to be paid will be calculated as a percentage of the cost of having the Defect corrected, assessed as specified in the SCC.

23. Performance Guarantee

23.1 The Performance Security (or Guarantee) shall be provided to the Procuring Agency no later than the date specified in the Letter of Acceptance and shall be issued in an amount and form acceptable to the Procuring Agency as specified in SCC, and denominated in the types and proportions of the currencies in which the Contract Price is payable as specified in the SCC.

23.2 Within Seven (07) days from the issuance of acceptance letter from the Procuring Agency, the successful Bidder shall furnish the Performance Guarantee in shape of ----- at the discretion of the PA in the amount **specified in SCC**. In case the amount of Bids security is equal or greater than

23.3 The proceeds of the Performance Guarantee shall be payable to the Procuring agency as compensation for any loss resulting from the Supplier's failure to complete its obligations under the Contract.

23.4 The Performance Guarantee shall be denominated in the currency of the Contract, or in a freely convertible currency acceptable to the Procuring agency and shall be in the acceptable form as specified in SCC.

23.5 The Performance Guarantee will be discharged by the Procuring agency and returned to the Supplier not later than thirty (30) days following the date of completion of the Supplier's performance obligations under the Contract, including any warranty obligations, unless otherwise **specified in SCC**.

23.6 The bid security of the successful bidder shall not be substituted with the Performance Guarantee.

24. Fraud and Corruption

24.1 The Procuring Agency requires the Supplier to disclose any commissions or fees that may have been paid or are to be paid to agents or any other party with respect to the Bidding process or execution of the Contract. The information disclosed must include at least the name and address of the agent or other party, the amount and currency, and the purpose of the commission, gratuity or fee.

25. Sustainable Procurement

25.1 The Bidder shall conform to the sustainable procurement contractual provisions, if and as specified in the SCC.

D. Bidder's Personnel

26. Description of Personnel

26.1 The titles, agreed job descriptions, minimum qualifications, and estimated periods of engagement in the carrying out of the Services of the Bidder's Key Personnel. The Key Personnel listed by title as well as by name are hereby approved by the Procuring Agency.

27. Removal and/or Replacement of Personnel

27.1 Except as the Procuring Agency may otherwise agree, no changes shall be made in the Key Personnel. If, for any reason beyond the reasonable control of the Bidder, it becomes necessary to replace any of the Key Personnel, the Bidder shall provide as a replacement a person of equivalent or better qualifications.

27.2 If the Procuring Agency finds that any of the Personnel have (i) committed serious misconduct or have been charged with having committed a criminal action, or (ii) have reasonable cause to be dissatisfied with the performance of any of the Personnel, then the Bidder shall, at the Procuring Agency's written request specifying the grounds thereof, provide as a replacement a person with qualifications and experience acceptable to the Procuring Agency.

27.3 The Bidder shall have no claim for additional costs arising out of or incidental to any removal and/or replacement of Personnel.

E. Obligations of the Procuring Agency

28. Assistance and Exemptions

28.1 The Procuring Agency shall use its best efforts to ensure that the Government shall provide the Bidder such assistance and exemptions as specified in the SCC.

29. Change in the Applicable Law

29.1 If, after the date of this Contract, there is any change in the Applicable Law with respect to taxes and duties which increases or decreases the cost of the related Services rendered by the Bidder, then the remuneration and reimbursable expenses otherwise payable to the Bidder under this Contract shall be increased or decreased accordingly by agreement between the Parties, and corresponding adjustments shall be made to the amounts referred in the SCC.

30. Services and Facilities

30.1 The Procuring Agency shall make available to the Bidder and the Experts, for the purposes of the Services and free of any charge, the services, facilities and property described , at the times and in the manner specified in the SCC or terms of reference.

30.2 In case that such services, facilities and property shall not be made available to the Bidder, the Parties shall agree on (i) any time extension that it may be appropriate to grant to the Bidder for the performance of the Services, (ii) the manner in which the Bidder shall procure any such services, facilities and property from other sources, and (iii) the additional payments, if any, to be made to the Bidder as a result thereof.

F. Payments to the Bidder

31. Contract Price

31.1 The price payable shall be in Pakistani Rupees unless otherwise specified in the SCC. Prices charged by the Supplier for Goods delivered under the Contract shall not vary from the prices quoted by the Supplier in its Bid.

32. Terms and Conditions of Payment

32.1 Payments will be made to the Bidder according to the payment schedule stated in the SCC and as per actual invoice submitted by the Bidder.

32.2 Unless otherwise stated in the SCC, the advance payment shall be made against the provision by the Bidder of a bank guarantee for the same amount, and shall be valid for the period stated in the SCC. Any other payment shall be made after the conditions listed in the SCC for such payment have been met, and the Bidder have submitted an invoice to the Procuring Agency specifying the amount due.

33. Currency of Payment

33.1 Any payment under this Contract shall be made in the currency(ies) specified in the SCC.

G. Quality Control

34. Identifying Defects

34.1 The principle and modalities of Inspection of the Goods by the Procuring Agency shall be as indicated in the SCC. The Procuring Agency shall check the Bidder's performance and notify him of any Defects that are found. Such checking shall not affect the Bidder's responsibilities. The Procuring Agency may instruct the Bidder to search for a Defect and to uncover and test any service that the Procuring Agency considers may have a Defect. Defect Liability Period is as defined in the SCC.

35. Correction of Defects, and

Lack of Performance Penalty

35.1 The Procuring Agency shall give notice to the Bidder of any Defects before the end of the Contract. The Defects liability period shall be extended for as long as Defects remain to be corrected.

35.2 Every time notice a Defect is given, the Bidder shall correct the notified Defect within the length of time specified by the Procuring Agency's notice.

35.3 If the Bidder has not corrected a Defect within the time specified in the Procuring Agency's notice, the Procuring Agency will assess the cost of having the Defect corrected, the Bidder will pay this amount, and a Penalty for Lack of Performance.

36. Taxes and Duties

36.1 A Supplier shall be entirely responsible for all taxes, duties, fees, etc., incurred until delivery of the contracted Goods to the Procuring Agency.

H. Settlement of Disputes

37. Alternate Dispute Resolution

37.1 Upon the commencement of the Procurement Contract, any disputes arising between the contracting parties shall be resolved in accordance with Rule 66 of the Public Procurement Rules, 2026.

37.2 The procuring agency may refer the matter to the Chief Justice Islamabad High Court or Managing Director PPRA or the Secretary Ministry of Law & Justice for appointment of Arbitrator.

37.3 The fee for the Arbitrator shall be specified in Pak Rupees as determined by the appointing authority which shall be borne and shared equally by the contracting parties.

38. Change Orders

The Procuring Agency may at any time, by a written order given to the Supplier, make changes within the general scope of the Contract in any one or more of the following:

- a) Drawings, designs, or specifications, where Goods to be furnished under the Contract are to be specifically manufactured for the Procuring Agency;
- b) The method of shipment or packing;
- c) The place of delivery; and/or
- d) The Services to be provided by the Supplier.

39. Contract Amendments

39.1 Subject to GCC Clause 32, no variation in or modification of the terms of the Contract shall be made except by written amendment signed by the parties.

40. Sub-Contracts

40.1 The Supplier shall consult the Procuring Agency in the event of subcontracting under this contract if not already specified in the Bid. Subcontracting shall not alter the Supplier's obligations.



Special Conditions of Contract

SECTION VIII. SPECIAL CONDITIONS OF CONTRACT

The following Special Conditions of Contract shall supplement the General Conditions of Contract. Whenever there is a conflict, the provisions herein shall prevail over those in the Conditions of Contract. The corresponding clause number of the GCC is indicated in parentheses.

Number of GC Clause

Amendments of, and Supplements to, Clauses in the General Conditions of Contract

Number of GC Clause 1

Definitions

The Procuring Agency is: **IESCO-PMU (Islamabad Electric Supply company (IESCO)), Director procurement Office of Director (Procurement) Project Management Unit (PMU) Near 132kV Rawal Grid Station, Club Road, Kashmir Chowk Islamabad Capital Territory**

The Supplier is:

The title of the subject procurement is: **NCB-302 Procurement of Fan with motor for 40 MVA T/F, Fan with motor for 20/26 MVA T/F , Fan with motor for 10/13 MVA T/F, Fan with motor for 21/30 MVA T/F (132/66)(Estimated cost amounting to Rs. 6,166,623) including GST & all other taxes**

Number of GC Clause 3

Applicable/Governing Law:

The Contract shall be interpreted in accordance with the laws of Islamic Republic of Pakistan

Number of GC Clause 4

Language:

The language of the Contract, all correspondence and communications to be given, and all other documentation to be prepared and supplied under the Contract shall be in **English**.

Number of GC Clause 5

Notices:

The addresses for the notices are:

The Authority:

**IESCO-PMU (Islamabad Electric Supply company (IESCO)), Director procurement Office of Director (Procurement) Project Management Unit (PMU) Near 132kV Rawal Grid Station, Club Road, Kashmir Chowk Islamabad Capital Territory
+92-319-599-2205
Iescopmu@iesco.com.pk**

Contractor/ Bidder:

[Name, address and telephone number].

The Contractor/ Bidder's Representative(s)

[Name, address, telephone number and e-mail address]

Number of GC Clause 7.1

The Authorized Representatives are:

For the Procuring Agency:

**IESCO-PMU (Islamabad Electric Supply company (IESCO)), Director procurement
Office of Director (Procurement) Project Management Unit (PMU) Near 132kV Rawal Grid Station,
Club Road, Kashmir Chowk Islamabad Capital Territory
+92-319-599-2205
Iescopmu@iesco.com.pk**

For the Bidder:

Name:

Designation:

Address:

Number of GC Clause 8

Effectiveness of the contract

Number of GC Clause 9

Commencement of Contract:

Number of GC Clause 11.2

Expiration of Contract:

Number of GC Clause 15

Termination

In the event of termination of the contract due to any reason as already defined in the General Conditions of Contract, the Bidder shall be responsible for providing to the Authority the Goods till the time of alternate arrangements.

Number of GC Clause 17

Conflict of Interest:

The Procuring Agency reserves the right to determine on a case-by-case basis whether the Bidder should be disqualified from providing goods or services due to a conflict of a nature described in Clause GCC 17.

Number of GC Clause 22

Liquidated Damages

If the Bidder fails to provide services as required under the contract or in case of any data loss/data breach or any incident compromising the data security or other such failures related to any services, the Bidder shall pay to the Procuring Agency as Liquidated Damages at a rate of **0.05% to 10.00%** of the Contract value, in accordance with the extent of performance failure & the cost of investigating such incidents as judged by the Authority.

Number of GC Clause 23

Performance Guarantee:

Instrument of Performance Guarantee shall be in the Name of : **Chief Engineer (Development) IESCO from any Scheduled Bank of Pakistan having rating A+.**

The amount of performance guarantee shall be **10.00%** of the contract price in acceptable form of **Bank Guarantee**

Number of GC Clause 32

Payment terms:

Payment will be made to the Bidder against the procured Goods and services according to the actual invoice or running bills submitted by the Bidder against the services provided within the time given in the conditions of the contract.

Number of GC Clause 33

Currency of Payment:

All the payment to be released to the contractor/Bidder shall be in Pakistani Rupees.

Number of GC Clause 34

Identifying Defects:

The Authority reserves the right at any time to inspect the premises of the provider to inspect the goods and monitor the goods being provided.

Inspections & Tests Requirements

Quality and quantity inspection shall be carried out prior to shipment of Goods by the manufacturer(s) at the supplier's own expense and responsibility in terms of the items specified in the specifications. The supplier shall submit the inspection certificate issued by him which should be attached with the certificate(s) of the manufacturer(s) to the Procuring Agency in order to ensure that the goods are manufactured in compliance with the contract.

Factory Acceptance Tests (FAT) shall be carried out at the premises of Manufacturer jointly witnessed with IESCO Engineers. The Contractor shall keep the Engineer informed of the progress of manufacture and notify the Engineer approximately six (6) weeks in advance, in writing as to when the Goods or any part thereof will be ready for inspection and for shipping to wharf at the port of entry/disembarkation

Following the receipt of such notice, the Engineer shall nominate to arrange pre-shipment inspection of the Goods or any part thereof including the packing at the Contractor's premises and will issue a pre-shipment

Inspection Report or waiver to pre-shipment inspection. The Goods or any part thereof shall be shipped or delivered only upon issuance of pre-shipment inspection report. The Goods/material shall be subject to the type, sample and routine tests as described in the Specifications.

The contractor shall provide free of charge all such assistance, instruments, machines, labor and materials as are normally required for carrying out such tests. In case a part or whole of the equipment being supplied at the project by the contractor is from within the country (Pakistan) or outside country, the cost of performing as well as witnessing any test by the Inspectors during pre-shipment local inspection shall be borne by the contractor if such tests are clearly intended by or provided

for in the specifications or as agreed between IESCO and the contractor. Two (2) number authorized Engineers from IESCO will carry out inspection of the material at manufacturer's works. A notice of at least six (6) weeks advance, in writing shall have to be given to the IESCO by the Supplier when the stores against the order are ready for inspection. Manufacturer will provide facilities for tests as per tender specifications free of cost.

All reasonable facilities as provided in the specifications or followed by Trade & Industry in general shall have to be offered to the Inspecting officers, by the Supplier at their expense for carrying out Testing and Inspection. If Goods are being manufactured on other premises, the Contractor shall obtain permission of the Engineer/IESCO to carry out such inspection, examinations and testing at those premises.

For such purpose, the Supplier shall provide free access at all times during manufacture, assembly and testing to the premises in which the work is being carried out. The contractor will cover all the expenses in context of witnessing of the tests by the Inspectors including 1st class traveling (by air or by road depending on the distance from Islamabad Pakistan to the place or places of inspections), boarding & lodging in any A class accommodation, local transportation and daily allowance

As per prevailing rules per inspector to meet other expenses. Abroad Testing witnessing @ 250 USD and 15% incidental charges per inspector. Local Testing Witnessing as per prevailing rules and regulation of TA/DA. The supplier shall submit the inspection certificate issued by him which should be attached with the certificate(s) of the manufacturer(s) to the Procuring Agency in order to ensure that the goods are manufactured in compliance with the contract

In case the Goods fail to withstand any test, the cost of repeating such test and the cost of witnessing such test by the authorized Engineer/ Inspectors of IESCO shall be borne by the contractor and the equipment released or modified to the satisfaction of the Engineer without any additional cost to the IESCO

Any inspection and /or witnessing of tests or the waiving of such tests and /or surveillance by the IESCO/Engineer or their two Nos. representatives / Inspectors shall not relieve the Supplier of its obligations and responsibilities under the Contract regardless of any approval or consent given by the IESCO/Engineer or their two Nos. Representatives Inspector. Two copies of all the Inspection and Tests Reports and certificates including that for-quality control shall be supplied to IESCO

The IESCO/Consultant or his two Nos. representatives/Inspector shall countersign the reports and certificates of such tests as have been witnessed. The Purchaser may reject any Goods or any part thereof that fail to pass any test and/or inspection or do not conform to the specifications. The Supplier shall either rectify or replace such rejected Goods or parts thereof or make alterations necessary to meet the specifications at no cost to the Purchaser, and shall repeat the test and/or inspection,

at no cost to the Purchaser, upon giving a notice. The Purchaser may require the Supplier to carry out any test and /or inspection not required by the Contract but deemed necessary to verify that the characteristics and performance of the Goods comply with the technical specifications, codes and standards under the Contract, the costs and expenses incurred in the carrying out of such test and/or inspection shall be borne by the Contractor / Supplier.

Further, if such test and /or inspection impede the progress of manufacturing and/or the Supplier's performance of its other obligations under the Contract, due allowance will be made in respect of the Delivery Dates and Completion Dates and the other obligations so affected. The Supplier shall obtain from any relevant third party or manufacturer any necessary permission or consent to enable the Purchaser or its designated representative to attend the test and/or inspection.

In case, due to any Pandemic/ urgency of material etc. where witnessing of factory acceptance testing/ foreign Inspection (if involved) may not be possible considering travels restrictions, requirement of material then third-party inspection will be opted through signing of Addendum after approval of Competent Authority. In such cases contractor will provide 03-year additional extended Warranty in lieu of waiver of physical inspection.

The third-party inspection will be carried out after obtaining approval of Credible Testing laboratory from IESCO conducted by third party inspector witnessed by two No. IESCO Engineers on line through Zoom/ skype. The charges of testing/ witnessing of type tests will be borne by Supplier. The material will be delivered after approval of inspection certificate & test reports of approved inspectors from IESCO

Delivery & Documents

For Goods supplied from abroad: (Outside purchaser's country on DDP) Upon shipment, the Supplier shall notify the Procuring Agency and the Insurance Company by cable the full details of the shipment, including Contract number, description of Goods, quantity, the vessel, the bill of lading number and date, port of loading, date of shipment, port of discharge, etc

The Supplier shall mail the documents (but not limited to the following papers) to the Procuring Agency, with a copy to the Insurance Company: (i) One original plus four copies of the Supplier's invoice showing Goods' description, quantity, unit price, and total amount; (ii) original and four copies of the negotiable, clean, on-board bill of lading marked "freight prepaid" and four copies of nonnegotiable bill of lading

(iii) One original plus four copies of the packing list identifying contents of each package, (iv.) Insurance Certificate, (v.) Manufacturers or Supplier's warranty certificate, (vi.) inspection certificate, issued by the nominated inspection agency, and the Supplier's factory inspection report; and

(vii.) Certificate of country of origin issued by the chamber of commerce and industry or equivalent authority in the country of origin in duplicate. The above documents shall be received by the Procuring Agency at least one week before arrival of the Goods at the port or place of arrival and, if not received, the Supplier will be responsible for any consequent expenses

For Goods from within Pakistan: (within purchaser's country on EXW) Upon delivery of the Goods to the transporter, the Supplier shall notify the Procuring Agency and mail the following but not limited documents to the Procuring Agency: (i.) one original plus four copies of the Supplier's invoice showing Goods' description, quantity, unit price, and total amount;

(ii.) delivery note, railway receipt, or truck receipt; (iii.) Manufacturers or Supplier's warranty certificate (iv.) inspection certificate issued by the nominated inspection agency, and the Supplier's factory inspection report; and

(v.) Certificate of country of origin issued by Pakistan Chamber of Commerce and Industry or equivalent authority in the country of origin in duplicate. The above documents shall be received by the Procuring Agency before arrival of the Goods and, if not received, the Supplier will be responsible for any consequent expenses

Number of GC Clause 37

Following is the guidance for Dispute Resolution

(a) For Contracts to be entered with foreign Contractor/ Service Provider:

All disputes arising in connection with the present Contract shall be finally settled under the Rules of Conciliation and Arbitration of the International Chamber of Commerce by one or more arbitrators appointed in accordance with said Rules.

(b) For Contracts to be entered with nationals of Pakistan:

i. If any dispute of any kind whatsoever shall arise between the Authority and the Bidder in connection with or arising out of the Contract, including without prejudice to the generality of foregoing, any question regarding its existence, validity, termination and the execution of the Contract – whether during developing phase or after their completion and whether before or after the termination, abandonment or breach of the Contract – the parties shall seek to resolve any such dispute or difference by mutual diligent negotiations in good faith within 14 (fourteen) days following a notice sent by one Party to the other Party in this regard.

ii. At future of negotiation the dispute shall be resolved through mediation and mediator shall be appointed with the mutual consent of the both parties.

iii. At the event of failure of mediation to resolve the dispute relating to this contract such dispute shall finally be resolved through binding Arbitration in accordance with GCC clause 38.

iv. The cost of the mediation and arbitration shall be shared by the parties in equal proportion however the both parties shall bear their own costs and lawyer's fees regarding their own participation in the mediation and arbitration. However, the Arbitrator may make an award of costs upon the conclusion of the arbitration making any party to the dispute liable to pay the costs of another party to the dispute.

v. Arbitration proceedings as mentioned in the above clause regarding resolution of disputes may be commenced prior to, during or after completion of the contract.

Notwithstanding any reference to the arbitration herein, the parties shall continue to perform their respective obligations under the Contract unless they otherwise agree that the Authority shall pay the Bidder any monies due to the Bidder.

Rules of procedure for arbitration proceedings:

Any dispute between the Authority and a Bidder who is a national of the Islamic Republic of Pakistan arising in connection with the present Contract shall be referred to adjudication or arbitration in accordance with the laws of the Islamic Republic of Pakistan including Arbitration Act 1940, however above provision shall prevail in referring the case to the Arbitrator.

Place of Arbitration and Award:

The arbitration shall be conducted in English language and place of arbitration shall be at Islamabad. The award of the arbitrator shall be final and shall be binding on the parties.



Bid Securing Declaration

Form 9: Bid Securing Declaration

Date: [insert date (as day, month and year)]

Bid No.: **P111373**

Alternative No.: [insert identification No if this is a Bid for an alternative]

To: **IESCO-PMU (Islamabad Electric Supply company (IESCO)), Director procurement Office of Director (Procurement) Project Management Unit (PMU) Near 132kV Rawal Grid Station, Club Road, Kashmir Chowk Islamabad Capital Territory**

We, the undersigned, declare that:

We understand that, according to your conditions, Bids must be supported by a Bid Securing Declaration.

We accept that we will be blacklisted and henceforth cross debarred for participating in respective category of public procurement proceedings for a period of (not more than) six months, if fail to abide with a bid securing declaration, however without indulging in corrupt and fraudulent practices, if we are in breach of our obligation(s) under the Bid conditions, because we:

1. have withdrawn or modified our Bid during the period of Bid Validity specified in the Form of Bid;
2. Disagreement to arithmetical correction made to the Bid price; or
3. having been notified of the acceptance of our Bid by the Procuring Agency during the period of Bid Validity, (i) failure to sign the contract if required by Procuring Agency to do so or (ii) fail or refuse to furnish the Performance Security or to comply with any other condition precedent to signing the contract specified in the Bidding Documents.

We understand this Bid Securing Declaration shall expire if we are not the successful

Bidder, upon the earlier of (i) our receipt of your notification to us of the name of the successful Bidder; or (ii) twenty-eight (28) days after the expiration of our Bid.

Signed: [insert signature of person whose name and capacity are shown] In the capacity of [insert legal capacity of person signing the Bid Securing Declaration]

Name: [insert complete name of person signing the Bid Securing Declaration]

Duly authorized to sign the Bid for and on behalf of: [insert complete name of Bidder]

Dated on day of , [insert date of signing]
Corporate Seal (where appropriate)



Contract Form

SECTION IX: CONTRACT FORMS

THIS AGREEMENT made the ____ day of _____ 20____ between **IESCO-PMU (Islamabad Electric Supply company (IESCO)), Director procurement Office of Director (Procurement) Project Management Unit (PMU) Near 132kV Rawal Grid Station, Club Road, Kashmir Chowk Islamabad Capital Territory**

(hereinafter called “the Procuring Agency”) of the one part and [name of Bidder] of [city and country of Bidder] (hereinafter called “the Bidder”) of the other part:

WHEREAS the Procuring Agency invited Bids for provision of goods, viz., **NCB-302 Procurement of Fan with motor for 40 MVA T/F, Fan with motor for 20/26 MVA T/F , Fan with motor for 10/13 MVA T/F, Fan with motor for 21/30 MVA T/F (132/66)(Estimated cost amounting to Rs. 6,166,623) including GST & all other taxes (P111373)** and has accepted a Bids by the Bidder for the provision of Goods in the sum of [contract price in words and figures] (hereinafter called “the Contract Price”).

NOW THIS CONTRACT WITNESSETH AS FOLLOWS:

1. In this Contract words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract referred to.

2. The following documents shall be deemed to form and be read and construed as part of this Contract, In the event of any ambiguity or conflict between the Contract Documents listed below, the order of precedence shall be the order in which the Contract Documents are listed below:-

1. This form of Contract;
2. the Form of Bids and the Price Schedule submitted by the Bidder;
3. the Schedule of Requirements;
4. the Technical Specifications;
5. the Special Conditions of Contract;
6. the General Conditions of the Contract;
7. the Procuring Agency’s Letter of Acceptance; and
8. [add here: any other documents]

3. In consideration of the payments to be made by the Procuring Agency to the Bidder as hereinafter mentioned, the Bidder hereby covenants with the Procuring Agency to provide the Goods related services and to remedy defects therein in conformity in all respects with the provisions of the Contract.

4. The Procuring Agency hereby covenants to pay the Bidder in consideration of the provision of Goods and the remedying of defects therein, the Contract Price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.

IN WITNESS whereof the parties hereto have caused this Contract to be executed in accordance with their respective laws the day and year first above written.


Signed, sealed, delivered by _____ the _____ (for the Procuring Agency)

Witness to the signatures of the Procuring Agency:

.....

Signed, sealed, delivered by _____ the _____ (for the Procuring Agency)

Witness to the signatures of the Bidder:





Integrity Pact

Integrity Pact

DECLARATION OF FEES, COMMISSION AND BROKERAGE ETC. PAYABLE BY THE SUPPLIERS OF GOODS, SERVICES & WORKS IN CONTRACTS WORTH RS.10.00 MILLION OR MORE

Contract

Number: Contract

Value: Contract Title:

Dated:

[Name of Supplier] hereby declares that it has not obtained or induced the procurement of any contract, right, interest, privilege or other obligation or benefit from Government of Pakistan or any administrative subdivision or agency thereof or any other entity owned or controlled by it (GoP) through any corrupt business practice.

Without limiting the generality of the foregoing [Name of Supplier] represents and warrants that it has fully declared the brokerage, commission, fee etc. paid or payable to anyone and not given or agreed to give and shall not give or agree to give to anyone within or outside Pakistan either directly or indirectly through any natural or juridical person, including its affiliate, agent, associate, broker, consultant, director, promoter, shareholder, sponsor or subsidiary, any commission, gratification, bribe, finder's fee or kickback, whether described as consultations fee or otherwise, with the object of obtaining or inducing the procurement of a contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP, except that which has been expressly declared pursuant hereto.

[Name of Supplier] certifies that it has made and will make full disclosure of all agreements and arrangements with all persons in respect of or related to the transaction with GoP and has not taken any action or will not take any action to circumvent the above declaration, representative or warranty.

[Name of Supplier] accepts full responsibility and strict liability for making and false declaration, not making full disclosure, misrepresenting fact or taking any action likely to defeat the purpose of this declaration, representation and warranty. It agrees that any contract, right interest, privilege or other obligation or benefit obtained or procured as aforesaid shall, without prejudice to any other right and remedies available to GoP under any law, contract or other instrument, be voidable at the option of GoP.

Notwithstanding any rights and remedies exercised by GoP in this regard, [Name of Supplier] agrees to indemnify GoP for any loss or damage incurred by it on account of its corrupt business practices and further pay compensation to GoP in an amount equivalent to ten times the sum of any commission, gratification, bribe, finder's fee or kickback given by [Name of Supplier] as aforesaid for the purpose of obtaining or inducing the procurement of any contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP.



Performance Guarantee Form

Performance Guarantee Form

To: **IESCO-PMU (Islamabad Electric Supply company (IESCO)), Director procurement Office of Director (Procurement) Project Management Unit (PMU) Near 132kV Rawal Grid Station, Club Road, Kashmir Chowk Islamabad Capital Territory**

WHEREAS *[name of Bidder]* (hereinafter called “the Bidder”) has undertaken, in pursuance of Contract No. *[reference number of the contract]* dated *[insert date]* for provision of Goods (hereinafter called “the Contract”).

AND WHEREAS it has been stipulated by you in the said Contract that the Bidder shall furnish you with a Bank Guarantee by a reputable bank for the sum specified therein as security for compliance with the Bidder’s performance obligations in accordance with the Contract.

AND WHEREAS we have agreed to give the Bidders guarantee:

THEREFORE, WE hereby affirm that we are Guarantors and responsible to you, on behalf of the Bidder, up to a total of *[amount of the guarantee in words and figures]*, and we undertake to pay you, upon your first written demand declaring the Bidder to be in default under the Contract and without cavil or argument, any sum or sums within the limits of *[amount of guarantee]* as aforesaid, without your needing to prove or to show grounds or reasons for your demand or the sum specified therein.

This guarantee is valid until the: *[insert date]*


Signature and seal of the Guarantors

[name of bank or financial institution]

[address]

[date]





Annexure

Manufacturer experience annex

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Manufacturer experience annex** (page number: 78)

Production capacity annex

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Production capacity annex** (page number: 79)

Bidder information form

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Bidder information form** (page number: 80)

Bidder JV form

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Bidder JV form** (page number: 81)

Deviation from contractual provision

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Deviation from contractual provision** (page number: 82)

Deviation technical provision

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Deviation technical provision** (page number: 83)

Qualification information

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Qualification information** (page number: 84)

Manufacturer authorization

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Manufacturer authorization** (page number: 87)

Manufacturer information form

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Manufacturer information form** (page number: 88)

Production capacity of manufacturer

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Production capacity of manufacturer** (page number: 89)

Letter of bid

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Letter of bid** (page number: 90)

IESCO blacklisting policy

Information (Read-Only)

See Form Under Additional Forms and Documents: **IESCO blacklisting policy** (page number: 92)

Correction of defect in warranty period

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Correction of defect in warranty period** (page number: 121)

Type test requirement

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Type test requirement** (page number: 122)

Payment terms

Information (Read-Only)

See Form Under Additional Forms and Documents: **Payment terms** (page number: 123)

SPECS

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **SPECS** (page number: 125)

Price schedule NCB-302 EXW

Financial Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Price schedule NCB-302 EXW** (page number: 199)

Price schedule NCB-302 DDP

Financial Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Price schedule NCB-302 DDP** (page number: 200)





Procurement Forms

Past Experience and Completed Contracts

Bidder/Manufacturer/Joint Venture (JV) shall demonstrate successfully completion of at least two(02) No.contracts having similar complexity involving same OR higher Rating material/equipment during the last ten (10) years. The aggregate value of both contracts shall be equal to or greater than Rs. 5M but none of the contract value should be less than 30% of aggregate value.(Rs. 1.5M)

To substantiate compliance with this requirement, the Bidder/JV shall submit copies of relevant Purchase Orders / Contract Agreements along with Completion Certificates/GRN/Delivery Challan etc issued by the concerned client.

The manufacturer shall demonstrate at least five (05) years' experience in designing and manufacturing of similar nature/complex involving same or higher rated equipment/material. Two(02) years satisfactory operation performance of same or high rated equipment /material. For the ease of evaluation, related form are enclosed in annexure and the same will be considered during evaluation.

See Form Under Additional Forms and Documents: **Past Experience and Completed Contracts** (page number: 201)

Historical Contract Non-Performance, and Pending Litigation and Litigation History

History of Non-performing Contracts

Non-performance of a contract did not occur as a result of contractor default since 1st January 2025.

a Non-performance, as decided by the Purchaser, shall include all contracts where (a) nonperformance was not challenged by the contractor, including through referral to the dispute resolution mechanism under the respective contract, and (b) contracts that were so challenged but fully settled against the contractor. Nonperformance shall not include contracts where Purchaser's decision was overruled by the dispute resolution mechanism. Nonperformance must be based on all information on fully settled disputes or litigation, i.e. dispute or litigation that has been resolved in accordance with the dispute resolution mechanism under the respective contract and where all appeal instances available to the Bidder have been exhausted.

b This requirement also applies to contracts executed by the Bidder as Joint Venture partner.

pending litigation

All pending litigation, arbitration, Grievance Redressal committee (GRC) and Appellate GRC or other material events impacting the net worth and/or liquidity of the bidder, if any, shall be treated as resolved against the Bidder and so shall in total not represent more than 25% (twenty five percent) of the Bidder's last year net worth calculated as the difference between total assets and total liabilities.

See Form Under Additional Forms and Documents: **Historical Contract Non-Performance, and Pending Litigation and Litigation History** (page number: 202)

Current Contracts and Their Progress

Financial Resources shall be determined as per following :

Financial Resources = working capital + credit line from sheduled bank - current commitment as per attached proforma

See Form Under Additional Forms and Documents: **Current Contracts and Their Progress** (page number: 204)

Financial Capacity and Net Worth Evaluation Form

Financial Capability of Bidder

Submission of audited financial statements for the last three years to demonstrate the current soundness of the Bidder's financial position. Bidder's Net Worth for the last year calculated as difference between total assets and total liabilities should be positive. However, bidder's networth shall be equal to or greater than 40% of Rs. 5M (2M)

1 single entity = 100% comply

2 incase of JV lead partner 60% and member 40%

Specify proposed sources of financing, working capital, lines of credit, and other financial means, available to meet the cash flow demands shall be equal to or greater than Rs.5M.

1 single entity = 100% comply

2 incase of JV lead partner 60% and member 40%

See Form Under Additional Forms and Documents: **Financial Capacity and Net Worth Evaluation Form** (page number: 205)

Average Annual Turnover

Minimum average annual turnover of PKR calculated as total revenue of the Bidder over the last three Years shall be equal to or greater than Rs.7M.

1 single entity = 100% comply

2 incase of JV lead partner 60% and member 40%

See Form Under Additional Forms and Documents: **Average Annual Turnover** (page number: 207)





Additional Forms and Documents

Manufacturing Experience

Criteria		Compliance Requirements			Documents
Requirement	Single Entity	Joint Venture			Submission Requirements
		All Partners Combined	Each Partner	One Partner	
1. The manufacturer shall demonstrate at least five (05) years' experience in designing and manufacturing of similar nature/complex involving same or higher rated equipment/material. 2. Two (02) years satisfactory operation performance of same or high rated equipment /material.	Must meet requirement	Not applicable	Not applicable	Manufacturer must meet	Manufacturer Will provide the Detailed supply Record of similar or higher rated equipment. Satisfactory performance Of similar equipment for Two years.

Criteria	Compliance Requirements			Documents	
Requirement	Single Entity	Joint Venture			Submission Requirements
		All Partners Combined	Each Partner	One Partner	
In order to ensure the smooth and timely execution of order, the manufacturer will indicate its manufacturing / production capacity which shall be double the total sum of orders already in hand, expected orders in pipe line and this order (if placed on the bidder). The manufacturer shall provide the information with the bid to establish its capacity / capability to execute the order for which necessary documentary evidence may be attached related for the above mentioned requirements. In this context the manufacturer is required to fill in the relevant forms given in Forms of this tender document and submit the same with the bid. The purchaser may visit the site of supplier at any time during evaluation at the cost of supplier.	Must meet requirement	Not applicable	Not applicable	Manufacturer must meet	Forms

**A Bidder or Manufacturer shall provide evidence of production output.*

Bidder Information Form

Date of Bid Submission: _____

Request for Bid No.: NCB _____

Page _____ of _____ pages

1. Bidder's Name: _____
2. In case of JV, legal name of each member: _____
3. Bidder's actual or intended country of registration: _____
4. Bidder's year of registration: _____
5. Bidder's Address in country of registration: _____
6. Bidder's Authorized Representative Information Name: _____ CNIC No. _____ Address: _____ Telephone/Fax numbers: _____ Email Address: _____
7. Attached are copies of original documents of [please check the box(es) of the attached original documents] ☐ Articles of Incorporation (or equivalent documents of constitution or association), and/or documents of registration of the legal entity named above. ☐ In case of JV, letter of intent to form JV or JV agreement, in accordance with ITB 3.4. ☐ Establishing that the Bidder is not under the supervision of the Procuring Agency
8. Included are the organizational chart, a list of Board of Directors, and the beneficial ownership.

Bidder's JV Members Information Form

Date of Bid Submission: _____

Request for Bid No.: NCB _____

Page____of _____pages

1. Bidder's Name: _____
2. Bidder's JV Member's name: _____
3. Bidder's JV Member's country of registration: _____
4. Bidder's JV Member's year of registration: _____
5. Bidder's JV Member's legal address in country of registration: _____ _____
6. Bidder's JV Member's authorized representative information Name: _____ Address: _____ Telephone/Fax numbers: _____ Email Address: _____
7. Attached are copies of original documents of [please check the box(es) of the attached original documents] ☐ Articles of Incorporation (or equivalent documents of constitution or association), and/or registration documents of the legal entity named above, in accordance with ITB 4.4.
8. Included are the organizational chart, a list of Board of Directors, and the beneficial ownership.

Deviation from Contractual/Commercial Provision

It is presumed that bidder shall not take any deviation. However, if he intends to take deviation to specified contractual/commercial conditions, those must be listed in the space provided below.

Sr #	Section No	Clause No	Deviation	Clarifications

Sign & Stamped by bidders

Deviation from Technical Provision

It is presumed that bidder shall not take any deviation. However, if he intends to take deviation to specified terms, those must be listed in the space provided below:

Sr #	Section No.	Clause No	Deviation	Clarifications

Sign & Stamped by bidders

Form of Qualification Information

1. Individual Bidders or Individual Members of Joint Ventures

1.1 Constitution or legal status of Bidder:

(Attach copy)

Place of registration: _____

Principal place of business: _____

Power of attorney of signatory of Bid: _____

1.2 Total annual volume of Services performed in _____ years, in the internationally traded currency specified in the Bid Data Sheet: _____

1.3 Services performed as prime Supplier on the provision of Services of a similar nature and volume over the last _____ years. The values should be indicated in the same currency used for Item 1.2 above. Also list details of work under way or committed, including expected completion date.

Project name and country	Name of Procuring Agency (PA) and contact person	Type of Services provided and year of completion

1.4 Major items of Supplier's Equipment proposed for carrying out the Services. List all information requested below. Refer also to ITB 13.3(c).

Item of equipment	Description, make, and age (years)	Condition (new, good, poor) and number available	Owned, leased (from whom?), or to be purchased (from whom?)
(a)			
(b)			

1.5 Qualifications and experience of key personnel proposed for administration and execution of the Contract. Attach biographical data. Refer also to ITB 13.4(d).

Position	Name	Years of experience (general)	Years of experience in proposed position
(a)			
(b)			

1.6 Proposed sub-contracts and firms involved. Refer to GCC 24.

Sections of the Services	Value of Sub-contract	Sub-contractor (Name and address)	Experience in providing similar Services
(a)			
(b)			

1.7 Financial reports for the last (*insert period*) years: balance sheets, profit and loss statements, auditors' reports, etc. List below and attach copies.

1.8 Evidence of access to financial resources to meet the qualification requirements: cash in hand, lines of credit, etc. List below and attach copies of support documents mentioning that We certify/confirm that we comply with eligibility requirements as per ITB 3 of the bidding documents.

1.9 Name, address, and telephone, telex, and facsimile numbers of banks that may provide references if contacted by the Procuring Agency.

1.10 Information regarding any litigation, current or within the last (*insert period*) years, in which the Bidder is or has been involved.

Other party(ies)	Cause of dispute	Details of litigation award	Amount involved
(a)			
(b)			

1.11 Information regarding Occupation Health and Safety Policy and Safety

Records of the Bidder.

1.12 Statement of compliance with the requirements of ITB 3.4.

1.13 Proposed Program (service work method and schedule). Descriptions, drawings, and charts, as necessary, to comply with the requirements of the bidding documents.

2. Joint Ventures

2.1 The information listed in 1.11 - 1.12 above shall be provided for each member of the joint venture.

2.2 The information in 1.13 above shall be provided for the joint venture.

2.3 Attach the power of attorney of the signatory (ies) of the Bid authorizing signature of the Bid on behalf of the joint venture.

2.4 Attach the Contract among all members of the joint venture (and which is legally binding on all members), which shows that

- (a) all members shall be jointly and severally liable for the execution of the Contract in accordance with the Contract terms;
- (b) one of the members will be nominated as being in-charge, authorized to incur liabilities, and receive instructions for and on behalf of any and all members of the joint venture; and
- (c) the execution of the entire Contract, including payment, shall be done exclusively with the member in charge.

3. Additional Requirements

3.1 Bidders should provide any additional information required in the Bid Data Sheet and to fulfill the requirements of ITB 12.1, if applicable.

We, the undersigned declare that

- (a) The information contained in and attached to this form is true and accurate as of the date of bid submission

Or [delete] statement which does not apply]

- (b) The originally submitted pre-qualification information remains essentially correct as of date of submission

Authorized Signature: _____

Name and Title of Signatory: _____

Name of Bidder: _____

Address: _____

Manufacturer's Authorization

No. _____

Dated _____

Date of Bid Submission:

____/____/2025

Request for Bid No.:

NCB _____

To:

WHEREAS

We _____, who are official manufacturers of _____, having factories at _____, do hereby authorize M/s _____ to submit a Bid the purpose of which is to provide the following Goods, manufactured by us _____ and to subsequently negotiate and sign the Contract.

We hereby extend our full guarantee and warranty in accordance clause-18 of General Conditions of Contract, with respect to the Goods offered by the above firm.

Signed: _____

Name: _____

Title: _____

Date signed _____ day of _____ Month, _____ Year

Manufacturer's Information Form

Date of Bid Submission: _____

Request for Bid No.: NCB _____

Page ____ of ____ pages

1. Manufacturer's Name: _____
3. Manufacturer Country of Registration: _____
4. Manufacturer year of Registration: _____
5. Manufacturer's legal address of Head Office and Production sites in Country of Registration: _____
6. Manufacturer's Authorized Representative Information Name: _____ Address: _____ Telephone/Mob/Fax numbers: _____ Email Address: _____
1 Attached are copies of original documents of [please check the box(es) of the attached original documents] from concern chamber of commerce manufacturing country or Pakistani Embassy in manufacturing country ☐ Articles of Incorporation (or equivalent documents of Constitution or Association), and/or registration documents of the legal entity named above, in accordance with ITB 4.4. 2. Included are the organizational chart, a list of Board of Directors, and the Beneficial Ownership.

Production Capacity of Manufacturer

Sr #		Factory Capacity in unit as mentioned in Price schedule
A	Total Factory Production Capacity (No. or Sets or other unit)/Year	
B	Order in Hand (No. or Sets or other unit)	
C	Expected order during execution of this contract if awarded (No. or Sets or other unit)	
D	Quantity of this order	
E	Remaining Capacity of Factory (No. or Sets or other unit) E= (A-B-C-D)	
$A \geq 2 \times E$		

Signed & Stamped by Manufacture

Letter of Bid

No. _____

Dated _____

Date of Bid submission: _____

Request for Bid No.: (NCB) _____

Description of Bid: _____

To:

We, the undersigned Bidder, hereby submit our Bid,
 In submitting our Bid we make the following declarations:

- (a) **No reservations:** We have examined and have no reservations to the bidding document, including addenda issued in accordance with Instructions to Bidders (ITB 9);
- (b) **Eligibility:** We meet the eligibility requirements and have no conflict of interest in accordance with ITB 3;
- (c) **Bid/Proposal-Securing Declaration:** We have not been suspended nor declared ineligible by the Procuring Agency based on execution of a Bid Securing Declaration or Proposal Securing Declaration in the Procuring Agency's country in accordance with ITB 4;
- (d) **Conformity:** We offer to supply in conformity with the bidding document and in accordance with the Delivery Schedules specified in the Schedule of Requirements the following Goods: *[insert a brief description of the Goods and Related Services]*;
- (e) **Bid Validity Period:** Our Bid shall be valid for the period specified in BDS 17.1 (as amended, if applicable) from the date fixed for the Bid submission deadline specified in BDS 23.1 (as amended, if applicable), and it shall remain binding upon us, and may be accepted at any time before the expiration of that period;
- (f) **Performance Security:** If our Bid is accepted, we commit to obtain a performance security in accordance with the bidding document;
- (g) **One Bid per Bidder:** We are not submitting any other Bid(s) as an individual Bidder, and we are not participating in any other bid(s) as a Joint Venture member or as a subcontractor, and meet the requirements, other than Alternative Bids submitted in accordance with ITB 19;
- (h) **Suspension and Debarment:** We, along with any of our subcontractors, suppliers, consultants, manufacturers, or service providers for any part of the contract, are not subject to, and not controlled by any entity or individual that is subject to, a temporary suspension or a debarment imposed by the Procuring Agency. Further, we are not ineligible under Pakistan laws;
- (j) **State-owned enterprise or institution:** (check appropriate box)
 - i. We are not a state-owned enterprise or institution ☐
 - ii. We are a state-owned enterprise or institution but meet the requirements of this tender. ☐

- (k) **Binding Contract:** We understand that this Bid, together with your written acceptance thereof included in your Letter of Acceptance, shall constitute a binding contract between us, until a formal contract is prepared and executed;
- (l) **Not Bound to Accept:** We understand that you are not bound to accept the Most Advantageous Bid or any other Bid that you may receive; and
- (m) **Fraud and Corruption:** We hereby certify that we have taken steps to ensure that no person acting for us, or on our behalf, engages in any type of Fraud and Corruption.

- (a) **Total Price:** The total price of our Bid, excluding any discounts offered in item below is:

PKR _____
(In words) _____

- (c) **Discounts:** The discounts offered and the methodology for their application are:

(i) The discounts offered are: _____

(ii) The exact method of calculations to determine the net price after application of discounts is shown below:

- (d) **Commissions, gratuities and fees:** We have paid, or will pay the following commissions, gratuities, or fees with respect to the bidding process or execution of the Contract:

Name of Recipient	Address	Reason	Amount
Not Applicable			

Name of the Bidder:* _____

Name of the person duly authorized to sign the Bid on behalf of the Bidder: **

Title of the person signing the Bid: _____

Signature of the person named above:

Date signed _____ day of _____ Month, _____ Year

*: In the case of the Bid submitted by a Joint Venture specify the name of the Joint Venture as Bidder.

** : Person signing the Bid shall have the power of attorney given by the Bidder. The power of attorney shall be attached with the Bid Schedules.


MECHANISM FOR BLACKLISTING OF CONTRACTORS / CONSULTANTS / MANUFACTURERS



**Approved by IESCO Board of Directors (BoD) in its
178th Meeting held on 23rd August 2019.**

ISLAMABAD ELECTRIC SUPPLY COMPANY (IESCO)

28th October, 2019




DISCLAIMER

If any clause of this policy afterwards develops contradiction with PPRA Rules, then PPRA Rules will supersede the relevant clause of IESCO Mechanism for Blacklisting of Contractors / Consultants / Manufacturers.

TABLE OF CONTENTS

PREFACE	1
DEFINITIONS	2
Chapter No.1	
1.1 Introduction	4
1.2 Extent of Application	4
1.3 Basic Principles of Blacklisting Mechanism	5
Chapter No.2	
Grounds for Blacklisting	
2.1 General Grounds	6
2.2 Grounds at Competitive Bidding Stage	6
2.3 Grounds at Contract Implementation Stage	8
2.4 Blacklisted Person / Entity etc.	10
Chapter No.3	
Formulation of “IESCO Standing Committee for Blacklisting”	
3.1 Defining Structure of Committee	11
3.2 Provision of Additional Member	11
3.3 Timeline for Finalization of Recommendations	11
Chapter No.4	
Procedure for Suspension and Blacklisting.	12
4.1 The Competitive Bidding Stage	12
4.1.1 Initiation of Action	12
4.1.2 Notification	12
4.1.3 Hearings	13
4.1.4 Decision	13
4.1.5 Notice of Decision	13
4.2 Contract Implementation Stage	14
4.2.1 Initiation of Action	14
4.2.2 Notification	14
4.2.3 Hearings	14
4.2.4 Decision	15
4.2.5 Notice of Decision	15
4.3 Blacklisted Person / Entity etc.	15
Chapter No.5	
Review against Decision of the Procuring Agency	16
5.1 Filing an appeal for Review against decision	16
5.2 Constituting Decision Review Committee	16
5.3 Timeline for deciding the Appeal	16
5.4 Finalization of the Decision	16
Chapter No.6	
Appeal	
6.1 Filing an Appeal with the Authority	17
Chapter No.7	
Period of Debarment	
7.1 Period of Debarment for Blacklisted Firms	18

	Chapter No.8	
	Appraisal to Procurement Committee/Board of Directors	
8.1	Appraisal of Blacklisted Firms to Procurement Committee / Board of Directors (BoD)	19
	Chapter No.9	
	Communication of Notification to Authority	
9.1	Methodology for Communication of Notification of the PPRA / NTDC / WAPDA /DISCOs Delisting	20
9.2	Effectiveness	21
9.3	Amendments	21
9.4	Delisting	21
	Appendix-1 - Process to deal with Complaints	22
	Appendix-2 - Guidelines for Evaluation of Performances of Contractors	24
	Form for Hearing	25



PREFACE

This mechanism of blacklisting has been drafted in the light of Rule-19 “Blacklisting of suppliers and contractors” of the Public Procurement Rules, 2004 “PPRA Rules”. This Mechanism has been developed to mitigate the possibilities of corrupt practices and ensure the transparent and corruption free public procurement in the organization. The blacklisting policies of various procurement agencies have also been consulted. The policy was placed on IESCO website for more than 03 months & all the stake holders were invited to furnish their comments so that no one may have any objection after its implementation. This mechanism consists of 09 chapters containing Grounds for Blacklisting, Procedure for Suspension and Blacklisting, Formulation of “IESCO Standing Committee for Blacklisting”, Review against Decision of the Procuring Agency, Period of Debarment, Process to deal with Complaints & Guidelines for Evaluation of Performances of Contractors. The procedure has been developed for both of the procurement stages including competitive bidding stage and contract implementation stage. A disclaimer Clause has also been added so that Authority’s instructions could prevail. This document shall be considered an integral part of IESCO Bidding Documents / Tender Documents/ RFPs as well as contract agreements / purchase orders etc. The bidders shall have to submit an undertaking along with their bid that they have read all the contents of this blacklisting mechanism and they accept all the provisions of this document.

DEFINITIONS

In addition to definitions mentioned in bidding document, following definitions are also applicable:

- (i) **Authority:** The Public Procurement Regulatory Authority.
- (ii) **Appeal:** Right of firm/individual to bring its / his grievance against the issuance of Blacklisting Order at the appropriate legal forum.
- (iii) **Appellate Authority:** The department, office or government unit exercising general and/or administrative supervision/control over the blacklisting agency. Department level agencies shall exercise appellate authority over offices, agencies, under their jurisdiction. *Provided, further,* that blacklisting decisions of government agencies that are not subject to general and/or administrative supervision/control of any department, office or government unit shall be final and executor.
- (iv) **Award:** A written notice from the procuring entity accepting a bid or proposal.
- (v) **Blacklisting:** An administrative penalty disqualifying a person or an entity from participating in any government procurement for a given period.
- (vi) **Blacklisting Mechanism:** A mechanism adopted by IESCO as a procuring agency/entity for Blacklisting supplier(s), manufacturer(s), distributor(s), contractor(s) or Experts/consultants/consulting firm(s) etc.
- (vii) **Blacklisted Person/Entity.** A person/entity that was disqualified by an agency and/or is included in the PPRA/ADB/World Bank/Donor Agencies' (working with Government of Pakistan) Consolidated Blacklisting Report/sanctioning list.
- (viii) **Contractor** includes-suppliers, contractors and consultants
- (ix) **Consolidated Blacklisting Report:** The report prepared by the NTDC/WAPDA/DISCOs/PPRA/ADB/World Bank/Donor Agency working with Government of Pakistan containing the list of supplier(s), manufacturer(s), distributor(s), contractor(s) or Experts/ consultants/ consulting firm(s) blacklisted by procuring entities/agencies.
- (x) **Debarment:** state of being legally excluded from participating in all types of procurement proceedings of the procuring department for a given period.
- (xi) **Delist.** Removal of a person/entity from the Consolidated Blacklisting Report.
- (xii) **Procuring Agency:** Any department, attached department or any office of the Islamabad Electric Supply Company;

- (xiii) **Suspension.** Administrative action taken for infractions committed by a contractor during the competitive bidding stage, whereby such contractor is prohibited from further participation in the bidding process of an agency.
- (xiv) **Termination of Contract-** Extinction of contract by reason or resolution or rescission under applicable rules/regulations/laws arising from the default of the firms/individuals.



Chapter No.1

1.1 Introduction

Blacklisting is one of the effective tools used in the struggle against the corruption in connection with public procurement. The main objectives of any procurement process are transparency, economy, fairness and efficiency so that public money is spent on welfare of the public. Hence, blacklisting is an instrument, which may lead to the decrease of the potential corruption risks and also inculcate protection of public means and increase of effectiveness of allocation of the limited resources.

Rule-19 “Blacklisting of suppliers and contractors” of the Public Procurement Rules, 2004 (hereinafter “**PPRA Rules**”) stipulates that;

*“The procuring agencies shall specify a mechanism and manner to permanently or temporarily bar, from participating in their respective procurement proceedings, suppliers and contractors who either consistently fail to provide satisfactory performances or are found to be indulging in corrupt or fraudulent practices. Such barring action shall be duly publicized and communicated to the Authority:
Provided that any supplier or contractor who is to be blacklisted shall be accorded adequate opportunity of being heard.”*

In the light of the above said Clause, Blacklisting Mechanism (hereinafter **the Mechanism**) has been specified for all procurements made by IESCO. This policy shall govern the blacklisting of manufacturers, suppliers, distributors, contractors, consultants and consulting firms (“contractors” for brevity) involved in government procurement for offenses or violations committed during competitive bidding and contract implementation

Any capitalized terms and abbreviations used in this mechanism which are not defined herein shall have the meanings given to them in Public Procurement Regulatory Authority Ordinance, 2002 (hereinafter “**PPRA Ordinance**”) and PPRA Rules amended upto date.

1.2 Extent of Application

- i. The Mechanism shall be applicable and remain in force, along with any amendments thereto, within IESCO until any clear instructions or guidelines are imparted by the Government through PPRA, PEC, or any other competent forum.
- ii. The Mechanism shall also be applicable on the pre-qualified firms.
- iii. The Mechanism shall be applicable for suppliers / bidders / contractors / local agents / representatives / consultants / firms / individuals / distributors / Manufacturers / organization transacting business with IESCO.

- iv. Wherever any provision of this mechanism shall be in conflict with provisions of any applicable guidelines of donor agencies, or any other applicable Statute / Law or Rule enforced at the time in Pakistan, the provisions of the Statute / Law or rule shall prevail.
- v. After Approval of this mechanism by the competent Authority, it shall be considered an integral part of bidding document/tender document/RFP as well contract agreement/Purchase Order, unless otherwise specified PPRA rule-5. The bidder will submit an Undertaking along-with their bid that they have read and accept the provisions of this Mechanism. Non-submission of an Undertaking may result in rejection of their bid. The said Undertaking will subsequently become part of the Contract Agreement as well.

1.3 Basic Principles of Blacklisting Mechanism

Following are the important basic principles of Blacklisting Mechanism::

- i. To lay down effective mechanism for disciplining deviant Contractors against whom, misconduct has been established;
- ii. An opportunity will be provided to any contractor alleged to have committed an act of misconduct, to defend himself;
- iii. The formal hearing be conducted by a Committee/Committees.
- iv. The presenter has the sole responsibility for deciding the terms of suspension.
- v. Blacklisting is a temporary action and not permanent measure.
- vi. The period of blacklisting / suspension would invariably depend upon the seriousness / nature of offence committed by the erring contractor.
- vii. Blacklisting Mechanism is applicable for all type of national or international contractors, manufacturers, consultants, pre-qualified contractors /manufacturers, local agents, distributors and suppliers.

CHAPTER NO. 2

GROUND FOR BLACKLISTING

2.1 General Grounds

The following shall comprise the broad multilateral grounds for blacklisting:

- i. **Corrupt Practice**" the offering, giving, receiving, or soliciting, directly or indirectly, of anything of value to influence the action of a public official in the procurement process or in contract execution;
- ii. **Fraudulent Practice**" a misrepresentation or omission of facts in order to influence a procurement process or the execution of a contract
- iii. **Collusive Practice**" a scheme of arrangement between two or more bidders, with or without the knowledge of the Purchaser, designed to establish bid price at artificial, non-competitive levels, and
- iv. **Coercive Practice**" harming or threatening to directly or indirectly, persons or their property to influence their participation in the procurement process or affect the execution of a contract.

In addition to above, blacklisting of firms/individuals may be resorted to when the charges are of serious nature, which include but are not limited to the following:

2.2 Grounds at Competitive Bidding Stage

The procuring Agency shall impose on bidder(s)/JV/Entities/Consulting firm(s) or prospective bidders the penalty of suspension or blacklist them for a specific period for the offense from participating in the public bidding process, without prejudice to the imposition of additional administrative sanctions as the internal rules of the agency may provide and/or further criminal prosecution, as provided by applicable laws, for the following violations:

- i. Indulging in Corrupt, Fraudulent as well as Collusive & Coercive Practices.
- ii. Submission of eligibility requirements containing false information or falsified or spurious documents
- iii. Submission of false/forged/unauthentic Bid Security/Pay Order/CDR or infringement of documents to get undue monetary or any other benefit.
- iv. Submission of Bids that contain false information or falsified documents, or the concealment of such information in the Bids or making frivolous complaints and allegations in order to influence the outcome of eligibility screening or any other stage of the public bidding.

- v. Unauthorized use of one's name, or using the name of another for purpose of public bidding.
- vi. Withdrawal of a bid after submission, or refusal to accept an award, or enter into contract with the government without justifiable cause, after he had been adjudged as having submitted the Lowest Calculated Responsive Bid or Highest Rated/ranked Responsive Bid.
- vii. Refusal or failure to submit the required performance security within the prescribed time limit.
- viii. Any documented unsolicited attempt by a bidder to unduly influence the outcome of the bidding in his favor.
- ix. All other acts that tend to defeat the purpose of the competitive bidding, such as but not limited to: an eligible contractor not buying bid documents from procuring agency or not complying with the requirements during bid evaluation, and contractors habitually withdraw from bidding for at least three (3) times within a year.
- x. Bidder(s) (prior to or after bid submission) designed to establish bid prices at artificial, non-competitive levels and to deprive the procuring agencies of the benefit(s) of free and open competition and any request for, or solicitation of anything of value by any public official in the course of the exercise of his duty;
- xi. Involved in litigation or needless petitioning to influence or obstruct the procurement process either on his own behalf or at the behest of any other vested interest.
- xii. Breach of confidentiality of evaluation process as mentioned in Appendix-I based on illegal access or in any way to get undue benefit or to provide benefit or to frustrate the bidding/evaluation process. This will also include attempts to sabotage the bidding process directly or indirectly.
- xiii. Any effort by the bidder to influence the procuring agency in the examination, evaluation, ranking of Proposals, and recommendation for award of Agreement.

In addition to the penalty of suspension, the bid security posted by the concerned bidder or prospective bidder shall also be forfeited.

2.3 Grounds at Contract Implementation Stage

Without prejudice to the imposition of additional administrative sanctions as the internal rules of the procuring agency may provide and/or further criminal prosecution as provided by applicable laws, the procuring agency shall take against the contractors after the termination of the contract, the action of suspension for specific period from participating in the public bidding process, for violations committed during the contract implementation stage, which include but not limited to the following:

- a. Indulging in Corrupt, Fraudulent as well as Collusive & Coercive Practices.
- b. Extraordinary delay in signing or refusal to accept the Notification of Award (NOA) and/or the contract without any cogent reason.
- c. Failure of the contractor, due solely to his fault or negligence, to mobilize and start work or performance within the specified period in the Notice of Award (NOA).
- d. Submission of fake / frivolous or mutilated Performance Guarantee or Advance Payment guarantee etc.
- e. Failure by the contractor to fully and faithfully comply with its contractual obligations without valid cause, or failure by the contractor to comply with any written lawful instruction of the procuring entity or its representative(s) pursuant to the implementation of the contract. For the procurement of infrastructure projects or consultancy contracts, lawful instructions include but are not limited to the following:
 - i. Employment of competent technical personnel, competent engineers and/or work supervisors; and Deployment of committed equipment, facilities, support staff and manpower; and
 - ii. Provision of warning signs and barricades in accordance with approved plans and specifications and contract provisions;
 - iii. Stockpiling in proper places of all materials and removal from the project site of waste and excess materials, including broken pavement and excavated debris in accordance with approved plans and specifications and contract provisions;
 - iv. Renewal of the effective dates of the performance security after its expiration during the course of contract implementation.
- f. Assignment and subcontracting of the contract or any part thereof or substitution of key personnel named in the proposal without prior written approval by the procuring entity.
- g. For the procurement of goods, unsatisfactory progress in the delivery of the goods by the manufacturer, supplier or distributor arising from his

fault or negligence and/or unsatisfactory or inferior quality of goods, as may be provided in the contract or as under:

- i. Deviations from specifications and terms & conditions of the purchase order/contract.
- ii. Provision of fake prototype/type test reports
- iii. Provision of fake inspection call FAT/Type test
- iv. Failure to rectify the fault/damage/problem during period of warrantee
- v. Supply of goods through inappropriate way such as smuggling of goods
- vi. Supply of stolen goods/re-sold goods.
- vii. Provision of fake /forged custom /taxes /duties documents
- h. For the procurement of consulting services, poor performance by the consultant of his services arising from his fault or negligence. Any of the following acts by the consultant shall be construed as poor performance and is liable to be Blacklisted:
 - i. Defective design resulting in substantial corrective works in design and/or construction;
 - ii. Failure to deliver critical outputs due to consultant's fault or negligence; and
 - iii. Specifying materials which are inappropriate, substandard, or way above acceptable standards.
 - iv. Allowing defective workmanship or works by the contractor being supervised by the consultant.
 - v. Submitting CV's of key personnel in the prequalifying process or bid documents of professionals that are not in actual employment of the bidder or without consent of experts.
 - vi. Acting together (Contractor & Consultant) in secret toward a fraudulent or illegal end
- i. For the procurement of infrastructure projects, poor performance by the contractor or unsatisfactory quality and/or progress of work arising from his fault or negligence. Any of the following acts by the constructor shall be construed as poor performance:

- i. Negative slippage of 15% and above within the critical path of the project due entirely to the fault or negligence of the contractor; and
- ii. Quality of materials and workmanship not complying with the approved specifications/Drawing(s) arising from the contractor's fault or negligence.
- iii. Unnecessary delay in completion of project
- iv. Failure to rectify fault/problem/damages during defect liability.
- j. Willful or deliberate abandonment or non-performance of the project or contract by the contractor resulting to substantial breach thereof without lawful and/or just cause.
- k. In addition to above, other grounds for blacklisting of firms/individuals include but are not limited to the following:
 - i. Obtaining fraudulent payments;
 - ii. Obtaining contracts by misleading the purchaser;
 - iii. Refusal to pay IESCO dues etc.;
 - iv. Failure to fulfill contractual obligations Changes in the status of firm's ownership/partnership etc., causing dissolution of the firm which existed at the time of inspection prior to original registration of the firm
 - v. Registration of a firm with a new name by the Proprietor or family or a nominee thereof of a firm that has been already blacklisted;
 - vi. Contractors who have negotiated Plea Bargain under the National Accountability Ordinance 1999, or contractors involved with any other criminal proceedings conducted by any investigation agency where default has been proved specifically in relation to supplies made to or contracts concluded with IESCO or department thereof;.
 - vii. Non-compliance of the existing policy/rules/law of GoP during execution of contract.
 - viii. Hiring of underage personnel for assignments or works violating Child Labor (Prohibition and Regulation) Amendment Bill, 2016.
 - ix. Non-Adherence to safety codes.

For the Blacklisting of a Firm, in addition to the penalty of suspension for a certain period, the performance security posted by the contractor shall also be forfeited.

CHAPTER NO. 3

FORMULATION OF “IESCO STANDING COMMITTEE FOR BLACKLISTING”

3.1 Defining Structure of Committee

A permanent Committee namely “IESCO’s Standing Committee for Blacklisting” comprising of the following members shall examine the justification of the reasons given by the Project Authority prior to blacklisting / debarment of any firm/supplier/contractor/ individual.

i. General Manager Technical	Convener
ii. Director General/ Manager (Legal) IESCO	Member
iii. Representative of Finance Director (Not Less than the Rank of Manager)	Member
iv. Deputy Manager (Village Electrification Cell)	Member
v. Deputy Manager Procurement PMU	Member

The quorum for committee meeting will be 3 members including the Convener, the presence of Convener is mandatory. Committee shall evaluate the case and develop consensus however, in case of conflict among the member of committee, decision of convener shall be considered final.

3.2 Provision of Additional Member

Depending upon the nature of the case, the Committee may consult or appoint / nominate additional members from within IESCO with the approval of Chief Executive Officer (CEO) IESCO, provided that the Committee consists of an odd number of individuals as per spirit of Rule 48(1) of the PPRA Rules. Independence of any additional members shall be ensured while making the selection of such additional members. Furthermore, the aforementioned Standing Committee shall also be authorized to seek external expert advice or call any employee of IESCO as and when required.

3.3 Timeline for Finalization of Recommendations

The committee shall finalize its recommendations within the time specified in this mechanism.

CHAPTER NO. 4

PROCEDURE FOR SUSPENSION AND BLACKLISTING.

4.1 The Competitive Bidding Stage

4.1.1 Initiation of Action

Upon receipt of or obtaining information and / or knowledge that any person(s) is involved in practices mentioned in Article 2.1 and 2.2 of the Mechanism, the concerned project Authority / formation may initiate the suspension and blacklisting proceedings by filing its recommendations with the procuring agency or procuring agency also motu proprio (by itself) commence the proceedings upon prima facie (self-sufficient) determination that the bidder/ prospective bidder/ JV/ Person/Entity has committed any of the grounds for blacklisting during the competitive bidding stage as mentioned in article-2.1 & article-2.2 of the policy.

The Project Director or Project implementation Agency shall provide substantial evidence for the person/entity/JV/Firm against whom the case for blacklisting has been initiated.

4.1.2 Notification

Upon verification of the existence of grounds for blacklisting, the procuring agency shall immediately notify the contractor concerned in writing, advising him that:

- a. Complaint for suspension and blacklisting has been filed against him, or he has been considered by the procuring agency for suspension and blacklisting, stating the grounds for such;
- b. He has the opportunity to explain his position regarding why he should not be suspended and blacklisted;
- c. Hearing shall be conducted before the procuring agency or “IESCO’s Standing Committee for Blacklisting”, upon his request, where he may present documentary evidence, verbal testimony and cross-examine the witnesses presented against him; and
- d. The consequences of being suspended and blacklisted.

Within seven (7) calendar days from receipt of notification, the bidder shall submit its written answer with documentary evidence to the procuring agency or “IESCO’s Standing Committee for Blacklisting” with a manifestation for request of hearing to determine questions of fact, if he so desires. No time extension shall be allowed. if contractor fail to answer within the stipulated period, the procuring agency shall issue a resolution recommending its blacklisting with the immediate suspension of the contractor from participating in any bidding process of the agency for a certain period and the forfeiture of his bid security.

4.1.3 Hearings

If a hearing is requested by the contractor, the procuring agency shall immediately set the date and time for hearing. The hearing shall be non-litigious and shall be terminated within five (5) days. The procuring agency shall constitute an independent "Hearing Committee" comprising of odd Number members. The procuring agency may also invite a representative from PPRA or a duly recognized private group in a sector or discipline relevant to the procurement at hand as an observer for each hearing.

If no request is made, the procuring agency shall make a determination of the case based on the complaint, answer, documentary evidence submitted and facts verified. If the procuring agency is convinced that the contractor/bidder is at fault, it shall issue a resolution recommending for its blacklisting with suspension of the bidder from participating in any bidding process of the agency and the forfeiture of his bid security.

4.1.4 Decision

The Head of the Procuring Entity shall, within fifteen (15) days from receipt of the resolution and the records of proceedings, determine whether reasonable cause exists for the suspension of the contractor and the forfeiture of the latter's bid security. If the Head of the Procuring Entity determines that such reasonable cause exists, he shall issue a decision regarding its blacklisting and suspending the contractor from participating in any bidding process of the agency, and further declaring that his bid security is forfeited. Otherwise, he shall dismiss the case.

The decision shall clearly and distinctly state the facts, evidence and the law on which it is based, as well as the date of effectiveness of the penalty, if any.

In case a contractor commits more than one offense or a combination of offenses for the same project/contract in a particular agency, each violation shall be met the corresponding penalty.

4.1.5 Notice of Decision

The procuring agency shall furnish the suspended contractor a copy of the decision immediately from its promulgation.

4.2 Contract Implementation Stage

4.2.1 Initiation of Action

Procuring Agency shall commence the proceedings upon prima facie (self-sufficient) determination that the contractor has committed any of the grounds for blacklisting during the contract implementation stage as mentioned in bidding document/Contract agreement or any event as mentioned in article-2.1 & article-2.3 of the policy of written complaint from Engineer/ consultant/ supervisory office.

The Project Director or Project implementation Agency shall provide substantial evidence for the person/entity/JV/Firm/Contract against whom the case for blacklisting has been initiated.

4.2.2 Notification

Upon verification of the existence of grounds for blacklisting, the procuring agency shall immediately notify the contractor concerned in writing, advising him that:

Within seven (7) calendar days from receipt of notification, the contractor shall submit its written answer with documentary evidence to the procuring agency with a manifestation for request of hearing to determine questions of fact, if he so desires. No time extension shall be allowed.

If the contractor fail to answer within the stipulated period, the procuring agency shall issue a resolution recommending the blacklisting with immediate suspension of the contractor from participating in any bidding process of the agency and the forfeiture of his bid security.

4.2.3 Hearings

If a hearing is requested by the contractor, the procuring agency shall immediately set the date and time for hearing. The hearing shall be non-litigious and shall be terminated within five (5) days. The procuring agency shall constitute an independent "Hearing Committee" comprising of odd Number members. The procuring agency may also invite a representative from PPRA or a duly recognized private group in a sector or discipline relevant to the procurement at hand as an observer for each hearing.

If no request is made, the procuring agency shall make a determination of the case based on the complaint, answer, documentary evidence submitted and facts verified. If the procuring agency is convinced that the contractor is at fault, it shall issue a resolution recommending for blacklisting with suspension of the contractor from participating in any bidding process of the agency and the forfeiture of his performance security.

4.2.4 Decision

The procuring agency shall, within fifteen (15) days from receipt of the resolution and the records of proceedings, determine whether reasonable cause exists for the suspension of the contractor and the forfeiture of the latter's performance security. If the Head of the Procuring Entity determines that such reasonable cause exists, he shall issue a decision for blacklisting the contractor with suspending the contractor from participating in any bidding process of the agency, and further declaring that his performance security is forfeited. Otherwise, he shall dismiss the case.

The decision shall clearly and distinctly state the facts, evidence and the law on which it is based, as well as the date of effectivity of the penalty, if any.

In case a contractor commits more than one offense or a combination of offenses for the same project/contract in a particular agency, each violation shall be met the corresponding penalty

4.2.5 Notice of Decision

The procuring agency shall furnish the blacklisted contractor a copy of the decision immediately from its promulgation.

CHAPTER NO. 5

REVIEW AGAINST DECISION OF THE PROCURING AGENCY

5.1 Filing an Appeal for Review against decision

The Contractor shall have the right to lodge request to review the blacklisting decision, if the same is convinced that some concrete evidence proves the case otherwise in favor of the Contractor. For this purpose, the same will file an appeal within five (5) days from receipt of the notice of decision.

5.2 Constituting Decision Review Committee

The procuring agency shall constitute an independent “Decision Review Committee” comprising of three members and external observer(s) preferably PPRA representative.

5.3 Timeline for Deciding the Appeal

Committee shall resolve with finality the review application within ten (10) days from the filing thereof and furnish blacklisted/suspended contractor/bidder a copy of the resolution immediately from its promulgation.

5.4 Finalization of the Decision

The decision of the committee shall become final and executor after the lapse of fifteen days from the receipt of the notice of decision or decision of review application. If an appeal is filed, the affirmed, modified or reversed decision shall become final and executory upon receipt thereof by the department and person/entity concerned. Upon finality of the decision suspending the contractor, the procuring agency shall issue a Blacklisting Order disqualifying the erring contractor from participating in the bidding of all projects.

CHAPTER NO. 6

APPEAL

6.1 Filing an Appeal with the Authority

The Contracting Firm shall have the right to file an appeal with the Authority within ten days from the date of receipt of the decision for either or both of the following causes, provided that only a single application shall be filed with the Authority:

- a. The decision is not in conformity with the evidence and/or facts presented, hence does not construe grounds for Blacklisting laid down under Rule 19 of the PPRA Rules – 2004; and
- b. Newly discovered evidence or facts which could not be discovered and produced at the investigation and which when presented would probably alter the result of the investigation.

CHAPTER NO. 7

PERIOD OF DEBARMENT

7.1 Period of Debarment for Blacklisted Firms

The Blacklisting shall be for a reasonable specified period of time and as a general rule of prudence, the period may not exceed three years. The following time periods shall be considered for debarment on account of blacklisting;

Causes of Blacklisting	Time for Debarment
Corrupt & fraudulent & collusive practices, criminal breach of trust.	03 years
Submission of fake documents including financial instruments like securities & guarantees, submission of false Financial statement / Audit reports etc.	03 years and forfeiture of securities
Making false statement and allegation to gain undue advantage	03 years and forfeiture of securities
Commission of embezzlement, theft, cheating, forgery, bribery, falsification or destruction of records, receiving stolen property, false use of trademark, securing fraudulent registration, giving false evidence, furnishing false information.	03 years and forfeiture of securities
Breach of confidentiality of evaluation process as mentioned in Appendix 1 hereto	06 month to 02 years as mentioned in Appendix-1 and forfeiture of securities
Extraordinary delay in signing or refusal to accept a procurement contract without cogent reasons, when the bid has been accepted by IESCO	06 month to 02 years as determined by the committee and forfeiture of securities
Non-satisfactory performance as mentioned in Appendix-2	2 years and forfeiture of securities
The contractor was blacklisted by the government or the donor agency and subsequently adopted by IESCO	3 years or the time period for which the concerned agency debarred the contractor, whichever is higher

In case the person/ contractor / firm/ consortium appeared in Consolidated Blacklisting Report shall also be considered debarred in participation of bidding process.

Note: All the penalties given herein above will be in addition to the consequences already agreed upon by the parties in the contract or any other documents.

CHAPTER NO. 8

APPRAISAL TO PROCUREMENT COMMITTEE/BOARD OF DIRECTORS

8.1 Appraisal of Blacklisted Firms to Procurement Committee/ Board of Directors (BoD)

The Procuring Agency shall apprise the Procurement Committee/Board of Directors (BoD) before communicating its Blacklisting decision to the Authority, if a Firm/Company/Bidder/JV/Manufacturer/Subcontractor/Consultant etc. is declared blacklisted by the IESCO.



CHAPTER NO. 9

COMMUNICATION OF NOTIFICATION TO AUTHORITY

9.1 METHODOLOGY FOR COMMUNICATION OF NOTIFICATION TO THE PPRA/NTDC/WAPDA/DISCOS

9.1.1 Unless otherwise provided in these policies, the blacklisting agency concerned shall submit to the PPRA /NTDC/WAPDA /DISCOs, within seven (7) calendar days after the issuance of the blacklisting order/delisting orders made by the agency, the following documents:

- a. Blacklisting Order duly signed by the Head of procuring agency containing, among others, Department/Office Order or Board Resolution number, name and address of the blacklisted person/entity, license number, if applicable, project/contract and location/amount, specific ground(s)/offense(s) committed as provided in article-9, sanction imposed and its date of start and completion, date of issuance of the order to blacklist, and other conditions which can extend duration of sanctions in article-9.
- b. Delisting Order duly signed by the blacklisting agency containing, among others, Department/Office Order or Board Resolution number, name and address of the blacklisted person/entity, name of project/contract and location, specific sanction being lifted and the number of previously issued blacklisting Department/Office Orders or Board Resolutions, effectively date of delisting, and date of delisting approval.

9.1.2 The PPRA shall prepare the Consolidated Blacklisting Report every quarter, based on the submitted Blacklisting Orders and disseminate the same to procuring agencies. The report shall be further posted in the PPRA website and shall indicate the number of times a person/entity has been blacklisted, the type of offense/violation committed, the penalty imposed, and the blacklisting agency concerned. The PPRA shall delist from such report those whose sanctions are lifted automatically after serving the given penalty as provided for in article-9 hereof and those whose sanctions are lifted through the issuance of Delisting Orders.

9.1.3 In the case of procurement of infrastructure projects, a blacklisting agency should decide to refer the case of its blacklisted person/entity to Pakistan Engineering Council (PEC)/SECP for license suspension/revocation, it shall submit

to PEC/SECP a copy of the decision accompanied with supporting documents.

- 9.1.4** All existing blacklisting reports of the Government or any of its procuring agencies, as well as the list of constructors/Consultant/consulting firms whose licenses are suspended or revoked by the PEC as of the date of effectiveness, are hereby adopted and made part of the PPRA Consolidated Blacklisting Report upon the issuance of these orders.

9.2 EFFECTIVENESS

These guidelines / mechanism or any amendments thereof shall take effect immediately after its approval from Board of Directors of IESCO.

9.3 AMENDMENTS

In the implementation of this policy, the IESCO/PPRA may introduce modifications thereto through the amendment of its specific provisions as the need arises. Any amendment to this policy shall be applicable to government projects advertised for bid after the effectiveness of the said amendment.

9.4 DELISTING

A blacklisted person/entity shall automatically be delisted after the period for the penalty shall have elapsed, unless the blacklisting agency requests the PPRA/NTDC/DISCOs/WAPDA to maintain the blacklisted person/entity in the PPRA/PPRA/NTDC/DISCOs/WAPDA Consolidated Blacklisting Report due to justifiable reasons. In the latter case, the blacklisted person/entity shall be delisted only upon the blacklisting agency's issuance of a Delisting Order.

APPENDIX-1

PROCESS TO DEAL WITH COMPLAINTS

It has been frequently observed that after opening of tenders, the bidders start to influence the evaluation process. Such misleading attempts results in delay in finalizing of award of contract and cause financial loss to the National exchequer and stain its sanctity. The evaluation process is confidential till publication of award of contract process.


Provision of guidelines of international donor agencies and PPRA provides sufficient opportunity to bidders for redressal of their grievances. Hence, the attempts made by the bidders during evaluation process or thereafter to influence the contract award decisions fall under the definition of corrupt and fraudulent practices. Therefore, during bidding stage, the following mechanism shall be adopted in case of receipt of any complaint from the bidder.

- i. Anonymous complaints shall not be entertained.
- ii. The Procuring Agency reserves the right to call for an affidavit from the complainant verifying the truthfulness and correctness of the contents of the complaint.
- iii. The notice of displeasure and explanation will be immediately sent to those firms who lodge the complaint during the evaluation process.
- iv. If the firm itself or through its agent or any third party does not refrain from making complaints in the same tender, the official warning will be sent and their case will be sent to IESCO's Rights Protection Committee which may analyses the situation and suggest action including the rejection of the bid of the complainant, However, Project Authority with prior approval of CEO IESCO. May reject the bid even in first instance depending upon nature of the case or provision of the Bidding Documents.
- v. If the same bidder itself or through its agent or any third party lodges complaint in another tender floating in parallel before decision of Committee, its bid will straight forwardly be rejected by the project authority. It may also be debarred to participate in the next tender for six months under intimation to the Committee and CEO IESCO.
- vi. If the same bidder itself or through its agent or any third party lodges complaint third time in the same or any other tender within a period of one years, its bid will be rejected and bid security will be forfeited by the project authority. It may also be debarred to participate in the next tender for one year under intimation to the committee and CEO IESCO.
- vii. In order to monitor the record of the bidders, a data base will be maintained at IESCO's website and the offices of the project authorities regarding firms / supplier / contractors/consultant who consistently lodge complaints during the evaluation process by making clandestine access to confidential record and hamper the award of contract process.

- viii. In order to monitor the record of the persons, a data base will be maintained at IESCO's website and offices of the project authorities regarding such persons who consistently lodge frivolous complaints during the evaluation process by making clandestine access to confidential record and hamper the award of contract process.

NOTE:

It is clarified that the process provided above in Appendix-I is to discourage anonymous and frivolous complaints only and does not mean to prevent any person aggrieved by any act of the procuring agency from lodging a genuine complaint /grievance as provided under Rule-48 of the PPRA Rules-2004.



APPENDIX-2

GUIDELINES FOR EVALUATION OF PERFORMANCE OF CONTRACTORS

- i. After signing of the contract, the Project authority (or the Consultant / Engineer) must monitor and evaluate the Contractor's performance, that is, whether the Contractor is fulfilling his obligations based on the terms of the contract and plans that were developed and agreed upon with the Project authority at the time of signing of contract or during kick-off meetings. In case of breach of contract or consistent non-performance security or debarment / blacklisting.
- ii. Though the contractor's performance evaluation is an on-going process, which takes place throughout the duration of the contract and also during the Defect Liability / Warranty Period, hence a Contractors Performance Evaluation Report shall be drafted by the project authority once all of the contractual obligations of the latter have been completed so that the project authority have gained a more complete picture that will help it in formulating a more objective judgment.
- iii. The performance evaluation report may be prepared for all contracts of more than Rs. 50 million. When based on the Evaluation Report, the performance of the contractor is non-satisfactory in. EPC contract(s) (or the contractor receives 02 No Notices of Default within same contract or against consecutive contract (s) within a period of 2 years) and 03 No supply contracts awarded within a period of 02 years, the procuring agency may initiate the case of blacklisting of the contractors in accordance with the terms of this mechanism.
- iv. In case of any extra-ordinary delay in performance of a single contract of vital and critical importance, the procuring agency shall have the right to terminate the contract, recover the loss and debar the bidder/firm/JV/contractor/consultant from participation in future tenders. The procuring agency shall be the sole judge to determine the importance of the project.
- v. The above said assessment will be in addition to the provisions already agreed by the parties in the contract or any other documents.



No.

/IESCO/ISB

Dated:

Form for Hearing

Through Registered AD, Courier Service or email or Fax

1. A committee for investigation of blacklisting Proceedings in furtherance of Rule 19 PPRA, 2004 has been constituted to investigate and decide upon the allegations at Para-2/below. You are required to appear in person or defend in writing with evidence on _____ at IESCO Head Office as to why you should not be blacklisted for:
2.

*****Add charge*****
3. You are being given an opportunity to be heard and are required to appear in person or defend in writing with evidence on _____ at IESCO Head Office. In case of you failure to attend or pay heed the Committee shall proceed ex-parte.
4. [To be added in the third notice]. As of final notice you are directed to furnish a satisfactory explanation in writing with supporting evidence within three days of receipt of this notice, to show cause as to why the blacklisting penalty may not be imposed. Failing to pay heed to this last notice shall stand a presumption against you that you have no explanation to offer and the matter shall be proceeded ex-part.

General Manager (Technical)
IESCO Head Office,
Street No. 40, Sector G-7/4.
Islamabad - 46000

Correction of defects in the warranty period

The period for taking remedial action for failure of correction of defects in the warranty period is:
Thirty (30) Days from the date defect notified to the supplier at his cost and expense.



TYPE TEST Requirements

The contractor shall supply valid type test reports according to WAPDA/NTDC specification along with the bid for the material offered. In case the type test reports furnished by the bidder are not from one of the laboratories mentioned below or any other reputed independent testing laboratories accredited by STL (Short-Circuit Testing Liaison) or are not relevant to the material offered or do not meet or comply with the ratings and other requirements of the Purchaser's Specifications included in this bidding document or are otherwise not to the satisfaction of the Purchaser in any respect, the bidder has to arrange Type testing at any one of the laboratories mentioned in the NTDC revised Type Testing Policy 2023 at his cost/Price of the bid without disturbing the stipulated delivery period/ bid price given above duly witnessed by 02 Nos. IESCO Engineers.

1. HV & SC Lab, Rawat, Pakistan
2. KEMA Lab, Holland
3. CESI, Italy
4. CRIEPI Lab, Japan
5. KERI Lab, Korea
6. Any other lab approved by STL
7. ILAC Lab

Payment (GCC Clause 19)

The method and conditions of payment to be made to the Supplier under this Contract shall be as follows:

Payment for Goods supplied from abroad:

A) payment will be made by the Finance Director IESCO Islamabad on production of the following documents:

- a) Bill in triplicate mentioning clearly NTN No. & GST No.
- b) Delivery Challan and GRN duly stamped and signed by the consignee (in original).
- c) Warranty Certificate.
- d) General Sales Tax Invoice.
- e) Inspection Certificates
- f) Certificate from Chief Engineer (Development) IESCO Islamabad regarding acceptance of Performance Bond.
- g) Certificate from Excise & Taxation Department, certifying the fact that all payable professional taxes have been cleared by the supplier.
- h) Custom clearance certificate
- j) Certificate issued from consignee store Manager that materials received vide GRN No. ___ dated ___ has been taken on stock against stock code No. ___
- k) The payment of General Sales Tax, fixed by the Government, shall be made to the firm on production of General Sales Tax return cum payment Challan
- l) Advance payment is not applicable.
- L IESCO local committee certificate

OR

B) Finance Director IESCO will establish a confirmed and irrevocable Letter of Credit for Rs._____/ - through any nationalized bank of Pakistan in your favor. All charges relating to opening of Letter of Credit and negotiation thereon, shall be borne by contractor. The amount of material excluding General Sales Tax i.e. Rs. ____/ - in the Letter of Credit shall be available for negotiation and en-cashable on submission of following documents: -

- i) Bill in triplicate mentioning clearly NTN No. & GST No.
- ii) Delivery Challan and GRN duly stamped and signed by the consignee
- iii) Warranty certificate
- iv) Inspection certificate from Nominated Inspector
- v) Certificate issued by the Chief Engineer (Development), IESCO Islamabad regarding acceptance of Performance Bond.
- vi) Certificate from Excise & Taxation Department, certifying the fact that all payable professional taxes have been cleared by the supplier.
- vii) General Sales Tax Invoice.
- viii) Certificate issued from consignee store Manager that materials received vide GRN No. ___ dated ___ has been taken on stock against stock code No. ___
- ix) The payment of amount of 18% General Sales Tax i.e. Rs. ____/ - in the Letter of Credit shall be available for negotiation and en-cashable on production of General Sales Tax invoice and General Sales Tax return cum payment Challan, as envisaged in Payment.
- x) Advance payment is not applicable.

The method and conditions of payment to be made to the Supplier under this Contract shall be as follows:

Payment for Goods and Services supplied from within Pakistan:

A) 100% payment will be made by the Finance Director IESCO Islamabad on production of the following documents:

- a) Bill in triplicate mentioning clearly NTN No. & GST No.
- b) Delivery Challan and GRN duly stamped and signed by the consignee (in original).
- c) Warranty Certificate.
- d) General Sales Tax Invoice.
- e) Inspection Certificates
- f) Certificate from Chief Engineer (Development) IESCO Islamabad regarding acceptance of Performance Bond.
- g) Certificate from Excise & Taxation Department, certifying the fact that all payable professional taxes have been cleared by the supplier.
- h) Custom clearance certificate
- j) Certificate issued from consignee store Manager that materials received vide GRN No. ____ dated ____ has been taken on stock against stock code No. ____
- k) The payment of General Sales Tax, fixed by the Government, shall be made to the firm on production of General Sales Tax return cum payment Challan
- l) Advance payment is not applicable.

OR

B) Finance Director IESCO will establish a confirmed and irrevocable Letter of Credit for Rs. ____/- through any nationalized bank of Pakistan in your favor. All charges relating to opening of Letter of Credit and negotiation thereon shall be borne by contractor. The amount of material excluding General Sales Tax i.e., Rs. ____/- in the Letter of Credit shall be available for negotiation and en-cashable on submission of following documents: -

- i) Bill in triplicate mentioning clearly NTN No. & GST No.
- ii) Delivery Challan and GRN duly stamped and signed by the consignee
- iii) Warranty certificate
- iv) Inspection certificate from Nominated Inspector
- v) Certificate issued by the Chief Engineer (Development), IESCO Islamabad regarding acceptance of Performance Bond.
- vi) Certificate from Excise & Taxation Department, certifying the fact that all payable professional taxes have been cleared by the supplier.
- vii) General Sales Tax Invoice.
- viii) Certificate issued from consignee store Manager that materials received vide GRN No. ____ dated ____ has been taken on stock against stock code No. ____
- ix) The payment of amount of 18% General Sales Tax i.e., Rs. ____/- in the Letter of Credit shall be available for negotiation and en-cashable on production of General Sales Tax invoice and General Sales Tax return cum payment Challan, as envisaged in Payment.
- x) Advance payment is not applicable.

NATIONAL TRANSMISSION AND DESPATCH COMPANY LIMITED
(NTDC)



SPECIFICATION P-46:2022

POWER TRANSFORMERS

Prepared By:	Engr. Fasih Ahmed Asstt. Manager SSD (S&R) NTDC Engr. M. Umar Aziz Dy. Manager SSD (S&R) NTDC	
Checked By:	Muhammad Imran Maqbool Addl. Manager SSD (S&R) NTDC Engr. Zia-ul-Haq Manager SSD (S&R) NTDC	
Recommended By:		
 (Engr. Farooq Rashid) Chief Engineer (PSP) NTDC (Member SRC)	 (Engr. Taqi-ud-din) Chief Engineer (P&C) NTDC (Member SRC)	 (Engr. Shoaib Khan) Chief Engineer (C&M) NTDC (Member SRC)
 (Engr. Shahid Shafi Sial) Chief Engineer (SS Design) NTDC (Secretary SRC)	 (Engr. Anwar Ahmed Khan) General Manager AM (N), NTDC (Member SRC)	 (Engr. Dr. Khawaja Riffat Hassan) General Manager (D&E) NTDC (Convener SRC)

SUBSTATION DESIGN DEPARTMENT NTDC

Foreword:

This specification has been prepared by Substation Design Department of NTDC.

This specification is intended for the procurement of material and does not include necessary provisions of a contract.

This specification is subject to revision as and when required by Substation Design Department of NTDC. No other department is authorized to issue any change/amendment in it.

REVISIONS & AMENDMENTS

<i>Sr. No.</i>	<i>Description</i>	<i>Date</i>
<i>1</i>	<i>First approved</i>	<i>15th October, 1968</i>
<i>2</i>	<i>First revised edition</i>	<i>15th June, 1979</i>
<i>3</i>	<i>Second revised edition</i>	<i>5th September, 1982</i>
<i>4</i>	<i>Third revised edition</i>	<i>3rd January, 1984</i>
<i>5</i>	<i>Fourth revised edition</i>	<i>10th November, 2004</i>
<i>6</i>	<i>Fifth revised edition</i>	<i>16th September, 2008</i>
<i>7</i>	<i>Sixth revised edition</i>	<i>1st November, 2022</i>

All Rights Reserved. Unless otherwise specified, no part of this document may be reproduced or utilized in any form or by any means without permission in writing from NTDC.



1	SCOPE.....	6
2	REFERENCE STANDARDS.....	6
3	SERVICE CONDITIONS	7
3.1	AMBIENT TEMPERATURE	7
3.2	RELATIVE HUMIDITY	7
3.3	ALTITUDE	7
3.4	ATMOSPHERIC CONDITIONS	7
3.5	AUXILIARY SERVICES	7
3.6	INGRESS PROTECTION	8
4	RATINGS AND CHARACTERISTICS.....	8
4.1	GENERAL	8
4.2	RATINGS.....	8
4.3	RATED POWER	8
4.4	TERTIARY WINDING	8
4.5	TEMPERATURE-RISE	8
4.6	TAPPINGS	9
4.7	TOLERANCE FOR GUARANTEED VALUES	9
4.8	OPERATION AT HIGHER THAN RATED VOLTAGE	10
4.9	SHORT-CIRCUIT WITHSTAND CAPABILITY	10
4.10	INSULATION	10
4.11	NOISE POWER LEVEL	10
5	ACCESSORIES.....	11
5.1	RECOMMENDED ACCESSORIES	11
5.2	OPTIONAL ACCESSORIES	11
5.3	TEMPERATURE-RISE OF ACCESSORIES	12
5.4	OIL LEVEL INDICATORS	12
5.5	OIL TEMPERATURE INDICATORS	12
5.6	WINDING TEMPERATURE INDICATORS.....	13
5.7	BUCHHOLZ RELAY.....	14
5.8	FANS AND CONTROLS.....	14
5.9	TRANSFORMER AUXILIARY PANEL.....	15
5.10	OUTDOOR CONTROL CABINET	16
5.11	LIFTING, MOVING AND JACKING FACILITIES	17
5.12	CONSERVATOR	17
5.13	DRAIN AND FILTER VALVES.....	18
5.14	PRESSURE RELIEF DEVICES	18
5.15	EARTHING TERMINALS	18
5.16	INSPECTING FACILITIES	18
5.17	OPTIONAL ACCESSORIES	19
6	BUSHINGS AND BUSHING CURRENT TRANSFORMERS	21
6.1	BUSHINGS.....	21
6.2	BUSHING CURRENT TRANSFORMERS	22
7	TRANSFORMER OIL.....	22
8	ON-LOAD TAPCHANGER	22
8.1	GENERAL	22



8.2	CONSTRUCTION	23
8.3	CONTROLS	23
8.4	POSITION INDICATORS.....	23
8.5	HOUSING.....	24
9	CONSTRUCTION REQUIREMENTS	24
9.1	TRANSFORMER TANK	24
9.2	TANK COVER	24
9.3	TRANSFORMER CORE	25
9.4	WINDINGS.....	25
9.5	CLAMPING STRUCTURE.....	26
9.6	GUIDES	26
9.7	RADIATORS	26
9.8	BASE	26
9.9	PAINTING	26
9.10	LV CABLE BOX.....	27
10	RATING PLATE	27
11	LOSSES.....	29
12	TESTS	29
12.1	FACTORY ACCEPTANCE TESTS	29
12.2	TYPE TESTS	31
13	GUARANTEED VALUES.....	34
14	SHIPPING CONDITIONS.....	34
15	TRANSPORTATION LIMITATIONS.....	35
16	DRAWINGS AND DESCRIPTIVE DATA	36
16.1	DRAWINGS AND DATA TO BE SUBMITTED WITH THE BID.....	36
16.2	DOCUMENTS AND DRAWINGS TO BE SUBMITTED FOR APPROVAL.....	37
16.3	FINAL MANUFACTURER'S DATA	39
17	SPARE PARTS	39
17.1	TENDER REQUIREMENTS.....	39
17.2	CONDITION OF SPARE PARTS	39
17.3	COMPLIANCE TO THE BIDDER.....	39
17.4	ESTIMATION OF REQUIREMENTS	40
17.5	SPARE PARTS BOOKS	40
17.6	PACKING	40
17.7	LIST OF SPARES.....	40
18	LIST OF DRAWINGS.....	41
ANNEXURE-1		42
SCHEDULE OF TECHNICAL DATA.....		42
ANNEXURE-2		58
LIST OF TABLES		58
TABLE-I:		58



TABLE-II:.....	65
ANNEXURE-3	66





SPECIFICATION NO. P-46:2022 FOR POWER TRANSFORMERS

1 SCOPE

1.1 This specification describes three-phase, mineral-oil-immersed, core type power transformers suitable for outdoor installation under the service conditions mentioned herein.

1.2 It covers the transformers of the following ratings:

1. 132/11.5kV, 50/63MVA
2. 132/66/11.5kV, 31.5/40MVA
3. 132/11.5kV, 31.5/40MVA
4. 132/11.5kV, 20/26MVA
5. 132/34.5kV, 10/13MVA
6. 132/11.5kV, 10/13MVA
7. 66/34.5kV, 10/13MVA
8. 66/11.5kV, 10/13MVA

The transformers shall be of the conservator type and fitted with forced cooling equipment, on-load tap changer and other accessories as described herein.

1.3 Other than the ratings defined in the clause 1.2, this specification shall be applicable to all power transformer having high voltage rating up to 145kV. The technical parameters for those special transformers shall be provided in the tender documents, however requirements laid down in this specification regarding service conditions, mechanical protective devices and testing shall be applicable.

2 REFERENCE STANDARDS

2.1 The transformers shall be supplied and tested in accordance with the following International Electro-Technical Commission Standards amended to date. The definitions given in the below IEC Publications shall apply herein. In case the requirements laid down herein differ from those given in the below IEC Publications, the transformers shall comply with the requirements indicated herein.

- IEC Publication 60076-1: Power Transformers-General
- IEC Publication 60076-2: Power Transformers-Temperature rise for liquid immersed transformers
- IEC Publication 60076-3: Power Transformers- Insulation Levels, Dielectric tests and external clearances in air
- IEC Publication 60076-4: Power Transformers-Guide to lightning impulse and switching impulse Testing-Power Transformers and reactors
- IEC Publication 60076-5: Power Transformers-Ability to withstand short-circuit
- IEC Publication 60076-7: Power Transformers-Loading guide for oil-immersed power transformers
- IEC Publication 60076-8: Power Transformers-Application guide
- IEC Publication 60076-10: Power Transformers-Determination of sound levels
- IEC Publication 60076-18: Power Transformers-Measurement of frequency response
- IEC Publication 60076-20: Power Transformers- Energy Efficiency
- IEC Publication 60076-22: Power Transformers- Power Transformer and Reactor Fittings
- IEC Publication 60137: Insulated Bushings for alternating Voltages above 1000V
- IEC Publication 60815-1: Selection and dimensioning of high-voltage insulators intended for use in polluted conditions – Part 1: Definitions, information and general principles



- IEC Publication 60815-1: Selection and dimensioning of high-voltage insulators intended for use in polluted conditions – Part 2: Ceramic and glass insulators for A.C. systems
- IEC Publication 61869-1: Instrument Transformers-General requirements
- IEC Publication 61869-2: Instrument Transformers- Additional requirements for current transformers
- IEC Publication 60214-1: Tap-changer-Performance requirements and test methods
- IEC Publication 60214-2: Tap-Changer-Application guide
- IEC Publication 60296: Fluids for electro technical Applications-Unused mineral insulating oils for transformers and switchgear
- IEC Publication 60422: Mineral Insulating Oils in electrical equipment – Supervision and maintenance guide
- IEC Publication 60529: Degree of Protection Provided by Enclosure (IP Code)

3 SERVICE CONDITIONS

The power transformers and all accessories shall be suitable for satisfactory operation under the following service conditions.

3.1 Ambient Temperature

Maximum	50°C
Maximum mean over any 24 hours	45°C
Mean in any year	30°C
Minimum	-10°C

3.2 Relative Humidity

The relative humidity may range up to 100%. The maximum values of the ambient temperature and humidity, however, do not occur simultaneously. During the monsoons, high humidity may persist for many days at a time, with temperature ranging from 30°C to 40°C.

3.3 Altitude

Installations will be up to 1000 meter above sea level.

3.4 Atmospheric Conditions

- 3.4.1 It may be assumed that the air is not normally heavily polluted by dust, smoke, aggressive gases, vapours or salt spray. However, at certain times of the year, severe dust storms may be experienced.
- 3.4.2 Certain areas are subjected to heavily polluted atmosphere and insulation of bushings for installation in such areas shall have an extended creepage distance from live to earthed parts.

3.5 Auxiliary Services

- 3.5.1 The AC supply for control and auxiliary circuits shall be as under:

Type of System	3-Phase, 4 Wire, neutral solidly earthed
Rated Voltage	240/415
Limits of supply voltage which an AC operating device or auxiliary equipment shall be capable of operating correctly	+10% -15%
Rated Frequency	50 Hz
Limit of frequency between which an AC operating device or auxiliary equipment shall be capable of operating correctly	48-51 Hz



<i>Initial symmetrical 3-phase short-circuit current</i>	<i>15kA</i>
<i>One minute power frequency withstand voltage for the auxiliary circuits</i>	<i>2000V</i>

3.5.2 The DC supply for auxiliary circuits shall be 110V. The limits of variations are plus 15 percent and minus 20 percent.

3.6 Ingress Protection

All outdoor accessories, enclosures and control cabinets shall be weatherproof and all metal parts shall be corrosion and abrasion resistant and degree of protection shall be IP-55 as per IEC 60529.

4 RATINGS AND CHARACTERISTICS

4.1 General

The power transformers shall be self-cooled for ONAN rating, forced-air-cooled for ONAF rating, self-contained, equipped with conservators, radiators, on-load tap changers, transformer control & auxiliary panels and supplied complete with all other accessories specified herein and/or required for smooth normal operation at site. The transformer shall be supplied with tin plated copper bus bars (for rating above 26MVA) for LV cable connections. The size of the bus bars shall be according to the rating of the transformer i.e. under full load current at upper rating the max current density shall not be more than 1.2 A/mm²

4.2 Ratings

The specified ratings and design data of the power transformers shall be in accordance with Annexure-2, Table-I given herein.

4.3 Rated Power

4.3.1 The high and low voltage windings on each transformer shall be assigned two power ratings i.e. lower and upper as specified in Table-I. These ratings shall be such that the transformer can deliver respective rated current under steady loading conditions without exceeding the limits of temperature-rise specified in Table-I and clause 4.5 at both the ratings. In the case of 132/66kV transformers, this requirement must be met with the tertiary windings also loaded as specified in BOQ of tender and supplying rated kVA power to static capacitors.

4.3.2 The power transformers shall be capable of being loaded up to 1.5 times the rated value for intermittent overloading in accordance with IEC Loading Guide or its equivalent. The ratings of bushings, on-load tap changers and other auxiliary equipment shall be such that they do not limit the application of such overloads.

4.4 Tertiary Winding

A delta-connected tertiary winding shall be provided in 132/66kV transformers which shall have voltage and power ratings as specified in Table-I. This rated power shall be obtained with the other two windings also operating at rated power under either cooling condition. This requirement shall be met with a tertiary load consisting of static capacitors.

4.5 Temperature-rise

The maximum ambient temperature is 50°C and as such the temperature-rise of windings, core and oil when tested shall not exceed the following:

- a) Windings (measured by resistance) 55°C



- b) Top oil (measured by thermometer) 50 °C
- c) For core and other parts, the temperature-rise shall be such that in no case the temperature should reach a value that will injure the core itself or adjacent parts or materially affect the life of the transformer.

4.6 Tappings

The tappings shall be provided on the high voltage windings. The tapping power shall be equal to the rated power for connections on all tappings. The category of regulation shall be constant flux regulation. The voltage range for which the tappings are to be designed is specified in Table-I and Table-II.

4.7 Tolerance for Guaranteed Values

4.7.1 Tapping Voltages & Voltage Ratios

Tapping voltages of the tapped HV windings have been specified in Table-II given herein. The voltage ratios at different taps, including the principal tap, shall not vary by more than 0.5 percent of the specified value.

4.7.2 Short-Circuit Impedance

- 4.7.2.1 The tolerances for short-circuit impedance at principal tap and extreme taps between HV and LV windings of the transformers shall be as per table below:

At Principal tapping	a) When impedance value is $\geq 10\%$, $\pm 7.5\%$ of the specified value b) When Impedance value is $< 10\%$, $\pm 10\%$ of the specified value
At extreme tapping	a) When impedance value is $\geq 10\%$, $\pm 10\%$ of the specified value b) When Impedance value is $< 10\%$, $\pm 15\%$ of the specified value

- 4.7.2.2 The short-circuit impedance between LV and tertiary windings of 132/66kV transformers shall not differ by more than +15% or -10% of the specified value.

- 4.7.2.3 In any case the short-circuit impedance at principal tap differs by more than 5% (for impedance $< 10\%$) or 3.5% (for impedance $\geq 10\%$) of the specified/guaranteed value, the difference up to 5% or 3.5% (where applicable) shall be ignored whereas a penalty at the rate of the capitalized costs of no-load losses indicated in clause 11 per one percent of difference beyond 5% or 3.5% (where applicable) and up to the limit mentioned under 4.7.2.1 shall be payable by the supplier. The transformers having difference of short-circuit impedance beyond 10% or 7.5% (where applicable) of the specified/guaranteed value shall be rejected.

4.7.3 Regulations

Voltage regulation, computed from the impedance volts and watts, may exceed the guaranteed regulations at unity and 0.8 lagging power factor by no more than 10%.



4.7.4 Losses

4.7.4.1 The tolerance for total losses i.e. load and no-load losses shall not exceed 10% of the guaranteed values. The component losses may exceed the respective guaranteed values by up to 15% provided the tolerance specified for the total losses is not exceeded. If 10% tolerance specified for the total losses is exceeded, then transformer shall be rejected.

4.7.4.2 A penalty at twice the rate of the capitalized costs of no-load and load losses indicated in clause 11 shall be payable by the supplier for the losses in excess of the guaranteed values.

4.7.5 No Load Current

The tolerance for the no-load current shall be 30% of the guaranteed value.

4.8 Operation at Higher than Rated Voltage

4.8.1 The transformer shall be capable of continuous operation at an applied voltage equal to 110% of tapping voltage and at maximum frequency. At such higher applied voltage, it shall be capable of delivering continuously the tapping current. Except that, for applied voltages greater than the system highest voltage, the continuous current capability may be lower than the rated values.

4.8.2 The capability of the transformers for continuous operation at specified higher voltage (110%) without exceeding the permissible temperature-rise limit shall be verified during temperature-rise tests.

4.8.3 The manufacturer shall determine the operating conditions under which the maximum flux density will be attained in the core and shall state the maximum flux density. The maximum flux density on higher voltage operation shall not exceed 1.9 tesla according to the overvoltage operation data prescribed in Annexure-3 of this specification.

4.9 Short-circuit Withstand Capability

4.9.1 The transformers shall be designed and constructed to withstand without damage the thermal and dynamic effect of any external short-circuit at any terminal when connected to a high capacity 132kV or 66kV system. The symmetrical short-circuit withstand current in any winding is specified in Table-I as a multiple of rated current based on lower rated power for the winding.

4.9.2 The transformers may be subjected to frequent short-circuit/earth faults. The transformers shall, therefore, be so designed as to cope with the particular service conditions and shall withstand without damage the effects of the electro-mechanical forces arising under short-circuit conditions resulting from the frequent short-circuit faults with the peak value of the asymmetrical current equal to 2.55 times the rms value of the specified short-circuit current.

4.9.3 The transformers shall be capable of withstanding the thermal effects of the specified short-circuit current for three seconds. The maximum temperature of the windings calculated in accordance with the formula given in IEC Publication 60076-5 shall not exceed 250°C.

4.10 Insulation

The 132kV windings of 132/66kV transformers may be graded. The grading of the insulation shall be such that the winding can meet the test voltage requirements laid down in Table-I. All other windings shall be uniformly insulated.

4.11 Noise Power Level

The maximum noise power level for all type of transformer shall not be more than 70db at ONAN rating and 80db at ONAF rating.



5 Accessories

5.1 Recommended Accessories

5.1.1 The transformers shall be provided with at least the following accessories mounted generally in accordance with drawing No. EW/TS-193.

- a) Oil level indicators magnetic type,
(one each for main and OLTC conservators)
- b) Oil temperature indicators
Winding temperature indicator(s),
(one for rating up-to 30MVA and two for rating greater than or equal to 30MVA)
- c) Thermometer pockets
- d) Buchholz relay (with valves on both sides)
- e) Fans and controls
- f) Auxiliary panel
- g) Control cabinet
- h) Lifting eyes for cover only
(optional for transformers other than 10/13MVA)
- i) Facilities for lifting the core and coil assembly
- j) Lugs for lifting complete transformer
- k) Moving facilities/flanged roller wheels
- l) Jacking facilities
- m) Oil conservator with silica gel breather
- n) Drain and filter valves comprising:
 - i. One drain valve
 - ii. Two filter valves of about 30mm dia
 - iii. Two sampling valves of about 20mm dia
 - iv. Air release plug
 - v. Oil filling plug
- o) Pressure relief devices
- p) Earthing terminals for tank
- q) Inspection facilities
- r) Rating plate
- s) Terminal marking plate

5.1.2 Accessories not indicated in drawing No. EW/TS-193 shall be located at suitable places by the manufacturer with specific approval of the purchaser prior to manufacture.

5.1.3 Accessories with markings or dials shall be mounted at a height of approximately 1.5 meter from the base of transformer in such positions as to be easily readable by a person standing on the ground. If necessary, dial faces shall be mounted at an inclined angle for easy visibility/readability

5.2 Optional Accessories

- i. Self-regenerating breather
- ii. Fiber optic direct measurement system
- iii. Online-Dissolved Gas Analyzer



5.3 Temperature-rise of Accessories

For transformer accessories and their parts, the temperature-rise, when tested at the most severe operating ratings shall not exceed the values given below. The values shall be determined by the resistance method.

<i>Insulation Class</i>	<i>Maximum Temperature-rise</i>
<i>Y</i>	<i>40°C</i>
<i>A</i>	<i>55°C</i>
<i>E</i>	<i>70°C</i>
<i>B</i>	<i>80°C</i>
<i>F</i>	<i>105°C</i>
<i>H</i>	<i>130°C</i>
<i>C</i>	<i>No limit</i>

The classification of insulating materials is according to IEC Publication 60085.

5.4 Oil Level Indicators

- 5.4.1 Two oil level indicators shall be fitted one on each end of the conservator. The indicators shall be of the magnetic type. Both the indicators shall be provided with alarm contacts for low oil level. These oil type indicators shall be in accordance with IEC 60076-22-1
- 5.4.2 The indicators shall have a dark face dial with light markings and a light-colored indicating hand. The diameter of the dial shall be about 150mm. The dial marking shall show the oil levels corresponding to -10, 0, 15, 25, 35, 45, 55 and 90°C as well as the high and low oil levels.
- 5.4.3 The words “Oil Level” shall be marked on the dial or on a suitable name plate.
- 5.4.4 The contacts have rated current 2A rms and short time current 10 A rms for 30ms. The making and breaking capacity shall conform to IEC 60076-22-1.
- 5.4.5 The manufacturer shall provide the graph between “temperature Vs Oil Volume” for future reference. This graph shall be printed on the steel plate and shall be installed on the transformer at suitable location.

5.5 Oil Temperature Indicators

- 5.5.1 Two oil temperature indicators, one liquid type and the other of resistance type shall be provided to indicate the top oil temperature. These indicators shall be in accordance with IEC 60076-22-1.
- 5.5.2 The indicators shall have a dark face dial with light markings, a light-colored indicating hand and an orange maximum indicating hand with provisions for resetting. The diameter of the dial (inside bezel) shall be about 125mm. The dial markings shall cover a range of 0 to 120°C. The words “Oil Temperature” shall be marked on the dial or on a suitable nameplate. The indicating dial shall be mounted in the outdoor control cabinet.
- 5.5.3 The measuring element of the resistance type oil temperature indicator shall be mounted inside a stainless-steel tube.
- 5.5.4 One (01) alarm and two (02) trip contacts with each indicator shall be provided. Contacts shall also be provided for control of fans and for remote indication. The contacts shall be wired and connected to terminal blocks in the outdoor control cabinet. The contacts for fans, alarms and trip shall be wired for use as an alternate to the main scheme described in clause 5.5. Necessary wiring diagrams shall be provided showing the scheme and the changes required for the changeover.



- 5.5.5 The alarm and tripping contacts shall be adjustable to close between 60 to 120°C. Both shall reopen when the temperature has fallen by not more than 10°C below the preset value. The fan control contacts shall be adjustable to close at any temperature between 50°C & 100°C and to reopen when the temperature has dropped by 15°C to 30°C. All contacts shall be conveniently adjustable, and a setting scale shall be fitted. They shall be accessible on removal of the cover. The alarm and trip contacts have rated current 2A rms and short time current 10 A rms for 30ms. The making and breaking capacity shall conform to IEC 60076-22-1.
- 5.5.6 It shall be possible to move the pointers of the temperature indicators by hand in order to test the tripping, alarm and cooling apparatus circuits. The working parts of the instruments shall be visible through glass fronted covers.

5.6 Winding Temperature Indicators

- 5.6.1 The power transformers of ratings less than 30MVA shall be provided with one while power transformers of ratings above or equal to 30MVA shall be provided with two resistance type devices of different make for indicating the hottest spot winding temperature. Where two devices are provided the contacts of both devices shall be connected in parallel with each other. This indicator shall be in accordance with IEC 60076-22-1.
- 5.6.2 The device shall have a dial type indicator and a pointer to register the highest temperature reached. One (01) alarm and two (02) trip contacts with each indicator shall be provided. Contacts shall also be provided for control of fans and for remote indication. The dial marking shall cover a range of 0-130°C. The words “Winding Temperature” shall be marked on the dial or on a suitable nameplate.
- 5.6.3 The temperature indicator(s) shall be mounted in the outdoor control cabinet. There shall be provided a remote electrically operated repeater indicator for mounting on the transformer auxiliary panel in the control room.
- 5.6.4 The alarm and tripping contacts shall be adjustable to close between 70°C to 130°C. Both shall reopen when the temperature has fallen by not more than 10°C below the preset value. The fans control contacts shall be adjustable to close at any temperature between 50°C & 100°C and to reopen when the temperature has dropped by 15°C to 30°C. All contacts shall be conveniently adjustable, and a setting scale shall be fitted. They shall be accessible on removal of the cover. The alarm and trip contacts have rated current 2A rms and short time current 10 A rms for 30ms. The making and breaking capacity shall conform to IEC 60076-22-1.
- 5.6.5 It shall be possible to move the pointers of the temperature indicators by hand in order to test the tripping, alarm and cooling apparatus circuits. The working parts of the instrument shall be visible through glass fronted covers.
- 5.6.6 Terminals, links and an ammeter shall be provided in the outdoor control cabinet for each winding temperature indicator for:
- Checking the output of the CT
 - Disconnecting the heating coil from the CT secondary to enable the instrument to be used as an oil temperature indicator
- 5.6.7 A diagram and instruction plate embossed on the steel sheet for the above shall be fixed in outdoor control cabinet. It shall be durable and non-corrosive. The maintenance instructions shall include graphs or table showing the relationship between current injected into the heating coil and the corresponding indicated readings between no-load and full load of the transformer.



5.7 Buchholz Relay

5.7.1 A buchholz relay shall be provided with isolating valves on both sides of buchholz relay. It shall be designed to operate rapidly for internal transformer faults and will be equipped with one (1) alarm and two (2) trip contacts. The contacts have rated current 2A rms and short time current 10A rms for 30ms. The making and breaking capacity shall conform to IEC 60076-22-1. The alarm contact shall be set to operate from a low rate of gas evolution. The tripping contact shall be operated from a high rate of gas evolution or oil movement such as experienced from internal transformer faults or internal flashover. Further, during approval stage of buchholz relay, the manufacturer will submit all brochures, catalogues and test reports along with mentioning operating time of buchholz relay.

5.7.2 The buchholz relay shall be provided in accordance with IEC 60076-22-1.

5.8 Fans and Controls

5.8.1 The transformers shall be fitted with fans to meet the ONAF ratings. The number of fans shall be such that full ONAF rating of the transformer can be obtained with 25% of the total mounted fans not working. When the number of fans is four or less, the transformers shall be capable of full output with at least one fan shutdown. The fans provided with the transformer shall be in accordance with IEC 60076-22-6.

5.8.2 The fans shall be motor driven and of design suitable for continuous operation in the service conditions specified. The fan blades shall be made of galvanized steel unless otherwise approved. Galvanized wire mesh guards with mesh not greater than 20mm shall be provided over the blowers and all moving shafts and coupling shall be guarded. It shall be possible to remove a fan unit without dismantling of radiators or the supporting structures. All necessary ducting shall be installed and shall consist of galvanized steel sheet suitably stiffened by angles.

5.8.3 The motors for the fans shall be 3-phase AC operated. The output rating of the fan motors shall be enough for the duty required. The temperature-rise of fan motors shall be such that the maximum permissible temperature for the motor insulation is not exceeded under the service conditions specified herein. This may mean a reduction in the allowable temperature-rise of 10°C and corresponding de-rating of motor output. The insulation class of motor and name of manufacturer along with origin of country should be mentioned in schedule of technical data.

5.8.4 Each fan, or a group of fans, shall be provided with a miniature circuit breaker for protection and with an electrically operated contactor and with controls for starting and stopping the motors by hand or automatically. It shall be possible to select automatic or manual control. Selection for hand/automatic operation shall be made at the transformer auxiliary panel. For spare fans, separate MCB with 1 NC contact shall be provided in outdoor control cabinet.

5.8.5 The automatic starting of the fan motors shall be controlled from the contacts on the winding temperature indicator described in clause 5.5. Contacts shall be provided for remote indication of fan operation.

5.8.6 The control equipment shall be mounted in the outdoor control cabinet and all wiring, conduit and cable boxes between the outdoor control cabinet and the fans shall be provided. Further, all wiring and conduit should be run in cable trays.

5.8.7 An AC under voltage relay with contact closure upon the voltage failure adjustable between 0.2 and 4.0 seconds shall be provided on each transformer to actuate alarm of service power failure. The contacts shall be suitable for operation on ungrounded 110V DC service. This relay shall be in the outdoor control cabinet.



5.9 Transformer Auxiliary Panel

5.9.1 Each power transformer shall be supplied with a transformer auxiliary panel for remote control and at least the following equipment shall be mounted on the front of the panel:

- i. Tap position indicator
- ii. Oil and winding temperature remote indicators
- iii. Switches/push buttons for manual raise/lower of tap-changer taps
- iv. Indication lights for “tap-changer in progress”, “raise/lower” of tap-changer taps
- v. Selector switch for individual/parallel operation of transformer tap-changers
- vi. Switches/push buttons for manual operation of cooling fans from remote
- vii. Indication lamps for indicating operation of each fan or group of fans
- viii. Selector switch for selecting operation of cooling fans i.e. local, remote and automatic
- ix. Automatic voltage regulator, if specified in the tender enquiry
- x. Emergency stop switch for tap-changer

5.9.2 The transformer auxiliary panels shall be dimensioned 600mm (W), 600mm (D) and 2200mm (H), wired and constructed as specified herein. It shall have a single leaf hinged door at the rear. The instruments shall have a scale length not less than 125mm. Rear mounted auxiliary relays and devices shall be mounted at right angle to the panel and be so situated that they shall not interfere with or prevent free access to wiring.

5.9.3 Panels will be made from steel sheet of minimum 2.3mm thickness with edges formed into a rectangular pattern or welded to steel shapes so that each section is rigid and self-supporting. Cutouts for relays, meters, instruments and accessories shall be cold punched. All interior and exterior surfaces of panels, tops, sections and doors shall be thoroughly cleaned of rust and scale before applying a rust inhibitor primary coat of paint.

5.9.4 Unfinished concealed surfaces will not be accepted. Interior and exterior surfaces shall be finished with several coats of thick drying lacquer or paint with a dull grey-green color. Minimum thickness of the paint shall be 0.1mm.

5.9.5 The auxiliary panel will be completely assembled, wired and tested at the factory. The schematic wiring of the panel shall be provided on a plate of stainless steel or brass fixed on the panel in a visible position. The markings on the plate shall be indelible and marked by engraving. Shipment will be as a complete unit except that certain components may be shipped un-mounted to ensure safe delivery.

5.9.6 Wiring between devices and terminal blocks shall be carried in troughs or in neatly formed packs which shall be tied or otherwise secured at frequent intervals to prevent undue stress on equipment or connections. Connections across portions which are hinged or otherwise moveable shall be made with flexible wire, formed to distribute the bending motion. No connections shall be made with wire smaller than 2.5 sq mm, except to annunciator relays or to similar miniature devices where use of smaller flexible wiring is indicated. Ends of each wire shall be identified by a machine lettered permanent fiber or plastic labels securely attached to the conductor. Stacking of wires on terminals will not be permitted.

5.9.7 Terminal blocks shall be mounted at an easily accessible position approximately 300mm from the base and shall be equipped with barriers, terminal strips and color-coded strips. The AC and DC circuits shall be physically segregated in groups. The AC 240/415V circuit terminals will be fitted with non-inflammable transparent plastic covers to prevent accidental contact with live parts. Each incoming and outgoing conductor shall be connected to an individual terminal. Each terminal block shall have an individual marking strip which shall be machine lettered or engraved with the



circuit designation of the terminals which shall also be shown on the wiring diagrams. One spare marking strip shall be provided for each terminal block. Ten Percent (10%) spare terminal blocks of each type shall also be mounted on the auxiliary panel.

- 5.9.8 All metallic cases of control and indicating devices shall be provided with an accessible copper tail to facilitate connection by means of bare copper conductors of not less than 2.5 sq. mm section to the nearest earth bar.
- 5.9.9 If specified in the tender enquiry, the auxiliary panel shall be equipped with automatic voltage regulator along with its ancillary equipment suitable for operation at the auxiliary P.T. voltage of 110V and CT secondary current of 2A (Min.). The panel shall be completely wired for parallel operation of power transformers. The out-of-step lockout and signaling relays shall be provided.

5.10 Outdoor Control Cabinet

- 5.10.1 A steel sheet, vermin-proof, vibration free, well ventilated and weather-proof cabinet, constructed generally as specified above, shall be provided for the power transformer ancillary and control apparatus. It shall be mounted on the power transformer.
- 5.10.2 The cabinet shall be divided into separate compartments for accommodation of:
- i. Oil and winding temperature indicators and ancillary equipment
 - ii. Control and protective gear for the cooling apparatus including a circuit breaker in the incoming circuit capable of carrying and breaking the full load current of all fan motors
 - iii. Terminal boards and gland plates for all alarm/trip contacts of accessories, terminal leads of the tap changer and the AD/DC incoming and outgoing cables. All the terminals shall be properly labeled
- 5.10.3 All instruments and equipment shall be mounted on panels and back of panel wiring shall be used. Each compartment shall preferably have a separate access door. The door shall have lift-off type hinges and be fastened by handles with provision for locking. The door of the temperature indication compartment shall be provided with glazed window of adequate size for observing temperature indication equipment.
- 5.10.4 It shall be possible to remove the temperature indicators from the panel without the necessity of passing the connecting leads and the capillary tubes through the various compartments.
- 5.10.5 Identification labels shall be provided on the outside of the control cabinet doors. The schematic wiring of the control cabinet shall be provided on a plate of stainless steel or brass fixed on the cabinet in a visible position. The markings on the plate shall be indelible and marked by engraving.
- 5.10.6 All wiring and cables installed on and around the side of the power transformer and connections from the accessories to the outdoor control cabinet shall withstand inclement weather conditions for entire life of power transformer and enclosed in metallic conduits or raceways. The conduits may be rigid or flexible. The cables shall conform to NTDC specification P-100 (amended to date) with the exception that these shall be without copper screen.
- 5.10.7 Lighting arrangements and thermostatically controlled heaters shall be provided for the outdoor control cabinet. Lighting and heater should have flexible arrangement which can be replaced easily.



5.11 Lifting, Moving and Jacking Facilities

5.11.1 Lifting Facilities

Lifting eyes shall be provided for lifting the cover alone in case the latter is separable from the core and coil assembly. Adequate facilities shall be provided for lifting the core and coil assembly from the tank.

Lugs for lifting the complete transformer shall be provided. The bearing surface of the lifting lugs shall be free from sharp edges and each lifting lug shall be provided with a hole having a minimum diameter of 20mm for guying purposes.

5.11.2 Moving Facilities

The base of the transformer shall have members forming a rectangle which will permit rolling in the directions of the center lines of the segments.

The points of support of these members shall be so located that the center of gravity will not fall outside these points of supports for a tilt of the base of 15° or less from the horizontal, with or without oil in the transformer or in the tap-changer compartment.

Bidirectional flanged rollers shall be provided on power transformers. Unless otherwise specified, the gauge shall be 1676 mm in both directions. Blocking devices for the rollers shall be provided. Provisions shall be made on or adjacent to the base for pulling the transformer parallel to either side. The wheel assembly shall also conform to the requirement laid down in IEC 60076-22-7.

5.11.3 Jacking Facilities

Jacking facilities shall be located near the outer ends of the base. The jacking pads or lugs shall be so designed that the lifting member of jacks of suitable capacity can be inserted when the transformer is completely assembled.

5.12 Conservator

5.12.1 The transformers shall be provided with conservators complete with sump and drain valve and having a capacity of not less than 7.5% of the total cold oil volume in the transformer and radiators.

5.12.2 If the sump is formed by extending the feed pipe inside the conservator, this extension shall be for at least 75 mm. The minimum indicated oil level shall be with the feed pipe covered by not less than 15 mm depth of oil. The indicated range of oil levels shall correspond to average oil temperatures from -10°C to 90°C.

5.12.3 Two oil level indicators as specified in clause 5.3 shall be provided, one on each end of the conservator.

5.12.4 One end of the conservator shall be removable for cleaning purposes and the drain valve shall be so situated that the conservator can be completely emptied when mounted as in service.

5.12.5 The pipe from the transformer to the conservator shall be of at least 75 mm inside diameter and shall rise at an angle of from three to seven degrees to the horizontal. A valve shall be provided at the conservator to cutoff the oil supply to the transformer.

5.12.6 Each conservator vessel shall be fitted with a silica gel dehydration breather of adequate size; the silica gel container being mounted approximately 1.5 m above ground level and arranged so that the tinted crystals may be easily observed. The breather bottom shall be equipped with a glass



bowl containing oil to prevent the moisture from penetrating silica gel when the transformer is not 'breathing' and to give a visual indication in the form of air bubbles during breathing process. The breathers provided shall conform to the IEC 60076-22-7.

5.13 Drain and Filter Valves

5.13.1 The transformers shall be fitted with the following valves:

- a) One drain valve of adequate size so situated that the tank can be drained of oil as far as practicable. The size of the valve shall be 75 to 100 mm dia for smaller transformers but shall be greater as required for the larger transformers.
- b) Two filter valves of about 40mm dia, one at the top and other at the bottom of the tank, diagonally opposite to each other for connection to the oil circulating system. The flanges shall have four holes on a bolt circle diameter of 110mm. The hole size shall be 14mm.
- c) Devices of 20mm dia for sampling the oil at the bottom and middle or top of the tank but independent of the specified filter valves and situated so as to be readily accessible with the transformer live and in service.
- d) Globe valves shall be provided on each side of the buchholz relay. The coupling of the valves shall be made by means of flanges for easy replacement of the relay.

5.13.2 All valves opening to atmosphere shall be fitted with blank flanges. All valves shall be of iron body with bronze or stainless-steel trim. They shall be the globe or other approved type. Means shall be provided for locking the valves. Each valve shall be provided with an indicator clearly showing its position. Manufacturer's catalogue/literature shall be submitted with the bid and for approval before installation.

5.13.3 Manufacturer shall ensure that these valves fitted with the transformer shall conform the requirements laid down in the IEC 60076-22-7.

5.14 Pressure Relief Devices

5.14.1 One or two pressure relief devices as necessary as per manufacturer design and suitably located shall be provided for rapid release of any dangerous pressure within the transformer. The device shall operate at a pressure less than the test pressure of the tank and the outlet shall be arranged to face away from the bushings as well as adjacent transformer or other equipment. If a diaphragm is used, it shall be of approved material, permanently resistant to strong sunlight. The pressure relief device shall be in accordance with the requirements laid down in IEC 60076-22-1.

5.14.2 One Alarm and two trip contact with each pressure relief device having rated current 2A rms and short time current 10 A rms for 30ms shall be provided. The making and breaking capacity shall conform to IEC 60076-22-1.

5.15 Earthing Terminals

Two earthing terminals each capable of carrying the full low voltage current for three seconds shall be provided, with provision for fitting to any of the bottom four corners of the tank, to suit local earthing arrangements. They shall be suitable for 95 to 185 sq mm standard copper earthing lead. It shall further conform to other requirements as laid down in IEC 60076-22-7.

5.16 Inspecting Facilities

5.16.1 Adequate facilities shall be provided for inspection, testing and carrying out minor repairs in the interior of the transformers when assembled without draining the oil completely. Such facilities shall include at least two hand holes on the top cover to afford easy access to lower ends of the bushings, terminals, the upper portion of the coils and permit replacement of auxiliaries without



removing the tank cover or un-tanking. Suitably sized and located manhole(s) shall be provided for the inspection of tap-changer.

- 5.16.2 The smallest dimensions of hand hole and manhole shall be about 300mm and 800mm respectively or as approved. The covers shall have adequate handles to facilitate lifting.

5.17 Optional Accessories

5.17.1 Self-regenerating Breather

If required in the bidding document, the manufacture shall supply the transformer with the self-regenerating, maintenance free silica gel breather for both transformer compartment and on load tap changer. The size of the breather shall mainly depend upon volume of oil in transformer along-with other factors i.e., service conditions, properties of the oil etc. The offered breather shall conform to all requirements laid down in IEC 60076-22-7.

The breather shall have option to trigger regeneration process by two different principles i.e., condition or time based.

The breather shall have two signaling contacts one for silica-gel regeneration other for device error. The rating of contacts shall be 2A rms and short time current 10 A rms for 30ms. The making and breaking capacity shall conform to IEC 60076-22-7.

The breather shall be equipped with data logger which can record the information about oil temperature, relative humidity, number of regeneration cycle and error state of the device with time & date stamp. The internal memory of the logger shall be large enough to store data for 10 years minimum. The sampling rate shall not be more than 30 mins. These parameters i.e. oil temperature and relative humidity shall be displayed in outdoor control cabinet and transformer auxiliary panel through analogue output signal while status display shall be on the connection box of the breather.

The breather shall be equipped with universal power supply and capable of operating at both AC and DC auxiliary supply voltages as mentioned under clause 3.5.

The logger data shall be accessible through USB (local communication) while requirements of MODBUS (remote) communication for SCADA/SAS system shall be mentioned during bidding stage.

The type test reports of the offered breather shall be provided in accordance with IEC 60076-22-7 clause 6.6.5.3.

All routine tests shall be performed on the device as per clause 6.6.5.2 of IEC 60076-22-7.

5.17.2 Fiber-Optic Direct Temperature Measurement System

If required in the bidding document, the manufacture shall equip the transformer with fiber-optic temperature measurement system. It shall mainly measure the hot-spot temperature of windings directly. It shall also be used to measure core/clamping structure temperature and oil temperature at inlet and outlet of the radiators. This system is recommended for transformer having rating greater than 26MVA.



This system shall consist of probes/sensors, tank-wall plate for interfacing, extension cables and controller. The probes/sensor shall be installed in the winding directly while the tank wall plate shall be used for interfacing between probes/sensors and controller through extension cables. The probe/sensor shall be highly robust and protected against static fatigue and abrasion and it shall be able to withstand pull test of 60N force. The probe/sensor shall exhibit very low partial discharge i.e less than 2pC under extra high voltage. The tank wall plate shall have penetrators welded on the plate. The number of penetrators shall be as per number of the probes/sensor used.

For all two winding transformers having rating less than 100MVA, total six (06) number of sensors shall be used one for each LV and HV winding. For three winding transformers, an additional sensor shall be used for the tertiary winding of the central limb. For two winding transformers have rating greater than 100MVA, the central limb windings (HV & LV) shall have two sensors, while for three winding transformer, all three tertiary winding shall have sensor. The sensors shall be placed at the top of the windings and their placement shall be in the region where maximum hot-spot temperature of the winding is expected. Other guidelines of the IEC 60076-2 Annex-E shall be followed in this regard.

In addition to the above, all transformers shall have one sensor installed in the middle of the top part of the transformer core for monitoring of core temperature. The requirement of the sensors at the inlet and outlet of the radiators to monitor the temperature of the oil shall be mentioned in the bidding document.

The controller shall have enough channels to accommodate all the temperature sensors and shall be mounted in the out-door control cabinet while necessary arrangements shall be made for remote control and indications on front of the transformer auxiliary panels. The controller shall have enough internal memory to store the temperature readings Vs loading of the transformer with time & date stamp for the life span of the transformer i.e., 25 years.

The controller shall be equipped with universal power supply and capable of operating at both AC and DC auxiliary supply voltages as mentioned under clause 3.5.

The controller data shall be accessible through USB (local communication) while requirements of MODBUS (remote) communication for SCADA/SAS system shall be mentioned during bidding stage.

5.17.3 Online Dissolved Gas Analyzer

If required in the bidding document, the transformer shall be equipped with on-line dissolved gas analyzer (ODGA). Unless stated otherwise, the analyzer shall be capable of analysis of Hydrogen (H₂), Carbon Monoxide (CO) and water content in the transformer oil.

The ODGA shall conform to following IEC publications (latest edition):

IEC 60567 – Oil-Filled Electrical Equipment - Sampling of gases and analysis of free and dissolved gases – Guidance

IEC 60599 - Mineral oil-filled electrical equipment in service - Guidance on the interpretation of dissolved and free gases analysis

The measurement technique of the ODGA shall be either Solid State Sensor, Infrared, Fourier Transform Infrared, Micro Electronic Sensor, Near Infrared or Non-Dispersive Infrared. The other measuring techniques like gas chromatography or Photoacoustic spectrometry shall be subject to approval.



Both single valve and close loop installation shall be acceptable. It can be connected to the top oil filtration valve and bottom drain valve.

Sampling of fault gas, accuracy, repeatability and detection limit (sensitivity) shall comply with IEC 60567.

For ODGA, alarms shall be provided and adjustable for gas level and rate of change. Alarm shall be for two stages i.e. high and too high.

The ODGA shall have data logger to record gas level, water content and rate of change. The information such as oil temperature, oil pressure, transformer load, device error, time and date stamp of each sample taken shall also be recorded in the logger. The internal memory of the logger shall be large enough to store data for 10 years minimum.

The ODGA shall be equipped with universal power supply and capable of operating at both AC and DC auxiliary supply voltages as mentioned under clause 3.5.

The data of ODGA logger shall be accessible through USB (local communication) while requirements of MODBUS (remote) communication for SCADA/SAS shall be mentioned during bidding stage.

6 BUSHINGS AND BUSHING CURRENT TRANSFORMERS

6.1 Bushings

6.1.1 The bushing used for $U_m \geq 52\text{kV}$ shall be RIP (Resin Impregnated Paper) insulated and condenser type equipped with test tap at the bushing flange. The bushing shall be manufactured and tested in accordance with the IEC Publication 60137 (Amended to date).

6.1.2 The bushings used for $U_m < 52\text{kV}$ shall be as per latest DIN standard. The 11.5kV bushings shall be of the following types in accordance with latest DIN standard:

For 10/13MVA transformer and Type DT20Nf1000

31.5/40MVA transformer tertiary

For 20/26MVA transformer Type DT20Nf2000

For 31.5/40MVA transformer Type DT20Nf3150

For 50/63MVA transformer Type DT 20Nf 4500

6.1.3 Neutrals of star-connected windings shall be brought out through cover mounted bushings. The 11.5, 34.5 and 66kV neutral bushings shall be the same as the corresponding line terminal bushings. The 132kV neutral bushings shall be as specified for the 66kV line terminals.

6.1.4 All bushings shall be wet process porcelain, homogeneous, free from laminations, cavities or other physical flaws and shall be well vitrified, tough and impervious to moisture. Bushings shall be glazed, brown colored. Fittings made of steel shall be galvanized.

6.1.5 The bushings shall be cover mounted and located to develop their full insulation and impulse strength between bushing terminals and earthed metal parts. The impulse and power frequency withstand test voltages for the windings specified in Table-I shall be applicable also for the corresponding bushings.

6.1.6 The minimum creepage distance (SCD) shall be 31 mm/kV based on highest operating voltage of the system. However, any change of creepage distance will be specified in the relevant tender documents.



6.1.7 Arcing horns shall not be fitted on the bushings unless specified in the tender/ enquiry.

6.2 Bushing Current Transformers

6.2.1 The bushing type current transformers shall be provided as and where specified in Table-I. They shall be manufactured and tested in accordance with IEC Publication 61869-1 & 2 and listed in Table-I.

6.2.2 All secondary leads shall be brought to an outlet box near each bushing and terminated in non-split current shorting type terminal blocks located in control cabinet.

6.2.3 The current transformers shall have short-circuit withstand capability as given in clause 4.9.

6.2.4 The terminal markings for the current transformers shall be in accordance with IEC Publication 61869-1 & 2.

7 TRANSFORMER OIL

7.1 A sufficient quantity of mineral insulating oil shall be supplied with each transformer for its filling to proper level. Insulating oil shall be straight run mineral oil obtained from fractional distillation of crude petroleum, refined specially for use as insulating and cooling medium in oil immersed transformers

7.2 The insulation oil shall be virgin uninhibited mineral oil with general specifications conforming to IEC-60296 (amended to date). The manufacturer shall guarantee that the oil is suitable for mixing with other mineral oils (different bases) in any combination and the mixture shall still meet the required functional properties of this specification.

7.3 The oil shall be clear and free from additives, moisture, sediments, foreign materials, Poly Chlorinated Biphenyl (PCBs) and Sulphur compounds, which may be injurious to environment and equipment or to any of its components, such as insulation, paint, varnish and metallic or other parts.

7.4 Before delivery, test reports containing results to confirm the properties of transformer oil as mentioned in IEC-60296 shall be provided by the manufacturer for approval.

7.5 If the transformer oil will be delivered in containers or drums, these shall be approved by the purchaser. The containers and/or drums shall be well-cleaned internally and shall otherwise be in such a condition that there is no risk of endangering the oil quality.

8 ON-LOAD TAPCHANGER

8.1 General

8.1.1 The on-load tap changer shall be of the vacuum type design vessel fitted inside the transformer tank, motor operated mechanism and controls in accordance with IEC Publication 60214-1 and described herein.

8.1.2 The on-load tap changer shall have current rating as specified in Table-I and be suitable to withstand mechanical and thermal stresses referred in clause 4.9. At all taps of the on-load tap changer, the transformer winding shall be capable of withstanding the impulse test voltage and the power frequency test voltage specified in Table-I. It shall be suitable for continuous operation in conjunction with an automatic voltage regulating relay.

8.1.3 The bidder shall provide the name of the manufacturer in the bid and obtain specific approval of NTDC prior to the selection of the on-load tap changer for installation in the transformers.



8.2 Construction

8.2.1 The on-load tap changer shall permit high speed changeover with long life span, high switching and short-circuit performance and shall be mechanically robust. The spring-operated energy stored diverter switch shall transfer with rapid action the power circuit from one tap to the next, while two adjacent taps are bridged, without the possibility either for a portion of the transformer winding to be open circuited or short-circuited except through the current limiting resistors. The main contacts shall be faced with suitable alloy for extending their working life.

8.2.2 Diverter components shall be easily renewable. The diverter switch shall be enclosed in a separate oil-filled vessel fitted with drain valve, oil level indicator, relief vent and a gas alarm relay of suitable type and design with two contacts. The connection of this separate oil-filled vessel to the conservator shall be via an easily replaceable filter such that fouled oil can be tapped off while the transformer is in service and is automatically replaced with fresh oil from the conservator or alternatively the conservator may be divided into two compartments separated by a filter for connection to the main tank and the tap-changer compartment.

The diverter switch vessel should be made of non-hygroscopic and non-inflammable materials preferably of glass fiber reinforced epoxy or materials of equivalent characteristics.

8.2.3 An operation counter shall be provided to register the accumulated number of tap changes performed.

8.3 Controls

8.3.1 The tap-changer shall be remote controlled manually from the transformer auxiliary panel. It shall also be possible to operate the tap-changer locally. A local/remote switch shall be provided in the tap-changer control cabinet to select the point of operation. A crank for hand operation of the drive mechanism in case of AC supply failure shall also be provided. It shall be electrically interlocked to prevent operation of the motor while the hand crank is engaged.

8.3.2 Provision shall be made for automatic control of the tap-changer by means of automatic voltage regulator installed on the auxiliary panel.

8.3.3 The motor drive control shall follow the step-by-step principle i.e. after energization; the switching operation is automatically and irrevocably accomplished. If, after a voltage dropout during the running time of the motor drive, the voltage is present again the motor drive automatically shall restart in the direction in which it had previously started. A safety connection shall be provided to interrupt the supply voltage in case of false phase sequence.

8.3.4 The tap-changer shall be equipped with an emergency stop switch. Mechanically operated electric limit switches and mechanical stops shall be provided in the driving mechanism to prevent over-travel beyond the maximum raise and lower positions.

8.4 Position Indicators

Two position indicators shall be provided, one installed on the transformer auxiliary panel and the other in the motor drive unit mounted on the transformer. The remote indicator shall be fitted with adjustable maximum and minimum indicating stops. The local indicator shall be so located that it can be read while operating the tap-changer. The remote indicator shall be of the servo type. The position indicators shall be marked as follows:

The principal tap shall be marked on the dial center line and shall be indicated by the letter N. The range for raising the voltage of the LV winding with respect to the HV winding shall be on the right-hand side of the dial and this range shall be marked with an arrow and the letter R. The lower



range shall correspondingly be on the left side and marked with the letter L. The tap position numbers shall also be marked on the dial in smaller figures. The markings shall correspond to the tap numbers given on the rating plate.

8.5 Housing

The control equipment and the drive mechanism shall be housed in a sheet steel or cast aluminum, vermin proof, well ventilated weather, and corrosion proof cabinet. The doors shall have lift-off type hinges and be fastened by integral handles with provision for locking. Identification labels on the outside of the doors shall be provided.

9 CONSTRUCTION REQUIREMENTS

9.1 Transformer Tank

- 9.1.1 The active part shall be housed in a conventional type of tank other than bell type. Tank shall be of electrically welded mild steel construction suitably stiffened and braced to prevent distortion or damage under service conditions or during transport by road, rail, or sea when the complete transformer filled with oil is lifted by crane or jacks.
- 9.1.2 The tank shall be thoroughly oil tight and be capable of withstanding; when empty, a vacuum of 720mm of mercury and a pressure of 0.4kg/sq cm additional to that present when filled with oil at a head equivalent to that imposed by the conservator in service when the oil temperature is 75°C.

9.2 Tank Cover

- 9.2.1 Tank cover shall be of adequate strength to prevent distortion when lifted and shall be provided with specified inspection openings and pockets for oil and winding temperature indicators. The thermometer pockets shall be in accordance with IEC 60076-22-7. Protection shall be provided for capillary tubes for oil/winding temperature indicators.
- 9.2.2 The cover design shall be such as to ensure no external pockets in which water can lodge and the elimination of all air pockets during the oil filling operation. The connections between the cover and conservator shall be placed so as to ensure positive operation of the buchholz relay upon the formation of gas or sudden movement of oil. The inside of the cover shall present the minimum obstruction to the passage of gas bubbles to the buchholz relay. Water shall not accumulate on the outside surfaces.
- 9.2.3 The joints between tank and cover and the hand hole/manhole joints shall be provided with suitable flanges, sufficient and properly placed bolts and gaskets. Gaskets between metal surfaces shall be set in grooves or held in position by retainers so arranged that all parts are bolted metal to metal. The gaskets shall be made of resilient material which will not deteriorate under the action of hot oil and will remain oil tight. All necessary precautions shall be taken to prevent ingress of moisture between flange plates, around gaskets and O-rings at insulator/flange interfaces etc. due to high humidity. The bidder shall supply complete information about the material of the gasket and the method of installation and compression control.
- 9.2.4 It must be possible to remove any bushing without removing the tank cover.
- 9.2.5 In case of power transformer of 10/13MVA, it will be obligatory on part of the manufacturer to construct transformer cover in a manner that it can be separated from the transformer tank without core and winding as and when required. For transformers beyond the above capacity, it would be the option of the manufacturer to provide either transformer cover as integral part of the core and winding or provide separable cover. In either case, however, a bell type cover shall not be offered and accepted.



9.3 Transformer Core

- 9.3.1 Transformer core shall be made of high grade, non-ageing, cold-rolled electrical silicon steel. Laminations shall have low losses and high permeability. B-H and specific loss curve shall be furnished to ascertain the core material. The laminations are cut through CNC machines and sharp projections should be removed; they shall be annealed to relieve shearing stresses. All laminations shall be machine coated to ensure a thin uniform coating. The coating material shall be heat resistant, inert to the action of the hot oil and shall be baked-on. The core shall be rigidly clamped with insulated clamping bolts or by other approved method, into a one-piece steel structure which will retain its shape under the most severe stresses encountered during shipment and handling and under short-circuit conditions. Insulation packet of the core shall be connected so that potential difference will not exist between them. Flux distortion will be minimized to reduce noise level. Cooling ducts shall be provided in ample number throughout the core to eliminate hot spots.
- 9.3.2 The design of the magnetic circuit (core) shall be such as to avoid static discharges, development of short-circuit paths within itself or to the earth clamping structure and the production of flux components at right angles to the plane of the laminations which may cause local heating.
- 9.3.4 The magnetic circuit (core) shall be earthed externally through 1 kV bushing which shall be installed on the top cover plate inside the core earthing box/turret. The core shall not be linked to the clamping structure of the transformer. The bushing shall be internally connected to the cover plate of the turret/earthing box. The turret shall be connected to main earth strip of transformer body. Identification nameplate/label shall be provided for the "Core" on outside the tank cover.
- 9.3.5 Magnetic circuit (core) having an insulated sectional construction shall be provided with a separate link for each individual section and the arrangement of the connections shall be subject to approval. Where oil ducts or insulated barriers parallel to the plane of the laminations divide the magnetic circuit (core) into two or more electrically separate parts, the ducts and insulating barriers which have a thickness greater than 0.25mm are to be bridged with tinned copper strips so inserted as to maintain electrical continuity.

9.4 Windings

- 9.4.1 All conductors used in the coil structures shall be copper free from scale, burrs, and silvers. All permanent current carrying joints or splices shall be brazed or compressed.
- 9.4.2 The turns and coils shall be thoroughly insulated, and all insulation shall be thoroughly treated with insulating varnish or equivalent compounds as necessary to develop the full electrical and mechanical strength at the transformer, and to minimize deterioration. All materials used shall be insoluble, free from PCB and chemically inactive in hot transformer oil and shall not soften or become brittle under operating conditions.
- 9.4.3 The windings shall be in a manner which will ensure that they remain electrostatically balanced and that their magnetic centers remain coincident under all conditions of operation.
- 9.4.4 The coils shall have been wound and assembled so that the voltage between turns is kept as low as is consistent with good design and coordinated with voltage gradient distribution during voltage surge.
- 9.4.5 The windings shall be thoroughly seasoned during manufacturing by the application of axial pressure at a high temperature for such length of time as will ensure that further shrinkage is unlikely to occur in service. Provision shall, however, be made for taking up any further construction by means of spring loaded and adjustable clamps, or other similar devices.



- 9.4.6 The windings and leads of all transformers shall be braced to withstand the shocks which may occur through rough handling and vibration during transport, switching and other transient service conditions.
- 9.4.7 The coils, barriers, bracings and insulation shall be arranged to afford ample oil circulation, reduce the occurrence of hot spots and withstand deformation from maximum transient forces.
- 9.4.8 The assembled core and coils shall be vacuum dried and impregnated with dry oil before removal from the treating tank.

9.5 Clamping Structure

- 9.5.1 A strong rigid clamping structure shall be used to clamp the interior assembly. This structure shall also be used to fasten the core and coils securely to the transformer tank and shall be provided with lifting lugs for un-tanking. Ample allowance shall be provided between core and coils and the tank bottom for collection of sediment.
- 9.5.2 Adequate provision shall be made to prevent movement of the transformer core assembly relative to the tank during transport and installation or while in service.
- 9.5.3 The clamping structure shall be earthed externally through 1 kV bushing which shall be installed on the top cover plate inside the core clamp earthing box/turret. The bushing shall be internally connected to the cover plate of the turret/earthing box. The turret shall be connected to main earth strip of transformer body. Identification nameplate/label shall be provided for the "Core clamp" on the outside of the tank cover.

9.6 Guides

Suitable guides shall be provided to position the various parts during assembly or dismantling operations.

9.7 Radiators

- 9.7.1 The radiators shall be connected directly to the tank body below the tank cover and shall be detachable. They shall be fitted with a valve at each point of connection to the tank and with drain and filling plugs.
- 9.7.2 Radiators shall be designed to prevent accumulation of water on outside surface, to be accessible for cleaning and repainting, to drain completely into the tank, and to vent thoroughly into the tank without residual air pockets when the tank is being filled with oil.
- 9.7.3 Radiators shall withstand the pressure conditions specified for the tank.
- 9.7.4 The radiators shall conform to the additional requirements as laid down in IEC 60076-22-2.

9.8 Base

The base of the transformer shall be rigidly welded steel frame fabricated from structural shapes of adequate size to withstand moving, shipping, handling the transformer and supporting the weight of the transformer on a concrete foundation in service.

9.9 Painting

- 9.9.1 All surfaces of all equipment, structures, control cabinets etc. shall be painted except where painting will interfere with the normal operation of the equipment. Where surfaces are left unpainted for mounting purposes, they shall be suitably protected to prevent rusting during storage and ocean transport.



- 9.9.2 After surface preparation and cleaning of all surfaces to be painted, the surfaces not in contact with oil shall be primed with two coats of an epoxy primer containing zinc or aluminum. The surfaces shall be finish coated with two coats of enamel applied to provide a uniform smooth surface free from blemishes.
- 9.9.3 After the tank and conservator have been shot blasted inside, the inner surfaces shall be painted with two coats of oil resisting paint.
- 9.9.4 The interior and exterior surfaces of the transformer, structures and cabinets shall be given manufacturer's final finish before shipping as given below:
- a) Transformer and outdoor control cabinet - Dark grey conforming to RAL 7001.
 - b) Indoor auxiliary panel - Light grey conforming to RAL 7032.

9.10 LV Cable Box

- 9.10.1 The 50/63MVA and higher rating power transformer shall be provided with the LV cable box which shall be mounted at the top cover plate. The necessary arrangement which includes but not limited to copper bus bars, post insulators, supporting brackets etc. shall be provided by the manufacturer to accommodate six XLPE copper cables of 500 mm² per phase. However, for higher rating power transformers the size and number of cables per phase shall be mentioned in tender documents. Necessary provisions shall be provided to install surge arresters in the LV cable box later on.
- 9.10.2 The phase to phase and phase to earth clearance in LV cable box shall not be less than 160mm. However, in case of clearance less than 160 mm, fire resistant insulation barrier shall be provided. The minimum thickness of the insulation barrier shall not be less than 6 mm. Moreover, dielectric tests on the transformer shall be conducted with LV cable box fully installed thereon.
- 9.10.3 The cable box shall be sealed properly to avoid ingress of any dust or water. A drainage valve of appropriate size shall be provided on suitable location. The valve shall be used to drain out any water accidentally accumulated in the box.
- 9.10.4 The LV cable box shall have same color as of Transformer i.e. Dark grey conforming to RAL 7001.
- 9.10.5 Proper clearance in front of the LV cable box shall be provided so that the cable connection may be made without any difficulties. It will be preferred not to install the radiators under LV cable box.
- 9.10.6 The lower rating transformer may also be provided with LV cable box. However, this requirement shall be mentioned in the tender documents.

10 RATING PLATE

- 10.1 Each transformer shall be provided with a rating plate of stainless steel or brass fixed on the transformer in a visible position. The markings on the rating plate shall be indelible and marked by engraving and shall include the data (on ONAN & ONAF MVA base) in accordance with IEC Publication 60076-1 and Table-I & Table-II herein:

- 1. Manufacturer's type designation _____
- 2. Manufacturer's name _____
- 3. Type of transformer _____
- 4. Reference specifications _____
(IEC Standards & NTDC Specifications)



5. Manufacturer's Sr. No. _____
6. Year of manufacture _____
7. Number of phases _____
8. Number of windings _____
9. Type of cooling _____
10. Rated voltage HV/LV/Tertiary kV _____
11. Rated current HV/LV/Tertiary A _____
12. Rated frequency Hz _____
13. Vector group symbols _____
14. Winding normal temperature-rise °C _____
15. Top oil normal temperature-rise °C _____
16. Rated power ONAN/ONAF _____
- a) 55°C winding temperature-rise MVA _____
- b) 60°C winding temperature-rise MVA _____
- c) 65°C winding temperature-rise MVA _____
17. Impulse withstand voltage _____
- HV/LV/Tertiary kV_p _____
18. Power frequency withstand voltage _____
- HV/LV/Tertiary kV_{rms} _____
19. HV winding uniformly insulated or graded _____
20. Short-circuit Impedance on ONAN & ONAF MVA base (measured value) _____
- a) HV-LV % _____
- b) LV-Tertiary % _____
- c) HV-Tertiary % _____
21. Maximum exciting current on ONAN & ONAF MVA base % _____
22. Type designation of tap-changer along with make _____
23. Tapping range % _____
- (and indication of the winding which is fitted with tapplings).
24. Number of taps _____
25. A table giving tapping voltages and currents _____
- at all taps along with tapping connection.
26. Permissible higher operating voltage for the _____
- tappings including principal tapping. % _____
27. Diagram showing tap-changer connections _____
28. Short-circuit impedance (%) at principal tap and extreme taps _____
- at ONAN & ONAF rating:
- a) HV-LV % _____
- b) LV-Tertiary % _____
- c) HV-Tertiary % _____
29. Weight of case and fittings kg _____
30. Weight of core and coil kg _____
31. Weight of oil kg _____
32. Total Weight kg _____
33. Shipping weight of heaviest part kg _____
34. Weight of heaviest part for un-tanking kg _____
35. Quantity of oil kg _____
36. Reference specification of transformer oil _____
37. Losses at 75°C _____



- a. No-Load loss, 100% kW _____
- b. Load loss, 100% upper rated power (ONAF) kW _____
- 38. Auxiliary power of fans (without spare fans) kW _____
- 39. X/R ratio _____
- 40. Bushing current transformers (where applicable)
 - a. Ratio A _____
 - b. Accuracy class with limit factor _____
 - c. Burden VA _____
 - d. Number of CTs _____
 - e. Number of cores of each CT _____
 - f. Resistance of secondary winding _____

10.2 Approval of the rating plate(s) shall be obtained from NTDC.

11 LOSSES

11.1 The manufacturer shall design the transformers for optimum losses.

11.2 In the evaluation of transformer tenders, the following rates shall be used for the capitalization of losses:

Capital cost of no-load loss.....US\$ 8200 per kW

Capital cost of load loss including.....US\$ 3000 per kW
consumption of fan motors

11.3 The capitalized costs of no-load losses at 100% voltage and load losses at principal tap corresponding to the 100% upper rated power and reference temperature of 75°C, including corresponding consumption of fan motors shall be added to the bid prices of transformers to obtain adjudication prices. The losses to be taken shall be the guaranteed losses plus 10% tolerances except when guaranteed losses indicated by the bidders in the bids already include the tolerances and are explicitly stated in the bids to be final not subject to any further tolerance in which case the guaranteed losses will be taken for capitalization.

12 TESTS

12.1 Factory Acceptance Tests

The following FATs shall be made on each transformer and accessories in accordance with the relevant IEC Publications and details given hereunder:

12.1.1 Tests on Power Transformer

The following tests shall be made on each transformer:

Sr. No.	Description of Tests	Applicable Standard
1.	Measurement of winding resistance	
2.	Voltage ratio measurement and check of phase displacement	
3.	Measurement of short circuit impedance (principal tapping), short-circuit impedance at extreme taps and load loss at principle and extreme taps.	



4.	Measurement of no-load loss and current, at 90%, rated, 105%, 110% and 120% voltage	60076-1
5.	Tests on on-load tap-changer	
6.	Measurement of capacitance winding-to-earth, between windings and of bushings & measurement of dissipation factor (tan delta) of the insulation system capacitances including bushings.	
7.	Measurement of D.C insulation resistance between each winding to earth and between windings.	
8.	Leak Testing with pressure for liquid immersed transformers (tightness test).	
9.	Measurement of Frequency Response Analysis (FRA).	60076-3
10.	Check of the ratio and polarity of built-in current transformers.	
11.	Dielectric Tests	
a)	Full wave impulse voltage withstand test on line terminals of each winding and neutral (LI & LIN)	
b)	Applied Voltage Test (AV)	
c)	Line terminal AC withstand test (LTAC) in case of non-uniformly insulated winding	
d)	Induced Voltage Test with Partial Discharge Measurement (IVPD)	
e)	Auxiliary Wiring Insulation Test (AuxW)	

Measurement of dissolved gases analysis in dielectric liquid from each separate oil compartment (except diverter switch compartment) shall be performed as part of FATs after above mentioned dielectric tests.

12.1.2 Tests on Accessories

Unless specified to the contrary, the operational tests in accordance with relevant IEC standard on following accessories shall be made on each assembled power transformer at the manufacturer's works with same type of accessories installed:

a) Buchholz Relay

The Tests shall be carried out to indicate proper installation and functioning of relay for operation with slow and fast evolution of gas in the power transformer. The test shall be carried out as per IEC 60076-22-1.

b) Cooling Equipment

Tests shall be carried out on each set or group of cooling fans to indicate proper operation of cooling equipment with auxiliary supply variations listed in clause 3.5 and without exceeding temperature rises specified in clause 5.2. The tests shall be carried out in accordance with IEC 60076-22-6.



c) Temperature Indicators

Tests shall be made for proper calibration and functioning of oil and winding temperature indicators. All the tests shall be carried out in accordance with latest version of IEC 60076-22-1.

d) On-load Tap-changer

The following routine tests shall be made on each on-load tap-changer:

Sr. No.	Description of Tests	Applicable Standard
1.	Mechanical test	IEC 60214
2.	Insulation test on auxiliary circuit	

In addition, the report of the routine tests carried out by tap changer manufacturer in accordance with latest IEC Standard shall also be provided.

e) Bushing Current Transformers

The following tests shall be made on each bushing CT where specified in accordance with IEC Publication 61869 (1&2). The manufacturer's report can be accepted in lieu of actual testing.

Sr. No.	Description of Tests	Applicable Standard
1.	Verification of terminal markings	IEC 61869-1 & 2
2.	Power frequency test on secondary windings	
3.	Overvoltage inter-turn test	
4.	Composite error test.	

12.1.3 **Transformer Oil**

Tests on oil filled in each transformer shall be carried out in accordance with IEC-60422.

12.1.4 The overall weight of the transformer without radiators shall be verified on one (01) transformer from the offered lot. This shall be at discretion of the inspector.

12.2 Type Tests

12.2.1 The type tests mentioned below shall be carried out on one power transformer with the same characteristics, ratings and major components viz OLTCs, HV/LV bushings, bushings C.Ts, fans and radiators etc. All external components and fittings that are likely to affect the performance of the transformer during type testing shall also be in place. The supplier/bidder/manufacturer shall supply type test reports along with the bid for the offered equipment.

12.2.2 The equipment will be subjected to all type tests from any ISO/IEC 17025 accredited independent laboratory acceptable to the engineer in the presence of NTDC & DISCO's representatives at the expense of the bidder in the following cases:



- Non-submission of the relevant type test reports.
- Submitted type test reports are not from laboratory designated in the tender enquiry
- Submitted type test reports are not to the full satisfaction of the Engineer.

For the on-load tap changer and HV/LV bushings, duly certified and complete type test reports for the tests already carried out on identical units in accordance with the latest applicable IEC publications from STL Laboratories, shall be acceptable in lieu of actual tests. In absence of such valid type test reports, the bidder shall submit an undertaking to the effect that, in case of award of contract, the requisite tests shall be carried out at an ISO/IEC 17025 accredited independent laboratory acceptable to NTDC & DISCOs in presence of the NTDC & DISCO's representatives at the bidder's expense (like visa stamping, boarding, lodging and daily allowance etc.).

The validity of type test report will be 10 years in case of no change in design, construction and manufacturing place. In case of change in accessories viz OLTC, radiators and fans following type tests shall be repeated given the design and construction of the power transformer remains the same.

Sr. No.	Change of Accessory	Type Tests to be repeated
1.	On-Load Tap Changer (OLTC)	All Type tests
2.	Radiators	Temperature Rise Test
3.	Fans	Temperature Rise Test & Noise Power Level

If any poor field performance quoted during type test validity period by any end user and subsequently vetted by CE (SS Design) NTDC then all type tests will be repeated immediately.

12.2.3 TYPE TESTS ON TRANSFORMER

12.2.3.1 Dielectric Tests:

The test shall be performed in the sequence given below:

Sr. No.	Description of Tests	Applicable Standard
1.	Lightning impulse test (LI, LIN)	IEC-60076-3
2.	Applied voltage test (AV)	
3.	Line Terminal AC withstand test (LTAC) in case of non-uniformly insulated winding	
4.	Induced voltage test with partial discharge measurement (IVPD)	

Measurement of dissolved gases in dielectric liquid from each separate oil compartment (except diverter switch compartment) shall be performed as part of type test before & after above mentioned dielectric tests.

12.2.3.2 Temperature Rise Test

The temperature rise test shall be carried out as per latest IEC 60076-2. During the test, 25% fans as selected by the Inspector shall remain shut-off while the remaining fans shall operate at the minimum specified supply voltage. The losses to be fed for temperature-rise test shall be the



guaranteed no load loss at 110% of the rated voltage and load losses at extreme minus tap of the power transformer for both ONAN & ONAF ratings plus tolerance if applicable.

The temperature rise test shall be repeated after 05 (five) years at manufacturer's works through random sampling against any purchase order/Contract Agreement without intimation to the bidder/manufacturer to make sure quality check. Moreover, Dissolved Gas Analysis will be performed before and after temperature rise test. In case of failure of temperature rise test all type tests will be repeated.

12.2.3.3 Special Tests on Transformers

Sr. No.	Description of Tests
1.	Measurement of zero-sequence impedance
2.	Measurement of acoustic sound level (for both ONAN & ONAF cooling conditions)
3.	Measurement of frequency response analysis (FRA)
4.	Measurement of harmonics of the no-load current
5.	Measurement of power taken by fan motors
7.	Determination of Weight of power transformer

12.2.3.4 Short Circuit Withstand Test

The power transformers of each rating shall be required to be tested for short-circuit dynamic capability test in accordance with IEC 60076-5. However, the Symmetrical short-circuit withstand current test shall be performed as a multiple of winding rated current based on lower rated power as mentioned in Table-1(25).

In case a transformer fails in the short-circuit testing, another transformer after rectification of the design defects causing the failure shall be tested at the manufacturer's expenses. The failed transformer shall stand rejected and it will not be delivered to NTDC/DISCO's under any P.O/Contract.

If the second transformer also fails, the whole lot of the transformers with same design, ratings and characteristics will be rejected and P.O/Contract will be cancelled.

12.2.3.5 Seal Leakage test

It will be performed as per Clause 11.8 of IEC-60076-1

12.2.3.6 De-tanking

It will be performed as per Clause 4.2.7.4 of IEC-60076-5

12.2.4 TYPE TESTS ON ACCESSORIES

12.2.4.1 On-Load Tap-changers

The following type tests shall be carried out on one on-load tap-changer in each group of on-load tap-changers with the same design, characteristics and ratings in accordance with IEC Publication 60214:

- a. Temperature-rise test of contacts
- b. Switching tests:
 - i. Service duty test
 - ii. Breaking capacity test
- c. Short-circuit current test



- d. Transition resistors test
- e. Mechanical endurance test
- f. Applicable dielectric tests
- g. Mechanical load test for motor drive mechanism
- h. Over-run test for motor drive
- i. Degree of protection of motor drive cubicle

12.2.4.2 HV/LV Bushings

The complete type testing of offered bushing one from each group with same design, characteristics and ratings shall be conducted in accordance with IEC Publication 60137 (Amended to date) in case the offered bushing is not already approved by NTDC.

12.2.4.3 Bushing Current Transformers

If the bushing current transformers are being used for protection purpose, then complete type test report of offered bushing current transformer from any independent Laboratory with the same design, characteristics and ratings in accordance with IEC Publication 61869-1 & 2 (Amended to date) shall be provided.

12.2.4.4 Verification of Transformer weights

The manufacturer shall verify the weight of lift able assembly during un-tanking of the transformer after short circuit test and the overall weight of the transformer without radiators shall also be verified.

The type test reports shall incorporate design information and sufficient details to identify the power transformers and accessories with that of other transformers of the same design and construction. The information shall include the performance data as well as drawings such as specified in clause 16.

13 GUARANTEED VALUES

13.1 The bidders shall specifically list in the bids any exceptions to these specifications under “Exceptions to Purchaser’s Specifications”. The bidders shall certify that the design shall be such that the name plate rating of the transformer and accessories shall be maintained during the life of the equipment under the specified service and operating conditions.

13.2 The bidders shall indicate in the bids the guaranteed figures for no-load current, losses and efficiencies etc. as listed in “Schedule of Technical Data”.

14 SHIPPING CONDITIONS

14.1 Transformers shall be transported by railway and/or suitable road trailer to the site. The transformer to be supplied shall comply with the transport limitations given in clause 15.

14.2 Should the shipping and railroad weight limitations permit; the transformers shall be shipped filled with oil. The supplier shall, however, have the option of shipping the transformer assembled or disassembled with the main components such as conservator, bushings, radiators and large accessories removed/dismantled.

14.3 If disassembled and without oil, due to shipping and railroad limitations, the transformer shall be shipped in its own tank with nitrogen gas filled under slight positive pressure, with radiator, conservator and bushings removed. A temporary pressure gauge shall be installed to facilitate monitoring of internal gas pressure. Valves shall be sealed and effectively protected to prevent tampering, removal or loss of gas while in transit. The method of shipment shall be such as to protect



the case, radiators, core and coils, bushings, oil, parts and accessories against corrosion, dampness, breakage or vibration injury that might be encountered in transportation and handling.

- 14.4 The bushing not attached to the transformer shall be packed with its lower end protected by a metal container filled with oil so that the bushing remains healthy during long storage period up to 10 years.

15 TRANSPORTATION LIMITATIONS

- 15.1 For ease in transportation, the maximum transport dimensions of transformers shall be in accordance with drawing Nos. EW/DZ-18A & 19A. The maximum transport dimensions of 10/13MVA power transformers over railroad shall fit in the profile given in drawing No. EW/DZ-18A and those of 20/26MVA, 31.5/40MVA transformers shall fit in the profile given in drawing No. EW/ DZ-19A and 50/63MVA power transformer shall fit in the profile given in approved drawing.

- 15.2 For transportation of power transformers over railway, well-wagon type and flat-wagon type bogies are available with the following characteristics:

- a) Flat wagons are available with their floor levels above railway track as shown in drawing Nos. EW/DZ-18A and 19A. The dimensioning of the consignment when used with flat wagons has, therefore, to be restricted to fit in the profile shown in drawing Nos. EW/DZ-18A and 19A above the floor level for flat wagons shown therein.
- b) For well wagons to be used for 10/13MVA power transformers (type B.W), the width of cross girder in well is 2413mm and weight carrying capacity 29464 kg over 3048mm length and 39624 kg over 9144mm length.
- c) For well wagons to be used for 20/26MVA, 31.5/40MVA and 50/63MVA transformers well wagons type B.W.L, B.W.H. Type-I and flat wagons are available, and their characteristics are as under:
 - B.W.L: The width of cross girder in well is 2134mm and the carrying capacity over 3048mm is 39240 kg and over 9448mm is 50, 800 kg. Clear opening to track for an available length of 2311mm is permissible.
 - B.W.H: The width of cross girder in well is 2134mm. The carrying capacity at 2438mm is 71120 kg and at 7925mm is 91440 kg. Clear opening up to maximum length of 3454mm is available.
 - Type-I: The width of cross girder in well is 2200mm and the carrying capacity at 1829mm, 2438mm, 3048mm and 3454mm is 120904 kg, 123,952 kg, 127000 kg and 132080 kg respectively. The clear opening available is 3454mm.
- d) Flat wagons type BB and BBX are available with a carrying capacity of 11704 kg and 67056 kg and having the width over sole bars of 2845mm and 3251mm respectively. However, the base of the flats is 1397mm and 1340mm above the railway track.



16 DRAWINGS AND DESCRIPTIVE DATA

16.1 Drawings and data to be submitted with the bid

- 16.1.1 The information as applicable in the schedule of technical data attached shall be furnished with the bid for each type of power transformer.
- 16.1.2 Outline General Arrangement drawings of transformer:
- a) Plan
 - b) Elevation
 - c) End View
 - d) Dimensions of both fully erected and shipping conditions
- 16.1.3 Dimensional drawings of HV and LV bushings showing complete details.
- 16.1.4 Sketches showing outline, weight, dimensions, nameplate and the location and connections of bushing current transformers.
- 16.1.5 List of all accessories with detailed weights, dimensions, clearances, spacing of wheels and center of gravity.
- 16.1.6 Dimensional drawing of the transformer auxiliary panel showing the details of front mounted equipment.
- 16.1.7 Drawing showing the dimensions and major details of the transformer outdoor control cabinet.
- 16.1.8 Dimensional drawing and details of transformer oil containers.
- 16.1.9 The type of on-load tap-changer offered with name of the manufacturer and the descriptive data and literature showing characteristics, construction, operation, the switching speed of the on-load tap-changer.
- 16.1.10 Details of proposed gasket material, method of gasket installation and compression control.
- 16.1.11 Typical excitation and composite error curves from 0 to 10 times rated secondary current for bushing current transformers.
- 16.1.12 Descriptive data/brochures and literature showing characteristics and construction etc. of the following items:
- a. Oil temperature indicators
 - b. Winding temperature indicators
 - c. Oil level indicators
 - d. Tap-changer indicators
 - e. Buchholz relay
 - f. Pressure relief device
 - g. Valves
 - h. Automatic voltage regulator if required in the tender enquiry
 - i. Online Dissolved Gas Analyzer (if applicable)
 - j. Self-regenerating breather (if applicable)
 - k. Fiber Optic Temperature measurement system (if applicable)
- 16.1.13 The following test reports shall be furnished:
- a) Type and routine tests carried on identical power transformers



- b) Type and routine tests on bushings
- c) Type and routine tests on bushing current transformers

16.2 Documents and Drawings to be submitted for Approval

The supplier shall furnish documents and drawings described below. The drawings shall be approved from NTDC prior to manufacturing.

1. Instruction Books

- i. Parts books and spare parts book for the transformer, tap-changer and transformer accessories.
- ii. Instruction books for the installation, handling and storage of tap-changer, transformer and its accessories.
- iii. Instruction books for the commissioning, operation and maintenance of tap-changer, transformer and its accessories.
- iv. Instructions for transformer dehydration using all methods and recommended method for dehydration.

2. Descriptive Literature of Transformer Accessories

- i. The switching capacity of the contacts of accessories such as oil level indicator, transformer and tap changer buchholz relays and oil and winding temperature indicators be given for 250V AC and DC supplies.
- ii. Magnetic oil level indicators showing dial markings for the high and low oil levels and also markings for oil filling at temperatures of -10, 5, 0, 15, 25, 35, 45 and 55 deg C.
- iii. Transformer and tap changer buchholz relays indicating pressure and/or speed of oil flow for the operation of contacts and details of float arrangement.
- iv. Oil temperature indicators showing details of sensing, measuring and indicating elements. Instructions for adjusting and compensating resistors, principle of operation and internal wiring details may be given. The measuring range and details of auxiliary supply units, if used, and switching range for the control of fans and operation of alarm and trip contacts be supplied.
- v. Winding temperature indicators showing details of measuring and indicating, heating resistance sensing element and the matching units, ammeter and ammeter switch. Principle of operation and internal wiring detail of the temperature measuring and indicating units be provided along with auxiliary supply units and measuring the switching range for fan control and operation of alarm and trip contacts be provided. The graph showing relationship between heating current and the corresponding indicator reading shall be given.
- vi. On-load tap-changer, driving mechanism, position transmitter and indicator. The mode of tap-changer connections used whether "Changeover" or "Coarse/Fine" shall be indicated.
- vii. HV and LV bushings CTs indicating constructional details. The excitation, ratio and phase angle error curves shall be supplied.
- viii. Pressure relief device, all types of valves and gaskets indicating "materials used and details of compression control of gaskets".
- ix. Fan motors including their protection switches and starting contacts indicating ratings, air displacement of fan, thermal and short current characteristics of protective switches etc.
- x. Cooling fan controls including supply ON/OFF switches, fuses, contacts, auxiliary relays, indicating lamps, push buttons for manual operation and selector switches for local/manual, remote/automatic selection of fans control indicating their dimensions and ratings.



- xi. Over-excitation curve, over fluxing withstand duration curve, overload curve and thermal damage curve of the power transformer.
- xii. Transformer gaskets specifications, characteristics and compression control of all types of gaskets used in the transformer, control cabinet for cooling and tap-changer and the auxiliary panel.

3. List of Drawings

- i. Rating plate and connection diagram.
- ii. Loading profile.
- iii. Transportation views.
- iv. Dimension drawing of transformer showing outside dimensions for both fully erected and shipping conditions and hoisting specification required for un-tanking. The drawing shall also show complete parts lists and accessories referred to the drawing.
- v. Dimensional drawings of oil ducts and valves.
- vi. Dimensional drawings for HV and LV bushings showing details of terminal size, diameter and size of holes for fixing flange and size of lower extension for bushing CT Creepage distance etc.
- vii. Dimensional drawing of HV and LV bushing CTs.
- viii. Schematic wiring and Dimensional drawing of tap-changer showing detail of components of diverter switch and tap selector. The drawing should show detail of fixing and tap-changer with the core frame and/or top cover.
- ix. Dimensional drawing of outdoor control cabinet for cooling control, and auxiliary panel showing fabrication details, ventilation arrangement, gasket installation, cable glands and earthing facilities along with the detailed configuration of the equipment installed.
- x. Gasket installation. The drawing should include details of installation of all type of gaskets used in the transformer.
- xi. Winding sectional view with detail of insulation and core construction drawings.
- xii. The drawing should give sufficient details to facilitate major repairs by field staff.
- xiii. Schematic diagrams for transformer protections and cooling fan control and indications.
- xiv. Schematic diagram of tap-changer motor drive control and indication.
- xv. Schematic and wiring diagram for tap-changer parallel operation.
- xvi. Wiring diagram of outdoor control cabinet for cooling.
- xvii. Wiring diagram and dimensional drawing of the transformer auxiliary panel.
- xviii. Wiring diagram of transformer accessories including bushing CTs, resistance sensing element, matching unit for winding temperature indicator, transformer and tap changer buchholz relays, oil temperature indicators, oil level indicator and transformer cooling fans control and its auxiliary relays.
- xix. Cable connections of transformer accessories and cooling fans.

4. List of Calculations

- i. Windings hot spot calculations
- ii. Calculation of maximum peak value of magnetizing in-rush current
- iii. Calculation to support short-circuit withstand capacity of the transformer



16.3 Final Manufacturer's Data

The supplier shall furnish the required drawings, operating instructions and descriptive data described below before shipment of the power transformers:

- i. Drawings showing outside dimensions for both fully erected and shipping conditions and hoisting space required for un-tanking.
- ii. Drawings showing details of coil and core constructions in sufficient detail to facilitate major field repairs by NTDC/DISCOs field staff.
- iii. Drawings showing details and location of all accessories including bushings and on-load tap-changer.
- iv. Complete parts list and parts book.
- v. Diagrams and descriptive information of the buchholz relay, oil temperature and level indicators, winding temperature indicator, forced cooling controls, on-load tap-changer, bushings & bushing CTs, pressure relief device and valves.
- vi. Complete instructions and directions for setting the transformer, assembling unmounted parts, putting the transformer in service and for operation and maintenance.
- vii. Rating plate drawings.
- viii. Detailed schematic and wiring diagrams including control diagrams of transformer control cabinets and auxiliary panel.
- ix. Glossy photographs of size 297x210mm with binding edge on 297mm dimension shall be supplied, with the instructions manual covering installation, operation and maintenance of the power transformers for the following views:
 - a) Top of assembled transformer with bushings
 - b) Side of assembled transformer facing HV bushings
 - c) Side of assembled transformer facing LV bushings
 - d) Side of core and coil assembly facing HV leads
 - e) Side of core and coil assembly facing LV leads
 - f) View of tap-changer and tap connections with the main windings

17 SPARE PARTS

17.1 Tender Requirements

The requirements of spare parts to be supplied against an order shall be clearly indicated by the purchaser in the schedule of prices keeping in view the available stock of spares. A list of commonly required spares is given in clause 17.7 for guidance of purchaser.

17.2 Condition of Spare Parts

All spare parts shall be new, unused and strictly interchangeable with the parts by which they are intended to be replaced and shall strictly conform to the relevant specifications.

17.3 Compliance to the Bidder

The bidder shall attach to this list:

- i. A list with the prices of the supplementary spare parts, which he deems necessary to stock.
- ii. A list with the prices of the spare parts necessary when alternatives are offered. While preparing the list of the supplementary spare parts, the bidder shall keep the contents of clause 17.4 in view.



17.4 Estimation of Requirements

17.4.1 The list of spare parts has been prepared keeping in view of the following concepts:

- i. Replacement required in due course of time due to wear and tear of the equipment under normal working conditions.
- ii. Replacement required due to accidents, malfunctioning of the equipment or any other emergencies.
- iii. Replacement of the heat sensitive parts such as gaskets, due to severe service conditions.

17.5 Spare Parts Books

17.5.1 For each separate piece of equipment, the contractor shall give a spare parts book. This spare parts book shall contain an assembly drawing of the equipment which shall show all parts of the equipment separately marked, designated and referenced. The book shall also contain sketches of each part with the part number and the designation of the part. The material of the part shall also be indicated. These sketches and lists of parts shall be cross-indexed with the assembly drawings. The spare parts books shall present information in a simple manner so that non-technical personnel may be able to indent these spare parts. The lists of spare parts required shall be made with reference to the spare parts books.

17.6 Packing

17.6.1 The spare parts shall be treated and packed for long storage under the service conditions specified in clause 3. Each spare part shall be clearly marked or labeled on the outside of its packing with its description and purpose, and, when more than one spare part is packed in a single case or container, a general description of its contents shall be shown on the outside of such case or container and a detailed list enclosed. All cases, containers or other packages shall be marked and numbered in an approved manner for purposes of identification.

17.6.2 All cases, containers or other packages are liable to be opened for examination and packing shall be designed to facilitate opening and thereafter repacking.

17.6.3 In every packing for shipment one number installation, erection, maintenance and operation instruction book enclosed in a waterproof polyethylene material shall be provided.

17.7 List of Spares

The following spare parts shall be required for each group of 5 Nos. power transformers of same characteristics and ratings:

Item No.	Description	Quantity
i)	HV bushing complete with gasket and terminal connectors	2
ii)	LV bushing complete with gasket and terminal connectors	2
iii)	Tertiary bushing complete with gasket and terminal connectors	1
iv)	Neutral bushing	1
v)	Bushing CT if applicable	1 for each voltage
vi)	Complete set of pressure relief device	1



Item No.	Description	Quantity
vii)	Fan with motor	3
viii)	Complete buchholz relay	1
ix)	Oil level indicator, magnetic type	1
x)	Oil temperature indicator liquid type	1
xi)	Oil temperature indicator resistance type	1
xii)	Winding temperature indicator	1
xiii)	Tapchanger protective relay	1
xiv)	Silicagel, kg	30
xv)	Transformer oil, litres	1000
xvi)	Air breather (each type)	1
xvii)	Remote tap position indicator	1

18 LIST OF DRAWINGS

The following drawings are attached:

Item No.	Description	Drawing No.
i)	Max. profile for 10MVA transformer	EW/DZ-18
ii)	Max. profile for 20MVA and 31.5MVA transformer	EW/DZ-19
iii)	Typical relative positions of power transformer accessories	EW/TS-193
iv)	High voltage bushing for transformers	EW/DF-393
v)	11.5kV bushing for transformers	PDW/DF-372



Annexure-1

SCHEDULE OF TECHNICAL DATA FOR POWER TRANSFORMER

‘A’– NTDC SPECIFIED DATA/PARAMETER
‘B’– PROPOSED DATA/PARAMETERS BY THE CONTRACTOR/BIDDER/SUPPLIER/VENDOR
‘C’ – REMARKS SUPPORTING THE PROPOSED DEVIATION IN COLUMN ‘B’
(*) – DATA/PARAMETER TO BE PROVIDED/PROPOSED BY THE CONTRACTOR/ BIDDER/ SUPPLIER/ VENDOR IN COLUMN ‘B’

REFERENCE SECTION NO.	DESCRIPTION	‘A’	‘B’	‘C’
	Name of Manufacturer	*		
	Type/designation of Power Transformer	*		
	Type Test Certificate	*		
	Make and Origin of Paper Insulation	*		
	Origin of core	*		
	Specific total loss (W/Kg) of core at 1.5 T flux density	*		
4.2	Vector Group Rated voltage of windings a) HV Winding, kV b) LV Winding, kV c) Tertiary Winding, (if applicable)kV			
4.3	Rated Power of Transformer (temperature-rise measured by resistance) a) With 55°C temperature rise of winding i) ONAN Cooling, kVA ii) ONAF Cooling, kVA b) With 60°C temperature rise of winding i) ONAN Cooling, kVA ii) ONAF Cooling, kVA c) With 65°C temperature rise of winding i) ONAN Cooling, kVA ii) ONAF Cooling, kVA			



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	Temperature-rise of oil corresponding to the kVA and temperature-rise values given: a) With 55°C temperature rise of winding i) ONAN Cooling, kVA ii) ONAF Cooling, kVA			
	b) With 60°C temperature rise of winding i) ONAN Cooling, kVA ii) ONAF Cooling, kVA c) With 65°C temperature rise of winding i) ONAN Cooling, kVA ii) ONAF Cooling, kVA			
	Hottest spot winding temperature-rise corresponding to kVA and temperature-rise ratings given in: a) With 55°C temperature rise of winding i) ONAN Cooling, kVA ii) ONAF Cooling, kVA b) With 60°C temperature rise of winding i) ONAN Cooling, kVA ii) ONAF Cooling, kVA c) With 65°C temperature rise of winding i) ONAN Cooling, kVA ii) ONAF Cooling, kVA			
4.4	Tertiary winding rating, corresponding to 55°C temperature-rise of winding (measured by resistance) where applicable: i) ONAN Cooling, kVA ii) ONAF Cooling, kVA			
4.6	Tapping voltages at all plus and minus tapping, Volts	Attach Table		
4.7.2	Short-circuit Impedance (principal tap) on ONAN MVA base: a) High voltage-low voltage, percent b) Low voltage-tertiary, percent c) High voltage-tertiary, percent			



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	Resistance voltage (principal tap) on ONAN MVA base a) High voltage-low voltage, percent b) Low voltage-tertiary, percent c) High voltage-tertiary, percent Reactance voltage (principal tap) on ONAN MVA base: a) High voltage-low voltage, percent b) Low voltage-tertiary, percent c) High voltage-tertiary, percent			
	Zero sequence impedance (principal tap) on ONAN MVA base: a) High voltage-low voltage, percent b) Low voltage-tertiary, percent c) High voltage-tertiary, percent			
	Short-circuit Impedance at extreme taps on ONAN MVA base: a) At extreme plus tap i) High voltage-low voltage percent ii) Low voltage-tertiary percent iii) High voltage-tertiary percent b) At extreme minus tap i) High voltage-low voltage percent ii) Low voltage-tertiary percent iii) High voltage-tertiary percent			
4.7.3	Regulation (principal tap) on ONAN MVA base: a) 100% power factor percent b) 80% power factor percent c) 70% power factor percent	*		
4.7.4	Guaranteed no-load losses at rated frequency: a) 100% voltage, kW b) 105% voltage, kW c) 110% voltage, kW d) 120% voltage, kW	*		
	Guaranteed load losses for reference temperature of 75°C including corresponding consumption of fan motors: a) At principal tap i) 100% ONAN Rating kW ii) 75% ONAN Rating kW	*		



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	iii) 50% ONAN Rating kW iv) 100% ONAF Rating kW v) 75% ONAF Rating kW vi) 50% ONAF Rating kW	* * * *		
	b) At extreme plus tap i) 100% ONAN Rating kW ii) 75% ONAN Rating kW iii) 50% ONAN Rating kW iv) 100% ONAF Rating kW v) 75% ONAF Rating kW vi) 50% ONAF Rating kW c) At extreme minus tap i) 100% ONAN Rating kW ii) 75% ONAN Rating kW iii) 50% ONAN Rating kW iv) 100% ONAF Rating kW v) 75% ONAF Rating kW vi) 50% ONAF Rating kW	* * * * * * * * * * * *		
	Tolerance applicable for a) Guaranteed no-load losses at 100% voltage, percent b) Guaranteed load losses at 100% ONAF rating at principal tap, percent			
4.7.5	Exciting current on ONAN MVA base: a) 90% voltage, percent b) 100% voltage, percent c) 105% voltage, percent d) 110% voltage, percent e) 120% voltage, percent	* * * * *		
4.8	Highest operating voltage for which tapping are designed for continuous overvoltage operation, percent of tapping voltage, percent	110 %		
	Overvoltage Operation	Attach Table as per Annex-3		
	Max. flux density and operating conditions at which it occurs, Tesla Frequency, Hz Voltage, HV, Volts Voltage, LV, Volts Load Current, Amp			
	Design flux density at rated voltage, rated current and frequency, Tesla			



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
4.9	Short-circuit characteristics at rated voltage: a) Max. asymmetrical short-circuit current for which the mechanical bracings are designed and constructed to withstand without damage frequent short-circuit faults i) HV winding, kA_{peak} ii) LV winding, kA_{peak} iii) Tertiary winding, kA_{peak} b) Max. symmetrical short-circuit current for which the mechanical bracings are designed and constructed to withstand without damage frequent short-circuit faults i) HV Winding 1 sec A 2 sec A 3 sec A 4 sec A 5 sec A ii) LV Winding 1 sec A 2 sec A 3 sec A 4 sec A 5 sec A iii) Tertiary Winding 1 sec A 2 sec A 3 sec A 4 sec A 5 sec A c) Short circuit duration, sec			
4.10	i) Impulse test voltage a) HV winding, kV_{peak} b) LV winding, kV_{peak} c) Tertiary winding, kV_{peak}			



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	ii) Separate source power frequency test voltage a) HV winding, kV,r.m.s. b) LV winding, kV,r.m.s. c) Tertiary winding, kV,r.m.s.			
	iii) Induced overvoltage withstands test kV, rms			
4.11	Guaranteed noise power level a) ONAN Rating, db b) ONAF Rating, db	70 80		
5.4	Oil Level Indicators a) Type Designation b) Manufacturer c) Catalogue No. d) Contact Rating 110V & 250 V DC and 250AC (A)	* * * *		
5.5	Oil Temperature Indicators a) Type Designation b) Manufacturer c) Catalogue No. d) Contact Rating at 110V & 250 V DC and 250AC (A)	* * * *		
5.6	Winding temperature indicator (catalogue to be attached with bid) a) Local i) Type designation ii) Manufacturer iii) Catalogue No. iv) Contact rating between 110V & 250V DC and 250V AC A	* * * *		
	b) Remote i) Type designation ii) Manufacturer iii) Catalogue No. iv) Contact rating between 110V & 250V DC and 250V AC A	* * * *		
5.7	Buchholz Relay (catalogue to be attached with bid) a) Type designation b) Manufacturer	* *		



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	c) Catalogue No. d) Contact rating between 110V & 250V DC and 250V AC A	* *		
5.8	Transformer Cooling Fans & Radiators a) Type Designation b) Manufacturer c) Total No. of fans d) No. of fans required for full upper rating output under specified conditions e) No. of spare fans f) Motor rating i) H.P ii) r.p.m g) Total fan consumption at full load kW h) Type of Radiators (Plate or tube) i) No. of Radiators j) No. of tubes/plates in one radiator k) Radiator dimensions Length(L) Width(W) Height(H)	* * * * * * * * * * * * * * *		
5.12.6	Breather (catalogue to be attached with bid) a) Type b) Make c) Number	* * *		
5.13	Valve (catalogue to be attached with bid) a) Type b) Make c) Size i) Drain valve ii) Filter valve iii) Sampling valve	* * * * * *		
5.14	Pressure relief device (catalogue to be attached with the bid) a) Type designation b) Manufacturer c) Catalogue No. d) Pressure range for operation, kg/cm ² e) Contact rating if applicable	* * * *		



	a) Type Designation i. Main Tank Compartment ii. OLTC Compartment b) Make c) Number d) Quantity of Silica-gel in single unit, (kg) e) Power Consumption i. Non-regeneration state (mA) ii. Regeneration state (A) f) Contact Rating at 110V & 250 V DC and 250AC (A) g) Status indication provided h) Data logger with local USB communication provided. i) Internal Memory of data logger MB j) No. of years for which data can be stored in data logger year k) Sampling rate min l) MODBUS (remote) communication provided m) Protocol for MODBUS n) Lifetime of silica gel year	* * * * * * * * * Yes/No Yes/No * ≥10 ≥30 Yes/No * *	
.17.2	Fiber optic direct temperature measurement system (catalogue to be attached with the bid) a) Type Designation i.Sensor/probe ii Controller	* *	



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	250AC for fan control (A)	*		
	g) USB port for local communication provided	Yes/No *		
	h) Internal Memory of controller (MB)	>25		
	i) No. of years for which data can be stored in controller (year)	*		
	j) Response time (sec)	Yes/No *		
	k) MODBUS (remote) communication provided	*		
	l) Protocol for MODBUS			
5.17.3	On-line Dissolved Gas Analyzer (Catalogue to be attached with the bid)			
	a) Type Designation	*		
	b) Make	*		
	c) Dimensions (LxWxH) (mm)	*		
	d) Weight (kg)	*		
	e) Analysis Technique	*		
	f) Measurements (Accuracy/Repeatability/ Detection Limit)			
	i. H ₂ % /% / ppm	±15/*/*		
	ii. CO % /% / ppm	±15/*/*		
	iii. H ₂ O % /% / ppm	±15/*/*		
	g) USB port for local communication provided	YES/NO		
	h) Internal Memory (MB)	>10		
	i) No of years for which data can be stored	≥1		
	j) Frequency of sampling hrs			
	k) Alarms and indications			
	i. Each Gas Level (ppm)			
	ii. Rate of change of gas (%)	*		
	iii. Gas Ratio	*		
	iv. Alarm Contacts/Rating	*		
	l) MODBUS (remote) Communication provided	NO/2A		
	m) Protocol for MODBUS	Yes/No		
	n) List of consumables attached	Yes/No		



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
6.1	High voltage bushings			
	a) Rating i) Voltage, kV ii) Current, A iii) Impulse withstand voltage, kV _{peak} iv) Power frequency withstand voltage, kV _{rms} b) Type c) Manufacturer d) Catalogue number (catalogue to be attached with bid) e) Creepage distance mm	* * *		
	Low voltage bushings			
	a) Rating i) Voltage, kV ii) Current, A iii) Impulse withstand voltage, kV _{peak} iv) Power frequency withstand voltage, kV _{rms} b) Type c) Manufacturer d) Catalogue number (catalogue to be attached with bid) e) Creepage distance mm	* * *		
	HV neutral bushing			
	a) Rating i) Voltage, kV ii) Current, A iii) Impulse withstand voltage, kV _{peak} iv) Power frequency withstand Voltage, kV _{rms} b) Type c) Manufacturer d) Catalogue number (catalogue to be attached with bid) e) Creepage distance mm	* * *		



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	LV neutral bushing			
	a) Rating i) Voltage, kV ii) Current, A iii) Impulse withstand voltage, kVpeak iv) Power frequency withstand voltage, kVrms b) Type c) Manufacturer d) Catalogue number (catalogue to be attached with bid) e) Creepage distance mm	* * *		
	Tertiary bushings			
	a) Rating i) Voltage, kV ii) Current, A iii) Impulse withstand voltage, kVpeak iv) Power frequency withstand voltage, kVrms b) Type c) Manufacturer d) Catalogue number (catalogue to be attached with bid) e) Creepage distance mm	* * *		
	Core and Clamp structure grounding bushings			
	a) Rating i) Voltage, kV ii) Current, A iii) Impulse withstand voltage, kVpeak iv) Power frequency withstand voltage, kVrms b) Type c) Manufacturer d) Catalogue number (catalogue to be attached with bid) e) Creepage distance mm	* * *		



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
6.2	High voltage bushing current transformers (catalogue to be attached with the bid) a) Manufacturer b) Type c) Number d) Ratio e) Accuracy Class f) Accuracy Limit Factor g) Rated Burden, VA h) Short-time thermal current, kA i) Continuous thermal current, kA j) Dynamic current, kA k) Resistance of the secondary winding, Ω l) No. of cores in each bushing CT	* * *		
	Low voltage bushing current transformers (catalogue to be attached with the bid) a) Manufacturer b) Type c) Number d) Ratio e) Accuracy Class f) Accuracy Limit Factor g) Rated Burden, VA h) Short-time thermal current, kA i) Continuous thermal current, kA j) Dynamic current, kA k) Resistance of the secondary winding, Ω l) No. of cores in each bushing CT	* * *		
8.0	Type of on-load tap changer (catalogue and data to be supplied with bid) a) Manufacturer b) Type c) Rated Current, A d) Step Voltage, V e) No. of Steps f) Motor Drive i) Type ii) Supply Voltage, V	* * 23 * *		



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	iii) H.P iv) Insulation Level (Voltage to Earth), kVrms g) Tap changer protective relay (catalogue to be attached with the bid) i) Type ii) Make iii) Contact Rating h) Insulation levels i) Voltage to earth, kV,rms ii) Impulse test voltage kV,peak iii) One minute power frequency test voltage (50 Hz) kV,rms i) Internal insulation levels Impulse/ one minute power frequency test voltage i) Between selected and pre-selected tap, kV,rms kV,peak ii) Across fine tap winding kV,rms kV,peak iii) Between phases of fine tap winding kV,rms kV,peak	* * *		
	iv) Across coarse and fine tap winding, if applicable kV,rms kV,peak v) Across coarse tap winding, if applicable kV,rms kV,peak vi) Between phases of coarse tap winding kV,rms kV,peak			



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	j) Remote tap position indicator i) Type designation ii) Manufacturer iii) Method of remote indication k) Temperature-rise of contacts at 1.2 times maximum rated through current. l) Permissible number of operations at rated step voltage. m) Permissible number of operations at reduced step voltage. n) Permissible number of operations for selector switch. o) Temperature-rise of transition resistors at 1.5 times max. Rated through current. p) Mechanical endurance. i) No. of operations without requiring overhauling ii) Total No. of permissible operations in life time.	* * *		
	Automatic voltage regulator, if required (catalogue to be attached with bid) a) Type designation b) Manufacturer c) Catalogue No. d) Input PT supply voltage, V e) Input CT supply current, A f) Voltage adjustment range percent of the voltage to be regulated, percent	* * *		
	g) Sensitivity range percent of the voltage to be regulated, percent h) Under voltage blocking percent of the voltage to be regulated, percent i) Over current blocking percent of normal current, percent			
9.0	Type of construction	core		
	a) Weight of core and coils: complete assembly of core & coil including pressing arrangement / pressing clamps, internal	*		




REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	connections (star / delta / tappings but without OLTC) b) Weight of case and fittings: All outer steel parts tank, cover, conservator, ladder valves control cabinets, accessories, Bushings, Tank Shielding etc. c) Weight of core: Weight of electrical steel d) Weight of coil: Weight of all winding for all three phases (with insulation paper) kg e) Weight of copper: Weight of all copper in Transformer including winding & internal connections (without consideration of any insulation over them) f) Weight of oil: total Weight of oil including in main tank / conservator tank for main Transformer and for OLTC chamber, oil in radiator, oil in Bushing turrets / domes. g) Total Weight: h) Shipping weight of heaviest piece: i) Weight of heaviest piece for un-tanking: *All weights shall be in kgs * Sum of a), b) & f) shall be total weight of T/F	* * * * * * * *		
	Total volume of oil (liters) at 20°C a) Main Tank Ltr b) Conservator Ltr c) Radiators Ltr	* * *		
	Tank dimensions (mm) a) Length (L) mm b) Width (W) mm c) Height (H) mm	* * *		
	Overall dimensions a) Length (L) mm b) Width (W) mm c) Height (H) mm	* * *		



REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
	Thickness of plates			
	a) Tank Cover mm	*		
	b) Tank Sides mm	*		
	c) Tank Bottom mm	*		
	d) Radiator mm	*		

Note:

1. The data/parameters in (*) are to be filled by the manufacturer/bidder in column (A).
2. Any data/parameters in column (A) to be specified by the purchaser shall not be left blank.





Annexure-2

List of Tables

Table-I:

STANDARD RATINGS FOR POWER TRANSFORMER

Sr. No.	Rating/ Characteristics	66/11.5kV 10/13MVA	66/34.5kV 10/13MVA	132/11.5kV 10/13MVA	132/34.5kV 10/13 MVA	132/11.5kV 20/26MVA	132/11.5kV 31.5/40MVA	132/66/11.5kV 31.5/40MVA	132/11.5kV 50/63MVA
1.	No. of phases	3	3	3	3	3	3	3	3
2.	No. of windings	2	2	2	2	2	2	3	2
3.	Frequency Hz	50	50	50	50	50	50	50	50
4.	Rated Power, ONAN/ONAF Cooling, kVA								
	a) HV winding	10000/13000	10000/13000	10000/13000	10000/13000	20000/26000	31500/40000	31500/40000	50000/63000
	b) LV Winding	10000/13000	10000/13000	10000/13000	10000/13000	20000/26000	31500/40000	31500/40000	50000/63000
	c) Tertiary Winding	-	-	-	-	-	-	10000	-
5.	Rated voltage ratio	66000/11500	66000/34500	132000/11500	132000/34500	132000/11500	132000/11500	132000/66000/ 11500	132000/11500
6.	Rated voltage, kV								
	a) HV winding	66	66	132	132	132	132	132	132
	b) LV Winding	11.5	34.5	11.5	34.5	11.5	11.5	66	11.5
	c) Tertiary Winding	-	-	-	-	-	-	11.5	-
7.	System highest voltage, kV								
	a) HV winding	72.5	72.5	145	145	145	145	145	145



Sr. No.	Rating/ Characteristics	66/11.5kV 10/13MVA	66/34.5kV 10/13MVA	132/11.5kV 10/13MVA	132/34.5kV 10/13 MVA	132/11.5kV 20/26MVA	132/11.5kV 31.5/40MVA	132/66/11.5kV 31.5/40MVA	132/11.5kV 50/63MVA
	b) LV Winding	12.5	36	12.5	36	12.5	12.5	72.5	12.5
	c) Tertiary Winding	-	-	-	-	-	-	12.5	-
8.	Method of connection and system earthing								
	a) HV Winding	Delta Connected	Delta Connected	Delta Connected	Delta connected	Delta Connected	Delta Connected	Star Connected neutral brought out and solidly earthed	Delta Connected
	b) LV Winding	Star Connected neutral brought out and solidly earthed	Star Connected neutral brought out and solidly earthed	Star Connected neutral brought out and solidly earthed	Star connected neutral brought out and solidly earthed	Star Connected neutral brought out and solidly earthed	Star Connected neutral brought out and solidly earthed	Star Connected neutral brought out and solidly earthed	Star Connected neutral brought out and solidly earthed
	c) Tertiary Winding	-	-	-	-	-	-	Delta Connected	-
9.	Insulation level								
	a) HV Winding								
	i. Full wave Lightning Impulse (LI) kV peak	325	325	650	650	650	650	650	650



Sr. No.	Rating/ Characteristics	66/11.5kV 10/13MVA	66/34.5kV 10/13MVA	132/11.5kV 10/13MVA	132/34.5kV 10/13 MVA	132/11.5kV 20/26MVA	132/11.5kV 31.5/40MVA	132/66/11.5kV 31.5/40MVA	132/11.5kV 50/63MVA
	ii. Applied Voltage (AV)/ Line terminal AC withstand (LTAC), kV r.m.s	140	140	275	275	275	275	275	275
	b) LV Winding								
	i. Full wave Lightning impulse (LI), kV peak	110	170	110	170	110	110	325	110
	ii. Applied Voltage (AV)/ Line Terminal AC withstand (LTAC), kV r.m.s	38	70	38	70	38	38	140	38
	c) Tertiary Winding								
	i) Full wave Lightning Impulse (LI), kV peak	-	-	-	-	-	-	110	-
	ii) Applied Voltage (AV)/ Line Terminal AC withstand (LTAC) kV r.m.s	-	-	-	-	-	-	38	-
10.	Applied voltage (AV) test for graded insulate of 132kV Star-connected winding, kV rms	-	-	-	-	-	-	140	-



Sr. No.	Rating/ Characteristics	66/11.5kV 10/13MVA	66/34.5kV 10/13MVA	132/11.5kV 10/13MVA	132/34.5kV 10/13 MVA	132/11.5kV 20/26MVA	132/11.5kV 31.5/40MVA	132/66/11.5kV 31.5/40MVA	132/11.5kV 50/63MVA
11.	Vector Group symbols	Dyn11	Dyn11	Dyn11	Dyn11	Dyn11	Dyn11	YNyn0d1	Dyn11
12.	Short-circuit Impedance (at principal tap) based on lower rated power of transformer, percent								
	a) Between HV and LV	9	9	9	9	10	10	10	12
	b) Between LV and Tertiary	-	-	-	-	-	-	8 (31.5MVA base)	-
13.	Permissible temperature-rise, °C								
	a) Winding (measured by resistance method)	55	55	55	55	55	55	55	55
	b) Top of Oil (measured by thermometer)	50	50	50	50	50	50	50	50



Sr. No.	Rating/ Characteristics	66/11.5kV 10/13MVA	66/34.5kV 10/13MVA	132/11.5kV 10/13MVA	132/34.5kV 10/13 MVA	132/11.5kV 20/26MVA	132/11.5kV 31.5/40MVA	132/66/11.5kV 31.5/40MVA	132/11.5kV 50/63MVA
14.	Tapping range of HV winding, percent	±10	±10	±10	±10	±10	±10	±10	±10
15.	No. of steps (on-load)	±11	±11	±11	±11	±11	±11	±11	±11
16.	Rated through current in tap-changer, A	200	200	200	200	200	200	200	>350
17.	Short-circuit test currents for the tap-changer, A	3000	3000	3000	3000	3000	3000	3000	>3000
18.	Maximum noise power level lower/upper rating, db.	70/80	70/80	70/80	70/80	70/80	70/80	70/80	70/80
19.	No. of HV bushing	3	3	3	3	3	3	3	3
20.	No. of HV neutral Bushing	-	-	-	-	-	-	1	-
21.	No. of LV bushing	3	3	3	3	3	3	3	3
22.	No. of LV neutral Bushing	1	1	1	1	1	1	1	1
23.	No. of tertiary bushing	-	-	-	-	-	-	3	-
24.	Bushing type current transformers								
	1) <u>HV winding</u>	-							
	a) Ratio	-							
	b) Standard accuracy class	-	200/5 10P	-	100/5 10P	-	-	-	400/5 10P
	c) Accuracy limit current factor	-	10	-	10	-	-	-	10



Sr. No.	Rating/ Characteristics	66/11.5kV 10/13MVA	66/34.5kV 10/13MVA	132/11.5kV 10/13MVA	132/34.5kV 10/13 MVA	132/11.5kV 20/26MVA	132/11.5kV 31.5/40MVA	132/66/11.5kV 31.5/40MVA	132/11.5kV 50/63MVA
	d) Rated output, VA e) No. of cores/phase f) Number	- - -	30 2 3	- - -	30 2 3	- - -	- - -	- - -	30 2 3
	2) <u>LV winding</u> a) Ratio b) Standard accuracy class c) Accuracy limit current factor d) Rated output, VA e) No. of cores/phase	- - - - - - -	400/5 10P 10 30 2	- - - - -	400/5 10P 10 30 2	- - - - -	- - - - -	- - - - -	4000/5 10P 10 30 2
25.	Symmetrical short-circuit withstand current as a multiple of winding rated current based on lower rated power a) HV Winding b) LV Winding	 12 12	 12 12	 12 12	 12 12	 11 11	 11 11	 11 11	 9 9



Sr. No.	Rating/ Characteristics	66/11.5kV 10/13MVA	66/34.5kV 10/13MVA	132/11.5kV 10/13MVA	132/34.5kV 10/13 MVA	132/11.5kV 20/26MVA	132/11.5kV 31.5/40MVA	132/66/11.5kV 31.5/40MVA	132/11.5kV 50/63MVA
	c) Tertiary Winding	-	-	-	-	-	-	24	-
26.	Duration of short-circuit current, Sec	3	3	3	3	3	3	3	3





Table-II:

Tapping Voltages for High Voltage Windings

Tap Position	Tapping Volts	
	132kV	66kV
1	145200	72600
2	144000	72000
3	142800	71400
4	141600	70800
5	140400	70200
6	139200	69600
7	138000	69000
8	136800	68400
9	135600	67800
10	134400	67200
11	133200	66600
12 (Principal Tap)	132000	66000
13	130800	65400
14	129600	64800
15	128400	64200
16	127200	63600
17	126000	63000
18	124800	62400
19	123600	61800
20	122400	61200
21	121200	60600
22	120000	60000
23	118800	59400



Annexure-3


Table for Overvoltage Operation
(To be filled in and submitted with technical data schedule)

HV Tapping	Applied Voltage kV	Operating time for rated tapping current, Hrs			Permissible current for continuous operation, A			Max. flux density, Tesla			Temp. Rise of core °C			Temp. Rise of windings °C		
		‘A’	‘B’	‘C’	‘A’	‘B’	‘C’	‘A’	‘B’	‘C’	‘A’	‘B’	‘C’	‘A’	‘B’	‘C’
132kV Winding																
145,200	152,000	*			*			≤1.9			*			55°		
132,000	152,000	*			*			≤1.9			*			55°		
132,000	145,000	Con ²			F.L ³			≤1.9			*			55°		
118,800	145,000	*			*			≤1.9			*			55°		
118,800	132,000	Con			F.L			≤1.9			*			55°		
66kV Winding																
72,600	76,000	*			*			≤1.9			*			55°		
66,000	76,000	*			*			≤1.9			*			55°		
66,000	72,500	Con			F.L			≤1.9			*			55°		
59,400	72,500	*			*			≤1.9			*			55°		
59,400	66,000	Con			F.L			≤1.9			*			55°		

¹ Please refer to Technical Data Schedule for 'A', 'B' and 'C'

² Continuous operation


³ Full Load Current




SIDE VIEW-2

ELEVATION

SIDE VIEW-1



PLAN



ISOMETRIC VIEW


LEGEND:

1. Plug screw of sludge opening
2. Mounting of current transformer
3. Conservator
4. Rating plate
5. Draining/filling pipeline for tank
6. Draining pipeline of OLTC
7. Buchholz relay
8. Dehydrating breather (OLTC)
9. Dehydrating breather (Tank)
10. Roller/wheel
11. Motor drive unit
12. Oil temp.indicator liquid type
13. Oil level indicator for OLTC
14. Oil level indicator for tank
15. Oil temp.ind.with thermo well
16. Radiator
17. Pressure Relief device(As many as required as per NTDC specification)
18. Closing butterfly valve
19. Winding temp indicator
20. Fan
21. Core and Clamp Grounding Bushing
22. Lifting lugs of top corner
23. Inspection window
24. Isolating valves, both sides on buchholz relay
25. HV bushing
26. LV bushing
27. Ladder
28. Bottom sampling valve


Note:

- (i) All the equipment are required as per NTDC specification P:46(ammended to date). However manufacturer may change their position as per their design requirement.
- (ii) All the power transformer wiring should be routed through proper cable tray.
- (iii) This diagram is for information purpose only however manufacturer may change as per their design requirement.

NATIONAL TRANSMISSION AND DESPATCH COMPANY			SUBSTATION DESIGN DEPARTMENT (NTDC)
DRAWN	QAZI ADEEL		TYPICAL RELATIVE POSITIONS OF POWER TRANSFORMER ACCESSORIES.
CHECKED BY :			
ASSTT MANAGER	FASIH AHMED		
			DWG No. EW / TS-193
			DATE :- 07 - 10 - 2022





FOR 20NF 3150



FOR 20NF 1000/2000


- ALL DIMENSIONS IN MM
- TERMINALS SHALL BE TIN PLATED.




SYMBOL	CURRENT A	CLASS OUT DOOR	IN DOOR	a	b	d ₁	d ₂	d ₃	d ₄	d ₅	e	f	l ₁	l ₂	NO OF HOLES
20NF1000	1000	20N	—	530	168	M30x2	M12	110	180	163	314	148	626	65	6
20NF2000	2000	20N	—	605	168	M42x3	M12	135	200	183	314	178	701	65	6
20NF 3150	3150	20NF	—	626	160	M48x3	M12	135	200	183	316	180	720	65	6

		PAKISTAN				DESIGN	
		WATER AND POWER DEVELOPMENT AUTHORITY				DEPTT: (P)	
		DRAWN	A. QAYYUM	<i>A. Qayyum</i>		11.5KV BUSHING FOR POWER TRANSFORMER	
		CHECKED	A. LATIF				
		JUNIOR ENGINEER	M. ASIF PERVAIZ	<i>M. Asif Pervais</i>			
		SENIOR ENGINEER	A. MAJEED	<i>A. Majeed</i>			
OCT.2004	20NF 3150 BUSHING ADDED.	DIRECTOR	ASLAM IQBAL	<i>Aslam Iqbal</i>		SCALE	DATE 22.8.1982
DATE	REVISIONS	CHIEF ENGINEER	M.A.SHEIKH	<i>M.A. Sheikh</i>		DWG. NO. PDW/DF-372	

PDW/DF-372




LV Busbar Arrangement
for 40MVA



2.	22-08-1982	Caption revised.		
1.	17-06-1968	Type of wagon added.		
NO	DATE	REVISIONS	SIG	DWG No. DZ-19
TYPICAL RELATIVE POSITIONS OF POWER TRANSFORMER ACCESSORIES				
Redrawn by: QAZI ADEEL		Scale:		Date: 22-01-2021

NATIONAL TRANSMISSION & DESPATCH COMPANY



1.	17-06-1968	Type of wagon added.		
NO	DATE	REVISIONS	SIG	DWG No. EW / DZ-18A
TYPICAL RELATIVE POSITIONS OF POWER TRANSFORMER ACCESSORIES				
Redrawn by: QAZI ADEEL		Scale:		Date: 22-01-2021



NATIONAL GRID COMPANY OF PAKISTAN

(Formerly NTDC)

Chief Engineer (Substation Design) NGC

No. CED/NGC/MSR/

97/ 3307-38

Date: 14-11-2025

1. M/s IMS Engineering Pvt. Ltd, IMS Center, 10-K, Block-6, PECHS, Karachi.
2. M/s Chint Electric Co. Ltd China, House No # 180, Street 6, Block C, Phase 5, DHA, Lahore.
3. M/s Racheena Corporation, 3rd floor, Al Hafeez shopping mall, Main Boulevard, Gulberg-III, Lahore.
4. M/s Elsewedy Electric, 504, 5th Floor, Haly Tower, DHA Phase 2, Main Boulevard Sector R, Lahore.
5. M/s Pak Elektron Limited (PEL) 14-km, Ferozepur Road, Lahore.
6. M/s Hitachi Energy, Pakistan 904-A, Haly Tower, Sector R, DHA Phase 2, Lahore.
7. M/s Siemens Pakistan 15-A, State Life Building, Sir Agha Khan Road, Lahore.
8. M/s HEC Hattar Industrial Estate, Distt Haripur.
9. M/s TBEA Shenyang, China Through M/s Alpine Enterprises Office 509, 510, 515,516 National Tower, Egerton Road, Lahore.
10. M/s Transfopower Industries (Pvt.) Ltd., Thokar Niaz Baig, Lahore.
11. General Manager PPMC, Evacuee Trust Complex, Islamabad.
12. Chief Engineer (Development) PMU PESCO, Peshawar.
13. Chief Engineer (Development) PMU IESCO, Islamabad.
14. Chief Engineer (Development) PMU LESCO, Lahore.
15. Chief Engineer (Development) PMU FESCO, Faisalabad.
16. Chief Engineer (Development) PMU GEPCO, Gujranwala.
17. Chief Engineer (Development) PMU MEPCO, Multan.
18. Chief Engineer (Development) PMU SEPCO, Sukkur.
19. Chief Engineer (Development) PMU HESCO, Hyderabad.
20. Chief Engineer (Development) PMU QESCO, Quetta.
21. Chief Engineer (Development) PMU TESCO, Peshawar.

SUBJECT NGC SPECIFICATION FOR POWER TRANSFORMER P-46:2022- AMENDEMENT NO. 1

It is conveyed that Amendment No. 1 in NGC specification for Power Transformer P-46:2022 has been approved by Managing Director NGC for use in all future Projects/tenders with immediate effect. The approved amendment is enclosed herewith for circulation among all concerned stakeholders.

DA As Above:

(Shahid Shafi Sial)
Chief Engineer (SS Design) NGC

CC:

1. Dy. MD (AD&M) NGC, WAPDA House, Lahore.
2. Dy. MD (P&E) NGC, WAPDA House, Lahore.
3. General Manager (D&E) NGC, 154- WAPDA House, Lahore.
4. General Manager AM (North) NGC, WAPDA House, Lahore
5. General Manager AM (South) NGC RCC building Sehwan Road, Jamshoro.
6. General Manager TSG NGC, TSG training center NKLP, Lahore.
7. General Manager Project Delivery (North) NGC, 219-WAPDA House, Lahore.
8. General Manager Project Deliver (South) NGC, Hyderabad.

NTDC Specification P-46:2022

Amendment No. 1

1. Clause 8.1.3

“The bidder shall provide the name of the manufacturer in the bid and obtain specific approval of NTDC prior to the selection of the on-load tap changer for installation in the transformers.”

is replaced with:

“The bidder shall provide the OLTC from NGC approved/prequalified manufacturer in the bid.”

2. Clause 12.2.2

The text of Clause 12.2.2 is amended as follows:

The equipment will be subjected to all type tests from any ISO/IEC 17025 accredited independent laboratory acceptable to the engineer in the presence of NGC & DISCO's representatives at the expense of the bidder in the following cases:

- Non-submission of the relevant type test reports.
- Submitted type test reports are not from laboratory designated in the tender enquiry
- Submitted type test reports are not to the full satisfaction of the Engineer.

For On Load Tap Changer, type tests will be carried out as per Clause 7: Type Test Requirements of SOP for Qualification of OLTCs manufactured by New Entrants.

For HV/LV bushings, duly certified and complete type test reports for the tests already carried out on identical units in accordance with the latest applicable IEC publications from STL Laboratories, shall be acceptable in lieu of actual tests. In absence of such valid type test reports, the bidder shall submit an undertaking to the effect that, in case of award of contract, the requisite tests shall be carried out at an ISO/IEC 17025 accredited independent laboratory acceptable to NGC & DISCOs in presence of the NGC & DISCO's representatives at the bidder's expense (like visa stamping, boarding, lodging and daily allowance etc.).

The validity of type test report will be 10 years in case of no change in design, construction and manufacturing place. In case of change in accessories viz OLTC, radiators and fans following type tests shall be repeated given the design and construction of the power transformer remains the same.

Sr. No.	Change of Accessory	Type/Routine ¹ Tests to be repeated
1.	On-Load Tap Changer (OLTC)	All Routine ² Tests
2.	Radiators	Temperature Rise Test
3.	Fans	Temperature Rise Test & Noise Power Level

If any poor field performance is quoted during type test validity period by any end user and subsequently vetted by the **General Manager (Design & Engineering) NGC³**, then all type tests will be repeated.

Date of Approval:

12.11.2025

Approved by:

Engr. Muhammad Shahid Nazir
Managing Director NGCP

(Engr. Shahid Shafi Sial)
C.E. (SS Design) NGC
(Secretary SRC)

(Engr. Sharjeel Babar)
C.E. (P&C) NGC
(Member SRC)

(Engr. Shahida Wazir)
C.E. (C&M) NGC
(Member SRC)

(Engr. Muhammad Shoaib)
G.M. AM (N) NGC
(Member SRC)

(Engr. Taqi-ud-Din)
G.M. (D&E) NGC
(Convener SRC)

¹ Added vide Amendment No.1 dated 12.11.2025

² Substituted vide Amendment No.1 dated 12.11.2025

³ Substituted vide Amendment No.1 dated 12.11.2025

Price Schedule: Goods Manufactured in Pakistan

Name of Bidder Page of

NCB	Sr. No	ITEM DESCRIPTION	Unit	Qty	Unit rate on *EXW without sales tax [in Rs] (including all transportation charges, loading , Un loading etc upto IESCO Regional Store New Wah	Total Price on EXW without sales tax [in Rs] including transportation charges, loading , Un loading, all types of duties etc, upto IESCO Regional Store New Wah
1		2	3	4	5	6=(4x5)
PMU/Goods/ NCB-302	1.	Fan with motor for 40 MVA T/F	No.	9		
	2.	Fan with motor for 20/26 MVA T/F	No.	12		
	3.	Fan with motor for 10/13 MVA T/F	No.	14		
	4.	Fan with motor for 21/30 MVA T/F (132/66)	No.	3		
Total Price of NCB-302 without GST/PST						
Total Price of NCB-302 Including GST /PST						

Note:

1. The Bidder must fill the price in this Form in accordance with the instructions otherwise bid will be rejected
2. In case of discrepancy between unit price and total, the unit price shall prevail.
3. The Currencies should be in accordance with instruction BDS-12

*EXW price included all taxes and duties excluding GST

IESCO Designated Store/place: *IESCO Regional Store, Hassan Abdaal Road, New Wah.*

Name in the capacity of

Signature of Bidder: _____

Duly authorized to sign the Bid for and on behalf of

Dated on day of 20

Price Schedule: Goods Manufactured Outside Pakistan, to be Imported

Name of Bidder Page of

NCB	Sr. No	ITEM DESCRIPTION	Unit	Qty	Unit rate on *DDP upto Karachi Port without sales tax [in Rs] (including all transportation charges, loading , Un loading etc upto IESCO Regional Store New Wah	Total Price on *DDP upto Karachi Port without sales tax [in Rs] including transportation charges, loading , Un loading, all types of duties etc, upto IESCO Regional Store New Wah
1		2	3	4	5	6=(4x5)
PMU/Goods/ NCB-302	1.	Fan with motor for 40 MVA T/F	No.	9		
	2.	Fan with motor for 20/26 MVA T/F	No.	12		
	3.	Fan with motor for 10/13 MVA T/F	No.	14		
	4.	Fan with motor for 21/30 MVA T/F (132/66)	No.	3		
Total Price of NCB-302 without GST/PST						
Total Price of NCB-302 Including GST /PST						

Note:

1. The Bidder must fill the price in this Form in accordance with the instructions otherwise bid will be rejected
2. In case of discrepancy between unit price and total, the unit price shall prevail.
3. The Currencies should be in accordance with instruction BDS-12

*DDP price included all taxes and duties excluding GST

IESCO Designated Store/place: IESCO Regional Store, Hassan Abdaal Road, New Wah.

Name in the capacity of

Signature of Bidder:

Duly authorized to sign the Bid for and on behalf of

Dated on day of 20

Past Experience / Contracts

Contracts over <i>[insert amount]</i> during the last three years:				
Procuring Agency	Value	Year	Goods/Services Supplied	Country of Destination



Historical Contract Non-Performance, and Pending Litigation and Litigation History

[The following table shall be filled in for the Applicant and for each member of a Joint Venture]

Applicant's Name: *[insert full name]*

Date: *[insert day, month, year]*

Joint Venture Member Name: *[insert full name]*

IFP No. and title: *[insert IFP number and title]*

Page *[insert page number]* of *[insert total number]* pages

☐ Not debarred due to deviation from commitment of Bid Securing Declaration- ☐ Not debarred due to non-performance			
Year	Non-performed portion of contract	Contract Identification	Total Contract Amount (current value, currency, exchange rate and PKR equivalent)
<i>[insert year]</i>	<i>[insert amount and percentage]</i>	Contract Identification: <i>[indicate complete contract name/ number, and any other identification]</i> Name of Procuring Agency: <i>[insert full name]</i> Address of Procuring Agency: <i>[insert street/city/country]</i> Reason(s) for nonperformance: <i>[indicate main reason(s)]</i>	<i>[insert amount]</i>
Pending Litigation, in accordance with Section III, Qualification Criteria and Requirements			
☐ Pending litigation in accordance with Section III, Qualification Criteria and Requirements, Sub-Factor 2.3 as indicated below.			
Year of dispute	Amount in dispute (currency)	Contract Identification	Total Contract Amount (currency), US\$ PKR Equivalent (exchange rate)

<i>[insert year]</i>	<i>[insert amount]</i>	Contract Identification: [indicate complete contract name, number, and any other identification] Name of Procuring Agency: <i>[insert full name]</i> Address of Procuring Agency: <i>[insert street/city/country]</i> Matter in dispute: <i>[indicate main issues in dispute]</i> Party who initiated the dispute: <i>[indicate "Procuring Agency" or "Supplier"]</i> Status of dispute: <i>[Indicate if it is being treated by the Adjudicator, under Arbitration or being dealt with by the Judiciary]</i>	<i>[insert amount]</i>
☐ No consistent history of court/arbitral award decisions in accordance with Section III, Qualification Criteria and Requirements, Sub-Factor 2.4. ☐ Consistent history of court/arbitral award decisions in accordance with Section III, Qualification Criteria and Requirements, Sub-Factor 2.4 as indicated below.			
Year of award	Outcome as percentage of Net Worth	Contract Identification	Total Contract Amount (currency), PKR Equivalent (exchange rate)
<i>[insert year]</i>	<i>[insert percentage]</i>	Contract Identification: [indicate complete contract name, number, and any other identification] Name of Procuring Agency: <i>[insert full name]</i> Address of Procuring Agency: <i>[insert street/city/country]</i> Matter in dispute: <i>[indicate main issues in dispute]</i> Party who initiated the dispute: <i>[indicate "Procuring Agency" or "Supplier"]</i> Court/ arbitral award decision: <i>[Indicate if the award decision was against the Applicant or any member of a joint venture.]y]</i>	<i>[insert amount]</i>

Current Contract Commitments / Works in Progress

Bidders and each member to a JV should provide information on their current commitments on all contracts that have been awarded, or for which a letter of intent or acceptance has been received, or for contracts approaching completion, but for which an unqualified, full completion certificate has yet to be issued.

Current Contract Commitments					
No.	Name of Contract	Employer's Contact Address, Tel, Fax	Value of Outstanding Work [Current Eq. PKR]	Estimated Completion Date	Average Monthly Invoicing Over Last Six Months [Eq. PKR/month]
1					
2					
3					
4					
5					

Financial Situation and Performance

[The following table shall be filled in for the Applicant and for each member of a Joint Venture]

Applicant's Name: [insert full name]

Date: [insert day, month, year]

Joint Venture Member Name: [insert full name]

IFP No. and title: [insert IFP number and title]

Page [insert page number] of [insert total number] pages

1. Financial data

Type of Financial information in (currency)	Historic information for previous [insert number] years, [insert in words] (amount in currency, currency, exchange rate*, PKR equivalent)				
	Year 1	Year 2	Year 3		
Statement of Financial Position (Information from Balance Sheet)					
Total Assets (TA)					
Total Liabilities (TL)					
Total Equity/Net Worth (NW)					
Current Assets (CA)					
Current Liabilities (CL)					
Working Capital (WC)					
Information from Income Statement					
Total Revenue (TR)					
Profits Before Taxes (PBT)					
Cash Flow Information					
Cash Flow from Operating Activities					

* Refer ITA 14 for the exchange rate

3. Financial documents

The Applicant and in case of JV, members of JV shall provide copies of financial statements for [number] years pursuant Section III, Qualifications Criteria and Requirements. The financial statements shall:

- (a) reflect the financial situation of the Applicant or in case of JV member, and not an affiliated entity (such as parent company or group member).
 - (b) be independently audited or certified in accordance with local legislation.
 - (c) be complete, including all notes to the financial statements.
 - (d) correspond to accounting periods already completed and audited.
- ☐ Attached are copies of financial statements¹ for the [number] years required above; and complying with the requirements.

¹ If the most recent set of financial statements is for a period earlier than 12 months from the date of Application, the reason for this should be justified.

Average Annual Turnover (Annual Sales Value)

[The following table shall be filled in for the Applicant and for each member of a Joint Venture]

Applicant's Name: *[insert full name]*

Date: *[insert day, month, year]*

Joint Venture Member Name: *[insert full name]*

IFP No. and title: *[insert IFP number and title]*

Page *[insert page number]* of *[insert total number]* pages

Annual Turnover Data			
Year	Amount Currency	Exchange rate* (If applicable)	PKR equivalent
<i>[indicate calendar year]</i>	<i>[insert amount and indicate currency]</i>		
		Average Annual Turnover **	

* Refer ITA for date and source of exchange rate.

** Total PKR equivalent for all years divided by the total number of years. See Section III, Qualification Criteria and Requirements, ITA.