

Standard Bidding Document

CRITICAL REQUIREMENT OF SECURITY EQUIPMENT AND OTHER PARAPHERNALIA AT VARIOUS AIRPORTS / LOCATIONS (CONSTRUCTION OF BARRACKS, JS APARTMENTS AND MOQs FOR ASF AT AIIAP LAHORE) (Works)

National

Single Stage-Two Envelope



July 27, 2026

*ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority
(PAA)), Divisional Engineer
ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District),
Lahore Division (Division), Punjab (Province).
Phone: +92-345-567-2161, Email: abrahamad161@gmail.com*

Table of Contents

REQUEST FOR BIDS	1
Instructions to Bidders	3
Bid Data Sheet	31
Bids Data Sheet (BDS)	32
Eligibility Criteria	36
Evaluation Criteria	37
Jobs/Lots	38
Related Services :	40
Work Specifications and Market Rates	41
Scope of Work	281
Price Schedule	283
General Conditions of Contract	285
Special Conditions of Contract	295
Bid Securing Declaration	300
Contract Form	302
Integrity Pact	305
Performance Guarantee Form	307
Annexure	310
General Conditions of Contract	285
Special Conditons of Contract (Civil works)	311
Special Conditions of Contract (E/M Works)	311

Drawings	311
List of approved Manufacturers	311
List of approved Banks	312
HSE Manual	312
Integrity Pact	305
Procurement Forms	313
Past Construction Experiences	1
Contractor's Key Personnel Representative and Their Schedules	1
Historical Contract Non-Performance, and Pending Litigation and Litigation History	1
Current Contracts and Their Progress	1
Financial Capacity and Net Worth Evaluation Form	1
Average Annual Turnover	1
Additional Forms and Documents	316

REQUEST FOR BIDS

PROCUREMENT OF CIVIL WORKS

1. The **ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA))** has reserved Funds for the procurement planned for FY **2026-27**. The **ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA))** intends to apply part of the proceeds of this Fund to cover eligible payments under the contract for the "**CRITICAL REQUIREMENT OF SECURITY EQUIPMENT AND OTHER PARAPHERNALIA AT VARIOUS AIRPORTS / LOCATIONS (CONSTRUCTION OF BARRACKS, JS APARTMENTS AND MOQs FOR ASF AT AIIAP LAHORE)**" with the reference of "**P72208**".
2. The **ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA))** invites sealed Bids from eligible Bidders for procurement of Works (**CRITICAL REQUIREMENT OF SECURITY EQUIPMENT AND OTHER PARAPHERNALIA AT VARIOUS AIRPORTS / LOCATIONS (CONSTRUCTION OF BARRACKS, JS APARTMENTS AND MOQs FOR ASF AT AIIAP LAHORE)**) described in the bidding documents on **EPADS v2.0**.
3. **Single Stage-Two Envelope** will be used by adopting **Least Cost Based Selection (LCBS)** Technique for the subject procurement, in line with the Public Procurement Rules, 2004 and any Regulations, Regulatory Guides, Procurement Guidelines or Instructions issued by the Authority from time to time.
4. All Bids must be accompanied by a Bid Security amount described in Bid Security Section in Bidding Document in the form of **Pay Order, Call at Deposit**. Or all bids must be accompanied by bid securing declaration in the format specified in the Bidding documents
5. E-Bidding documents, containing detailed terms & conditions, specifications and requirements etc. are available on **e-Pak Acquisition and Disposal System (EPADS)** at

<https://epads.gov.pk/opportunities/federal/procurements/72208> for all the interested bidders registered on **EPADS v2.0**. Bidders are required to get themselves registered on **EPADS v2.0** to participate in Bidding process.

6. The e-bids, prepared in accordance with the instructions in the e-Bidding documents, must be submitted through **EPADS v2.0** on or before **Wednesday, August 19, 2026 11:00 AM**. E-bids will be opened by using **EPADS v2.0** on the same day at **Wednesday, August 19, 2026 11:30 AM**. Manual submission of Bids shall not be entertained. Those vendor who have not yet registered on the new version of **EPADS v2.0**, may register themselves on <https://vendors.epads.gov.pk/>. A tutorial to explain the registration process is available at <https://www.youtube.com/watch?v=MNW6T38v7tc>.


In terms of Rules 48 of Public Procurement Rules, 2004 Grievance Redressal Committee (GRC) is notified for the subject procurement and notification copy is available on the procuring agency's website and on Authority's website at (www.ppra.org.pk).

ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY)
(Pakistan Airports Authority (PAA)), Divisional Engineer

ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY),
Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province).

+92-345-567-2161

abrarahmad161@gmail.com



Instructions to Bidders

A. INTRODUCTION

1. Scope of Bid

1.1. The Procuring agency/Employer (PA), as indicated in the Bid Data Sheet (BDS) invites Bids for the execution of Works as specified in the BDS and Section V- Works Requirements. The name, identification, and number of lots (contracts) of this National/ International Competitive Bidding process are specified in the BDS.

2. Source of Funds

2.1. Source of funds as referred in Clause 2 of Bid Data Sheet.

3. Eligible Bidders

3.1. A bidder may be natural person, company or firm or public or semi-public agency of Pakistan or any foreign country, or any combination of them with a formal existing agreement (on Judicial Papers) in the form of a joint venture or consortium. In the case of a joint venture or consortium, all members shall be jointly and severally liable for the execution of the Contract in accordance with the terms and conditions of the Contract. The joint venture or consortium shall nominate a Lead Member as nominated in the BDS, who shall have the authority to conduct all business for and on behalf of any and all the members of the joint venture or consortium during the Bidding process, and in case of award of contract, during the execution of contract. Verifiable copy of the agreement that forms a joint venture, consortium or association shall be required to be submitted as part of the Bid.

Any bid submitted by the joint venture, consortium or association shall indicate the part of proposed contract to be performed by each party and each party shall be evaluated (or post qualified if required) with respect to its contribution only, and the responsibilities of each party shall not be substantially altered without prior written approval of the Procuring Agency and in line with any instructions issued by the Authority.

(The limit on the number of members of JV or Consortium may be prescribed

in BDS, in accordance with the guidelines issued by the PPRA).

3.2. The invitation for bids is open to all prospective bidders subject to any provisions of incorporation or licensing by the respective national/international incorporating agency or statutory body established for that particular trade or business. Procuring agencies shall specify the registration/licensing requirements for the foreign bidder keeping in view the requirement of that business.

3.3. A Bidder shall not have a conflict of interest. All Bidders found to have a conflict of interest shall be disqualified. A Bidders may be considered to have a conflict of interest with one or more parties in this Bidding process, if they:

3.3.1. are associated or have been associated in the past, directly or indirectly with a firm or any of its affiliates which have been engaged by the Procuring agency/Employer to provide consulting services for the preparation of design or technical specifications of the works that are the subject of the bid; or

3.3.2. have controlling shareholders in common; or

3.3.3. receive or have received any direct or indirect subsidy from any of them; or

3.3.4. have the same legal representative for purposes of this Bid; or

3.3.5. have a relationship with each other, directly or through common third parties, that puts them in a position to have access to information about or influence on the bid of another bidder, or influence the decisions of the Procuring agency/Employer regarding this Bidding process; or

3.3.6. Submit more than one bid in this bidding process.

3.4. A Bidder may be ineligible if –

3.4.1. he is declared bankrupt or, in the case of company or firm, insolvent;

3.4.2. payments in favor of the bidder is suspended in accordance with the judgment of a court of law other than a judgment declaring bankruptcy and resulting (in accordance with the national laws) in the total or partial loss of the right to administer and dispose of its property;

3.4.3. the bidder is convicted, by a final judgment of a Court of Law or relevant Professional Statutory Body, of any offence involving professional conduct;

3.4.4. The bidder is debarred/ blacklisted by a national level Procuring agency/Employer and hence debarred due to involvement in corrupt and fraudulent practices, or performance failure or due to breach of bid securing declaration.

3.5. As and when required, bidders shall provide to the Procuring agency/Employer evidence of their eligibility, proof of compliance with the necessary legal requirements to carry out the contract effectively.

3.6. Bidders shall submit proposal relating to the nature, conditions and modalities of sub-contracting wherever the sub-contracting of any elements of the contract is envisaged.

4. Eligible Material and Equipment

4.1. All the material and equipment to be mobilized under the contract shall have their origin in eligible source countries, and all expenditures made under the contract will be limited to such materials and equipment. For this purpose, ineligible countries are stated in the section-IV titled as “Eligible Countries”.

B. BIDDING DOCUMENTS

5. Contents of Bidding Documents

5.1. The scope of Works, bidding procedures, and terms and conditions of the contract are prescribed in the bidding documents. In addition to the Invitation for Bids, the bidding documents which should be read in

conjunction with any addenda issued in accordance with ITB 7.1 include:

Section I -Invitation for Bids

Section II Instructions to Bidders (ITBs)

Section III Bid Data Sheet (BDS)

Section IV Eligible Countries

Section V Evaluation and Qualification Criteria

Section VI Works Requirements Technical Specifications & Schedule of Requirements

Section VII Standard Bidding Forms

Section VIII General Conditions of Contract (GCC)

Section IX Particular Conditions of Contract (PCC)

Section X Contract Forms

5.2. The bidder is expected to examine all instructions, forms, specifications, terms and conditions prescribed in the bidding documents. Failure to furnish all the information required in the bidding documents will be at the bidder's risk and may result in the rejection of his bid.

6. Clarification of Bidding Document, Pre-bid Meeting

6.1. A prospective bidder requiring any clarification of the bidding document may notify the Procuring agency/Employer through EPADS.

6.2. The Procuring agency/Employer shall respond to the request for clarification in accordance with Rule 31 of the Public Procurement Rules 2004.

6.3. Should the Procuring Agency deem it necessary to amend the BIDDING document as a result of a clarification, it shall do so following the procedure under ITB 7.

6.4. If indicated in the BDS, the bidder's designated representative is invited at the bidder's cost to attend a pre-bid meeting at the place, date and time mentioned in the BDS. During this pre-bid meeting, prospective bidders may request clarification of the schedule of requirement, the evaluation criteria or any other aspects of the bidding documents.

6.5. Minutes of the pre-bid meeting, if applicable, including the text of the questions asked by bidders, including those during the meeting (without identifying the source) and the responses given, together with any responses prepared after the meeting will be uploaded on EPADS. Any modification to the bidding documents that may become necessary as a result of the pre-bid meeting shall be made by the Procuring agency/Employer exclusively through the use of an Addendum pursuant to ITB 7. Non-attendance at the pre-bid meeting will not be a cause for disqualification of a bidder.

6.6. The bidder is advised to visit and examine the Site of Works and its surroundings and obtain for itself on its own responsibility all information that may be necessary for preparing the bid and entering into a contract for construction of the Works. The costs of visiting the Site shall be at the bidder's own expense.

6.7. The bidder and any of its authorized personnel will be granted permission by the Procuring agency/Employer to enter upon its premises and lands for the purpose of such visit, but only upon the express condition that the bidder and its personnel will release and indemnify the Procuring agency/Employer from and against all liability in respect thereof, and will be responsible for death or personal injury, loss of or damage to property, and any other loss, damage, costs, and expenses incurred as a result of the inspection.

7. Amendment of Bidding Documents

7.1. The procuring agency may issue notification of any change, addition, modification or deletion in accordance with Rule 23 of the Public Procurement Rules 2004 i.e. Bidding Documents.

7.2. To give prospective bidders reasonable time in which to take an addendum/corrigendum into account in preparing their bids, the Procuring agency/Employer may, at its discretion, extend the deadline for the submission of bids:

Provided that the Procuring agency/Employer shall extend the deadline for submission of bid in pursuance of Rule 27 of the Public Procurement Rules 2004, i.e. Extension of time for submission of bids, if such an addendum is

issued within last three (03) days of the bid submission deadline.

C. PREPARATION OF BIDS

8. Language of Bid

8.1. The bid prepared by the bidder, as well as all correspondence and documents relating to the bid exchanged by the bidder and the Procuring agency/Employer shall be written in the English language unless specified in the BDS. Supporting documents and printed literature furnished by the bidder may be in another language provided they are accompanied by an accurate translation of the relevant pages in the English language unless specified in the BDS, in which case, for purposes of interpretation of the bidder, the translation shall govern.

9. Documents Constituting the Bids

9.1. The Bids prepared by the Bidder shall constitute of all the documents required in the BDS.

10. Documents Establishing Eligibility of Material, Equipment and Works, their Conformity to Bidding Documents

10.1. The bid prepared by the bidder shall constitute the following components: -

10.1.1. Documentary evidence established in accordance with ITB 10 that the material and equipment to be utilized by the Bidder for the executions of works are eligible material and equipment and conform to the Bidding Documents;

10.1.2. Documentary evidence established in accordance with ITB 11 that the bidder has been authorized to carry out the Construction works;

10.1.3. Documentary evidence established in accordance with ITB 11 that the bidder is eligible and/or qualified for the subject bidding process;

10.1.4. Form of Bid and Bid Prices completed in accordance with ITB 12 and 13;

10.1.5. Completed schedules as required, including priced Bill of Quantities in accordance with ITB 13.

10.1.6. Technical Proposal completed in all aspects in accordance with ITB-15.

10.1.7. Bid security or Bid Securing Declaration furnished in accordance with ITB 17;

10.1.8. Any other document required in the BDS.

10.2. In addition to the requirements, bids submitted by a JV shall include a copy of the Joint Venture Agreement entered into by all members. Alternatively, a letter of intent to execute a Joint Venture Agreement in the event of a successful bid shall be signed by all members and submitted with the bid, together with a copy of the proposed Agreement.

10.3. The bidder shall furnish, as part of its bid, all those documents establishing the eligibility in conformity to the terms and conditions specified in the bidding documents for all material, equipment and works which the bidder proposes to execute.

10.4. The documentary evidence of conformity of the material, equipment and works to the Bidding Documents may be in the form of literature, drawings, and data, and shall consist of:

10.4.1. a detailed description of the work methodology, approach, schedule and resources to be mobilized at site;

10.4.2. an item-by-item commentary on the Procuring agency/Employer's Technical Specifications demonstrating substantial responsiveness of the material, equipment and works to those specifications, or a statement of deviations and exceptions to the provisions of the Technical Specifications;

10.4.3. any other procurement specific documentation requirement as stated in the BDS.

10.5. The required documents and other accompanying documents must be in English. In case any other language than English is used the pertinent translation into English shall be attached to the original version.

11. Documents Establishing Eligibility and Qualification of the Bidder

11.1. The bidder shall furnish, as part of its bid, all those documents establishing the bidder's eligibility to participate in the bidding process and/or its qualification to perform the contract if its bid is accepted.

11.2. The documentary evidence of the bidder's eligibility to bid shall establish to the satisfaction of the Procuring agency/Employer that the bidder, at the time of submission of its bid, is from an eligible country as defined in Section-IV titled as "Eligible Countries".

11.3. The documentary evidence of the bidder's qualification to perform the contract if its bid is accepted shall establish to the satisfaction of Procuring agency/Employer that:

11.3.1. The bidder has the financial and technical capability necessary to perform the Contract, meets the qualification criteria specified in Section-V, Evaluation and Qualification Criteria and BDS.

11.3.2. In the case of a bidder not doing business within Pakistan, the bidder is or will be (if awarded the contract) represented by a local bidder (Joint Venture) in accordance with the PEC works bylaws, and in case of award of works such foreign firm is required to participate in the execution of works to carry out its obligations as prescribed in the Conditions of Contract and /or Technical Specifications.

11.3.3. That the bidder meets the qualification criteria listed in Section-V, Evaluation and Qualification Criteria and BDS.

12. Forms of Bid

12.1. The Bidder shall fill the Form of Bids furnished in the bidding documents. The Bids Form must be completed without any alterations to its format and no substitute shall be accepted.

13. Bid Prices

13.1. The bid prices quoted by the bidder in the Standard bid Forms, Bill of Quantities and in the Price Schedules shall conform to the requirements specified below or exclusively mentioned hereafter in the bidding documents.

13.2. The bidder shall fill in rates and prices for all items of the Works described in the Bill of Quantities. If a Price Schedule shows items listed but not priced, their prices shall be construed to be included in the prices of other items in the Bill of Quantities and will not be paid for separately by the Procuring agency/Employer.

13.3. Items not listed in the Price Schedule shall be assumed not to be included in the bid, and provided that the bid is still substantially responsive in their absence or due to their nominal nature, the corresponding average price of the respective item(s) of the remaining substantially responsive bidder(s) shall be construed to be the price of those missing item(s):

Provided that:

13.3.1. where there is only one (substantially) responsive bidder, or

13.3.2. where there is provision for alternate proposals and the respective items are not listed in the other bids,

The Procuring agency/Employer may fix the price of missing items in accordance with market survey, and the same shall be considered as final price.

13.4. The Bid price to be quoted in the Form of Bid in accordance with ITB 12 shall be the total price of the bid.

13.5. Unless otherwise specified in the BDS and the Contract, the rates and prices quoted by the bidder are subject to adjustment during the performance of the Contract in accordance with the provisions of the

Conditions of Contract.

13.6. If so specified in ITB 1.1, bids may be invited for individual lots (contracts) or for any combination of lots (packages).

13.7. Prices quoted by the Bidder shall be fixed during the bidder's performance of the contract and not subject to variation on any account. A bid submitted with an adjustable price will be treated as non-responsive and shall be rejected, pursuant to ITB 27, unless otherwise price adjustment is permissible under Conditions of the Contract.

13.8. All duties, taxes, and other levies payable by the Contractor under the Contract, or for any other cause, as of the date twenty-eight (28) days prior to the deadline for submission of bids, shall be included in the rates and prices and the total bid price submitted by the bidder.

14. Currencies of Bid and Payment

14.1. Prices shall be quoted in Pakistani Rupees unless otherwise specified in the BDS. Comparison of bids and tie of bid shall be treated in accordance with the Rule 30(2) of Public Procurement Rules, 2004.

15. Documents Comprising the Technical Proposal

15.1. The bidder shall furnish a Technical Proposal including a statement of work methods, equipment, personnel, schedule and any other information as stipulated in Section VII – Standard Bid Forms, in sufficient detail to demonstrate the adequacy of the bidder's proposal to meet the work requirements and the completion time.

16. Bid Validity Period

16.1. Bids shall remain valid for the period specified in the BDS after the bid submission deadline prescribed by the Procuring agency/Employer. A bid valid for a shorter period shall be rejected by the Procuring agency/Employer as non-responsive. The period of bid validity will be determined from the complementary bid securing instrument i.e. the expiry period of bid security or bid securing declaration as the case may be.

16.2. Under exceptional circumstances, prior to the expiration of the initial Bids/Bid validity period, the Procuring Agency may request the Bidders' consent to an extension of the period of validity of their Bids/Bid. Such request for extension of the period of bid validity shall be carried out in accordance with Rule 26 of the Public Procurement Rules, 2004.

17. Bid Security or Bid Securing Declaration

17.1. Pursuant to ITB 11.1 unless otherwise specified in the BDS, the bidder shall furnish as part of its bid, a Bid Security in accordance with Rule 25 of the Public Procurement Rules, 2004 in the amount and currency specified in the BDS or Bid Securing Declaration as specified in the BDS in the format provided in Section VII (Standard Bidding Forms).

In case Procuring agency/Employer is inviting bids in lots / packages, the bidder shall be required to submit his bid security against the respective lot/package for which he is submitting his bid.

Until the development of functionality of auto verification of financial instrument in EPADS, the scanned copy of bid security or bid securing declaration, as the case may be, shall be uploaded on E-PADS whereas the original instrument to be submitted to the procuring agency before closing of bid submission deadline,

17.2. The Bid Security shall be denominated in the local currency or in another freely convertible currency, and it shall be in the form specified in the **BDS** which shall be in any of the following:

17.2.1. A bank guarantee, an irrevocable letter of credit issued by a Scheduled bank in the form provided in the Bidding Documents or another form acceptable to the Procuring agency/Employer and valid for twenty-eight (28) days beyond the end of the validity of the Bid. This shall also apply if the period for Bid Validity is extended. In either case, the form must include the complete name of the bidder;

17.2.2. A cashier's or certified cheque; or

17.2.3. Another security as indicated in the **BDS**.

17.3. The Bid Security or Bid Securing Declaration shall be in accordance with the Form of the Bid Security or Bid Securing Declaration included in Section VII (Standard Bidding Forms) or another form approved by the Procuring agency/Employer prior to the bid submission.

17.4. The Bid Security shall be payable promptly upon written demand by the Procuring agency/Employer in case any of the conditions listed in ITB 17.9 are invoked.

17.5. Any bid not accompanied by a Bid Security or Bid Securing Declaration in accordance with ITB 17.1 or 17.3 shall be rejected by the Procuring agency/Employer and shall be declared as non-responsive bid, pursuant to ITB 27.

17.6. Unsuccessful bidders' Bid Security will be discharged or returned as promptly as possible, however in no case later than thirty (30) days after the expiration of the period of Bid Validity prescribed by the Procuring agency/Employer pursuant to ITB 16. The Procuring agency/Employer shall make no claim to the amount of the Bid Security, and shall promptly return the Bid Security document, after whichever of the following that occurs earliest:

17.6.1. The expiry of the Bid Security;

17.6.2. The entry into force of a procurement contract and the provision of a performance security (or guarantee), for the performance of the contract if such a security (or guarantee), is required by the Bidding documents;

17.6.3. The rejection by the Procuring agency/Employer of all Bids;

17.6.4. The withdrawal of the bid prior to the deadline for the submission of bids, unless the bidding documents stipulate that no such withdrawal is permitted.

17.7. The successful bidder's Bid Security will be discharged upon the bidder signing the contract pursuant to ITB 40, or furnishing the performance security (or guarantee), pursuant to ITB 41.

17.8. The Bid Security may be forfeited or the Bid Securing Declaration executed:

17.8.1. if a Bidder:

17.8.1.1. Withdraws its Bid during the period of Bid Validity as specified by the Procuring agency/Employer, and referred by the bidder on the Form of Bid except as provided for in ITB 16.2; or

17.8.2. In the case of a successful bidder, if the bidder fails:

17.8.2.1. to sign the contract in accordance with ITB 40; or

17.8.2.2. to furnish performance security (or guarantee) in accordance with ITB 41.

17.9. In case of Bid Security issued by the foreign bank is allowed by the Procuring agency/Employer, the same should be counter guaranteed by a corresponding bank in Pakistan. Furthermore, in case of joint venture, it should be in the name of Joint venture to ensure joint responsibility. In case the JV is not legally constituted at the time of bid submission, the bid security or bid securing declaration shall be in the names of all future members as named in the letter of bid.

18. Withdrawal of Bids

18.1. Before bid submission deadline, any bidder may withdraw, substitute, or modify its bid after it has been submitted by sending a written notice, duly signed by an authorized representative, and the corresponding must accompany the respective written notice.

19. Format and Signing of Bid

19.1. The Bidder shall prepare and submit Bids through EPADS with due diligence after carefully reading all the terms and condition before bid submission deadline.

D. SUBMISSION OF BIDS

20. Submission of Bids through EPADS v2.0

20.1. All bids shall be submitted through EPADS v2.0.

21. Deadline for Submission of Bids

21.1. All bids shall be received through **EPADS v2.0** not later than bid submission deadline as specified in the **BDS**.

21.2. The Procuring agency/Employer may, under exceptional circumstances and at its discretion, extend the deadline for the submission of bids, pursuant to Rule 27 of the Public Procurement Rules, 2004. Extension of Time for submission of bid, by amending the Bidding Documents in accordance with ITB 7, in which case all rights and obligations of the Procuring agency/Employer and bidders previously subject to the deadline will thereafter be subject to the new deadline.

22. Substitution and Modification of bids

22.1. A bidder may substitute or modify his bid after it has been submitted, provided that written notice of the substitution or modification of the bid, is received by the Procuring agency/Employer prior to the deadline for submission of bids.

22.2. Revised bid may be submitted after the substitution or modification made in the original bid in accordance with the provisions referred in **ITB 18**.

E. OPENING AND EVALUATION OF BIDS

23. Opening of Bids

23.1. The Procuring Agency will open bids in accordance with Rule 28 of the Public Procurement Rules, 2004 and as specified in the BDS.

24. Confidentiality

24.1. Information relating to the examination, clarification, evaluation and comparison of bids and recommendation of contract award shall not be disclosed to bidders or any other persons not officially concerned with such process until the time of the announcement of the respective evaluation report.

25. **Clarification of Bids**

25.1. Clarification of Bidding Documents shall be carried out in accordance with Rule 31 of the Public Procurement Rules, 2004.

25.2. The alteration or modification in the bid which in any case affect the following parameters will be considered as a change in the substance of a bid:

- 25.2.1. evaluation & qualification criteria;
- 25.2.2. required scope of work;
- 25.2.3. contract price;
- 25.2.4. all securities requirements;
- 25.2.5. tax requirements;
- 25.2.6. terms and conditions of bidding documents.
- 25.2.7. change in the ranking of the bidder

26. **Preliminary Examination of Bids**

26.1. Prior to the detailed evaluation of bids, the Procuring agency/Employer will determine whether each bid:

- 26.1.1. meets the eligibility criteria defined in **ITB 3** and **ITB 4**;
- 26.1.2. has been prepared as per the format and contents defined by the Procuring agency/Employer in the bidding documents;
- 26.1.3. has been properly signed;

26.1.4. is accompanied by the required securities; and

26.1.5. is substantially responsive to the requirements of the bidding documents.

The Procuring agency/Employer's determination of a bid's substantial responsiveness will be based on the contents of the bid itself.

26.2. A substantially responsive Bid is one which conforms to all the terms, conditions, and specifications of the Bidding Documents, without material deviation or reservation. A material deviation or reservation is one that: -

26.2.1. affects in any substantial way the scope, quality, or performance of the Works;

26.2.2. limits in any substantial way, inconsistent with the bidding documents, the Procuring agency/Employer's rights or the bidders' obligations under the Contract; or

26.2.3. if rectified, would affect unfairly the competitive position of other bidders presenting substantially responsive bids.

26.3. The Procuring agency/Employer will confirm that the documents and information specified under ITB 9, 10 and 11 have been provided in the bid. If any of these documents or information is missing, or is not provided in accordance with the Instructions to Bidders, the bid shall be rejected.

26.4. The Procuring agency/Employer may waive-off any minor informality, nonconformity, or irregularity in a bid which does not constitute a material deviation, provided such waiver does not prejudice or affect the relative ranking of any Bidder.

Explanation: A minor informality, non-conformity or irregularity is one that is merely a matter of form and not of substance. It also pertains to some immaterial defect in a Bid or variation of a bid from the exact requirements of the invitation that can be corrected or waived without being prejudicial to other bidders. The defect or variation is immaterial when the effect on quantity, quality, or delivery is negligible when contrasted with the total cost or scope of the works. The Procuring agency/Employer either shall give the bidder an opportunity to cure any deficiency resulting from a minor

informality or irregularity in a bid or waive the deficiency, whichever is advantageous to the Procuring agency/Employer. Examples of minor informalities or irregularities include failure of a bidder to –

26.4.1. Submit the number of copies of signed bids required by the invitation;

26.4.2. Furnish required information concerning the number of its employees;

26.4.3. the firm submitting a bid has formally adopted or authorized, before the date set for opening of bids, the execution of documents by typewritten, printed, or stamped signature and submits evidence of such authorization and the bid carries such a signature.

26.5. Provided that a Technical Bid is substantially responsive, the Procuring agency/Employer may request the bidder to submit the necessary information or documentation, within a reasonable period of time, to rectify nonmaterial nonconformities or omissions in the Technical Bid related to documentation requirements. Requesting information or documentation on such nonconformities shall not be related to any such aspect of the technical Proposal linked with the ranking of the bidders. Failure of the bidder to comply with the request may result in the rejection of its bid.

26.6. Provided that a Technical Bid is substantially responsive, the Procuring agency/Employer shall rectify quantifiable nonmaterial nonconformities or omissions related to the Financial Proposal. To this effect, the Bid Price shall be adjusted, for comparison purposes only, to reflect the price of the missing or nonconforming item or component.

26.7. If a bid is not substantially responsive, it will be rejected by the Procuring agency/Employer and may not subsequently be evaluated for complete technical responsiveness.

27. Examination of Terms and Conditions; Technical Evaluation

27.1. The Procuring agency/Employer shall examine the bid to confirm that all terms and conditions specified in the **GCC** and the **PCC** have been

accepted by the bidder without any material deviation or reservation.

For this purpose:

“Deviation” means departure from the requirements specified in the Bidding Document.

“Reservation” means setting of limiting conditions or withholding from complete acceptance of the requirements specified in the Bidding Document.

27.2. The Procuring agency/Employer shall evaluate the technical aspects of the bid submitted in accordance with ITB 30, to confirm that all requirements specified in Section VI – Works Requirement, Technical Specifications of the Bidding Documents have been met without material deviation or reservation.

27.3. If after the examination of the terms and conditions and the technical evaluation, the Procuring agency/Employer determines that the bid is not substantially responsive in accordance with ITB 27, it shall reject the bid.

28. Correction of Arithmetic Errors

28.1. Bids determined to be substantially responsive will be checked for any arithmetic errors. Errors will be corrected as follows: -

28.1.1. if there is a discrepancy between unit prices and the sub-total price that is obtained by multiplying the unit price and quantity, the unit price shall prevail, and the sub-total price shall be corrected, unless in the opinion of the Procuring agency/Employer there is an obvious misplacement of the decimal point in the unit price, in which the total price as quoted shall govern and the unit price shall be corrected;

28.1.2. if there is an error in a total corresponding to the addition or subtraction of sub-totals, the sub-totals shall prevail, and the total shall be corrected; and

28.1.3. where there is a discrepancy between the amounts in figures and in words, the amount in words will govern.

28.1.4. Where there is discrepancy between grand total of price schedule and amount mentioned on the Form of Bid, the amount referred in Price Schedule shall be treated as correct subject to elimination of other errors.

28.2. The amount stated in the Bid will, be rectified by the Procuring agency/Employer in accordance with the above procedure for the correction of errors and, with, the concurrence of the bidder, shall be considered as binding upon the bidder. If the bidder does not accept the corrected amount, its bid shall be rejected after forfeiture of Bid Security or execution of the Bid Securing Declaration, as the case may be, in accordance with **ITB 41.3**.

29. Conversion to Single Currency

29.1. The unit rates and the prices shall be quoted by the bidder entirely in Pak rupees. A bidder expecting to incur expenditures in other currencies for inputs to the Works from outside the Procuring agency/Employer's country (referred to as the "Foreign Currency Requirements") shall indicate the same in the letter of bid-financial proposal. The proportion of the Bid Price (excluding Provisional Sums) needed by him for the payment of such Foreign Currency Requirements either (i) entirely in the currency of the Bidder's home country or, (ii) at the bidder's option, entirely in Pak rupees provided always that a bidder expecting to incur expenditures in a currency or currencies other than those stated in (i) and (ii) above for a portion of the foreign currency requirements, and wishing to be paid accordingly, shall indicate the respective portions in his bid. Comparison of bids quoted in different currencies and conversion of bids into a single currency shall be carried out in accordance with Rule 30(2) of the Public Procurement Rules, 2004.

30. Evaluation of Bids

30.1. The Procuring agency/Employer shall evaluate and compare only the bids determined to be substantially responsive, pursuant to **ITB 27**.

30.2. In evaluating the Technical Proposal of each Bid, the Procuring agency/Employer shall use the criteria and methodologies listed in the BDS

and in terms of works requirement. No other evaluation criteria or methodologies shall be permitted.

30.3. The Procuring agency/Employer's evaluation of a bid will take into account:

30.3.1. the bid price, excluding provisional sums and the provision, if any, for contingencies in the summary bill of quantities, but including day work items, where priced competitively;

30.3.2. converting the amount resulting from applying above, if relevant, to a single currency in accordance with ITB 29;

30.4. The estimated effect of the price adjustment provisions of the Conditions of Contract, applied over the period of execution of the Contract, shall not be taken into account in bid evaluation.

30.5. If these bidding documents allow bidders to quote separate prices for different lots, and the award to a single bidder of multiple lots, the methodology of evaluation to determine the lowest evaluated lot combinations in the Form of Bid, is specified in the **BDS**.

30.6. If the bid, which results in the Evaluated Bid Price (Successful Bid), is seriously unbalanced or front loaded in the opinion of the Employer, the Employer may require the Bidder to produce detailed price analyses for any or all items of the Bill of Quantities, to demonstrate the internal consistency of those prices with the construction methods and schedule proposed. After evaluation of the price analyses, taking into consideration the schedule of estimated Contract payments, the Employer may require that the amount of the performance security be increased at the expense of the Bidder to a level sufficient to protect the Employer against financial loss in the event of default of the successful Bidder under the Contract.

Explanation:

"Unbalanced" or "front-loaded" bids consist of deliberately submitting bids with artificially high prices or unit rates for the early stages of a construction project, offset by artificially low prices or unit rates for the later stages of the project, to improve the contractor's cash flow.

31. Domestic Preference

31.1. If the **BDS** so specifies, the Procuring agency/Employer will grant a margin of preference to the domestic contractor in line with the rules, regulations, regulatory guides or instructions issued by the Authority from time to time.

32. Determination of Successful Bid

32.1. The Procuring agency/Employer shall compare the evaluated bids in accordance with the predefined bidding procedure, of all substantially responsive bids to determine the Successful bidder.

33. Qualification of Bidder

33.1. The Procuring agency/Employer shall determine to its satisfaction whether the bidder is substantially responsive and whose bid is declared as Successful bid either continues to meet (if prequalification applies) or meets (if post-qualification applies) the qualifying criteria specified in Evaluation and Qualification Criteria.

Note: In case of international bidding, the parameters for incorporation or licensing within Pakistan may be fulfilled as part of post qualification.

33.2. The determination shall be based upon an examination of the documentary evidence of the bidder's qualifications submitted by the bidder, pursuant to **ITB 11**.

33.3. Prior to contract award, the Procuring agency/Employer will verify that the successful bidder (including each member of a JV) is not blacklisted/debarred. The Procuring agency/Employer will conduct the same verification for each sub-contractor proposed by the successful bidder.

34. Sub-Contractors

34.1. The bidder shall provide details regarding any specialized sub-contractor to the Procuring agency/Employer. In case change of sub-contractors, the bidder shall promptly notify the Procuring agency/Employer and obtain approval for replacement of sub-contractors.

34.2. Bidders may propose sub-contracting up to the percentage of total value of contracts or the volume of works as specified in the **BDS**.

35. **Abnormally Low Financial Bid**

35.1. A procuring Agency may reject abnormally low bids. The decision of the Procuring agency/Employer to reject a bid and reasons for the decision shall be recorded in the procurement proceedings and promptly communicated to the bidder concerned. Moreover, the Procuring agency/Employer shall not incur any liability solely by rejecting abnormally bid

Guidance for Procuring agency/Employer:

An abnormally low bid means, in the light of the Procuring agency/Employer's estimate and of all the bids submitted, the bid appears to be abnormally low by not providing a margin for normal levels of profit. In order to identify the Abnormally Low Bid (ALB) following approaches can be considered to minimize the scope of subjectivity:

35.1.1. Comparing the bid price with the cost estimate;

35.1.2. Comparing the bid price with the bids offered by other bidders submitting substantially responsive bids; and

35.1.3. Comparing the bid price with prices paid in similar contracts in the recent past either government- or development partner-funded.

35.2. The Procuring agency/Employer will determine to its satisfaction whether the bidder that is selected as having submitted the successful bid is qualified to perform the contract satisfactorily, in accordance with the criteria listed in **ITB 11**

35.3. The determination will take into account the bidder's financial and technical capabilities. It will be based upon an examination of the documentary evidence of the bidder's qualifications submitted by the bidder, pursuant to **ITB 11**, as well as such other information as the Procuring agency/Employer deems necessary and appropriate. Factors not included in these bidding documents shall not be used in the evaluation of the bidders' qualifications.

35.4. Procuring agency/Employer may seek “Certificate for Independent Price Determination” from the bidder and the results of reference checks may be used in determining award of contract.

Explanation: The Certificate shall be furnished by the bidder. The bidder shall certify that the price is determined keeping in view of all the essential aspects such as raw material, its processing, value addition, optimization of resources due to economy of scale, transportation, insurance and margin of profit etc.

35.5. An affirmative determination will be a prerequisite for award of the contract to the bidder. A negative determination will result in rejection of the bidder’s bid, in which event the Procuring agency/Employer will proceed to the next ranked bidder to make a similar determination of that bidder’s capabilities to perform satisfactorily.

F. AWARD OF CONTRACT

36. Criteria of Award

36.1. Subject to **ITB 36 and 37**, the Procuring agency/Employer will award the Contract to the bidder whose bid has been determined to be substantially responsive to the bidding documents and who has been declared as Successful Bidder, provided that such bidder has been determined to be:

36.1.1. eligible in accordance with the provisions of **ITB 3**;

36.1.2. is determined to be qualified to perform the Contract satisfactorily;
and

36.1.3. Successful negotiations have been concluded, if any.

37. Negotiations

37.1. The Committee of the Procuring agency/Employer may negotiate with the Most Advantageous Bidder relating to the following areas:

37.1.1. a minor alteration to the technical (drawings, design technical specifications) details of the statement of works;

37.1.2. Methodology, work plan, staffing in view to streamline the work;

37.1.3. a minor amendment to the Particular conditions of Contract;

37.1.4. finalizing payment arrangements;

37.1.5. clarifying details that were not apparent or could not be finalized at the time of Bidding;

37.2. Where negotiation fails to result into an agreement, the Procuring agency/Employer may invite the next ranked bidder for negotiations. Where negotiations are commenced with the next ranked bidder, the Procuring agency/Employer shall not reopen earlier negotiations.

38. Procuring agency's Right to reject All Bids

38.1. The procuring agency has the right to reject all bids in accordance with Rule 33 of the Public Procurement Rules, 2004. However, the Authority (i.e. **PPRA**) may call from the Procuring agency/Employer the justification of those grounds.

39. Notification of Award

39.1. The procuring agency shall announce and publish the evaluation result in accordance with Rule 35 of the Public Procurement Rules, 2004.

39.2. Where no complaints have been lodged, the bidder whose bid has been accepted will be notified of the award by the Procuring agency/Employer prior to expiration of the bid validity period through EPADS. However, the Procuring agency/Employer shall not award any procurement contract at least for five (05) days after the announcement of final evaluation report. The notification letter (herein after and in the condition of the contract and contract form called "Letter of Acceptance" will specify the sum that the Procuring agency/Employer will pay the successful bidder in consideration for the execution and completion of the

works as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price).

39.3. The notification of award will constitute the formation of the Contract, subject to the bidder furnishing the Performance Security (or guarantee) in accordance with **ITB 41** and signing of the contract in accordance with **ITB 40**.

39.4. Upon the successful bidder's furnishing of the performance security (or guarantee) pursuant to **ITB 41**, the Procuring agency/Employer will promptly notify each unsuccessful bidder, the name of the successful bidder and the Contract amount and will discharge the Bid Security or Bid Securing Declaration of the bidder(s) pursuant to **ITB 17**.

40. Signing of Contract

40.1. Promptly after notification of award, Procuring agency/Employer shall send the successful bidder the draft agreement, incorporating all terms and conditions as agreed by the parties to the contract.

40.2. Immediately after the Redressal of grievance by the **GRC**, and after fulfillment of all conditions precedent of the Contract Form, the successful bidder and the Procuring agency/Employer shall sign the contract.

40.3. Where no formal signing of a contract is required, work order issued to the bidder shall be construed to be the contract.

41. Performance Security (or Guarantee)

41.1. After the receipt of the Letter of Acceptance, the successful bidder, within the specified time, shall deliver to the Procuring agency/Employer a Performance Guarantee in the amount and in the form stipulated in the BDS and PCC, denominated in the type and proportions of currencies in the Letter of Acceptance and in accordance with the Conditions of Contract.

41.2. If the Performance Guarantee is provided by the successful bidder and it shall be in the form specified in the BDS which shall be in any of the following:

41.2.1. certified cheque, cashier's or manager's cheque, or bank draft;

41.2.2. irrevocable letter of credit issued by a scheduled bank of Pakistan or in the case of an irrevocable letter of credit issued by a foreign bank, the letter shall be confirmed or authenticated by a scheduled bank of Pakistan;

41.2.3. bank guarantee confirmed by a reputable local bank or, in the case of a successful foreign bidder, bonded by a foreign bank; or

41.2.4. surety bond callable upon demand issued by any reputable surety or insurance company.

Any Performance Guarantee submitted shall be enforceable in Pakistan.

41.3. Failure of the Most Advantageous Bidder to comply with the requirement of **ITB 40** shall constitute sufficient grounds for the annulment of the award and forfeiture of the Bid Security or declare blacklisted (in case bid securing declaration is submitted) in which event the Procuring agency/Employer may make the award to the next most advantageous bidder or reinitiate the procurement process afresh (as a case may be).

42. **Advance Payment**

42.1. Advance payment will be provided to the bidder in percentage and in the manner as agreed by the both parties in terms of Conditions of the Contract.

42.2. The Procuring agency/Employer will provide an advance payment as stipulated in the Conditions of Contract, subject to a maximum amount, as stated and/or Conditions of the Contract. The advance payment request shall be accompanied by an advance payment security (guarantee) in the form provided in Section X. For the purpose of receiving the advance payment, the bidder shall make and estimate of, and include in its bid, the expenses that will relate to the purchase of equipment, machinery, materials, and on the engagement of labor during the first month beginning with the date of the Procuring agency/Employer's "**Notice to Commence**" as specified in the **PCC**.

43. General Performance of the Bidders

43.1. The Procuring agency/Employer reserves the right to obtain information regarding performance of the bidders on their previously awarded contracts / works. The Procuring agency/Employer may seek information / report from the previous employer for consideration. However, the Procuring agency/Employer shall incorporate such parameters in the evaluation criteria and accordingly decide the fate of the bid submitted.

44. Corrupt & Fraudulent Practices

44.1. Procuring agencies (including beneficiaries of Government funded projects and procurement) as well as Bidders/Suppliers/Contractors under Government financed contracts, observe the highest standard of ethics during the procurement and execution of such contracts, and will avoid to engage in any corrupt and fraudulent practices.

G. GRIEVANCE REDRESSAL & COMPLAINT REVIEW MECHANISM


45. Grievance Redressal

45.1. Grievance Redressal shall be carried out in accordance with Rule 48 of the Public Procurement Rules, 2004 i.e. Redressal of grievances by the procuring agency and "Redressal of Grievances Regulations 2021".

H. MECHANISM OF BLACKLISTING

46. Mechanism of Blacklisting

46.1. The Procuring agency/Employer shall proceed Blacklisting of Bidders/Contractors in accordance with Rule 19 of the Public Procurement Rules, 2004 i.e. Blacklisting and "Blacklisting and Debarment of Bidders or Contractors Regulations 2024.



Bid Data Sheet

Bids Data Sheet (BDS)

The following specific data for the procurement of Goods to be procured shall complement, supplement, or amend the provisions in the Instructions to Bidders (ITB). Whenever there is a conflict, the provisions herein shall prevail over those in ITB.

BDS Clause Number	ITB Number	Amendments of, and Supplements to, Clauses in the Instruction to Bidders
A. Introduction		
1	1.1	Name of Procuring Agency:ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA)) The subject of procurement is:CRITICAL REQUIREMENT OF SECURITY EQUIPMENT AND OTHER PARAPHERNALIA AT VARIOUS AIRPORTS / LOCATIONS (CONSTRUCTION OF BARRACKS, JS APARTMENTS AND MOQs FOR ASF AT AIAP LAHORE) Expected commencement date: Thursday, October 1, 2026
2.	2.1	Financial year for the operations of the Procuring Agency:2026-27 Name and identification number of the Contract: P72208
3.	3.1	JV/Consortium or Association Allowed: Yes Number of JV/Consortium Members: 3

B. Bidding Documents

4.	6.2 & 6.4	The Bidders may seek clarifications through EPADS v2.0 : Clarification Date: Thursday, August 13, 2026
5.	7.2	Any addendum, in case issued, shall be published on ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA)) website and on EPADS v2.0 .

C. Preparation of Bids

6.	8.1	List of documents required along with the bid: No
7.	9.1	The qualification criteria to establish the supply / production capability of the bidder. <i>see Eligibility Criteria</i>
8.	11.2	Works and Their related documents: <i>See section Required Scope of Work</i>
9.	11.1	Price schedule will be provided according to the format defined and acquired. <i>see section price schedule.</i>
10.	11.4	Specifications: <i>see section of specifications.</i>

11.	11.5 & 13.5	The price shall be Fixed. The bid price shall be adjusted in accordance with Appendix provided - Formula for Price Adjustment.
12.	14.1	Currency of the Bids shall be : PKR
13.	16.1	The Bids/Bid Validity period shall be: 120 Days
14.	17.1	The amount of Bid Security shall be as defined in Bid Security Section for items and lots given in BDS 6
15.	17.2	The Bid Security shall be in the form of: Pay Order, Call at Deposit
16.	15.1	Alternative Bids to the requirements of the bidding documents willnot be permitted.
D. Submission of Bids		
17.	18.1 & 21.1	Bid shall be submitted online on EPADS v2.0 whereas hard copy of the bid security should be submitted to the following; ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province). Bids that are not submitted on EPADS v2.0 shall be disqualified. The deadline for Bids submission is: Wednesday, August 19, 2026 11:00 AM

E. Opening and Evaluation of Bids

18.	24.1	The Bids opening shall take place on EPADS v2.0. Day : Wednesday Date:August 19, 2026 Time : 11:30 AM
19.	30.2	Selection technique adopted will be: Least Cost Based Selection (LCBS) <i>see Evaluation Criteria</i>

F. Award of Contract

20.	41.1 & 41.2	The Performance guarantee shall: 5.00%. The Performance Guarantee shall be acceptable in the form of:Pay Order, Banker's Cheque, Call at Deposit, Bank Guarantee
21.	45.1	Arbitrator shall be appointed by mutual consent of the both parties.

G. Review of Procurement Decisions

22.	37	Grievance against this procurement shall be submitted online on EPADS v2.0.
-----	----	--

Eligibility Criteria

Bidder's Type	Required Registration
Sole Proprietorship Partnership Firm Company (Private Limited)	NADRA CITIZENSHIP (CNIC/NICOP) FBR (NTN) FBR (GSTN) SECP PEC

Evaluation Criteria

Least Cost Based Selection (LCBS)

Technical Marks	100
Passing Marks	100
General Experience	
Projects of similar nature and complexity Completed / In hand in last ten years. (Minimum value Rs. 300 Million (M) or above) Mandatory Criteria: At least 03 projects of similar nature (as prescribed in description) must be completed / In hand NOTE: Work completion certificates or any other document validating the successful completion of claimed works must be provided (Qualitative)(Doc Required)	10
Personnel Capabilities	
Project Manager: 01 No. B.Sc / M.Sc Civil Engineer registered with Pakistan Engineering Council (PEC) with at least 15 years of relevant experience Note: Valid registration with PEC, valid experience certificates bearing stamp of employer(s) explicitly mentioning the tenure of service and employment proof with the current company (Bidder) must be provided (Qualitative)(Doc Required)	10
Site Manager(s) Civil: 03 Nos. B.Sc / M.Sc Civil Engineers (01 no. for each site) registered with Pakistan Engineering Council (PEC) with at least 7 years of relevant experience Note: Valid registration with PEC, valid experience certificates bearing stamp of employer(s) explicitly mentioning the tenure of service and employment proof with the current company (Bidder) must be provided (Qualitative)(Doc Required)	10

Site Manager Electrical: 01 No. B.Sc / M.Sc Electrical Engineer registered with Pakistan Engineering Council (PEC) with at least 7 years of relevant experience Note: Valid registration with PEC, valid experience certificates bearing stamp of employer(s) explicitly mentioning the tenure of service and employment proof with the current company (Bidder) must be provided (Qualitative)(Doc Required)	10
Associates Engineers (DAE) Civil: 03 Nos. DAE Civil (01 no. for each site) with at least 10 years of relevant experience Notes: Valid educational certificate(s) , valid experience certificates bearing stamp of employer(s) explicitly mentioning the tenure of service and employment proof with the current company (Bidder) must be provided (Qualitative)(Doc Required)	10
Associates Engineers (DAE) Electrical: 01 No. DAE Electrical with at least 10 years of relevant experience Notes: Valid educational certificate(s) , valid experience certificates bearing stamp of employer(s) explicitly mentioning the tenure of service and employment proof with the current company (Bidder) must be provided (Qualitative)(Doc Required)	10
Surveyor(s): 02 Nos. Surveyors with at least 10 years of survey experience Notes: Valid educational certificate(s) , valid experience certificates bearing stamp of employer(s) explicitly mentioning the tenure of service and employment proof with the current company (Bidder) must be provided (Qualitative)(Doc Required)	10
Equipment Capability	
03 Nos. Dumper Trucks 01 No. Excavator with all accessories 03 Nos. Concrete Mixer Machines 03 Nos. Vibrators 01 No. Mobile Crane 01 No. Total Station with all accessories 02 Nos. Levelling Instruments Notes: 1) Contractor (lead partner is case of JV) must submit an undertaking on non-judicial stamp paper that all the necessary / required equipment either owned or rented will be made available at site as per the site requirements (Qualitative)(Doc Required)	10
Financial Soundness	
Average Annual Turnover for the last 3 years must be Rs. 500 (M) or above (Qualitative)(Doc Required)	10
Average Working Capital in last 3 years must be Rs. 100 (M) or above (Qualitative)(Doc Required)	10

Jobs/Lots

Lot Title : CRITICAL REQUIREMENT OF SECURITY EQUIPMENT AND OTHER PARAPHERNALIA AT VARIOUS AIRPORTS / LOCATIONS
(CONSTRUCTION OF BARRACKS, JS APARTMENTS AND MOQs FOR ASF AT AIIAP LAHORE)

Bid Security : 15000000 PKR

Job	Delivery Schedule	Quantity
ASF Barracks for 192 personnel	Address: ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province). Schedule: 545 Days Quantity: 2/job	2/job
16 x MOQs (3 Bed) - G+3 (08 MOQs per Block)	Address: ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province). Schedule: 545 Days Quantity: 2/job	2/job
ASF 16 x JS apartments (2 bed) - G+3 (16 apartments per Block)	Address: ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province). Schedule: 545 Days Quantity: 1/job	1/job

Related Services :

No



Work Specifications and Market Rates


Lot Title: CRITICAL REQUIREMENT OF SECURITY EQUIPMENT AND OTHER PARAPHERNALIA AT VARIOUS AIRPORTS / LOCATIONS
(CONSTRUCTION OF BARRACKS, JS APARTMENTS AND MOQs FOR ASF AT ALLIP LAHORE)

Specifications / Requirements:							
Sr. No	Ref. No.	Description	Unit	Qty	Rate		Amount

1	ASF Barracks Building works-01	Excavation for raft foundations, underground tanks and septic tanks (rectangular or square) in all kinds of soil (except gravelly and murum soil wet silt, clay or mud, conglomeration of gravel and boulders, soft, sandy or disintegrated and hard rock) and back filling the excavated material all round the trenches including breaking clods, watering, consolidation by ramming in layers not exceeding 9 inches (229 mm) in depth to full compaction, dressing and disposal of surplus excavated stuff as directed, lead up to one chain (30.5 R.m) and lift upto 5 feet (2.135 m)	100 Cft	327.5	1902.25	One Thousand Nine Hundred Two Rupees and Twenty Five Paisas	1376811
---	--------------------------------	--	---------	-------	---------	---	---------

2	ASF Barracks Building works-02	Providing and carrying out Termite proofing in foundations, under floors and wood work surface with a solution using of confront TC or ABILITY 2.5 % EC (Fipronil as an active ingredient) or approved equivalent by spraying all around the sides of foundation, trenches, flooded under floor @ 1/2 Liters of chemical per % Sft) with water and spraying the solution of the area to be treated as completed as per direction of Engineer incharge (Based on P.No 428/199)	P.Sft	327.5	18.382	Eighteen Rupees and Thirty Eight Paisas	335876
---	--------------------------------	---	-------	-------	--------	---	--------

3	ASF Barracks Building works-03	Providing and laying 1:4:8 (1 cement 4 sand and 8 coarse aggregate) cement concrete using crushed graded boulders 1 inch (25 mm) and down gauge in foundation including leveling, compacting and curing etc. complete	100 Cft	327.5	34306.426	Thirty Four Thousand Three Hundred Six Rupees and Forty Three Paisas	2483099
---	--------------------------------	---	---------	-------	-----------	--	---------



4	ASF Barracks Building works-04	Providing and laying reinforced cement concrete using crushed graded boulder 3/4 inch (19 mm) and down gauge and lawrencepur sand having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in raft or strip foundation with columns and pillars, of any shape including form work and its removal, compacting, leveling and curing etc. complete but excluding the cost of reinforcement, in foundation basement and plinth.	100 Cft	327.5	54298.006	Fifty Four Thousand Two Hundred Ninety Eight Rupees and One Paisa	11790269
---	--------------------------------	---	---------	-------	-----------	---	----------

5	ASF Barracks Building works-05	Providing and laying reinforced cement concrete using crushed graded boulder 3/4 inch (19 mm) and down gauge and lawrencepur sand having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in column footing of required shape including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in foundation basement and plinth.	100 Cft	327.5	61109.174	Sixty One Thousand One Hundred Nine Rupees and Seventeen Paisas	83108
---	--------------------------------	--	---------	-------	-----------	---	-------

6	ASF Barracks Building works-06	Providing and laying reinforced cement concrete using crushed graded boulder 3/4 inch (19 mm) and down gauge and lawrencepur sand having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in columns of square or rectangular shape of regular section including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement, in foundation basement and plinth.	100 Cft		66501.764	Sixty Six Thousand Five Hundred One Rupees and Seventy Six Paisas	389700
---	--------------------------------	--	---------	--	-----------	---	--------

7	ASF Barracks Building works-07	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in plinth beams of required shape and design including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement, in foundation basement and plinth.	100 Cft		64324.274	Sixty Four Thousand Three Hundred Twenty Four Rupees and Twenty Seven Paisas	1779209
---	--------------------------------	---	---------	--	-----------	--	---------

8	ASF Barracks Building works-08	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in columns of square or rectangular shape of regular section including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement in Ground Floor	100 Cft		81591.034	Eighty One Thousand Five Hundred Ninety One Rupees and Three Pisas	1762366
---	--------------------------------	---	---------	--	-----------	--	---------

9	ASF Barracks Building works-09	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in columns of square or rectangular shape of regular section including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement in First Floor.	100 Cft		85527.078	Eighty Five Thousand Five Hundred Twenty Seven Rupees and Eight Paisas	1693436
---	--------------------------------	---	---------	--	-----------	--	---------


10	ASF Barracks Building works-10	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in columns of square or rectangular shape of regular section including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement in Second Floor	100 Cft		88621.904	Eighty Eight Thousand Six Hundred Twenty One Rupees and Ninety Paisas	1754714
----	--------------------------------	---	---------	--	-----------	---	---------

11	ASF Barracks Building works-11	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight beams, lintels cantilever beams of required shape or section including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement in Ground Floor.	100 Cft		74064.942	Seventy Four Thousand Sixty Four Rupees and Ninety Four Paisas	1821998
----	--------------------------------	---	---------	--	-----------	--	---------

12	ASF Barracks Building works-12	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight beams, lintels cantilever beams of required shape or section including M.S form work & M.S folding Pipes and its removal, compacting and curing etc. complete but excluding the cost of reinforcement in First Floor.	100 Cft		78000.986	Seventy Eight Thousand Rupees and Ninety Nine Paisas	1918824
----	--------------------------------	--	---------	--	-----------	--	---------

13	ASF Barracks Building works-13	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight beams, lintels cantilever beams of required shape or section including M.S form work & M.S folding Pipes and its removal, compacting and curing etc. complete but excluding the cost of reinforcement in First Floor.	100 Cft		81095.812	Eighty One Thousand Ninety Five Rupees and Eighty One Paisas	2054968
----	--------------------------------	--	---------	--	-----------	--	---------

14	ASF Barracks Building works-14	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary slab 5 inches (127 mm) to 6 inches (152 mm) thick Including form work and its removal compacting and curing etc. complete but excluding the cost of reinforcement in Ground Floor	100 Cft		71634.374	Seventy One Thousand Six Hundred Thirty Four Rupees and Thirty Seven Paisas	5184896
----	--------------------------------	--	---------	--	-----------	---	---------



15	ASF Barracks Building works-15	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary slab 5 inches (127 mm) to 6 inches (152 mm) thick Including M.S form work & M.S folding Pipes and its removal compacting and curing etc. complete but excluding the cost of reinforcement in First Floor.	100 Cft		96899.712	Ninety Six Thousand Eight Hundred Ninety Nine Rupees and Seventy One Paisas	7013601
----	--------------------------------	--	---------	--	-----------	---	---------

16	ASF Barracks Building works-16	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary slab 5 inches (127 mm) to 6 inches (152 mm) thick Including M.S form work & M.S folding Pipes and its removal compacting and curing etc. complete but excluding the cost of reinforcement in Second Floor	100 Cft		99994.538	Ninety Nine Thousand Nine Hundred Ninety Four Rupees and Fifty Four Paisas	7237605
----	--------------------------------	--	---------	--	-----------	--	---------

17	ASF Barracks Building works-17	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary cantilevered slab horizontal sun-shade or chajja tapered or straight average 5 inches (127 mm) to 6 inches (152 mm) thick including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in basement plinth and ground floor.	100 Cft		78451.898	Seventy Eight Thousand Four Hundred Fifty One Rupees and Ninety Paisas	342050
----	--------------------------------	---	---------	--	-----------	--	--------

18	ASF Barracks Building works-18	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary cantilevered slab horizontal sun-shade or chajja tapered or straight average 5 inches (127 mm) to 6 inches (152 mm) thick including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in first floor.	100 Cft		82387.942	Eighty Two Thousand Three Hundred Eighty Seven Rupees and Ninety Four Paisas	359211
----	--------------------------------	--	---------	--	-----------	--	--------

19	ASF Barracks Building works-19	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary cantilevered slab horizontal sun-shade or chajja tapered or straight average 5 inches (127 mm) to 6 inches (152 mm) thick including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in Second floor.	100 Cft		85482.768	Eighty Five Thousand Four Hundred Eighty Two Rupees and Seventy Seven Paisas	372705
----	--------------------------------	---	---------	--	-----------	--	--------

20	ASF Barracks Building works-20	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight stairs and landing of required section including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in basement plinth and ground floor.	100 Cft		88774.938	Eighty Eight Thousand Seven Hundred Seventy Four Rupees and Ninety Four Paisas	585915
----	--------------------------------	--	---------	--	-----------	--	--------

21	ASF Barracks Building works-21	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight stairs and landing of required section including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in First floor	100 Cft		92710.982	Ninety Two Thousand Seven Hundred Ten Rupees and Ninety Eight Paisas	611892
----	--------------------------------	--	---------	--	-----------	--	--------

22	ASF Barracks Building works-22	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight stairs and landing of required section including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in Second floor	100 Cft		95805.808	Ninety Five Thousand Eight Hundred Five Rupees and Eighty One Paisas	632318
----	--------------------------------	---	---------	--	-----------	--	--------

23	ASF Barracks Building works-23	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in shelves 1-1/2 inches to 2 inches (38 to 51 mm) thick cast in situ including form works and its removal, compacting and curing etc. complete but excluding the cost of reinforcement Ground Floor	100 Cft		105537.964	One Lakh Five Thousand Five Hundred Thirty Seven Rupees and Ninety Six Paisas	18997
----	--------------------------------	--	---------	--	------------	---	-------

24	ASF Barracks Building works-24	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in shelves 1-1/2 inches to 2 inches (38 to 51 mm) thick cast in situ including form works and its removal, compacting and curing etc. complete but excluding the cost of reinforcement first Floor	100 Cft		109474.008	One Lakh Nine Thousand Four Hundred Seventy Four Rupees and One Paisa	19705
----	--------------------------------	---	---------	--	------------	---	-------

25	ASF Barracks Building works-25	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in shelves 1-1/2 inches to 2 inches (38 to 51 mm) thick cast in situ including form works and its removal, compacting and curing etc. complete but excluding the cost of reinforcement Second Floor	100 Cft		112568.834	One Lakh Twelve Thousand Five Hundred Sixty Eight Rupees and Eighty Three Paisas	20262
----	--------------------------------	--	---------	--	------------	--	-------

26	ASF Barracks Building works-26	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work including septic tanks and under ground tanks and in projections for future extension in Foundation, plinth and ground floor.	P.Kg		395.43	Three Hundred Ninety Five Rupees and Forty Three Paisas	60380579
----	--------------------------------	--	------	--	--------	---	----------

27	ASF Barracks Building works-27	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work including septic tanks and under ground tanks and in projections for future extension in Foundation, plinth and first floor	P.Kg		401.646	Four Hundred One Rupees and Sixty Five Paisas	20551423
----	--------------------------------	--	------	--	---------	---	----------

28	ASF Barracks Building works-28	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work in projections for future extension in Second Floor	P.Kg		407.862	Four Hundred Seven Rupees and Eighty Six Paisas	20990210
----	--------------------------------	--	------	--	---------	---	----------

29	ASF Barracks Building works-29	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls more than 13-1/2 inches (343 mm) thick including scaffolding, raking out joints and curing etc. Complete in foundation, basement and plinth (foundation and basement masonry upto 5 feet (1.52 Ru.m.) depth and plinth upto 4 feet (1.2 Ru.m.) height from ground level) .	100 Cft		50581.608	Fifty Thousand Five Hundred Eighty One Rupees and Sixty One Paisas	515932
----	--------------------------------	--	---------	--	-----------	--	--------

30	ASF Barracks Building works-30	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9" to 13-2 inches (228 mm to 343 mm) thick including scaffolding, raking out joints and curing etc. complete in foundation, basement and plinth (foundation and basement masonry up to 5 feet (1.52 Ru.m.) depth and plinth up to 4 feet (1.2 Ru.m.) height from ground level)	100 Cft		54015.99	Fifty Four Thousand Fifteen Rupees and Ninety Nine Paisas	3301457
31	ASF Barracks Building works-31	Providing a coat of bitumen emulsion at 10 Lbs. per % sft. (0.49 Kg/sm) on walls and floor in ground floor.	100 Sft		1415.05	One Thousand Four Hundred Fifteen Rupees and Five Paisas	19556

32	ASF Barracks Building works-32	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in superstructure in Ground Floor	100 Cft		57765.358	Fifty Seven Thousand Seven Hundred Sixty Five Rupees and Thirty Six Paisas	5195416
33	ASF Barracks Building works-33	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in superstructure in First Floor	100 Cft		61042.884	Sixty One Thousand Forty Two Rupees and Eighty Eight Paisas	5490197

34	ASF Barracks Building works-34	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in superstructure in second Floor Beyond 25' upto 30' height	100 Cft		63637.784	Sixty Three Thousand Six Hundred Thirty Seven Rupees and Seventy Eight Paisas	5723582
35	ASF Barracks Building works-35	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in superstructure in Third Floor Beyond 25' upto 30' height	100 Cft		66232.684	Sixty Six Thousand Two Hundred Thirty Two Rupees and Sixty Eight Paisas	2410870

36	ASF Barracks Building works-36	Providing and laying first class solid burnt brick masonry set in cement mortar 1:4 in straight or curved walls 4-1/2 inches (114 mm) and less in thickness including scaffolding, raking, out joints and curing etc. complete in ground floor superstructure	100 Cft		63709.17	Sixty Three Thousand Seven Hundred Nine Rupees and Seventeen Paisas	556818
37	ASF Barracks Building works-37	Providing and laying first class solid burnt brick masonry set in cement mortar 1:4 in straight or curved walls 4-1/2 inches (114 mm) and less in thickness including scaffolding, raking, out joints and curing etc. complete in first floor	100 Cft		66986.696	Sixty Six Thousand Nine Hundred Eighty Six Rupees and Seventy Paisas	585464

38	ASF Barracks Building works-38	Providing and laying first class solid burnt brick masonry set in cement mortar 1:4 in straight or curved walls 4-1/2 inches (114 mm) and less in thickness including scaffolding, raking, out joints and curing etc. complete in first floor	100 Cft	70264.1982	Seventy Thousand Two Hundred Sixty Four Rupees and Twenty Paisas	614109
39	ASF Barracks Building works-39	Supplying stacking and filling sand of approved quality from outside sources in foundation, trenches, plinth or under floor, etc. including dressing, watering and consolidation by ramming in layers not exceeding 9 inches (229 mm) in depth to full compaction and lift up to 5 feet (1.52 m)	100 Cft	6817.916	Six Thousand Eight Hundred Seventeen Rupees and Ninety Two Paisas	2960748

40	ASF Barracks Building works-40	Supplying and laying vitrified brick ballast 2" to 1-1/2" (51 mm to 38 mm) gauge of approved quality for base or wearing coat etc.; in Layers not exceeding 6" (152 mm) thick, consolidating by approved mechanical means to required grade and camber including watering etc., with all lead and lift complete	100 Cft		12419.05	Twelve Thousand Four Hundred Nineteen Rupees and Five Paisas	593134
41	ASF Barracks Building works-41	Providing and laying 1:4:8 cement concrete bed under floors using graded stone ballast 2 inches (51 mm) and down gauge with leveling and ramming, watering and curing etc. complete	100 Cft		30851.45	Thirty Thousand Eight Hundred Fifty One Rupees and Forty Five Paisas	1473465

42	ASF Barracks Building works-42	Providing and laying floors of 2 inches (51 mm) thick 1:2:4 cement concrete using graded screened bajri 3/4 inch (19 mm) and down gauge in ground floor laid in panels including form work, consolidation, finishing and curing etc. complete	100 Sft	9631.678	Nine Thousand Six Hundred Thirty One Rupees and Sixty Eight Paisas	1394282
43	ASF Barracks Building works-43	Providing and laying light colour, glazed/non skid vitrified porcelain tiles (Polished) exceeding 3600 Sq.cm each (Pak made) on walls and floors, in any floor, laid with dry bond (stile bond) over existing floor including jointing to tiles with joint filler of approved quality as per direction of the Engineer in charge	100 Sft	66618.426	Sixty Six Thousand Six Hundred Eighteen Rupees and Forty Three Paisas	14020514

44	ASF Barracks Building works-44	Providing and laying floor of 3/4" (19 mm) thick Granite tiles Pakistani Origin more than 3 Sq.ft. upto 5 Sq.ft. more than (0.28 Sq.m upto 1.46 Sq.m) size fine dressed on the surface without winding treads, risers, and mid stair landings, stairs/steps (in treads, risers and midstair landings) over 1 inch (25 mm) cement mortar 1:4 (one cement, four sand) setting the marble tile with grey cement, slurry over cement mortar, jointing and washing the tiles with white cement slurry including curing, rubbing and polishing etc. complete including the cost of mortar	100 Sft		114456.482	One Lakh Fourteen Thousand Four Hundred Fifty Six Rupees and Forty Eight Paisas	3124662
----	--------------------------------	---	---------	--	------------	---	---------

45	ASF Barracks Building works-45	Making nosing of treads as per design and instructions of the Engineer-in-Charge	P. Rft		183.75	One Hundred Eighty Three Rupees and Seventy Five Paisas	242550
46	ASF Barracks Building works-46	½ " (13 mm) thick cement plaster 1:4 on wall and columns etc. including making edges, corners and curing etc. complete in Ground Floor	100 Sft		6134.576	Six Thousand One Hundred Thirty Four Rupees and Fifty Eight Paisas	1684923
47	ASF Barracks Building works-47	½ " (13 mm) thick cement plaster 1:4 on wall and columns etc. including making edges, corners and curing etc. complete in First Floor	100 Sft		6565.076	Six Thousand Five Hundred Sixty Five Rupees and Eight Paisas	1447337
48	ASF Barracks Building works-48	½ " (13 mm) thick cement plaster 1:4 on wall and columns etc. including making edges, corners and curing etc. complete in Ground Floor Beyond 30' upto 35' height	100 Sft		6995.576	Six Thousand Nine Hundred Ninety Five Rupees and Fifty Eight Paisas	1542245

49	ASF Barracks Building works-49	¼ " (6.4 mm) thick cement plaster 1:4 on soffits of ceiling, cantilever slabs, sides and soffits of beams etc. including making edges, corners and curing etc. complete in Ground Floor	100 Sft	5393.626	Five Thousand Three Hundred Ninety Three Rupees and Sixty Three Paisas	827706
50	ASF Barracks Building works-50	¼ " (6.4 mm) thick cement plaster 1:4 on soffits of ceiling, cantilever slabs, sides and soffits of beams etc. including making edges, corners and curing etc. complete in First Floor	100 Sft	5824.126	Five Thousand Eight Hundred Twenty Four Rupees and Thirteen Paisas	893770
51	ASF Barracks Building works-51	¼ " (6.4 mm) thick cement plaster 1:4 on soffits of ceiling, cantilever slabs, sides and soffits of beams etc. including making edges, corners and curing etc. complete in First Floor Beyond 30' upto 35' height	100 Sft	6254.626	Six Thousand Two Hundred Fifty Four Rupees and Sixty Three Paisas	959835

52	ASF Barracks Building works-52	Providing and fixing M.S. moulded steel door frames of 5.73" x 2-1/2" (146 mm x 63 mm) manufactured from mild steel sheet of 18 gauge (1.41 mm) conforming to B.S.S. 1245 having a double rebate size 1-1/2" x 1/2" (38 mm x 12 mm) provision of 3 Nos. M.S. plate, section 1-1/2" x 1/4" (38 mm x 6 mm) (2 Nos. 6 inch long welded with frame at not less than 10 points and 1 Nos. 12 inch long welded with frame at not less than 20 points), with holes and threads for fixing steel hinges, fitted with one locking box of same sheet (point welded inside the frame), 6 Nos. 6 inches long flat iron fixing lugs of 1-1/4" x 3/16" section, treated with special red oxide primer coat all around including cutting holes and filling the cavity with cement concrete 1:2:4 etc. in any floor at any height complete as directed by the	P.Rft		657.72	Six Hundred Fifty Seven Rupees and Seventy Two Paisas	994473
----	--------------------------------	---	-------	--	--------	---	--------

53	ASF Barracks Building works-53	Providing and fixing M.S. moulded steel door frames of 10" x 2-1/2" manufactured from mild steel sheet of 18 gauge conforming to B.S.S. 1245 having a double rebate size 1-1/2" x 1/2" (38 mm x 12 mm) provision of 3 Nos. M.S. plate, section 1-1/2" x 1/4" (38 mm x 6 mm) (2 Nos. 6 inch long welded with frame at not less than 10 points and 1 Nos. 12 inch long welded with frame at not less than 20 points), with holes and threads for fixing steel hinges, fitted with one locking box of same sheet (point welded inside the frame), 6 Nos. 6 inches long flat iron fixing lugs of 1-1/4" x 3/16" section, treated with special red oxide primer coat all around including cutting holes and filling the cavity with cement concrete 1:2:4 etc. in any floor at any height complete as directed by the	P.Rft		971.404	Nine Hundred Seventy One Rupees and Forty Paisas	961690
----	--------------------------------	---	-------	--	---------	--	--------

54	ASF Barracks Building works-54	Providing and fixing 1-1/2 inches (38 mm) thick solid core deodar wood flushed veneered door shutters, with and including the cost of commercial plywood facing 3 mm. thick (3 ply) on both faces, fixed over best quality deodar wood frame 2 inches wide all-round 6 inches wide lock rail and 2nd class deodar wood solid core, i/c., 3/8 inch thick best quality deodar wood lipping on all sides as per approved drawing, manufactured under power driven hydraulic press, including the cost of approved iron fittings but excluding the cost of handles and locking arrangement	P.Sft		2027.984	Two Thousand Twenty Seven Rupees and Ninety Eight Paisas	6984377
----	--------------------------------	--	-------	--	----------	--	---------


55	ASF Barracks Building works-55	Providing and fixing with brass screws lucky lock knob set of approved design (Taiwan make) cutting wood to required shape and size with two operating keys as per direction of the Engineer-in-Charge	Each	5459.132	Five Thousand Four Hundred Fifty Nine Rupees and Thirteen Paisas	818870
56	ASF Barracks Building works-56	Providing and fixing approved chromium plated brass handles 7" (178 mm) size heavy type with necessary brass screws	Each	851.634	Eight Hundred Fifty One Rupees and Sixty Three Paisas	153294
57	ASF Barracks Building works-57	Providing and fixing with brass screws or specially supplied screws hydraulic door closer Rayobi or approved design No. 72, Japan make, cutting wood etc., to required shape and size as per direction of engineer-in-charge	Each	13063.75	Thirteen Thousand Sixty Three Rupees and Seventy Five Paisas	940590

58	ASF Barracks Building works-58	Providing and laying heated asphalt on third floor roof at the rate of 20 Lbs. per hundred square feet (0.98 Kg per s.m) finished with washed coarse sand 3 cubic feet per hundred square feet (0.086 C.M. per s.m) including ramming with thappies etc. complete	100 Sft		5662.818	Five Thousand Six Hundred Sixty Two Rupees and Eighty Two Paisas	869016
59	ASF Barracks Building works-59	Providing and laying single layer of polythene sheet of 500 gauge (0.005 inch or 0.13 mm thick) under floors for water proofing laid as per specifications and instructions of the Engineer-in-Charge in Ground Floor	100 Sft		1470.014	One Thousand Four Hundred Seventy Rupees and One Paisa	225588

60	ASF Barracks Building works-60	Providing and fixing of Diamond Jumbolon insulation board 1-1/2" thick and polythene sheet over diamond jumbolon insulation for roof insulation as per directions of the Engineer-in-Charge in any floor in any height.	P.Sft		191.058	One Hundred Ninety One Rupees and Six Paisas	2931976
61	ASF Barracks Building works-61	Providing and laying 1st class burnt clay tiles of 9" X 4-1/2" X 1-1/2" size grouted with 1:3 cement mortar over 4" thick (avg) puddled earth compacted and smooth finished to slope mixed with bhoosa at the rate of one seer of bhoosa for one cft. of puddled earth in Second Floor including flush pointing on tiles works with 1:3 cement mortar and curing complete	100 Sft		21871.85	Twenty One Thousand Eight Hundred Seventy One Rupees and Eighty Five Paisas	3356454

62	ASF Barracks Building works-62	Providing and laying 1:2:4 cement concrete khuras 2" (51 mm) thick 2 ft. x 2 ft. (610 mm x 610 mm) size on roof including finishing with cement plaster 1:4, curing etc. complete	Each		244.762	Two Hundred Forty Four Rupees and Seventy Six Paisas	3916
63	ASF Barracks Building works-63	Providing and laying gola 3" x 3" (76 mm x 76 mm) concrete 1:2:4 using graded screened bajri at junction of roof slab and walls and finished with cement plaster 1:4 including curing etc. complete	100 Rft		4483.304	Four Thousand Four Hundred Eighty Three Rupees and Thirty Paisas	34073
64	ASF Barracks Building works-64	Providing and fixing 4" (100 mm) dia polyvinyle chloride rain water (PVC) down pipe with mild steel clamps, bolts and nuts fixed in cement concrete 1:2:4 etc. complete	P. Rft		1006.138	One Thousand Six Rupees and Fourteen Paisas	482946

65	ASF Barracks Building works-65	Providing and fixing 4" (80 mm) dia polyvinyle chloride (PVC) bend of any degree for rain water down pipe with clamps, bolts and nuts in cement concrete 1:2:4 etc. complete.	Each		2447.382	Two Thousand Four Hundred Forty Seven Rupees and Thirty Eight Paisas	78316
----	--------------------------------	---	------	--	----------	--	-------



66	ASF Barracks Building works-66	Providing and fixing fully glazed Champagne anodized or powder coated aluminium Sliding windows as per British standard manufactured by Lucky, Prime, Chawla, Krudson and Pakistan Cables. (fixing through their approved fabricators), Deluxe model box 101 section 95mm x 30mm and 1.6mm thick including the cost of aluminium netting ,fittings, with all accessories cutting hole etc. and making good damages to walls etc. complete as required in any floor as per direction of engineer-in-charge, including the cost of glass6mm thick	P.Sft		2119.894	Two Thousand One Hundred Nineteen Rupees and Eighty Nine Paisas	8110714
----	--------------------------------	---	-------	--	----------	---	---------

67	ASF Barracks Building works-67	Providing and fixing P.V.C board 2' x 2' tiles printed ceiling including Aluminum T & L angle 1" x 1" i.c hanger clips jointing clips and G.I Wire etc complete as required in any floor	P.Sft		324.52	Three Hundred Twenty Four Rupees and Fifty Two Paisas	14092606
68	ASF Barracks Building works-68	Painting iron work with synthetic enamel paint of approved make and shade two coats over and including the cost of one priming complete at any height in any floor	100 Sft		8499.75	Eight Thousand Four Hundred Ninety Nine Rupees and Seventy Five Paisas	84148
69	ASF Barracks Building works-69	Painting wood work with synthetic enamel paint of approved make and shade two coats over and including the cost of one priming coat complete at any height in any floor	100 Sft		8336.804	Eight Thousand Three Hundred Thirty Six Rupees and Eighty Paisas	574239

70	ASF Barracks Building works-70	Painting with (ICI) Dulux plastic emulsion paint VIP of approved shade two coats over and including the cost of wall putty / priming coat complete over plastered surface at any height in any floor. (Page No. 390/162)	100 Sft	9432.332	Nine Thousand Four Hundred Thirty Two Rupees and Thirty Three Paisas	6336829
71	ASF Barracks Building works-71	Painting three coats with weather shield paint deluxe (ICI) make of approved shade on plaster surface (External) and including the cost of cleaning the surface, sand papering etc. complete at any height any floor	100 Sft	6172.25	Six Thousand One Hundred Seventy Two Rupees and Twenty Five Paisas	965463

72	ASF Barracks Building works-72	Providing and fixing cabinet wall mounted of 3/4" thick lamminated board with best quality deodar wood frame and beading 1/8" thick hard borad backing required section in approved pattern etc. fixed on wall with rawal plug, screws i/c cost of glue, nails, piano hinges, handles and painting or polishing as drawing complete all as respect	P.Sft		1908.55	One Thousand Nine Hundred Eight Rupees and Fifty Five Paisas	24734808
----	--------------------------------	--	-------	--	---------	--	----------

73	ASF Barracks Building works-73	Providing and fixing 2" dia. stainless steel pipe (18 guage) railing along with 4", 3/4" dia. parallel pipe having S.S pipe vertical post 2" dia. at 3 ft c/c average spacing and 4" dia. vertical post at start turning and end point including cost of labour, welding charges fitting and fixing in marble floor and wall etc. complete as per direction of the engineer incharge	P.Rft		3128.132	Three Thousand One Hundred Twenty Eight Rupees and Thirteen Paisas	337838
----	--------------------------------	--	-------	--	----------	--	--------

74	ASF Barracks Building works-74	Providing and fixing Windows roll up blinds sunscreen, dark out, or translucent fabric any colour/shade best quality (imported) with manual roll up arrangements complete in all respect with all other required accessories and hardware from the approved suppliers and manufacturers as per direction of Engineer incharge	P. Sft		440.412	Four Hundred Forty Rupees and Forty One Paisas	908130
75	ASF Barracks Sanitary works-01	Making connection with the existing G.I. pipe upto 2 inches dia including cutting the pipe and providing and fixing necessary fittings	Each		2181.9	Two Thousand One Hundred Eighty One Rupees and Ninety Paisas	4363.8

76	ASF Barracks Sanitary works-02	P/F 1-1/2" Ø uPVC pipe "D" class and specials etc. including cutting and fitting complete with and including the cost of cutting trench upto 1-1/2 feet deep refilling, watering, ramming, and disposal of surplus earth within one chain and after cleaning the pipe and cartage within 10 miles (16.09 km.) (working pressure 12 kg/cm2)	Rft		204.358	Two Hundred Four Rupees and Thirty Six Paisas	167573.56
77	ASF Barracks Sanitary works-03	P/F 1" Ø uPVC Pipe "E" class with specials and clamps etc., including cutting and fitting, complete with and including the cost of breaking through walls and roof and making good etc.; after cleaning the pipe and cartage within 10 miles (working pressure 12 kg/cm2)	Rft		144.788	One Hundred Forty Four Rupees and Seventy Nine Paisas	34749.12

78	ASF Barracks Sanitary works-04	--do-- but 3/4" Ø uPVC E Class pipe	Rft		135.632	One Hundred Thirty Five Rupees and Sixty Three Paisas	135632
79	ASF Barracks Sanitary works-05	P/F of 1-1/2 inch dia ball valve (with PVC Ball) made to B.S.S. 1212.	Each		1220.24	One Thousand Two Hundred Twenty Rupees and Twenty Four Paisas	4880.96
80	ASF Barracks Sanitary works-06	--do-- but 1" Ø Ball Valve	Each		985.18	Nine Hundred Eighty Five Rupees and Eighteen Paisas	27585.04

81	ASF Barracks Sanitary works-07	Providing and fixing Pakistani best quality European style white glazed earthenware W.,C pan complete with and including the cost of plastic seat and buffers, 13.6 litres flushing cistern with internal fittings complete, P.V.C flushing pipe with fittings and making requisite number of holes in walls, plinth and floor for pipe connections and making good in cement concrete 1:2:4.	Each		20037.5	Twenty Thousand Thirty Seven Rupees and Fifty Paisas	240450
----	--------------------------------	---	------	--	---------	--	--------


82	ASF Barracks Sanitary works-08	Providing and fixing squatting type W.C.Pan in white vitreous china with integral treads (Pakistani) orissa pattern and uPVC. trap 100mm dia. Complete with and including the cost of 13.6 litres best quality low level plastic flushing cistern with internal fittings complete, P.V.C. flushing pipe suitable for this type with fittings and making requisite number of holes in walls, plinth & floor for pipe connections and making good in cement concrete 1:2:4.	Each		17118.5	Seventeen Thousand One Hundred Eighteen Rupees and Fifty Paisas	1643376
----	--------------------------------	---	------	--	---------	---	---------

83	ASF Barracks Sanitary works-09	P/F of 22 inches x 16 inches (560x406 mm) lavatory basin in white glazed earthenware (Pakistani) complete with and including the cost of glazed earthenware half pedestal, Brass oxidized bolts kit built into walls 1/2 inches dia. Chrome plated mixer, 1-1/4 inches rubber plug and chrome plated brass chain 1-1/4 inches dia brass waste of approved pattern 1-1/4 inches dia chromium plated battal trap with unions and making requisite, number of holes in walls, plinth and floor for pip.e connections and making good in cement concrete 1:2:4.	Each		21253.75	Twenty One Thousand Two Hundred Fifty Three Rupees and Seventy Five Paisas	1275225
----	--------------------------------	---	------	--	----------	--	---------

84	ASF Barracks Sanitary works-10	Providing & fixing chromium plated Muslim bib-cock with Muslim Shower of approved quality.	Each	4734.45	Four Thousand Seven Hundred Thirty Four Rupees and Forty Five Paisas	511320.6
85	ASF Barracks Sanitary works-11	Providing and fixing 1/2 inches dia. (15 mm) CP Bib cocks.	Each	1582.56	One Thousand Five Hundred Eighty Two Rupees and Fifty Six Paisas	189907.2
86	ASF Barracks Sanitary works-12	P/F of 1/2 inch dia CP stop cocks/ Tee Stop Cock (Master / Faisal etc.) as directed	Each	1722.56	One Thousand Seven Hundred Twenty Two Rupees and Fifty Six Paisas	310060.8

87	ASF Barracks Sanitary works-13	Providing and fixing 24 inches x 18 inches (610 mm x 457 mm) looking mirror of Imported glass 5 mm thick fixing with CP clamps and screws	Each	3043.572	Three Thousand Forty Three Rupees and Fifty Seven Paisas	182614.32
88	ASF Barracks Sanitary works-14	P/F bath room accessories of set of 6 pieces consist of one shelf, one towel rod with bracket, one towel ring, one soap dish, one tooth Brush holder with glass, one tissue paper holder one double hook etc complete of approved quality as per direction of Engineer in-charge.	Each	16537.5	Sixteen Thousand Five Hundred Thirty Seven Rupees and Fifty Paisas	992250
89	ASF Barracks Sanitary works-15	Providing and fixing uPVC Multi floor trape of sizes with gratings including cutting and makeing the requisite number of holes in walls plinth and floors and making good in 1:2:4, C.C.	Each	2043.202	Two Thousand Forty Three Rupees and Twenty Paisas	245184.24

90	ASF Barracks Sanitary works-16	P/F 4" dia (u.P.V.C) "E" class pipe with specials and clamps etc., including cutting and fitting, complete with and including the cost of breaking through walls and roof and making good etc.; after cleaning the pipe and cartage within 10 miles (working pressure 12 kg/cm2).	Rft		1006.768	One Thousand Six Rupees and Seventy Seven Paisas	861793.408
----	--------------------------------	---	-----	--	----------	--	------------



91	ASF Barracks Sanitary works-17	Providing and fixing 6" x 6" (150 mm x 150 mm) with 4 inches (100 mm) outlet cement concrete C.I. gully trap wt: 42 lbs. (19 kg.) complete with 4 inches thick (100 mm) 1:2:4 cement concrete for bed and kerb, 1/2 inch (13 mm) thick cement plaster (1:3) to the kerb, C.I. grating 6 inches x 6 inches (150 mm x 150 mm) and C.I. cover and frame 12 inches x 12 inches (305 mm x 305 mm) (inside) etc., complete.	Each		5794.6	Five Thousand Seven Hundred Ninety Four Rupees and Sixty Paisas	231784
----	--------------------------------	---	------	--	--------	---	--------

92	ASF Barracks Sanitary works-18	Providing manhole type 'A' size 2 feet x 1-1/2 feet) (inside dimensions) x 2 feet (610 mm) deep as per approved design and specifications complete for 4 inches to 12 inches dia pipes up to 3 feet-11 inches depth with cast iron cover and frame 16 inches dia, inside (weight=1 Cwt.1 Qtr.) or 63.5 kg. fixed in 4 inches thick RCC 1:2:4 slab, 8 inches thick c.c. 1:3:6 block masonry walls set in 1:3 c.m; 6 inches thick 1:3:6 c.c. in foundation 1:2:4 c.c. in benching, 1/2 inches thick cement plaster in 1:3 C.M. to all inside wall surface, channels and benching etc. and to top including making requisite umber of main and branch channels but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	Each		14864.486	Fourteen Thousand Eight Hundred Sixty Four Rupees and Forty Nine Paisas	594579.44
----	--------------------------------	--	------	--	-----------	---	-----------

93	ASF Barracks Sanitary works-19	Add for extra depth beyond 2 feet and up to 3 feet-11 inches (610 mm and up to 1194 mm) for 'A' type manholes (for depth lesser than 2 feet or 610 mm deduct at the same rate).	P-Inch		280.224	Two Hundred Eighty Rupees and Twenty Two Paisas	269015.04
94	ASF Barracks Sanitary works-20	Providing 12" Ø RCC pipes and collars of class 'A' and fixing in trench including cutting, fitting and jointing with maxphalt composition and cement mortar (1:1) and testing with water to a head of 4 feet (1.22 m) above the top of the highest pipe including cartage within 10 miles	Rft		595.112	Five Hundred Ninety Five Rupees and Eleven Paisas	1047397.12

95	ASF Barracks Sanitary works-21	Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and .making the required channel etc., complete	Each	1050	One Thousand Fifty Rupees	4200
96	ASF Barracks Sanitary works-22	Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	P.Cft	3184.622	Three Thousand One Hundred Eighty Four Rupees and Sixty Two Paisas	127384.88
97	ASF Barracks Sanitary works-23	Providing and fixing water tank made of food grade polyethylene material 1000 gallon (Supper tuff) i/c cost of specials and cartage upto site as per direction of Engineer in charge	Each	132300	One Lakh Thirty Two Thousand Three Hundred Rupees	1587600

98	ASF Barracks Sanitary works-24	Providing and Fixing of 3" dia Bore hole with Submersible pump of approved make depth upto 450 ft complete in all respect as Instruction of Engineer Incharge	Each		550000	Five Lakh Fifty Thousand Rupees	2200000
----	--------------------------------	---	------	--	--------	---------------------------------	---------




99	ASF Barracks Soakage well and septic tank-01	Excavation for raft foundations, underground tanks and septic tanks (rectangular or square) in all kinds of soil (except gravelly and murum soil wet silt, clay or mud, conglomeration of gravel and boulders, soft, sandy or disintegrated and hard rock) and back filling the excavated material all round the trenches including breaking clods, watering, consolidation by ramming in layers not exceeding 9 inches (229 mm) in depth to full compaction, dressing and disposal of surplus excavated stuff as directed, lead up to one chain (30.5 R.m) and lift upto 5 feet (1.52 m)	100 Cft		1902.25	One Thousand Nine Hundred Two Rupees and Twenty Five Paisas	14990
----	--	---	---------	--	---------	---	-------

100	ASF Barracks Soakage well and septic tank-02	Providing and laying 1:4:8 (1 cement 4 sand and 8 coarse aggregate) cement concrete using crushed graded boulders 1 inch (25 mm) and down gauge in foundation including leveling, compacting and curing etc. complete	100 Cft	34306.426	Thirty Four Thousand Three Hundred Six Rupees and Forty Three Paisas	16467
101	ASF Barracks Soakage well and septic tank-03	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9" to 13-/2 inches (228 mm to 343 mm) thick including scaffolding, raking out joints and curing etc. complete in foundation, basement and plinth (foundation and basement masonry up to 5 feet (1.52 Ru.m.) depth and plinth up to 4 feet (1.2 Ru.m.) height from ground level)	100 Cft	54015.99	Fifty Four Thousand Fifteen Rupees and Ninety Nine Paisas	111273

102	ASF Barracks Soakage well and septic tank-04	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved wall 4-1/2 inches (114 mm) or less thickness including scaffolding, raking out joints and curing etc, complete in foundation, basement and plinth (foundation and basement masonry upto 5 (1.52 Ru.m.) feet depth and plinth upto 4 feet (1.2 Ru.m.) height from ground level) . (SH- 112/03)	100 Cft		59005.24	Fifty Nine Thousand Five Rupees and Twenty Four Paisas	18882
103	ASF Barracks Soakage well and septic tank-05	½ " (13 mm) thick cement plaster 1:4 on wall and columns etc. including making edges, corners and curing etc. complete in Ground Floor	100 Sft		6134.576	Six Thousand One Hundred Thirty Four Rupees and Fifty Eight Paisas	27606

104	ASF Barracks Soakage well and septic tank-06	Providing and laying floors of 2 inches (51 mm) thick 1:2:4 cement concrete using graded screened bajri 3/4 inch (19 mm) and down gauge in ground floor laid in panels including form work, consolidation, finishing, and curing etc. complete	100 Sft		9631.678	Nine Thousand Six Hundred Thirty One Rupees and Sixty Eight Paisas	6357
-----	--	--	---------	--	----------	--	------



105	ASF Barracks Soakage well and septic tank-07	Excavation for wells, circular underground tanks and soak spits etc., in all kinds of soil (except gravelly and murum soil, wet silt clay or mud, conglomeration of gravel and boulders, soft. sandy or disintegrated and hard rock) and back filling the excavated material all round the trenches including breaking clods, watering, consolidation by ramming in layers not exceeding 9 inches (229 mm) in depth to full compaction, dressing and disposal of surplus excavated stuff as directed, lead up to one chain (30.5 Ru.m)					
-----	---	---	--	--	--	--	--

106	i	lift up to 5 feet	100 Cft	2110.066	Two Thousand One Hundred Ten Rupees and Seven Paisas	9326
107	ii	lift up to 8 feet	100 Cft	2442.566	Two Thousand Four Hundred Forty Two Rupees and Fifty Seven Paisas	6448
108	iii	lift up to 11 feet	100 Cft	2775.066	Two Thousand Seven Hundred Seventy Five Rupees and Seven Paisas	7326

109	iv	lift up to 14 feet	100 Cft	3107.566	Three Thousand One Hundred Seven Rupees and Fifty Seven Paisas	8204
110	v	lift up to 17 feet	100 Cft	3440.066	Three Thousand Four Hundred Forty Rupees and Seven Paisas	9082
111	vi	lift up to 20 feet	100 Cft	3772.566	Three Thousand Seven Hundred Seventy Two Rupees and Fifty Seven Paisas	9960

112	vii	lift up to 23 feet	100 Cft	4105.066	Four Thousand One Hundred Five Rupees and Seven Paisas	10837
113	viii	lift up to 26 feet)	100 Cft	4437.566	Four Thousand Four Hundred Thirty Seven Rupees and Fifty Seven Paisas	11715
114	ix	lift up to 29 feet	100 Cft	4770.066	Four Thousand Seven Hundred Seventy Rupees and Seven Paisas	12593

115	x	lift up to 30 feet	100 Cft	5102.566	Five Thousand One Hundred Two Rupees and Fifty Seven Paisas	4490
116	ASF Barracks Soakage well and septic tank-08	Providing and laying first class solid burnt brick masonry in cement mortar 1:3 wells (steining) 9 inches (229 mm) to 13-1/2 inch (343 mm) thick including scaffolding curing etc. complete				
117	i	Depth upto 10 feet	100 Cft	73238.494	Seventy Three Thousand Two Hundred Thirty Eight Rupees and Forty Nine Paisas	232898

118	ii	Depth upto 15 feet	100 Cft	75032.524	Seventy Five Thousand Thirty Two Rupees and Fifty Two Paisas	118551
119	iii	Depth upto 20 feet	100 Cft	76826.554	Seventy Six Thousand Eight Hundred Twenty Six Rupees and Fifty Five Paisas	121386
120	iv	Depth upto 25 feet	100 Cft	78620.584	Seventy Eight Thousand Six Hundred Twenty Rupees and Fifty Eight Paisas	124221

121	v	Depth upto 30 feet	100 Cft	80414.614	Eighty Thousand Four Hundred Fourteen Rupees and Sixty One Paisas	127055
122	ASF Barracks Soakage well and septic tank-09	Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S angle iron frame, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge	P.Cft	3184.622	Three Thousand One Hundred Eighty Four Rupees and Sixty Two Paisas	159231

123	ASF Barracks Soakage well and septic tank-10	Providing and laying reinforced cement concrete using Lawrenecepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge in place of screened graded bajri in any item of RCC of mix not leaner than 1:2:4 crushing strength of works cube in this case will be 3000 lbs. per sq. inch (20.69 N/mm ² at 28 days) with a mix not leaner than 1:2:4 in curved beams, linteis and cantilever beams of required shape or section including form work and its removal, compacting and curing etc, complete but excluding the cost of reinforcement, in basement and ground floor	100 Cft		74270.252	Seventy Four Thousand Two Hundred Seventy Rupees and Twenty Five Paisas	47533
-----	--	---	---------	--	-----------	---	-------

124	ASF Barracks Soakage well and septic tank-11	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work in foundation, basement, plinth and ground floor of building including septic tanks and under ground tanks and in projections for future extension	P.Kg		395.43	Three Hundred Ninety Five Rupees and Forty Three Paisas	63269
-----	--	---	------	--	--------	---	-------


125	ASF Barracks Soakage well and septic tank-12	P/L Brick bats 3 inch and down gauge in soakage pit including cartage, wastage, etc complete as per direction of the Engineer Incharge	P.Cft		102	One Hundred Two Rupees	46104
-----	--	--	-------	--	-----	------------------------	-------



126	ASF MOQs Building Works-01	Excavation for raft foundations, underground tanks and septic tanks (rectangular or square) in all kinds of soil (except gravelly and murum soil wet silt, clay or mud, conglomeration of gravel and boulders, soft, sandy or disintegrated and hard rock) and back filling the excavated material all round the trenches including breaking clods, watering, consolidation by ramming in layers not exceeding 9 inches (229 mm) in depth to full compaction, dressing and disposal of surplus excavated stuff as directed, lead up to one chain (30.5 R.m) and lift upto 5 feet (2.135 m)	100 Cft		1902.25	One Thousand Nine Hundred Two Rupees and Twenty Five Paisas	426484
-----	----------------------------	--	---------	--	---------	---	--------

127	ASF MOQs Building Works-02	Providing and carrying out Termite proofing in foundations, under floors and wood work surface with a solution using of confront TC or ABILITY 2.5 % EC (Fipronil as an active ingredient) or approved equivalent by spraying all around the sides of foundation, trenches, flooded under floor @ 1/2 Liters of chemical per % Sft) with water and spraying the solution of the area to be treated as completed as per direction of Engineer incharge	P.Sft		18.382	Eighteen Rupees and Thirty Eight Paisas	151357
-----	----------------------------	---	-------	--	--------	---	--------

128	ASF MOQs Building Works-03	Providing and laying 1:4:8 (1 cement 4 sand and 8 coarse aggregate) cement concrete using crushed graded boulders 1 inch (25 mm) and down gauge in foundation including leveling, compacting and curing etc. complete.	100 Cft		34306.426	Thirty Four Thousand Three Hundred Six Rupees and Forty Three Paisas	769150
-----	----------------------------	--	---------	--	-----------	--	--------



129	ASF MOQs Building Works-04	Providing and laying reinforced cement concrete using crushed graded boulder 3/4 inch (19 mm) and down gauge and lawrencepur sand having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in raft or strip foundation with columns and pillars, of any shape including form work and its removal, compacting, leveling and curing etc. complete but excluding the cost of reinforcement, in foundation basement and plinth	100 Cft		54298.006	Fifty Four Thousand Two Hundred Ninety Eight Rupees and One Paisa	3652084
-----	----------------------------	--	---------	--	-----------	---	---------

130	ASF MOQs Building Works-05	Providing and laying reinforced cement concrete using crushed graded boulder 3/4 inch (19 mm) and down gauge and lawrencepur sand having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1- 1/2:3 in column footing of required shape including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in foundation basement and plinth.	100 Cft		61109.174	Sixty One Thousand One Hundred Nine Rupees and Seventeen Paisas	69664
-----	----------------------------------	---	------------	--	-----------	---	-------

131	ASF MOQs Building Works-06	Providing and laying reinforced cement concrete using crushed graded boulder 3/4 inch (19 mm) and down gauge and lawrencepur sand having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in columns of square or rectangular shape of regular section including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement, in foundation basement and plinth	100 Cft		66501.764	Sixty Six Thousand Five Hundred One Rupees and Seventy Six Paisas	236746
-----	----------------------------	---	---------	--	-----------	---	--------

132	ASF MOQs Building Works-07	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in plinth beams of required shape and design including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement, in foundation basement and plinth.	100 Cft		64324.274	Sixty Four Thousand Three Hundred Twenty Four Rupees and Twenty Seven Paisas	611081
-----	----------------------------	---	---------	--	-----------	--	--------

133	ASF MOQs Building Works-08	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in columns of square or rectangular shape of regular section including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement in Ground Floor	100 Cft		81591.034	Eighty One Thousand Five Hundred Ninety One Rupees and Three Pisas	1072106
-----	----------------------------	---	---------	--	-----------	--	---------

134	ASF MOQs Building Works-09	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in columns of square or rectangular shape of regular section including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement in First Floor.	100 Cft		85527.078	Eighty Five Thousand Five Hundred Twenty Seven Rupees and Eight Paisas	1123826
-----	----------------------------	---	---------	--	-----------	--	---------

135	ASF MOQs Building Works-10	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in columns of square or rectangular shape of regular section including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement in Second Floor	100 Cft		88621.904	Eighty Eight Thousand Six Hundred Twenty One Rupees and Ninety Paisas	1164492
-----	----------------------------	---	---------	--	-----------	---	---------

136	ASF MOQs Building Works-11	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in columns of square or rectangular shape of regular section including form work and its removal, compacting and curing etc. but excluding the cost of reinforcement in Third Floor	100 Cft		91716.73	Ninety One Thousand Seven Hundred Sixteen Rupees and Seventy Three Pisas	1205158
-----	----------------------------	--	---------	--	----------	--	---------


137	ASF MOQs Building Works-12	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight beams, lintels cantilever beams of required shape or section including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement in Ground Floor.	100 Cft		74064.942	Seventy Four Thousand Sixty Four Rupees and Ninety Four Paisas	1922726
-----	----------------------------	---	---------	--	-----------	--	---------

138	ASF MOQs Building Works-13	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight beams, lintels cantilever beams of required shape or section including M.S form work & M.S folding Pipes and its removal, compacting and curing etc. complete but excluding the cost of reinforcement in First Floor	100 Cft		78000.986	Seventy Eight Thousand Rupees and Ninety Nine Paisas	2024906
-----	----------------------------	---	---------	--	-----------	--	---------

139	ASF MOQs Building Works-14	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight beams, lintels cantilever beams of required shape or section including M.S form work & M.S folding Pipes and its removal, compacting and curing etc. complete but excluding the cost of reinforcement in Second Floor.	100 Cft		81095.812	Eighty One Thousand Ninety Five Rupees and Eighty One Paisas	2105247
-----	----------------------------	---	---------	--	-----------	--	---------

140	ASF MOQs Building Works-15	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight beams, lintels cantilever beams of required shape or section including M.S form work & M.S folding Pipes and its removal, compacting and curing etc. complete but excluding the cost of reinforcement in Third Floor.	100 Cft		87285.464	Eighty Seven Thousand Two Hundred Eighty Five Rupees and Forty Six Paisas	2265931
-----	----------------------------	--	---------	--	-----------	---	---------

141	ASF MOQs Building Works-16	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary slab 5 inches (127 mm) to 6 inches (152 mm) thick Including form work and its removal compacting and curing etc. complete but excluding the cost of reinforcement in Ground Floor	100 Cft		71634.374	Seventy One Thousand Six Hundred Thirty Four Rupees and Thirty Seven Paisas	1606043
-----	----------------------------	--	---------	--	-----------	---	---------



142	ASF MOQs Building Works-17	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary slab 5 inches (127 mm) to 6 inches (152 mm) thick Including M.S form work & M.S folding Pipes and its removal compacting and curing etc. complete but excluding the cost of reinforcement in First Floor	100 Cft		96899.712	Ninety Six Thousand Eight Hundred Ninety Nine Rupees and Seventy One Paisas	2172492
-----	----------------------------	---	---------	--	-----------	---	---------

143	ASF MOQs Building Works-18	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary slab 5 inches (127 mm) to 6 inches (152 mm) thick Including M.S form work & M.S folding Pipes and its removal compacting and curing etc. complete but excluding the cost of reinforcement in Second Floor	100 Cft		99994.538	Ninety Nine Thousand Nine Hundred Ninety Four Rupees and Fifty Four Paisas	2241878
-----	----------------------------	--	---------	--	-----------	--	---------

144	ASF MOQs Building Works-19	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary slab 5 inches (127 mm) to 6 inches (152 mm) thick Including M.S form work & M.S folding Pipes and its removal compacting and curing etc. complete but excluding the cost of reinforcement in Third Floor	100 Cft		103093.564	One Lakh Three Thousand Ninety Three Rupees and Fifty Six Paisas	2311358
-----	----------------------------	---	---------	--	------------	--	---------

145	ASF MOQs Building Works-20	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary cantilevered slab horizontal sun-shade or chajja tapered or straight average 5 inches (127 mm) to 6 inches (152 mm) thick including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in basement plinth and ground floor.	100 Cft		78451.898	Seventy Eight Thousand Four Hundred Fifty One Rupees and Ninety Paisas	112971
-----	----------------------------	---	---------	--	-----------	--	--------

146	ASF MOQs Building Works-21	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary cantilevered slab horizontal sun-shade or chajja tapered or straight average 5 inches (127 mm) to 6 inches (152 mm) thick including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in first floor.	100 Cft		82387.942	Eighty Two Thousand Three Hundred Eighty Seven Rupees and Ninety Four Paisas	118639
-----	----------------------------	--	---------	--	-----------	--	--------

147	ASF MOQs Building Works-22	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary cantilevered slab horizontal sun-shade or chajja tapered or straight average 5 inches (127 mm) to 6 inches (152 mm) thick including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in Second floor.	100 Cft		85482.768	Eighty Five Thousand Four Hundred Eighty Two Rupees and Seventy Seven Paisas	123095
-----	----------------------------	---	---------	--	-----------	--	--------

148	ASF MOQs Building Works-23	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in ordinary cantilevered slab horizontal sun-shade or chajja tapered or straight average 5 inches (127 mm) to 6 inches (152 mm) thick including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in Second floor.	100 Cft		88577.594	Eighty Eight Thousand Five Hundred Seventy Seven Rupees and Fifty Nine Paisas	127552
-----	----------------------------	---	---------	--	-----------	---	--------

149	ASF MOQs Building Works-24	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight stairs and landing of required section including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in basement plinth and ground floor.	100 Cft		88774.938	Eighty Eight Thousand Seven Hundred Seventy Four Rupees and Ninety Four Paisas	651608
-----	----------------------------	--	---------	--	-----------	--	--------

150	ASF MOQs Building Works-25	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight stairs and landing of required section including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in First floor.	100 Cft		92710.982	Ninety Two Thousand Seven Hundred Ten Rupees and Ninety Eight Paisas	680499
-----	----------------------------	---	---------	--	-----------	--	--------

151	ASF MOQs Building Works-26	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight stairs and landing of required section including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in Second floor.	100 Cft		95805.808	Ninety Five Thousand Eight Hundred Five Rupees and Eighty One Paisas	703215
-----	----------------------------	--	---------	--	-----------	--	--------

152	ASF MOQs Building Works-27	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in straight stairs and landing of required section including form work and its removal, compacting and curing etc. complete but excluding the cost of reinforcement, in third floor floor	100 Cft		98900.634	Ninety Eight Thousand Nine Hundred Rupees and Sixty Three Paisas	725931
-----	----------------------------	--	---------	--	-----------	--	--------

153	ASF MOQs Building Works-28	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in shelves 1-1/2 inches to 2 inches (38 to 51 mm) thick cast in situ including form works and its removal, compacting and curing etc. complete but excluding the cost of reinforcement Ground Floor	100 Cft		105537.964	One Lakh Five Thousand Five Hundred Thirty Seven Rupees and Ninety Six Paisas	94984
-----	----------------------------	--	---------	--	------------	---	-------

154	ASF MOQs Building Works-29	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in shelves 1-1/2 inches to 2 inches (38 to 51 mm) thick cast in situ including form works and its removal, compacting and curing etc. complete but excluding the cost of reinforcement first Floor	100 Cft		109474.008	One Lakh Nine Thousand Four Hundred Seventy Four Rupees and One Paisa	98527
-----	----------------------------	---	---------	--	------------	---	-------

155	ASF MOQs Building Works-30	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in shelves 1-1/2 inches to 2 inches (38 to 51 mm) thick cast in situ including form works and its removal, compacting and curing etc. complete but excluding the cost of reinforcement Second Floor	100 Cft		112568.834	One Lakh Twelve Thousand Five Hundred Sixty Eight Rupees and Eighty Three Paisas	101312
-----	----------------------------	--	---------	--	------------	--	--------

156	ASF MOQs Building Works-31	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1-1/2:3 in shelves 1-1/2 inches to 2 inches (38 to 51 mm) thick cast in situ including form works and its removal, compacting and curing etc. complete but excluding the cost of reinforcement Third Floor	100 Cft		115663.66	One Lakh Fifteen Thousand Six Hundred Sixty Three Rupees and Sixty Six Paisas	104097
-----	----------------------------	---	---------	--	-----------	---	--------

157	ASF MOQs Building Works-32	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work including septic tanks and under ground tanks and in projections for future extension in Foundation, plinth and ground floor	P.Kg		395.43	Three Hundred Ninety Five Rupees and Forty Three Paisas	24146538
-----	----------------------------	---	------	--	--------	---	----------

158	ASF MOQs Building Works-33	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work including septic tanks and under ground tanks and in projections for future extension in Foundation, plinth and first floor.	P.Kg		401.646	Four Hundred One Rupees and Sixty Five Paisas	11438878
-----	----------------------------	---	------	--	---------	---	----------

159	ASF MOQs Building Works-34	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work in projections for future extension in Second Floor	P.Kg		407.862	Four Hundred Seven Rupees and Eighty Six Paisas	11615910
-----	----------------------------	--	------	--	---------	---	----------

160	ASF MOQs Building Works-35	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work in projections for future extension in Third Floor	P.Kg		414.078	Four Hundred Fourteen Rupees and Eight Paisas	11792941
-----	----------------------------------	---	------	--	---------	--	----------

161	ASF MOQs Building Works-36	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls more than 13-1/2 inches (343 mm) thick including scaffolding, raking out joints and curing etc. Complete in foundation, basement and plinth (foundation and basement masonry upto 5 feet (1.52 Ru.m.) depth and plinth upto 4 feet (1.2 Ru.m.) height from ground level) .	100 Cft		50581.608	Fifty Thousand Five Hundred Eighty One Rupees and Sixty One Paisas	409711
-----	----------------------------	--	---------	--	-----------	--	--------

162	ASF MOQs Building Works-37	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9" to 13-2 inches (228 mm to 343 mm) thick including scaffolding, raking out joints and curing etc. complete in foundation, basement and plinth (foundation and basement masonry up to 5 feet (1.52 Ru.m.) depth and plinth up to 4 feet (1.2 Ru.m.) height from ground level)	100 Cft		54015.99	Fifty Four Thousand Fifteen Rupees and Ninety Nine Paisas	2625177
163	ASF MOQs Building Works-38	Providing a coat of bitumen emulsion at 10 Lbs. per % sft. (0.49 Kg/sm) on walls and floor in ground floor.	100 Sft		1415.05	One Thousand Four Hundred Fifteen Rupees and Five Paisas	20377

164	ASF MOQs Building Works-39	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in superstructure in Ground Floor	100 Cft		57765.358	Fifty Seven Thousand Seven Hundred Sixty Five Rupees and Thirty Six Paisas	6100022
165	ASF MOQs Building Works-40	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in superstructure in First Floor	100 Cft		61042.884	Sixty One Thousand Forty Two Rupees and Eighty Eight Paisas	6446129

166	ASF MOQs Building Works-41	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in superstructure in second Floor Beyond 25' upto 30' height	100 Cft		63637.784	Sixty Three Thousand Six Hundred Thirty Seven Rupees and Seventy Eight Paisas	6720150
167	ASF MOQs Building Works-42	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in superstructure in Third Floor Beyond 25' upto 30' height	100 Cft		66232.684	Sixty Six Thousand Two Hundred Thirty Two Rupees and Sixty Eight Paisas	6994171


168	ASF MOQs Building Works-43	Providing and laying first class solid burnt brick masonry set in cement mortar 1:4 in straight or curved walls 4-1/2 inches (114 mm) and less in thickness including scaffolding, raking, out joints and curing etc. complete in ground floor superstructure.	100 Cft		63709.17	Sixty Three Thousand Seven Hundred Nine Rupees and Seventeen Paisas	1476779
169	ASF MOQs Building Works-44	Providing and laying first class solid burnt brick masonry set in cement mortar 1:4 in straight or curved walls 4-1/2 inches (114 mm) and less in thickness including scaffolding, raking, out joints and curing etc. complete in first floor	100 Cft		66986.696	Sixty Six Thousand Nine Hundred Eighty Six Rupees and Seventy Paisas	1552752

170	ASF MOQs Building Works-45	Providing and laying first class solid burnt brick masonry set in cement mortar 1:4 in straight or curved walls 4-1/2 inches (114 mm) and less in thickness including scaffolding, raking, out joints and curing etc. complete in Second floor.	100 Cft		70264.222	Seventy Thousand Two Hundred Sixty Four Rupees and Twenty Two Paisas	1628725
171	ASF MOQs Building Works-46	Providing and laying first class solid burnt brick masonry set in cement mortar 1:4 in straight or curved walls 4-1/2 inches (114 mm) and less in thickness including scaffolding, raking, out joints and curing etc. complete in Third floor	100 Cft		73541.748	Seventy Three Thousand Five Hundred Forty One Rupees and Seventy Five Paisas	1704698

172	ASF MOQs Building Works-47	Supplying stacking and filling sand of approved quality from outside sources in foundation, trenches, plinth or under floor, etc. including dressing, watering and consolidation by ramming in layers not exceeding 9 inches (229 mm) in depth to full compaction and lift up to 5 feet (1.52 m)	100 Cft	6817.916	Six Thousand Eight Hundred Seventeen Rupees and Ninety Two Paisas	1834292
173	ASF MOQs Building Works-48	Supplying and laying vitrified brick ballast 2" to 1-1/2" (51 mm to 38 mm) gauge of approved quality for base or wearing coat etc.; in Layers not exceeding 6" (152 mm) thick, consolidating by approved mechanical means to required grade and camber including watering etc., with all lead and lift complete	100 Cft	12419.05	Twelve Thousand Four Hundred Nineteen Rupees and Five Paisas	367604

174	ASF MOQs Building Works-49	Providing and laying 1:4:8 cement concrete bed under floors using graded stone ballast 2 inches (51 mm) and down gauge with leveling and ramming, watering and curing etc. complete.	100 Cft		30851.45	Thirty Thousand Eight Hundred Fifty One Rupees and Forty Five Paisas	913203
175	ASF MOQs Building Works-50	Providing and laying floors of 2 inches (51 mm) thick 1:2:4 cement concrete using graded screened bajri 3/4 inch (19 mm) and down gauge in ground floor laid in panels including form work, consolidation, finishing and curing etc. complete	100 Sft		9631.678	Nine Thousand Six Hundred Thirty One Rupees and Sixty Eight Paisas	863769

176	ASF MOQs Building Works-51	Providing and laying light colour, glazed/non skid vitrified porcelain tiles (Polished) exceeding 3600 Sq.cm each (Pak made) on walls and floors, in any floor, laid with dry bond (stile bond) over existing floor including jointing to tiles with joint filler of approved quality as per direction of the Engineer in charge	100 Sft		66618.426	Sixty Six Thousand Six Hundred Eighteen Rupees and Forty Three Paisas	27201636
-----	----------------------------------	--	------------	--	-----------	---	----------



177	ASF MOQs Building Works-52	Providing and laying floor of 3/4" (19 mm) thick Granite tiles Pakistani Origin more than 3 Sq.ft. upto 5 Sq.ft. more than (0.28 Sq.m upto 1.46 Sq.m) size fine dressed on the surface without winding treads, risers, and mid stair landings, stairs/steps (in treads, risers and midstair landings) over 1 inch (25 mm) cement mortar 1:4 (one cement, four sand) setting the marble tile with grey cement, slurry over cement mortar, jointing and washing the tiles with white cement slurry including curing, rubbing and polishing etc. complete including the cost of mortar	100 Sft		114456.482	One Lakh Fourteen Thousand Four Hundred Fifty Six Rupees and Forty Eight Paisas	5228372
-----	----------------------------	---	---------	--	------------	---	---------

178	ASF MOQs Building Works-53	Making nosing of treads as per design and instructions of the Engineer-in-Charge	P. Rft	183.75	One Hundred Eighty Three Rupees and Seventy Five Paisas	271950
179	ASF MOQs Building Works-54	½ " (13 mm) thick cement plaster 1:4 on wall and columns etc. including making edges, corners and curing etc. complete in Ground Floor	100 Sft	6134.576	Six Thousand One Hundred Thirty Four Rupees and Fifty Eight Paisas	7941945
180	ASF MOQs Building Works-55	½ " (13 mm) thick cement plaster 1:4 on wall and columns etc. including making edges, corners and curing etc. complete in First Floor	100 Sft	6565.076	Six Thousand Five Hundred Sixty Five Rupees and Eight Paisas	8499279
181	ASF MOQs Building Works-56	½ " (13 mm) thick cement plaster 1:4 on wall and columns etc. including making edges, corners and curing etc. complete in Second Floor	100 Sft	6995.576	Six Thousand Nine Hundred Ninety Five Rupees and Fifty Eight Paisas	9056613

182	ASF MOQs Building Works-57	½ " (13 mm) thick cement plaster 1:4 on wall and columns etc. including making edges, corners and curing etc. complete in Second Floor	100 Sft		7426.076	Seven Thousand Four Hundred Twenty Six Rupees and Eight Paisas	9613947
183	ASF MOQs Building Works-58	¼ " (6.4 mm) thick cement plaster 1:4 on soffits of ceiling, cantilever slabs, sides and soffits of beams etc. including making edges, corners and curing etc. complete in Ground Floor	100 Sft		5393.626	Five Thousand Three Hundred Ninety Three Rupees and Sixty Three Paisas	241850
184	ASF MOQs Building Works-59	¼ " (6.4 mm) thick cement plaster 1:4 on soffits of ceiling, cantilever slabs, sides and soffits of beams etc. including making edges, corners and curing etc. complete in First Floor	100 Sft		5824.126	Five Thousand Eight Hundred Twenty Four Rupees and Thirteen Paisas	261154

185	ASF MOQs Building Works-60	¼ " (6.4 mm) thick cement plaster 1:4 on soffits of ceiling, cantilever slabs, sides and soffits of beams etc. including making edges, corners and curing etc. complete in Second Floor	100 Sft		6254.626	Six Thousand Two Hundred Fifty Four Rupees and Sixty Three Paisas	280457
186	ASF MOQs Building Works-61	¼ " (6.4 mm) thick cement plaster 1:4 on soffits of ceiling, cantilever slabs, sides and soffits of beams etc. including making edges, corners and curing etc. complete in Thrid Floor	100 Sft		6685.126	Six Thousand Six Hundred Eighty Five Rupees and Thirteen Paisas	299761

187	ASF MOQs Building Works-62	Providing and fixing M.S. moulded steel door frames of 5.73" x 2-1/2" (146 mm x 63 mm) manufactured from mild steel sheet of 18 gauge (1.41 mm) conforming to B.S.S. 1245 having a double rebate size 1-1/2" x 1/2" (38 mm x 12 mm) provision of 3 Nos. M.S. plate, section 1-1/2" x 1/4" (38 mm x 6 mm) (2 Nos. 6 inch long welded with frame at not less than 10 points and 1 Nos. 12 inch long welded with frame at not less than 20 points), with holes and threads for fixing steel hinges, fitted with one locking box of same sheet (point welded inside the frame), 6 Nos. 6 inches long flat iron fixing lugs of 1-1/4" x 3/16" section, treated with special red oxide primer coat all around including cutting holes and filling the cavity with cement concrete 1:2:4 etc. in any floor at any height complete as directed by the	P.Rft		657.72	Six Hundred Fifty Seven Rupees and Seventy Two Paisas	441988
-----	----------------------------	---	-------	--	--------	---	--------

188	ASF MOQs Building Works-63	Providing and fixing M.S. moulded steel door frames of 10" x 2-1/2" manufactured from mild steel sheet of 18 gauge conforming to B.S.S. 1245 having a double rebate size 1-1/2" x 1/2" (38 mm x 12 mm) provision of 3 Nos. M.S. plate, section 1-1/2" x 1/4" (38 mm x 6 mm) (2 Nos. 6 inch long welded with frame at not less than 10 points and 1 Nos. 12 inch long welded with frame at not less than 20 points), with holes and threads for fixing steel hinges, fitted with one locking box of same sheet (point welded inside the frame), 6 Nos. 6 inches long flat iron fixing lugs of 1-1/4" x 3/16" section, treated with special red oxide primer coat all around including cutting holes and filling the cavity with cement concrete 1:2:4 etc. in any floor at any height complete as directed by the	P.Rft		971.404	Nine Hundred Seventy One Rupees and Forty Paisas	839293
-----	----------------------------	---	-------	--	---------	--	--------

189	ASF MOQs Building Works-64	Providing and fixing 1-1/2 inches (38 mm) thick solid core deodar wood flushed veneered door shutters, with and including the cost of commercial plywood facing 3 mm. thick (3 ply) on both faces, fixed over best quality deodar wood frame 2 inches wide all-round 6 inches wide lock rail and 2nd class deodar wood solid core, i/c., 3/8 inch thick best quality deodar wood lipping on all sides as per approved drawing, manufactured under power driven hydraulic press, including the cost of approved iron fittings but excluding the cost of handles and locking arrangement.	P.Sft		2027.984	Two Thousand Twenty Seven Rupees and Ninety Eight Paisas	2214559
-----	----------------------------	---	-------	--	----------	--	---------


190	ASF MOQs Building Works-65	Providing and fixing with brass screws lucky lock knob set of approved design (Taiwan make) cutting wood to required shape and size with two operating keys as per direction of the Engineer-in-Charge	Each	5459.132	Five Thousand Four Hundred Fifty Nine Rupees and Thirteen Paisas	262038
191	ASF MOQs Building Works-66	Providing and fixing approved chromium plated brass handles 7" (178 mm) size heavy type with necessary brass screws . (Page No. 365/165)	Each	851.634	Eight Hundred Fifty One Rupees and Sixty Three Paisas	81757
192	ASF MOQs Building Works-67	Providing and fixing with brass screws or specially supplied screws hydraulic door closer Rayobi or approved design No. 72, Japan make, cutting wood etc., to required shape and size as per direction of engineer-in-charge . (Page No. 357/70)	Each	13063.75	Thirteen Thousand Sixty Three Rupees and Seventy Five Paisas	313530

193	ASF MOQs Building Works-68	Providing and laying heated asphalt on third floor roof at the rate of 20 Lbs. per hundred square feet (0.98 Kg per s.m) finished with washed coarse sand 3 cubic feet per hundred square feet (0.086 C.M. per s.m) including ramming with thappies etc. complete	100 Sft		5662.818	Five Thousand Six Hundred Sixty Two Rupees and Eighty Two Paisas	253921
194	ASF MOQs Building Works-69	Providing and laying single layer of polythene sheet of 500 gauge (0.005 inch or 0.13 mm thick) under floors for water proofing laid as per specifications and instructions of the Engineer-in-Charge in Ground Floor (P. No. 83/26+84/38x2)	100 Sft		1470.014	One Thousand Four Hundred Seventy Rupees and One Paisa	65915

195	ASF MOQs Building Works-70	Providing and fixing of Diamond Jumbolon insulation board 1-1/2" thick and polythene sheet over diamond jumbolon insulation for roof insulation as per directions of the Engineer-in-Charge in any floor in any height	P.Sft		191.058	One Hundred Ninety One Rupees and Six Paisas	856704
196	ASF MOQs Building Works-71	Providing and laying 1st class burnt clay tiles of 9" X 4-1/2" X 1-1/2" size grouted with 1:3 cement mortar over 4" thick (avg) puddled earth compacted and smooth finished to slope mixed with bhoosa at the rate of one seer of bhoosa for one cft. of puddled earth in Second Floor including flush pointing on tiles works with 1:3 cement mortar and curing complete	100 Sft		21871.85	Twenty One Thousand Eight Hundred Seventy One Rupees and Eighty Five Paisas	980734

197	ASF MOQs Building Works-72	Providing and laying 1:2:4 cement concrete khuras 2" (51 mm) thick 2 ft. x 2 ft. (610 mm x 610 mm) size on roof including finishing with cement plaster 1:4, curing etc. complete	Each		244.762	Two Hundred Forty Four Rupees and Seventy Six Paisas	1958
198	ASF MOQs Building Works-73	Providing and laying gola 3" x 3" (76 mm x 76 mm) concrete 1:2:4 using graded screened bajri at junction of roof slab and walls and finished with cement plaster 1:4 including curing etc. complete	100 Rft		4483.304	Four Thousand Four Hundred Eighty Three Rupees and Thirty Paisas	32280
199	ASF MOQs Building Works-74	Providing and fixing 4" (100 mm) dia polyvinyle chloride rain water (PVC) down pipe with mild steel clamps, bolts and nuts fixed in cement concrete 1:2:4 etc. complete	P. Rft		1006.138	One Thousand Six Rupees and Fourteen Paisas	321964

200	ASF MOQs Building Works-75	Providing and fixing 4" (80 mm) dia polyvinyle chloride (PVC) bend of any degree for rain water down pipe with clamps, bolts and nuts in cement concrete 1:2:4 etc. complete.	Each		2447.382	Two Thousand Four Hundred Forty Seven Rupees and Thirty Eight Paisas	78316
-----	----------------------------------	---	------	--	----------	--	-------



201	ASF MOQs Building Works-76	Providing and fixing fully glazed Champagne anodized or powder coated aluminium Sliding windows as per British standard manufactured by Lucky, Prime, Chawla, Krudson and Pakistan Cables. (fixing through their approved fabricators), Deluxe model box 101 section 95mm x 30mm and 1.6mm thick including the cost of aluminium netting ,fittings, with all accessories cutting hole etc. and making good damages to walls etc. complete as required in any floor as per direction of engineer-in-charge, including the cost of glass6mm thick	P.Sft		2119.894	Two Thousand One Hundred Nineteen Rupees and Eighty Nine Paisas	1589921
-----	----------------------------	---	-------	--	----------	---	---------

202	ASF MOQs Building Works-77	Providing and fixing P.V.C board 2' x 2' tiles printed ceiling including Aluminum T & L angle 1" x 1" i.c hanger clips jointing clips and G.I Wire etc complete as required in any floor	P.Sft		324.52	Three Hundred Twenty Four Rupees and Fifty Two Paisas	1455148
203	ASF MOQs Building Works-78	Painting iron work with synthetic enamel paint of approved make and shade two coats over and including the cost of one priming complete at any height in any floor	100 Sft		8499.75	Eight Thousand Four Hundred Ninety Nine Rupees and Seventy Five Paisas	50319
204	ASF MOQs Building Works-79	Painting wood work with synthetic enamel paint of approved make and shade two coats over and including the cost of one priming coat complete at any height in any floor	100 Sft		8336.804	Eight Thousand Three Hundred Thirty Six Rupees and Eighty Paisas	182076

205	ASF MOQs Building Works-80	Painting with (ICI) Dulux plastic emulsion paint VIP of approved shade two coats over and including the cost of wall putty / priming coat complete over plastered surface at any height in any floor	100 Sft		9432.332	Nine Thousand Four Hundred Thirty Two Rupees and Thirty Three Paisas	9494774
206	ASF MOQs Building Works-81	Painting three coats with weather shield paint deluxe (ICI) make of approved shade on plaster surface (External) and including the cost of cleaning the surface, sand papering etc. complete at any height any floor. (P. No. 390/172)	100 Sft		6172.25	Six Thousand One Hundred Seventy Two Rupees and Twenty Five Paisas	1740575

207	ASF MOQs Building Works-82	Providing and fixing cabinet wall mounted of 3/4" thick lamminated board with best quality deodar wood frame and beading 1/8" thick hard borad backing required section in approved pattern etc. fixed on wall with rawal plug, screws i/c cost of glue, nails, piano hinges, handles and painting or polishing as drawing complete all as respect	P.Sft		1908.55	One Thousand Nine Hundred Eight Rupees and Fifty Five Paisas	2442944
-----	----------------------------------	--	-------	--	---------	---	---------

208	ASF MOQs Building Works-83	Providing and fixing 2" dia. stainless steel pipe (18 guage) railing along with 4", 3/4" dia. parallel pipe having S.S pipe vertical post 2" dia. at 3 ft c/c average spacing and 4" dia. vertical post at start turning and end point including cost of labour, welding charges fitting and fixing in marble floor and wall etc. complete as per direction of the engineer incharge	P.Rft		3128.132	Three Thousand One Hundred Twenty Eight Rupees and Thirteen Paisas	750752
-----	----------------------------------	--	-------	--	----------	--	--------

209	ASF MOQs Building Works-84	Providing and fixing Windows roll up blinds sunscreen, dark out, or translucent fabric any colour/shade best quality (imported) with manual roll up arrangements complete in all respect with all other required accessories and hardware from the approved suppliers and manufacturers as per direction of Engineer incharge	P. Sft		440.412	Four Hundred Forty Rupees and Forty One Paisas	1522064
210	ASF MOQs Sanitary Works-01	Making connection with the existing G.I. pipe upto 2 inches dia including cutting the pipe and providing and fixing necessary fittings	Each		2181.9	Two Thousand One Hundred Eighty One Rupees and Ninety Paisas	4363.8

211	ASF MOQs Sanitary Works-02	P/F 1-1/2" Ø uPVC pipe "D" class and specials etc. including cutting and fitting complete with and including the cost of cutting trench upto 1-1/2 feet deep refilling, watering, ramming, and disposal of surplus earth within one chain and after cleaning the pipe and cartage within 10 miles (16.09 km.) (working pressure 12 kg/cm2)	Rft		204.358	Two Hundred Four Rupees and Thirty Six Paisas	122614.8
212	ASF MOQs Sanitary Works-03	P/F 1" Ø uPVC Pipe "E" class with specials and clamps etc., including cutting and fitting, complete with and including the cost of breaking through walls and roof and making good etc.; after cleaning the pipe and cartage within 10 miles (working pressure 12 kg/cm2)	Rft		144.788	One Hundred Forty Four Rupees and Seventy Nine Paisas	69498.24

213	ASF MOQs Sanitary Works-04	--do-- but 3/4" Ø uPVC E Class pipe	Rft		135.632	One Hundred Thirty Five Rupees and Sixty Three Paisas	162758.4
214	ASF MOQs Sanitary Works-05	P/F of 1-1/2 inch dia ball valve (with PVC Ball) made to B.S.S. 1212	Each		1220.24	One Thousand Two Hundred Twenty Rupees and Twenty Four Paisas	19523.84
215	ASF MOQs Sanitary Works-06	--do-- but 1" Ø Ball Valve	Each		985.18	Nine Hundred Eighty Five Rupees and Eighteen Paisas	55170.08

216	ASF MOQs Sanitary Works-07	Providing and fixing Pakistani best quality European style white glazed earthenware W.,C pan complete with and including the cost of plastic seat and buffers, 13.6 litres flushing cistern with internal fittings complete, P.V.C flushing pipe with fittings and making requisite number of holes in walls, plinth and floor for pipe connections and making good in cement concrete 1:2:4.	Each		20037.5	Twenty Thousand Thirty Seven Rupees and Fifty Paisas	641200
-----	----------------------------------	---	------	--	---------	--	--------


217	ASF MOQs Sanitary Works-08	Providing and fixing squatting type W.C.Pan in white vitreous china with integral treads (Pakistani) orissa pattern and uPVC. trap 100mm dia. Complete with and including the cost of 13.6 litres best quality low level plastic flushing cistern with internal fittings complete, P.V.C. flushing pipe suitable for this type with fittings and making requisite number of holes in walls, plinth & floor for pipe connections and making good in cement concrete 1:2:4.	Each		17118.5	Seventeen Thousand One Hundred Eighteen Rupees and Fifty Paisas	1095584
-----	----------------------------------	--	------	--	---------	--	---------

218	ASF MOQs Sanitary Works-09	P/F of 22 inches x 16 inches (560 x 406 mm) lavatory basin in white glazed earthenware (Pakistani) complete with and including the cost of glazed earthenware half pedestal, Brass oxidized bolts kit built into walls 1/2 inches dia. Chrome plated mixer, 1-1/4 inches rubber plug and chrome plated brass chain 1-1/4 inches dia brass waste of approved pattern 1-1/4 inches dia chromium plated battal trap with unions and making requisite, number of holes in walls, plinth and floor for pip.e connections and making good in cement concrete 1:2:4.	Each		21253.75	Twenty One Thousand Two Hundred Fifty Three Rupees and Seventy Five Paisas	1360240
-----	----------------------------------	---	------	--	----------	--	---------

219	ASF MOQs Sanitary Works-10	Providing & fixing chromium plated Muslim bib-cock with Muslim Shower of approved quality	Each		4734.45	Four Thousand Seven Hundred Thirty Four Rupees and Forty Five Paisas	378756
220	ASF MOQs Sanitary Works-11	Providing and fixing 1/2 inches dia. (15 mm) CP Bib cocks. (SH-307/2)	Each		1582.56	One Thousand Five Hundred Eighty Two Rupees and Fifty Six Paisas	253209.6
221	ASF MOQs Sanitary Works-12	P/F of 1/2 inch dia CP stop cocks/ Tee Stop Cock (Master / Faisal etc.) as directed	Each		1722.56	One Thousand Seven Hundred Twenty Two Rupees and Fifty Six Paisas	413414.4

222	ASF MOQs Sanitary Works-13	Providing and fixing 24 inches x 18 inches (610 mm x 457 mm) looking mirror of Imported glass 5 mm thick fixing with CP clamps and screws	Each	3043.572	Three Thousand Forty Three Rupees and Fifty Seven Paisas	194788.608
223	ASF MOQs Sanitary Works-14	P/F bath room accessories of set of 6 pieces consist of one shelf, one towel rod with bracket, one towel ring, one soap dish, one tooth Brush holder with glass, one tissue paper holder one double hook etc complete of approved quality as per direction of Engineer in-charge.	Each	16537.5	Sixteen Thousand Five Hundred Thirty Seven Rupees and Fifty Paisas	1058400
224	ASF MOQs Sanitary Works-15	Providing and fixing uPVC Multi floor trape of sizes with gratings including cutting and makeing the requisite number of holes in walls plinth and floors and making good in 1:2:4, C.C.	Each	2043.202	Two Thousand Forty Three Rupees and Twenty Paisas	261529.856

225	ASF MOQs Sanitary Works-16	P/F 4" dia (u.P.V.C) "E" class pipe with specials and clamps etc., including cutting and fitting, complete with and including the cost of breaking through walls and roof and making good etc.; after cleaning the pipe and cartage within 10 miles (working pressure 12 kg/cm2)	Rft		1006.768	One Thousand Six Rupees and Seventy Seven Paisas	1417529.344
-----	----------------------------------	--	-----	--	----------	--	-------------




226	ASF MOQs Sanitary Works-17	Providing and fixing 6" x 6" (150 mm x 150 mm) with 4 inches (100 mm) outlet cement concrete C.I. gully trap wt: 42 lbs. (19 kg.) complete with 4 inches thick (100 mm) 1:2:4 cement concrete for bed and kerb, 1/2 inch (13 mm) thick cement plaster (1:3) to the kerb, C.I. grating 6 inches x 6 inches (150 mm x 150 mm) and C.I. cover and frame 12 inches x 12 inches (305 mm x 305 mm) (inside) etc., complete.	Each		5794.6	Five Thousand Seven Hundred Ninety Four Rupees and Sixty Paisas	185427.2
-----	----------------------------------	---	------	--	--------	---	----------

227	ASF MOQs Sanitary Works-18	Providing manhole type 'A' size 2 feet x 1-1/2 feet) (inside dimensions) x 2 feet (610 mm) deep as per approved design and specifications complete for 4 inches to 12 inches dia pipes up to 3 feet-11 inches depth with cast iron cover and frame 16 inches dia, inside (weight=1 Cwt.1 Qtr.) or 63.5 kg. fixed in 4 inches thick RCC 1:2:4 slab, 8 inches thick c.c. 1:3:6 block masonry walls set in 1:3 c.m; 6 inches thick 1:3:6 c.c. in foundation 1:2:4 c.c. in benching, 1/2 inches thick cement plaster in 1:3 C.M. to all inside wall surface, channels and benching etc. and to top including making requisite umber of main and branch channels but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame	Each		14864.486	Fourteen Thousand Eight Hundred Sixty Four Rupees and Forty Nine Paisas	445934.58
-----	----------------------------------	---	------	--	-----------	--	-----------

228	ASF MOQs Sanitary Works-19	Add for extra depth beyond 2 feet and up to 3 feet-11 inches (610 mm and up to 1194 mm) for 'A' type manholes (for depth lesser than 2 feet or 610 mm deduct at the same rate).	P- Inch		280.224	Two Hundred Eighty Rupees and Twenty Two Paisas	201761.28
229	ASF MOQs Sanitary Works-20	Providing 12" Ø RCC pipes and collars of class 'A' and fixing in trench including cutting, fitting and jointing with maxphalt composition and cement mortar (1:1) and testing with water to a head of 4 feet (1.22 m) above the top of the highest pipe including cartage within 10 miles	Rft		595.112	Five Hundred Ninety Five Rupees and Eleven Paisas	666525.44

230	ASF MOQs Sanitary Works-21	Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and .making the required channel etc., complete	Each		1050	One Thousand Fifty Rupees	2100
231	ASF MOQs Sanitary Works-22	Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge	P.Cft		3184.622	Three Thousand One Hundred Eighty Four Rupees and Sixty Two Paisas	95538.66
232	ASF MOQs Sanitary Works-23	Providing and fixing water tank made of food grade polyethylene material 1000 gallon (Supper tuff) i/c cost of specials and cartage upto site as per direction of Engineer in charge	Each		132300	One Lakh Thirty Two Thousand Three Hundred Rupees	2116800

233	ASF MOQs Sanitary Works-24	Providing and Fixing of 3" dia Bore hole with Submersible pump of approved make depth upto 450 ft complete in all respect as Instruction of Engineer Incharge. (A.R)	Each		550000	Five Lakh Fifty Thousand Rupees	2200000
-----	----------------------------------	--	------	--	--------	--	---------




234	ASF MOQs Soakage well and septic tank-01	Excavation for raft foundations, underground tanks and septic tanks (rectangular or square) in all kinds of soil (except gravelly and murum soil wet silt, clay or mud, conglomeration of gravel and boulders, soft, sandy or disintegrated and hard rock) and back filling the excavated material all round the trenches including breaking clods, watering, consolidation by ramming in layers not exceeding 9 inches (229 mm) in depth to full compaction, dressing and disposal of surplus excavated stuff as directed, lead up to one chain (30.5 R.m) and lift upto 5 feet (1.52 m).	100 Cft		1902.25	One Thousand Nine Hundred Two Rupees and Twenty Five Paisas	14990
-----	--	---	------------	--	---------	--	-------

235	ASF MOQs Soakage well and septic tank-02	Providing and laying 1:4:8 (1 cement 4 sand and 8 coarse aggregate) cement concrete using crushed graded boulders 1 inch (25 mm) and down gauge in foundation including leveling, compacting and curing etc. complete	100 Cft		34306.426	Thirty Four Thousand Three Hundred Six Rupees and Forty Three Paisas	16467
236	ASF MOQs Soakage well and septic tank-03	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9" to 13-/2 inches (228 mm to 343 mm) thick including scaffolding, raking out joints and curing etc. complete in foundation, basement and plinth (foundation and basement masonry up to 5 feet (1.52 Ru.m.) depth and plinth up to 4 feet (1.2 Ru.m.) height from ground level)	100 Cft		54015.99	Fifty Four Thousand Fifteen Rupees and Ninety Nine Paisas	111273

237	ASF MOQs Soakage well and septic tank-04	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved wall 4-1/2 inches (114 mm) or less thickness including scaffolding, raking out joints and curing etc, complete in foundation, basement and plinth (foundation and basement masonry upto 5 (1.52 Ru.m.) feet depth and plinth upto 4 feet (1.2 Ru.m.) height from ground level)	100 Cft		59005.24	Fifty Nine Thousand Five Rupees and Twenty Four Paisas	18882
238	ASF MOQs Soakage well and septic tank-05	½ " (13 mm) thick cement plaster 1:4 on wall and columns etc. including making edges, corners and curing etc. complete in Ground Floor	100 Sft		6134.576	Six Thousand One Hundred Thirty Four Rupees and Fifty Eight Paisas	27606

239	ASF MOQs Soakage well and septic tank-06	Providing and laying floors of 2 inches (51 mm) thick 1:2:4 cement concrete using graded screened bajri 3/4 inch (19 mm) and down gauge in ground floor laid in panels including form work, consolidation, finishing, and curing etc. complete	100 Sft		9631.678	Nine Thousand Six Hundred Thirty One Rupees and Sixty Eight Paisas	6357
-----	--	--	------------	--	----------	--	------



240	ASF MOQs Soakage well and septic tank-07	Excavation for wells, circular underground tanks and soak spits etc., in all kinds of soil (except gravelly and murum soil, wet silt clay or mud, conglomeration of gravel and boulders, soft. sandy or disintegrated and hard rock) and back filling the excavated material all round the trenches including breaking clods, watering, consolidation by ramming in layers not exceeding 9 inches (229 mm) in depth to full compaction, dressing and disposal of surplus excavated stuff as directed, lead up to one chain (30.5 Ru.m)					
-----	--	---	--	--	--	--	--

241	i	lift up to 5 feet	100 Cft	2110.066	Two Thousand One Hundred Ten Rupees and Seven Paisas	9326
242	ii	lift up to 8 feet	100 Cft	2442.566	Two Thousand Four Hundred Forty Two Rupees and Fifty Seven Paisas	6448
243	iii	lift up to 11 feet	100 Cft	2775.066	Two Thousand Seven Hundred Seventy Five Rupees and Seven Paisas	7326

244	iv	lift up to 14 feet	100 Cft	3107.566	Three Thousand One Hundred Seven Rupees and Fifty Seven Paisas	8204
245	v	lift up to 17 feet	100 Cft	3440.066	Three Thousand Four Hundred Forty Rupees and Seven Paisas	9082
246	vi	lift up to 20 feet	100 Cft	3772.566	Three Thousand Seven Hundred Seventy Two Rupees and Fifty Seven Paisas	9960

247	vii	lift up to 23 feet	100 Cft	4105.066	Four Thousand One Hundred Five Rupees and Seven Paisas	10837
248	viii	lift up to 26 feet	100 Cft	4437.51	Four Thousand Four Hundred Thirty Seven Rupees and Fifty One Paisas	11715
249	ix	lift up to 29 feet	100 Cft	4770.01	Four Thousand Seven Hundred Seventy Rupees and One Paisa	12593

250	x	lift up to 30 feet	100 Cft	5102.51	Five Thousand One Hundred Two Rupees and Fifty One Paisas	4490
251	ASF MOQs Soakage well and septic tank-08	Providing and laying first class solid burnt brick masonry in cement mortar 1:3 wells (steining) 9 inches (229 mm) to 13-1/2 inch (343 mm) thick including scaffolding curing etc. complete				
252	i	Depth upto 10 feet	100 Cft	73238.494	Seventy Three Thousand Two Hundred Thirty Eight Rupees and Forty Nine Paisas	232898

253	ii	Depth upto 15 feet	100 Cft	75032.524	Seventy Five Thousand Thirty Two Rupees and Fifty Two Paisas	118551
254	iii	Depth upto 20 feet	100 Cft	76826.554	Seventy Six Thousand Eight Hundred Twenty Six Rupees and Fifty Five Paisas	121386
255	iv	Depth upto 25 feet	100 Cft	78620.584	Seventy Eight Thousand Six Hundred Twenty Rupees and Fifty Eight Paisas	124221

256	v	Depth upto 30 feet	100 Cft	80414.614	Eighty Thousand Four Hundred Fourteen Rupees and Sixty One Paisas	127055
257	ASF MOQs Soakage well and septic tank-09	Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S angle iron frame, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge	P.Cft	3184.622	Three Thousand One Hundred Eighty Four Rupees and Sixty Two Paisas	159231


258	ASF MOQs Soakage well and septic tank-10	Providing and laying reinforced cement concrete using Lawrencepur sand and crushed graded boulders 3/4 inch (19 mm) and down gauge in place of screened graded bajri in any item of RCC of mix not leaner than 1:2:4 crushing strength of works cube in this case will be 3000 lbs. per sq. inch (20.69 N/mm ² at 28 days) with a mix not leaner than 1:2:4 in curved beams, lintels and cantilever beams of required shape or section including form work and its removal, compacting and curing etc, complete but excluding the cost of reinforcement, in basement and ground floor.	100 Cft		74270.252	Seventy Four Thousand Two Hundred Seventy Rupees and Twenty Five Paisas	47533
-----	--	---	------------	--	-----------	---	-------

259	ASF MOQs Soakage well and septic tank-11	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work in foundation, basement, plinth and ground floor of building including septic tanks and under ground tanks and in projections for future extension	P.Kg		395.43	Three Hundred Ninety Five Rupees and Forty Three Paisas	63269
-----	--	---	------	--	--------	--	-------

260	ASF MOQs Soakage well and septic tank-12	P/L Brick bats 3 inch and down gauge in soakage pit including cartage, wastage, etc complete as per direction of the Engineer Incharge	P.Cft		102	One Hundred Two Rupees	46104
261	ASF JS Apartments Building Works-01	Excavation for raft foundations, underground tanks and septic tanks (rectangular or square) in all kinds of soil and back filling the excavated material all round the trenches including breaking clods, watering, consolidation by ramming in layers not exceeding 9 inches in depth to full compaction, dressing and disposal of surplus excavated stuff as directed, lead up to one chain and lift upto 5 feet	100 Cft		1902.25	One Thousand Nine Hundred Two Rupees and Twenty Three Paisas	331410

262	ASF JS Apartments Building Works-02	Cartage of sand, bajri, lime, surkhi, murum, manure, earth & building rubbish including loading, unloading and stacking etc at site dispose off (by mechanical means) beyond 2 miles (3.2 Km) lead.	100 Cft	676.718	Six Hundred Seventy Six Rupees and Seventy Two Paisas	117898
263	ASF JS Apartments Building Works-03	Providing & carrying out termite proofing in foundation. Under floos and wood work surface with a soloution using of confront TC with water and spraying the solutio of the area to be treated as completed as per direction of Engineer incharge	P.Sft.	18.382	Eighteen Rupees and Thirty Eight Paisas	80072

264	ASF JS Apartments Building Works-04	Providing and laying 1:4:8 (1 cement 4 sand and 8 coarse aggregate) cement concrete using crushed graded boulders 1 inch and down gauge in foundation including levelling, compacting and curing etc.complete.	100 Cft		34306.426	Thirty Four Thousand Three Hundred Six Rupees and Forty Three Paisas	392809
-----	--	--	------------	--	-----------	--	--------



265	ASF JS Apartments Building Works-05	Providing and laying reinforced cement concrete using crushed graded boulder 3/4 inch (19 mm) and down gauge and lawrencepur sand having a minimum works cube crushing strength of 3750 lbs. per sq inch (23.24 N/mm ²) at 28 days with a mix not leaner than 1:1- 1/2:3 in raft or strip foundation with columns and pillars, of any shape including form work and its removal, compacting, leveling and curing etc. complete but excluding the cost of reinforcement, in foundation basement and plinth.	100 Cft		54298.006	Fifty Four Thousand Two Hundred Ninety Eight Rupees and One Paisa	4139137
-----	--	--	------------	--	-----------	--	---------

266	ASF JS Apartments Building Works-06	--do-- but in columns of square shape of regular section in foundation basement and plinth	100 Cft	66501.764	Sixty Six Thousand Five Hundred One Rupees and Seventy Six Paisas	135664
267	ASF JS Apartments Building Works-07	--do-- but in plinth beams of required shape and design in foundation basement and plinth	100 Cft	64324.274	Sixty Four Thousand Three Hundred Twenty Four Rupees and Twenty Seven Paisas	345421
268	ASF JS Apartments Building Works-08	--do-- but in columns of square shape of regular section in the ground floor	100 Cft	81591.034	Eighty One Thousand Five Hundred Ninety One Rupees and Three Paisas	416114

269	ASF JS Apartments Building Works-09	--do-- but in columns of square shape of regular section in the 1st floor	100 Cft	85527.078	Eighty Five Thousand Five Hundred Twenty Seven Rupees and Eight Paisas	436188
270	ASF JS Apartments Building Works-10	--do-- but in columns of square shape of regular section in the 2nd floor	100 Cft	88621.904	Eighty Eight Thousand Six Hundred Twenty One Rupees and Ninety Paisas	451972
271	ASF JS Apartments Building Works-11	--do-- but in columns of square shape of regular section in the 3rd floor	100 Cft	91716.73	Ninety One Thousand Seven Hundred Sixteen Rupees and Seventy Three Paisas	467755

272	ASF JS Apartments Building Works-12	--do-- but in columns of square shape of regular section in the 4th floor	100 Cft		94811.556	Ninety Four Thousand Eight Hundred Eleven Rupees and Fifty Six Paisas	42665
273	ASF JS Apartments Building Works-13	--do-- but in Straight beams, Lintols, cantilever beams of required shape and section in basement and ground floor	100 Cft		74064.942	Seventy Four Thousand Sixty Four Rupees and Ninety Four Paisas	997655
274	ASF JS Apartments Building Works-14	--do-- but in Straight beams, Lintols, cantilever beams of required shape and section in the 1st floor	100 Cft		78000.986	Seventy Eight Thousand Rupees and Ninety Nine Paisas	1050673

275	ASF JS Apartments Building Works-15	--do-- but in Straight beams, Lintols, cantilever beams of required shape and section in the 2nd floor	100 Cft		81095.812	Eighty One Thousand Ninety Five Rupees and Eighty One Paisas	1092361
276	ASF JS Apartments Building Works-16	--do-- but in Straight beams, Lintols, cantilever beams of required shape and section in the 3rd floor	100 Cft		84190.638	Eighty Four Thousand One Hundred Ninety Rupees and Sixty Four Paisas	1134048
277	ASF JS Apartments Building Works-17	--do-- but in Straight beams, Lintols, cantilever beams of required shape and section in the 4th floor	100 Cft		87285.464	Eighty Seven Thousand Two Hundred Eighty Five Rupees and Forty Six Paisas	254874

278	ASF JS Apartments Building Works-18	--do-- but in ordinary slab 5 inches to 6 inches thick in basement plinth and ground floor	100 Cft		71634.374	Seventy One Thousand Six Hundred Thirty Four Rupees and Thirty Seven Paisas	1124660
279	ASF JS Apartments Building Works-19	--do-- but in ordinary slab 5 inches to 6 inches thick in the 1st floor	100 Cft		96899.712	Ninety Six Thousand Eight Hundred Ninety Nine Rupees and Seventy One Paisas	1521325
280	ASF JS Apartments Building Works-20	--do-- but in ordinary slab 5 inches to 6 inches thick in the 2nd floor	100 Cft		99994.538	Ninety Nine Thousand Nine Hundred Ninety Four Rupees and Fifty Four Paisas	1569914

281	ASF JS Apartments Building Works-21	--do-- but in ordinary slab 5 inches to 6 inches thick in the 3rd floor	100 Cft		103089.364	One Lakh Three Thousand Eighty Nine Rupees and Thirty Six Paisas	1618503
282	ASF JS Apartments Building Works-22	--do-- but in ordinary slab 5 inches to 6 inches thick in the 4th floor	100 Cft		106184.19	One Lakh Six Thousand One Hundred Eighty Four Rupees and Nineteen Paisas	208121
283	ASF JS Apartments Building Works-23	--do-- but in straight stair and landings in basement plinth and ground floor	100 Cft		88774.938	Eighty Eight Thousand Seven Hundred Seventy Four Rupees and Ninety Four Paisas	113632

284	ASF JS Apartments Building Works-24	--do-- but in straight stair and landingsin the 1st floor	100 Cft		92710.982	Ninety Two Thousand Seven Hundred Ten Rupees and Ninety Eight Paisas	118670
285	ASF JS Apartments Building Works-25	--do-- but in straight stair and landingsin the 2nd floor	100 Cft		95805.808	Ninety Five Thousand Eight Hundred Five Rupees and Eighty One Paisas	122631
286	ASF JS Apartments Building Works-26	--do-- but in straight stair and landingsin the 3rd floor (P.No.181/50+195/134+195/137+195/143+188/92+2x189/93)	100 Cft		98900.634	Ninety Eight Thousand Nine Hundred Rupees and Sixty Three Paisas	126593

287	ASF JS Apartments Building Works-27	--do-- but in ordinary cantilevered slab, sunshade or chajja 3 inches to less than 5 inches thick in basement plinth and ground floor	100 Cft		78451.898	Seventy Eight Thousand Four Hundred Fifty One Rupees and Ninety Paisas	1231695
288	ASF JS Apartments Building Works-28	--do-- but in ordinary cantilevered slab, sunshade or chajja 3 inches to less than 5 inches thick in the 1st floor	100 Cft		82387.942	Eighty Two Thousand Three Hundred Eighty Seven Rupees and Ninety Four Paisas	50257
289	ASF JS Apartments Building Works-29	--do-- but in ordinary cantilevered slab, sunshade or chajja 3 inches to less than 5 inches thick in the 2nd floor	100 Cft		85482.768	Eighty Five Thousand Four Hundred Eighty Two Rupees and Seventy Seven Paisas	167546

290	ASF JS Apartments Building Works-30	--do-- but in ordinary cantilevered slab, sunshade or chajja 3 inches to less than 5 inches thick in the 3rd floor	100 Cft	88577.594	Eighty Eight Thousand Five Hundred Seventy Seven Rupees and Fifty Nine Paisas	42517
291	ASF JS Apartments Building Works-31	--do-- but in ordinary cantilevered slab, sunshade or chajja 3 inches to less than 5 inches thick in the 4th floor	100 Cft	91672.42	Ninety One Thousand Six Hundred Seventy Two Rupees and Forty Two Paisas	117341

292	ASF JS Apartments Building Works-32	Providing and laying hard grade ribbed deformed (minimum yield point 60,000 psi) reinforcement bars with & including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement concrete 1:2:4 precast or m.s. chairs, tying with binding wire, cost of chairs and wires etc. in all kinds of RCC work including septic tanks and under ground tanks and in projections for future extension in Foundation, plinth and ground floor.	Kg		395.43	Three Hundred Ninety Five Rupees and Forty Three Paisas	15048089
293	ASF JS Apartments Building Works-33	--do-- but Reinforcement bars Gde-60 in 1st floor	Kg		401.646	Four Hundred One Rupees and Sixty Five Paisas	4563100

294	ASF JS Apartments Building Works-34	--do-- but Reinforcement bars Gde-60 in 2nd floor	Kg		407.862	Four Hundred Seven Rupees and Eighty Six Paisas	4633720
295	ASF JS Apartments Building Works-35	--do-- but Reinforcement bars Gde-60 in 3rd floor	Kg		414.078	Four Hundred Fourteen Rupees and Eight Paisas	4704340
296	ASF JS Apartments Building Works-36	--do-- but Reinforcement bars Gde-60 in 4th floor	Kg		420.294	Four Hundred Twenty Rupees and Twenty Nine Paisas	770399

297	ASF JS Apartments Building Works-37	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9" to 13-2 inches (228 mm to 343 mm) thick including scaffolding, raking out joints and curing etc. complete in foundation, basement and plinth (foundation and basement masonry up to 5 feet (1.52 Ru.m.) depth and plinth up to 4 feet (1.2 Ru.m.) height from ground level) .	100 Cft		54015.99	Fifty Four Thousand Fifteen Rupees and Ninety Nine Paisas	207421
-----	--	--	------------	--	----------	--	--------

298	ASF JS Apartments Building Works-38	Providing and laying first class solid burnt brick masonry set in cement mortar 1:6 in straight or curved walls 9 to 13-1/2 inches (229 mm to 343 mm) thick including scaffolding, raking, out joints and curing etc. complete in superstructure in Ground Floor	100 Cft		57765.358	Fifty Seven Thousand Seven Hundred Sixty Five Rupees and Thirty Six Paisas	1172059
299	ASF JS Apartments Building Works-39	--do-- but class solid burnt brick masonry in the 1st floor	100 Cft		61042.884	Sixty One Thousand Forty Two Rupees and Eighty Eight Paisas	1238560
300	ASF JS Apartments Building Works-40	--do-- but class solid burnt brick masonry in the 2nd floor	100 Cft		63637.784	Sixty Three Thousand Six Hundred Thirty Seven Rupees and Seventy Eight Paisas	1291211

301	ASF JS Apartments Building Works-41	--do-- but class solid burnt brick masonry in the 3rd floor	100 Cft		66232.684	Sixty Six Thousand Two Hundred Thirty Two Rupees and Sixty Eight Paisas	1343861
302	ASF JS Apartments Building Works-42	--do-- but class solid burnt brick masonry in the 4th floor	100 Cft		68827.584	Sixty Eight Thousand Eight Hundred Twenty Seven Rupees and Fifty Eight Paisas	355150

303	ASF JS Apartments Building Works-43	Providing and laying gola 3" x 3" size wrth lime surkhi concrete 1:2:4 (1 lime, 2 surkhi and 4 brick ballast) with 1" (25 mm) and down gauge brick ballast at the junction of roof slab and walls and finished with lime surkhi plaster 1:2 including curing etc., complete	100 Rft		3198.832	Three Thousand One Hundred Ninety Eight Rupees and Eighty Three Paisas	16506
304	ASF JS Apartments Building Works-44	Providing & laying of Aluminium foil 4mm thick Ezogrip of approved quality i/c the cost of clearing roof , cartage, wastage etc completed as per direction of Engineer incharge in any height in any floor	P-Sft		207.382	Two Hundred Seven Rupees and Thirty Eight Paisas	651179

305	ASF JS Apartments Building Works-45	1/4" thick cement plaster 1:4 on soffits of ceiling, cantilever slabs, sides and soffits of beams etc., in basement, mezzanine and ground floor including making edges, corners and curing etc., complete.	100 Sft.	5393.626	Five Thousand Three Hundred Ninety Three Rupees and Sixty Three Paisas	165692
306	ASF JS Apartments Building Works-46	---- do --- but ceiling polaster on 1st Floor	100 Sft.	5824.126	Five Thousand Eight Hundred Twenty Four Rupees and Thirteen Paisas	178917
307	ASF JS Apartments Building Works-47	---- do --- but ceiling polaster on 2nd Floor	100 Sft.	6254.626	Six Thousand Two Hundred Fifty Four Rupees and Sixty Three Paisas	192142

308	ASF JS Apartments Building Works-48	---- do --- but ceiling polaster on 3rd Floor	100 Sft.	6685.126	Six Thousand Six Hundred Eighty Five Rupees and Thirteen Paisas	205367
309	ASF JS Apartments Building Works-49	---- do --- but ceiling polaster on 4th Floor	100 Sft.	7115.626	Seven Thousand One Hundred Fifteen Rupees and Sixty Three Paisas	11172
310	ASF JS Apartments Building Works-50	1/2" thick cement plaster 1:4 on walls and columns etc. in basement, plinth, mezzanine and ground floor including making edges, corners, and curing etc., complete.	100 Sft.	6134.576	Six Thousand One Hundred Thirty Four Rupees and Fifty Eight Paisas	874913

311	ASF JS Apartments Building Works-51	---- do --- but Wall Plaster on 1st Floor	100 Sft.	6565.076	Six Thousand Five Hundred Sixty Five Rupees and Eight Paisas	201679
312	ASF JS Apartments Building Works-52	---- do --- but Wall Plaster on 2nd Floor	100 Sft.	6995.576	Six Thousand Nine Hundred Ninety Five Rupees and Fifty Eight Paisas	10983
313	ASF JS Apartments Building Works-53	---- do --- but Wall Plaster on 3rd Floor	100 Sft.	7426.076	Seven Thousand Four Hundred Twenty Six Rupees and Eight Paisas	163374
314	ASF JS Apartments Building Works-54	---- do --- but Wall Plaster on 4th Floor	100 Sft.	7856.576	Seven Thousand Eight Hundred Fifty Six Rupees and Fifty Eight Paisas	48397


315	ASF JS Apartments Building Works-55	Providing and fixing M.S. molded steel door frames of 5.73" x 2-1/2" (146 mm x 63 mm) manufactured from mild steel sheet of 18 gauge (1.41 mm) conforming to B.S.S. 1245 having a double rebate size 1-1/2" x 1/2" (38 mm x 12 mm) provision of 3 Nos. M.S. plate, section 1- 1/2" x 1/4" (38 mm x 6 mm) (2 Nos. 6 inch long welded with frame at not less than 10 points and 1 Nos. 12 inch long welded with frame at not less than 20 points), with holes and threads for fixing steel hinges, fitted with one locking box of same sheet (point welded inside the frame), 6 Nos. 6 inches long flat iron fixing lugs of 1-1/4" x 3/16" section, treated with special red oxide primer coat all around including cutting holes and filling the cavity with cement concrete 1:1:2 etc. in any floor at any height complete as directed by the Engineering Officer.	P.Rft		657.72	Six Hundred Fifty Seven Rupees and Seventy Two Paisas	1289131
-----	--	--	-------	--	--------	---	---------

316	ASF JS Apartments Building Works-56	Supplying stacking and filling sand of approved quality from outside sources in foundation, trenches, plinth or under floor, etc. including dressing, watering and consolidation by ramming in layers not exceeding 9 inches in depth to full compaction and lift upto 5 feet.	100 Cft.		6817.916	Six Thousand Eight Hundred Seventeen Rupees and Ninety Two Paisas	318192
317	ASF JS Apartments Building Works-57	Providing and laying 1:4:8 cement concrete bed under floors using graded stone ballast 2 inches and down gauge with levelling and ramming, watering and curing etc. complete.	100 Cft		30851.45	Thirty Thousand Eight Hundred Fifty One Rupees and Forty Five Paisas	535890

318	ASF JS Apartments Building Works-58	Providing and laying in situ 1:2:4 (1 cement 2 sand and 4 coarse aggregate) cement concrete using crushed graded boulders 3/4 inch (19 mm) and down gauge in foundation, basement and plinth including form work, compacting, curing and removal of form work etc. complete, foundation and basement up to 5 feet depth (1.52 m) and plinth up to 4 feet (1.2 m) height from ground level .	100 Cft.		54057.08	Fifty Four Thousand Fifty Seven Rupees and Eight Paisas	98924
-----	-------------------------------------	---	----------	--	----------	---	-------

319	ASF JS Apartments Building Works-59	Providing and laying light colour, glazed/non skid vitrified porcelean tiles (Polished) not exceeding 1600 Sqcm and upto 3600 each, (Pak made) on walls and floors, in any floor, laid with dry bond (stile bond) over a base of 1" thick cement mortar (1:3) including jointing to tiles with joint filler of approved quality as per direction of the Engineer incharge.	100 Sft		56855.036	Fifty Six Thousand Eight Hundred Fifty Five Rupees and Four Paisas	13021509
-----	--	---	------------	--	-----------	--	----------

320	ASF JS Apartments Building Works-60	P/F 12mm thick tempered glass, Swing door Pak made as per approved manufacrurers (fixing through their approved fabricators) D-Lock silicon, moving machines all accessories, cutting holes etc and making good damages erc compete as required in any floor as per direction of Engineer incharge.	Sft		3168.746	Three Thousand One Hundred Sixty Eight Rupees and Seventy Five Paisas	266175
-----	--	---	-----	--	----------	---	--------



321	ASF JS Apartments Building Works-61	P/F 12mm tempered glass fixed partition as per approved manufacrurers (fixing through their approved fabricators) i/c 3M safety film 175 micron, aluminuym section D-48 (100mm X 38mm and 233) thick i/c the aluminnum fittings and S.S pipe 1.5" X 3" (18 Guage) fixed on top with all accessories, cutting holes etc and making good damages erc compete as required in any floor as per direction of Engineer incharge.	Sft		2254.84	Two Thousand Two Hundred Fifty Four Rupees and Eighty Four Paisas	189407
-----	--	--	-----	--	---------	---	--------

322	ASF JS Apartments Building Works-62	Providing and fixing fully glazed Bronze anodized or powder coated aluminium Sliding windows as per British standard manufactured by Lucky, Alcop, Krudson, Pakistan cable and A.C.P. (fixing through their approved fabricators) deluxe model box section 95mm x 30mm and 2mm thick including the cost of aluminium netting ,fittings, with all accessories cutting hole etc. and making good damages to walls etc. complete as required in any floor as per direction of engineer-in-charge, but excluding the cost of glass pans..	Sft		1791.566	One Thousand Seven Hundred Ninety One Rupees and Fifty Seven Paisas	1891894
-----	-------------------------------------	---	-----	--	----------	---	---------

323	ASF JS Apartments Building Works-63	Providing and fixing Tinted glass panes 5mm thick to M.S. Box pipe / Aluminium doors, windows and ventilators etc including the cost of labour but excluding the cost of M.S. square pipe beading, rubber packing and screw in any floor at any height..	Sft		520.548	Five Hundred Twenty Rupees and Fifty Five Paisas	549699
324	ASF JS Apartments Building Works-64	Providing and fixing tinted or frosted glass paper with and including the cost of washing the glass with shampoo and finishing complete in all respect as directed in any floor	Sft		250	Two Hundred Fifty Rupees and Zero Paisas	570000

325	ASF JS Apartments Building Works-65	Providing and fixing Windo roll up blinds sunscreen, dark out, or translucent fabric any colour/shade best quality (imported) with manual roll up arraangements coomplete in all respect with all other required accessories and hardware from the approved suppliers and manufacturers as per direction of Engineer incharge ..	Sft		440.412	Four Hundred Forty Rupees and Forty One Paisas	465075
-----	--	---	-----	--	---------	---	--------

326	ASF JS Apartments Building Works-66	Providing and fixing 1-1/2 inches thick solid core deodar wood flushed veneered door shutters, with and including the cost of commercial plywood facing 3 mm. thick (3 ply) on both faces, fixed over best quality deodar wood frame 2 inches wide around 6 inches wide lock rail and 2nd class deodar wood solid core, i/c., 1/4 inch thick best quality deodar wood lipping on all sides as per approved drawing, manufactured under power driven hydraulic press, including the cost of approved iron fittings but excluding the cost of handles and locking arrangement..	Sft		2027.984	Two Thousand Twenty Seven Rupees and Ninety Eight Paisas	4769818
-----	--	--	-----	--	----------	--	---------

327	ASF JS Apartments Building Works-67	Providing and fixing iron grills with required section of flat iron as per approved design including welding all sides of the section at the junction, and fixing with sunk iron screws, painting two coats of red oxide paint etc. complete as required in any floor in masonry or concrete work.	Kg		455.084	Four Hundred Fifty Five Rupees and Eight Paisas	1333851
328	ASF JS Apartments Building Works-68	Providing & Fixing 2' dia stainless steel pipe (18 guage) railing alongwith 4 Nos 3/4" dia parallel pipe having S/S pipe vertical post 2" dia at 3 ft C/C average spacing and 4' dia vertical post at start turning and end point including cost of labour, welding charges fitting & fixing .completed as per direction of Engineer incharge	P.Sft		3128.132	Three Thousand One Hundred Twenty Eight Rupees and Thirteen Paisas	1107359

329	ASF JS Apartments Building Works-69	P/L 3/4 inch Granite Stone Pakistani origin Tiles more than 7 Sq. ft upto 16 Sq.ft inch size fine dressed on the surface, without winding in any floor over 1 inch cement mortar 1:2 setting the marble tile with grey cement slurry over cement mortar, jointing and washing the tiles with white cement slurry including curing, rubbing and polishing etc. complete, including the cost of mortar.	100 Sft		219860.9	Two Lakh Nineteen Thousand Eight Hundred Sixty Rupees and Ninety Paisas	492488
-----	--	---	------------	--	----------	--	--------

330	ASF JS Apartments Building Works-70	Providing and fixing kitchen wall cabinet making of shutter board box & 3/4 inch thick high gloss laminated lasani shutter, PVC beading PVC sheet backing of approved design etc, fixed with rawal plugs screws i/c cost of glue, nail, hinges, handles etc as per drwaing, completed in all respect.	P.Sft		2216.018	Two Thousand Two Hundred Sixteen Rupees and Two Paisas	620485
-----	--	--	-------	--	----------	---	--------

331	ASF JS Apartments Building Works-71	Providing and fixing kitchen wall cabinet making of shutter board box & 3/4 inch thick high gloss laminated lasani shutter, PVC beading PVC beading, deodar wooden fram 2.5 X 1.25 inch size making tray drawer of approved design etc, fixed with rawal plugs screws including cost of glue, nail, hinges, hadles etc as per drawings, complete in al respect.	P.Sft		2173.43	Two Thousand One Hundred Seventy Three Rupees and Forty Three Paisas	730272
-----	--	---	-------	--	---------	--	--------

332	ASF JS Apartments Building Works-72	Providing and fixing approved quality stainless steel sink 33" x 18" Pak made (Atlas) complete with brass oxidized bolt kit/angle iron brackets built into walls ½" dia CP sink mixer 1-1/4" rubber plug and CP brass chain 1-1/4" CP brass waste 1-1/4" dia malleable iron or CP brass bottle trap with malleable iron or brass unions and making requisite number of holes in walls, plinth and floor for pipe connections and making good in cement concrete 1:2:4	P- Each		23093	Twenty Three Thousand Ninety Three Rupees and Zero Paisas	369488
-----	--	--	------------	--	-------	---	--------

333	ASF JS Apartments Building Works-73	Providing & Fixing ward robe 24" deep consisting 19mm thick laminated sheet on bottom, top -sides partition, shelves & Shutters etc and 4mm thick pressed on back side, 2-1/2" X 1-1/4" best quality deodar wood frame and all open edge filled 3/4" molding PVC gola complete i/c the cost of glue iron nails screws, heavy type piano hinges 1/2" handle, catchers locks etc, complete in all respect as per direction of Engineer incharge.	P.Sft		1805.636	One Thousand Eight Hundred Five Rupees and Sixty Four Paisas	3177919
-----	-------------------------------------	--	-------	--	----------	--	---------

334	ASF JS Apartments Building Works-74	Providing and fixing with brass screws or specially supplied screws hydraulic door closer of approved design No. 5002, Japan make, cutting wood etc., to required shape and size as per direction of the engineer-in-charge	P- Each		13238.75	Thirteen Thousand Two Hundred Thirty Eight Rupees and Seventy Five Paisas	211820
335	ASF JS Apartments Building Works-75	Providing and fixing with C.P. brass screws main door handle type yale lock (Italy make) of approved design, cutting wood etc., to required size, with two operating keys, as per direction of the engineer-in-Charge.	P- Each		13859.132	Thirteen Thousand Eight Hundred Fifty Nine Rupees and Thirteen Paisas	1566082

336	ASF JS Apartments Building Works-76	Providing and fixing 4" (100 mm) dia polyvinyle chloride rain water (PVC) down pipe with mild steel clamps, bolts and nuts fixed in cement concrete 1;2:4 etc. complete ...	P-Rft		1006.138	One Thousand Six Rupees and Fourteen Paisas	201228
337	ASF JS Apartments Building Works-77	Providing and fixing 4" (100 mm) dia polyvinyle chloride (PVC) bend of any degree for rain water down pipe with clamps, bolts and nuts in cement concrete 1:2:4 etc. complete..	P- Each		2447.382	Two Thousand Four Hundred Forty Seven Rupees and Thirty Eight Paisas	19579
338	ASF JS Apartments Building Works-78	Painting with (ICI) Dulux plastic emulsion paint VIP of approved shade two coats over and including the cost of one priming coat complete over plastered surface at any height in any floor.	100 Sft.		9432.332	Nine Thousand Four Hundred Thirty Two Rupees and Thirty Three Paisas	5539231

339	ASF JS Apartments Building Works-79	Painting three coats with weather shield paint deluxe (ICI) make of approved shade on plaster surface (External) and including the cost of cleaning the surface, sand papering etc. complete at any height in any floor.	100 Sft.	6172.25	Six Thousand One Hundred Seventy Two Rupees and Twenty Five Paisas	515074
340	ASF JS Apartments Building Works-80	Painting wood work with synthetic enamel paint of approved make and shade two coats over and including the cost of one priming coat complete at any height in any floor .	100 Sft.	8336.804	Eight Thousand Three Hundred Thirty Six Rupees and Eighty Paisas	441184
341	ASF JS Apartments sanitary works-01	Making connection with the existing G.I. pipe upto 2 inches dia including cutting the pipe and providing and fixing necessary fittings.	Each	2181.9	Two Thousand One Hundred Eighty One Rupees and Ninety Paisas	2182

342	ASF JS Apartments sanitary works-02	P/F 1-1/2" Ø uPVC pipe "D" class and specials etc. including cutting and fitting complete with and including the cost of cutting trench upto 1-1/2 feet deep refilling, watering, ramming, and disposal of surplus earth within one chain and after cleaning the pipe and cartage within 10 miles (16.09 km.) (working pressure 12 kg/cm2)	Rft		204.358	Two Hundred Four Rupees and Thirty Six Paisas	191075
343	ASF JS Apartments sanitary works-03	P/F 1" Ø uPVC Pipe "E" class with specials and clamps etc., including cutting and fitting, complete with and including the cost of breaking through walls and roof and making good etc.; after cleaning the pipe and cartage within 10 miles (working pressure 12 kg/cm2).	Rft		144.788	One Hundred Forty Four Rupees and Seventy Nine Paisas	63707

344	ASF JS Apartments sanitary works-04	--do-- but 3/4" Ø uPVC E Class pipe	Rft		135.632	One Hundred Thirty Five Rupees and Sixty Three Paisas	43402
345	ASF JS Apartments sanitary works-05	P/F of 1-1/2 inch dia ball valve (with PVC Ball) made to B.S.S. 1212.	Each		1220.24	One Thousand Two Hundred Twenty Rupees and Twenty Four Paisas	1220
346	ASF JS Apartments sanitary works-06	--do-- but 1" Ø Ball Valve	Each		985.18	Nine Hundred Eighty Five Rupees and Eighteen Paisas	7881

347	ASF JS Apartments sanitary works-07	Providing and fixing Pakistani best quality European style white glazed earthenware W.,C pan complete with and including the cost of plastic seat and buffers, 13.6 litres flushing cistern with internal fittings complete, P.V.C flushing pipe with fittings and making requisite number of holes in walls, plinth and floor for pipe connections and making good in cement concrete 1:2:4.	Each		20037.5	Twenty Thousand Thirty Seven Rupees and Fifty Paisas	320600
-----	--	---	------	--	---------	--	--------


348	ASF JS Apartments sanitary works-08	Providing and fixing squatting type W.C.Pan in white vitreous china with integral treads (Pakistani) orissa pattern and uPVC. trap 100mm dia. Complete with and including the cost of 13.6 litres best quality low level plastic flushing cistern with internal fittings complete, P.V.C. flushing pipe suitable for this type with fittings and making requisite number of holes in walls, plinth & floor for pipe connections and making good in cement concrete 1:2:4.	Each		17118.5	Seventeen Thousand One Hundred Eighteen Rupees and Fifty Paisas	273896
-----	--	--	------	--	---------	--	--------

349	ASF JS Apartments sanitary works-09	P/F of 22 inches x 16 inches (560 x 406 mm) lavatory basin in white glazed earthenware (Pakistani) complete with and including the cost of glazed earthenware half pedestal, Brass oxidized bolts kit built into walls 1/2 inches dia. Chrome plated mixer, 1-1/4 inches rubber plug and chrome plated brass chain 1-1/4 inches dia brass waste of approved pattern 1-1/4 inches dia chromium plated battal trap with unions and making requisite, number of holes in walls, plinth and floor for pip.e connections and making good in cement concrete 1:2:4.	Each		21253.75	Twenty One Thousand Two Hundred Fifty Three Rupees and Seventy Five Paisas	680120
-----	--	---	------	--	----------	--	--------

350	ASF JS Apartments sanitary works-10	Providing & fixing chromium plated Muslim bib-cock with Muslim Shower of approved quality.	Each	4734.45	Four Thousand Seven Hundred Thirty Four Rupees and Forty Five Paisas	151502
351	ASF JS Apartments sanitary works-11	Providing and fixing 1/2 inches dia. (15 mm) CP Bib cocks.	Each	1582.56	One Thousand Five Hundred Eighty Two Rupees and Fifty Six Paisas	25321
352	ASF JS Apartments sanitary works-12	P/F of 1/2 inch dia CP stop cocks/ Tee Stop Cock (Master / Faisal etc.) as directed	Each	1722.56	One Thousand Seven Hundred Twenty Two Rupees and Fifty Six Paisas	82683

353	ASF JS Apartments sanitary works-13	Providing and fixing 24 inches x 18 inches (610 mm x 457 mm) looking mirror of Imported glass 5 mm thick fixing with CP clamps and screws	Each	3043.572	Three Thousand Forty Three Rupees and Fifty Seven Paisas	97394
354	ASF JS Apartments sanitary works-14	P/F bath room accessories of set of 6 pieces consist of one shelf, one towel rod with bracket, one towel ring, one soap dish, one tooth Brush holder with glass, one tissue paper holder one double hook etc complete of approved quality as per direction of Engineer in-charge.	Each	16537.5	Sixteen Thousand Five Hundred Thirty Seven Rupees and Fifty Paisas	529200
355	ASF JS Apartments sanitary works-15	Providing and fixing uPVC Multi floor trape of sizes with gratings including cutting and makeing the requisite number of holes in walls plinth and floors and making good in 1:2:4, C.C.	Each	2043.202	Two Thousand Forty Three Rupees and Twenty Paisas	98074

356	ASF JS Apartments sanitary works-16	P/F 4" dia (u.P.V.C) "E" class pipe with specials and clamps etc., including cutting and fitting, complete with and including the cost of breaking through walls and roof and making good etc.; after cleaning the pipe and cartage within 10 miles (working pressure 12 kg/cm2).	Rft		1006.768	One Thousand Six Rupees and Seventy Seven Paisas	579898
-----	-------------------------------------	---	-----	--	----------	--	--------



357	ASF JS Apartments sanitary works-17	Providing and fixing 6" x 6" (150 mm x 150 mm) with 4 inches (100 mm) outlet cement concrete C.I. gully trap wt: 42 lbs. (19 kg.) complete with 4 inches thick (100 mm) 1:2:4 cement concrete for bed and kerb, 1/2 inch (13 mm) thick cement plaster (1:3) to the kerb, C.I. grating 6 inches x 6 inches (150 mm x 150 mm) and C.I. cover and frame 12 inches x 12 inches (305 mm x 305 mm) (inside) etc., complete....	Each		5794.6	Five Thousand Seven Hundred Ninety Four Rupees and Sixty Paisas	23178
-----	-------------------------------------	--	------	--	--------	---	-------

358	ASF JS Apartments sanitary works-18	Providing manhole type 'A' size 2 feet x 1-1/2 feet) (inside dimensions) x 2 feet (610 mm) deep as per approved design and specifications complete for 4 inches to 12 inches dia pipes up to 3 feet-11 inches depth with cast iron cover and frame 16 inches dia, inside (weight=1 Cwt.1 Qtr.) or 63.5 kg. fixed in 4 inches thick RCC 1:2:4 slab, 8 inches thick c.c. 1:3:6 block masonry walls set in 1:3 c.m; 6 inches thick 1:3:6 c.c. in foundation 1:2:4 c.c. in benching, 1/2 inches thick cement plaster in 1:3 C.M. to all inside wall surface, channels and benching etc. and to top including making requisite umber of main and branch channels but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	Each		14864.486	Fourteen Thousand Eight Hundred Sixty Four Rupees and Forty Nine Paisas	193238
-----	-------------------------------------	--	------	--	-----------	---	--------

359	ASF JS Apartments sanitary works-19	Add for extra depth beyond 2 feet and up to 3 feet-11 inches (610 mm and up to 1194 mm) for 'A' type manholes (for depth lesser than 2 feet or 610 mm deduct at the same rate)...	P-Inch		280.224	Two Hundred Eighty Rupees and Twenty Two Paisas	65572
360	ASF JS Apartments sanitary works-20	Providing 12" Ø RCC pipes and collars of class 'A' and fixing in trench including cutting, fitting and jointing with maxphalt composition and cement mortar (1:1) and testing with water to a head of 4 feet (1.22 m) above the top of the highest pipe including cartage within 10 miles	Rft		595.112	Five Hundred Ninety Five Rupees and Eleven Paisas	524889

361	ASF JS Apartments sanitary works-21	Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and .making the required channel etc., complete	Each		1050	One Thousand Fifty Rupees and Zero Paisas	1050
362	ASF JS Apartments sanitary works-22	Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	Cft		3184.622	Three Thousand One Hundred Eighty Four Rupees and Sixty Two Paisas	41400

363	E/M Works-01	Wiring for sub-main with 2X4mm ² , PVC insulated wire 300/500 volts grade, single core, stranded copper conductor wire in 20 mm(3/4") dia UPVC conduit recessed in the wall, column and roof etc including 1.5 mm ² PVC insulated wire single core wire as ECC as required .	Per Rm	640	Six Hundred Forty Rupees Only	2048000
364	E/M Works-02	Providing & fixing 15 Amps Polycarbonate flame retardant 3-pin switch socket unit (Universal) with fancy gang plate fixed on die fabricated, powder coated metal board recessed in wall or column including connection as required. (Schneider / Philips)	Per Jobs	1290	One Thousand Two Hundred Ninety Rupees Only	412800

365	E/M Works-03	Wiring for sub-main with 2X6mm ² , PVC insulated wire 300/500 volts grade, single core, stranded copper conductor wire in 25 mm(1") dia UPVC conduit recessed in the wall, column and roof etc including 2.5 mm ² PVC insulated wire single core wire as ECC as required .	Per Rm	805	Eight Hundred Five Rupees Only	1449000
366	E/M Works-04	Providing & fixing flush type 20 Amps porcelain base 3 pin combine switch and socket unit, fitted on existing / given all kind of sheet or board including connection as required.	Per Jobs	486	Four Hundred Eighty-six Rupees Only	43740

367	E/M Works-05	Wiring for sub-main with 2X2.5mm ² , PVC insulated wire 300/500 volts grade, single core, stranded copper conductor wire in 20 mm(3/4") dia UPVC conduit recessed in the wall, column and roof etc including 1.5 mm ² PVC insulated wire single core wire as ECC as required .	Per Rm	449	Four Hundred Fourty Nine Rupees Only	9698400
368	E/M Works-06	Providing & fixing 13 Amps Polycarbonate flame retardant 3-pin switch socket unit (Universal) with fancy gang plate fixed on die fabricated, powder coated metal board recessed in wall or column including connection as required. (Schneider / Philips)	Per Jobs	1120	OneThousand One Hundred Twenty Rupees Only	1209600

369	E/M Works-07	Providing & installing 140 Cm (56") sweep ceiling fan with blades, canopy, standard length of down rod including connection with 14.0076" flexible wire complete as required.	Per Jobs	9349	Nine Thousand Three Hundred Fourty Nine Rupees Only	4786688
370	E/M Works-08	Providing & fixing Polycarbonate flame retardant, fan dimmer with plate fixed on die fabricated, powder coated, metal board recessed in the wall or column including connection as required. (Schneider / Philips)	Per Jobs	1197	One Thousand One Hundred Ninety Seven Rupees Only	612864
371	E/M Works-09	Providing & installing 30 Cm (12") sweep, Plastic body Exhaust fan complete with blades, motor, etc fixed in existing hole including connection with 14/.0076" flexible wire complete as required.	Per Jobs	4672	Four Thousand Six Hundred Seventy Two Rupees Only	981120

372	E/M Works-10	Providing, Installation, Testing & Commissioning of recessed / surface mounted ceiling lights / downlights including driver, having warm / neutralwhite / cool white colour, 11-13 watt, 80-90lm/watts efficiency, 0.9 or above power factor, 20000-25000 hours lifecycle, including connection, complete in all respect as approved by the Engineer Incharge. (PHILIPS/SIGNIFY, OSRAM, GE, Thorn)	Per Jobs	2737	Two Thousand Seven Hundred Thirty Seven Rupees Only	5118190
-----	--------------	---	----------	------	---	---------

373	E/M Works-11	Providing, Installation, Testing & Commissioning of recessed / surface mounted ceiling lights / downlights including driver, having warm / neutralwhite / cool white colour, 16-18 watt, 80-90lm/watts efficiency, 0.9 or above power factor, 20000-25000 hours lifecycle, including connection, complete in all respect as approved by the Engineer Incharge. (PHILIPS/SIGNIFY, OSRAM, GE, Thorn)	Per Jobs	3848	Three Thousand Eight Hundred Forty Eight Rupees Only	1924000
-----	--------------	---	----------	------	--	---------

374	E/M Works-12	Providing & fixing 10 Amps Polycarbonate flame retardant S.P switch with fancy required gang plate fixed on die fabricated, powder coated metal board recessed in wall or column including connection as required. (Schneider / Philips)	Per Jobs	471	Four Hundred Seventy One Rupees Only	1177500
375	E/M Works-13	Providing, Installation, Testing & Commissioning of 180- 200 Watts Flood Lights (IP66) including driver, having neutral white / cool white colour, 90 - 110 lm/watts efficiency, 0.9 or above power factor, 20000-25000 hours life cycle, including connection, complete in all respect as approved by the Engineer Incharge. (PHILIPS/SIGNIFY, OSRAM, GE, Thorn)	Per Jobs	51377	Fifty-one Thousand Three Hundred Seventy-seven Rupees Only	3288128

376	E/M Works-14	Wiring for light, or fan point with 1.5 mm ² single core, PVC insulated wire copper conductor wire in 20 mm (3/4")dia uPVC conduit recessed in the wall or column, roof etc. including 1mm ² single core PVC insulated wire as ECC as required.	Per Points	2945	Two Thousand Nine Hundred Forty Five Rupees Only	10219150
377	E/M Works-15	Providing & fixing gas stove superior quality, Double Burner Steel Body, with railcocks i/c making connection with gasline as approved by the engineer incharge as required.	Per Jobs	9123	Nine Thousand One Hundred Twenty-three Rupees Only	583872

378	E/M Works-16	Providing and fixing Kitchen Hood superior quality with SS canopy filter front and back made up of tempered glass, powerful blower motor, LED light and manual control as approved etc complete in all respect i/c electrical connection as required.	Per Jobs		37040	Thirty-seven Thousand Forty Rupees Only	2370560
379	E/M Works-17	Providing, Installing, Testing & Commissioning of Dual Supply (Gas & Electric) 50/55 gallons Geyser, with fully automatic thermostat, complete in all respect, as approved by the Engineer Incharge.	Per Jobs		66686	Sixty-six Thousand Six Hundred Eighty-six Rupees Only	4134532

380	E/M Works-18	Providing and laying HT 11KV, 3 core, 35 mm ² , stranded copper conductor, cu tape screened PVC bedded and PVC sheathed, XLPE armoured cable, laid in the ground in a trenches complete with cable warning tiles, sand etc as per Pak. P.W.D specification as required.	Per Rm	11705	Eleven Thousand Seven Hundred Five Rupees Only	2341000
381	E/M Works-19	Providing and fixing indoor / outdoor, 3 core, 35 mm ² , 11KV, XLPE, heat shrink termination ends Kit complete in all respect as required	Per Jobs	37962	Thirty-seven Thousand Nine Hundred Sixty-two Rupees Only	227772

382	E/M Works-20	Supply, installation, testing and commissioning of complete outdoor, weather proof, KIOSK Substation comprising 1000 kVA, 11 kV to 400 V step-down transformer, 4-way 11 kV RMU, LT panel, including all protection, control wiring, cable terminations, interconnections, RCC foundations, cable trenches, earthing system (equipment and neutral earthing), accessories and all civil/electrical works required for complete and satisfactory operation, as per WAPDA standards and approval of Engineer-in-Charge.	Per Jobs		23153125	Twenty-three Million One Hundred Fifty-three Thousand One Hundred Twenty-five Rupees Only	23153125
-----	--------------	---	----------	--	----------	---	----------

383	E/M Works-21	Providing & installation 45 cm (18") sweep, metallic body exhaust fan complete with blades, motor etc fitted in exsisting hole including connection with 14/0.0076" flexible wire complete as required. Pak, royal, GFC, Younas, Millat	Per Jobs	6415	Six Thousand Four Hundred Fifteen Rupees Only	410560
384	E/M Works-22	Providing & laying 4 core, 120 mm², PVC insulated & PVC sheathed, 600/1000 volts grade with stranded copper conductor, armoured underground, L.T cable buried in the ground dully covered with sand and warning cable tiles as per Pak. P.W.D specification as required.	Per Rm	22180	Twenty-two Thousand One Hundred Eighty Rupees Only	13197100

385	E/M Works-23	Providing & laying 4 core, 50 mm ² , PVC insulated & PVC sheathed, 600/1000 volts grade with stranded copper conductor, armoured underground, L.T cable buried in the ground dully covered with sand and warning cable tiles as per Pak. P.W.D specification as required.	Per Rm	10119	Ten Thousand One Hundred Nineteen Rupees Only	5666640
386	E/M Works-24	Providing & fixing 250 to 400 Amps, (Adjustable-High Breaking Capacity) 4 Pole circuit breaker fixed on existing board, I/c inter-connection as required.	Per Jobs	91961	Ninety-one Thousand Nine Hundred Sixty-one Rupees Only	643727

387	E/M Works-25	Providing & fixing compact / cubical 16 SWG MS, water proof, DB duly powder coated size 3 ft x 4 ft, 10 inches Depth with proper locking arrangement including earthing strip and comprising of followings i/c making connection & testing on load etc, complete as reqd. 01 No - MCCB 3 Pole, 250 A, adjustable, 36KA 415VAC 01 Set - Copper Busbars (300 A) 400-600 V AC, 50-60 HZ (4 pole) 5 Nos - MCCB 3 Pole, 160 Amps, adjustable, 36KA 415VAC 04 Nos - 3 -pole Circuit breaker, 32 A 15 KA 415 VAC 10 Nos - AC single pole Circuit breaker, 16 / 20 Amps. 03 Nos. - 220 VAC Mini Digital Voltmeters The job also includes making of foundation of suitable size as per instructions / satisfaction of Engineer In-charge	Per Jobs		584625	Five Hundred Eighty-four Thousand Six Hundred Twenty-five Rupees Only	4092375
-----	--------------	--	----------	--	--------	---	---------

388	E/M Works-26	Providing & fixing compact / cubical 16 SWG MS, DB duly powder coated size 3 ft x 4 ft, 6 inches Depth, recessed in wall, with proper locking arrangement earthing strip and comprising of followings i/c making connection & testing on load etc, complete as as per instructions / satisfaction of Engineer In-charge (A/R). 01 No - AC MCCB 3 Pole, 160 Amps, adjustable, 36KA 415VAC 01 Set - Copper Busbars (300 Amps) 400-600 V AC, 50-60 HZ (4 pole) 06 Nos - AC MCCB 3 Pole, 60 Amps, 30KA 415VAC 04 Nos - AC single pole Circuit breaker, 32 Amps 415 VAC 06 Nos - AC single pole Circuit breaker, 16 / 20 Amps. 03 Nos - 220 VAC Mini Digital Voltmeters	Per Jobs		373125	Three Hundred Seventy-three Thousand One Hundred Twenty-five Rupees Only	3731250
-----	--------------	---	----------	--	--------	--	---------

389	E/M Works-27	Providing & fixing compact / cubical 16 SWG MS DB duly powder coated size 12 inches x 14 inches, 6 inches Depth, recessed in wall, with proper locking arrangement, earthing strip and comprising of followings i/c making connection & testing on load etc, complete as as per instructions / satisfaction of Engineer In-charge (A/R). 01 No - AC three pole MCB, 50 Amps 10 KA 415 VAC 8 Nos - AC single pole Circuit breaker, 16 / 20 Amps. 03 Nos - 220 VAC Mini Digital Voltmeters	Per Jobs		70625	Seventy Thousand Six Hundred Twenty-five Rupees Only	4237500
-----	--------------	--	----------	--	-------	--	---------

390	E/M Works-28	Wiring for sub-main with 4x10mm ² , PVC insulated wire 450/750 volts grade, single core, stranded copper conductor wire in 30mm (1¼") dia uPVC conduit recessed in the wall, column and roof etc including 2.5mm ² PVC insulated wire single core wire as ECC as required.	Per Rm	2610	Two Thousand Six Hundred Ten Rupees Only	2035800
391	E/M Works-29	Providing and fixing 1" diameter 3ft long lighting copper rod with five spikes and balls on its head as required.	Per Jobs	26301	Twenty-six Thousand Three Hundred One Rupees Only	368214

392	E/M Works-30	Providing and fixing Earthing set with 2'x2'x1/4" copper plate buried in the ground at a depth of 12 feet or less if water comes out from the ground level (with salt and charcoal, or Earthing chemical Powder) etc making the pit 12 feet deep by excavation of all type of soil (except soft or hard rock) i/c fixing of 8 SWG copper wire in 1/2 " G.I conduit complete in all respect as required.	Per Jobs	65762	Sixty-five Thousand Seven Hundred Sixty-two Rupees Only	1381002
					GRAND TOTAL:	Rs751,287,171.66

Scope of Work

Barracks for 192 Personnel (02 Buildings)

The project comprises 02 nos. triple storey buildings (G+2) to serve as Barracks for the ASF staff personnel (192 in each building) consisting of a frame structure (R.CC beams, columns as main load carrying members) with a raft foundation. The overall footprint covered area of the building is approximately 6770 sft (Refer to attached drawings as Annexures)

16 x MOQs (3 bed) - G+3 (02 Buildings)

The project comprises 02 nos. 04 storey buildings (G+3) to serve as apartments to house Married officers of the ASF. The structure is consisting of a frame structure (R.CC beams, columns as main load carrying members) with a raft foundation. Area of one MOQ is 2242 sft. The total covered area for 04 storeys of the building is approximately 18304 sft with the area for single floor of 4576 sft (Refer to attached drawings as Annexures)

16 x JS apartments (2 bed) - G+3 (01 Building)


The project comprises 01 nos. 4 storey building (G+3) to serve as apartments to house Junior staff of the ASF staff personnel. The structure is consisting of a frame structure (R.CC beams, columns as main load carrying members) with a raft foundation. Area of one apartment is 745 sft. The total covered area for 04 storeys of the building is approximately 13962 sft with the area for single floor of 3490 sft (Refer to attached drawings as Annexures)

Major Scope of Work:

Civil Works are mainly

- Building works mainly consisting of excavation, RCC foundation, RCC superstructure, masonry, wood and finishing works, plaster / paint works etc.
- Water supply and sanitary works including sanitary fixtures in washrooms and sewerage works of the building with allied works
- Soakage well and septic tank

E/M Works are mainly Electrical works in the building



Price Schedule

For Individual Jobs

#	Job Title	Quantity	Unit Price (PKR)	Total Price (PKR)	Delivery Location	Delivery Period / Year	Country of Origin
1							
2							

For Lots

#	Lot Title	Total Lot Price (PKR)	Country of Origin
1	[Lot 1 Title]		





General Conditions of Contract

A. General

1. Definitions

1.1. Unless the context otherwise requires, the following terms whenever used in this Contract shall have the same meaning and shall be interpreted as indicated

1.1.1. “Applicable Law” means the laws and any other instruments having the force of law in the Government’s Country, or in such other country as may be specified in the Special Conditions of the Contract (SC), as they may be issued and in force from time to time;

1.1.2. “The Contract” means an agreement enforceable by law;

1.1.3. “The Contract Price” means the price payable to the Contractor under the Contract for the full and proper performance of its contractual obligations;

1.1.4. “The Services” means the work to be performed by the Contractor pursuant to this Contract and as prescribed in the Specifications and Schedule of Activities included in the Contractor’s Bid;

1.1.5. “Ancillary Services” means those services ancillary to the provision of Services, such as transportation and insurance, and any other incidental services, such as installation, commissioning, provision of technical assistance, training, and other such obligations of the Contractor covered under the Contract;

1.1.6. “GCC” means the General Conditions of Contract contained in this section;

1.1.7. “SCC” means the Special Conditions of Contract by which the GCC may be amended or supplemented;

1.1.8. “Day” means calendar day unless indicated otherwise;

1.1.9. “Effective Date” means the date on which this Contract comes into force and effect;

1.1.10. “The Contractor” means the individual or corporate body whose Bids to provide the Services has been accepted by the Procuring Agency;

1.1.11. “The Project Site,” where applicable, means the place or places named in Bid Data Sheet and technical Specifications;

1.1.12. “Government” means the Government of Pakistan;

1.1.13. “Local Currency” means the currency of Pakistan;

1.1.14. “In Writing” means communicated in written form with proof of receipt;

1.1.15. “Completion Date” means the date of completion of the Services by the Contractor as certified by the Procuring Agency;

1.1.16. “Foreign Currency” means any currency other than the currency of the country of the Procuring Agency;

1.1.17. "Party" means the Procuring Agency or the Contractor, as the case may be, and "Parties" means both of them;

1.1.18. "Service" means any object of procurement other than goods or works;

1.1.19. "Subcontractor" means any entity to which the Bidder subcontracts any part of the Services.

2. Applicable Law

2.1. The contract shall be governed and interpreted in accordance with the laws of Pakistan, unless otherwise specified in SCC.

3. Language

3.1. The Contract as well as all correspondence and documents relating to the Contract exchanged between the Contractor and the Procuring Agency, shall be written in the **English language** unless otherwise stated in the SCC. Supporting documents and printed literature that are part of the Contract may be in another language provided these are accompanied by an accurate translation of the relevant passages in English, in which case, for purposes of interpretation of the Contract, this translation shall govern.

4. Notices

4.1. Any notice, request, or consent made pursuant to this Contract shall be in writing and shall be deemed to have been made when delivered in person to an authorized representative of the Party to whom the communication is addressed, or when sent by registered mail, telex, telegram, or facsimile to such Party at the address specified in the SCC.

5. Location

5.1. The Services shall be performed at such locations as the Procuring Agency may approve and as specified in SCC.

5.2. A {DOCUMENTS}

6. Authorized Representatives / Authority of Member in charge

6.1. Any action required or permitted to be taken, and any document required or permitted to be executed, under this Contract by the Procuring Agency or the Contractor may be taken or executed by the officials specified in the SCC.

B. Commencement, Completion, Modification, and Termination of Contract

7. Effectiveness of Contract

7.1. This Contract shall come into effect on the date the Contract is signed by both parties and such other later date as may be stated in the SCC.

8. Commencement of Services

8.1. The Contractor shall confirm availability of Key Experts and begin carrying out the Services not later than the number of days after the Effective Date specified in the SCC.

9. Program schedule

9.1. Before commencement of the Services, the Contractor shall submit to the Procuring Agency for approval a Program showing the general methods, arrangements, order and timing for all activities. The Services shall be carried out in accordance with the approved Program as updated.

10. Starting Date/Expiration Date

10.1. The Contractor shall start carrying out the Services Five (05) days after the date the Contract becomes effective, or at such other date as may be specified in the SCC.

10.2. Unless terminated earlier pursuant to Clause **GCC 14** hereof, this Contract shall expire at the end of such time period after the Effective Date as specified in the SCC.

11. Entire Agreement

11.1. This Contract contains all covenants, stipulations and provisions agreed by the Parties. No agent or representative of either Party has authority to make, and the Parties shall not be bound by or be liable for, any statement, representation, promise or agreement not set forth herein.

12. Modification

12.1. Any modification or variation of the terms and conditions of this Contract, including any modification or variation of the scope of the Services, may only be made by written agreement between the Parties. However, each Party shall give due consideration to any modification(s) or variation(s) made by the other Party.

12.2. In cases of any modification(s) or variation(s), the prior written consent of the Procuring Agency is required.

13. Force Majeure

13.1. Definition

For the purposes of this Contract, "Force Majeure" means an event which is beyond the reasonable control of a Contractor and which makes a Contractor's performance of its obligations under the Contract impossible or so impractical as to be considered impossible under the circumstances.

13.2. No Breach of Contract

The failure of a Party to fulfill any of its obligations under the contract shall not be considered to be a breach of, or default under, this Contract in so far as such inability arises from an event of Force Majeure, provided that the Party affected by such an event (a) has taken all reasonable precautions, due care and reasonable alternative

measures in order to carry out the terms and conditions of this Contract, and (b) has informed the other Party as soon as possible about the occurrence of such an event.

13.3. Extension of Time

Any period within which a Contractor shall, pursuant to this Contract, complete any action or task, shall be extended for a period equal to the time during which such Party was unable to perform such action as a result of Force Majeure.

13.4. Payments

During the period of their inability to perform the Services as a result of an event of Force Majeure, the Contractor shall be entitled to continue to be paid under the terms of this Contract, as well as to be reimbursed for additional costs reasonably and necessarily incurred by them during such period for the purposes of the Services and in reactivating the Service after the end of such period.

14. Termination

14.1. By the Procuring Agency

The Procuring Agency may terminate this Contract in case of the occurrence of any of the events specified in paragraphs (a) through (e) of this Clause. In such an occurrence the Procuring Agency shall give at least thirty (30) calendar days' written notice of termination to the Contractor in case of the events referred to in (a) through (d); at least sixty (60) calendar days' written notice in case of the event referred to in (e);

14.1.1. If the Contractor fails to remedy a failure in the performance of its obligations hereunder, as specified in a notice of suspension;

14.1.2. If the Contractor becomes (or, if the Contractor consists of more than one entity, if any of its members becomes) insolvent or bankrupt or enter into any agreements with their creditors for relief of debt or take advantage of any law for the benefit of debtors or go into liquidation or receivership whether compulsory or voluntary;

14.1.3. If the Contractor fails to comply with any final decision reached as a result of arbitration proceedings;

14.1.4. If, as the result of Force Majeure, the Contractor is unable to perform a material portion of the Services for a period of not less than sixty (60) calendar days;

14.1.5. If the Procuring Agency, in its sole discretion and for any reason whatsoever, decides to terminate this Contract;

14.2. By the Contractor

The Contractor may terminate this Contract, by not less than thirty (30) calendar days' written notice to the Procuring Agency, in case of the occurrence of any of the events specified in paragraphs (a) through (d) of this Clause.

14.2.1. If the Procuring Agency fails to pay any money due to the Contractor pursuant to this Contract and not subject to dispute within forty-five (45) calendar days after receiving written notice from the Contractor that such payment is overdue;

14.2.2. If, as the result of Force Majeure, the Contractor is unable to perform a material portion of the Services for a period of not less than sixty (60) calendar days;

14.2.3. If the Procuring Agency fails to comply with any final decision reached as a result of arbitration;

14.2.4. If the Procuring Agency is in material breach of its obligations pursuant to this Contract and has not remedied the same within forty-five (45) days (or such longer period as the Bidder may have subsequently approved in writing) following the receipt by the Procuring Agency of the Contractor's notice specifying such breach.

C. Obligations of the Contractor

15. General

15.1. Standard of Performance

15.1.1. The Contractor shall perform the Services and carry out the Services with all due diligence, efficiency and economy, in accordance with generally accepted professional standards and practices, and shall observe sound management practices, and employ appropriate technology and safe and effective equipment, machinery, materials and methods. The Contractor shall always act, in respect of any matter relating to this Contract or to the Services, as a faithful adviser to the Procuring Agency, and shall at all times support and safeguard the Procuring Agency's legitimate interests in any dealings with the third parties;

15.1.2. The Contractor shall employ and provide such qualified and experienced Experts and Sub-Contractors as are required to carry out the Services.

15.2. Law Applicable to Services

The Contractor shall perform the Services in accordance with the Contract and in accordance with the Law of Pakistan and shall take all practicable steps to ensure that any of its Experts and Sub-Bidders, comply with the Applicable Law.

16. Conflict of Interests

16.1. Contractor Not to Benefit from Commissions and Discounts

The remuneration of the Contractor shall constitute the Contractor's sole remuneration in connection with this Contract or the Services, and the Contractor shall not accept for their own benefit any trade commission, discount, or similar payment in connection with activities pursuant to this Contract or to the Services or in the discharge of their obligations under the Contract, and the Contractor shall use their best efforts to ensure that the Personnel, any Subcontractors, and agents of either of them similarly shall not receive any such additional remuneration.

16.2. Contractor and Affiliates Not to be Otherwise Interested in Project

The Contractor agree that, during the term of this Contract and after its termination, the Contractor and its affiliates, as well as any Subcontractor and any of its affiliates, shall be disqualified from providing Services (other than the Services and any continuation thereof) for any project resulting from or closely related to the Services.

16.3. Prohibition of Conflicting Activities

Neither the Bidder nor its Subcontractors nor the Personnel shall engage, either directly or indirectly, in any of the following activities:

16.3.1. during the term of this Contract, any business or professional activities in the Government's country which would conflict with the activities assigned to them under this Contract;

16.3.2. during the term of this Contract, neither the Contractor nor their Subcontractors shall hire public employees in active duty or on any type of leave, to perform any activity under this Contract;

16.3.3. after the termination of this Contract, such other activities as may be specified in the **SCC**.

17. Insurance to be Taken Out by the Contractor

17.1. The Contractor(a) shall take out and maintain, and shall cause any Subcontractors to take out and maintain, at its (or the Sub-contractors', as the case may be) own cost but on terms and conditions approved by the Procuring Agency, insurance against the risks, and for the coverage, as shall be specified in the **SCC**; and (b) at the Procuring Agency's request, shall provide evidence to the Procuring Agency showing that such insurance has been taken out and maintained and that the current premiums have been paid.

18. Contractor's Actions Requiring Procuring Agency's Prior Approval

18.1. The Contractor shall obtain the Procuring Agency's prior approval in writing before taking any of the following actions:

18.1.1. appointing such members of the Personnel not provided by the Contractor;

18.1.2. changing the Program of activities; and

18.1.3. any other action that may be specified in the **SCC**.

19. Reporting Obligations

19.1. The Contractor shall submit to the Procuring Agency the reports and documents in the numbers, and within the periods as prescribed by the Procuring Agency.

20. Liquidated Damages

20.1. Payments of Liquidated Damages

The Contractor shall pay liquidated damages to the Procuring Agency at the rate per day stated in the **SCC** for each day that the Completion Date is later than the Intended Completion Date. The total amount of liquidated damages shall not exceed the amount defined in the **SCC**. The Procuring Agency may deduct liquidated damages from payments due to the Contractor. Payment of liquidated damages shall not affect the Contractor's liabilities.

20.2. Correction for Over-payment

If the Intended Completion Date is extended after liquidated damages have been paid, the Procuring Agency shall correct any overpayment of liquidated damages by the Contractor by adjusting the next payment certificate. The

Contractor shall be paid interest on the overpayment, calculated from the date of payment to the date of repayment, at the rates specified in **SCC**.

20.3. Lack of performance penalty

If the Contractor has not corrected a Defect within the time specified in the Procuring Agency's notice, a penalty for Lack of performance will be paid by the Contractor. The amount to be paid will be calculated as a percentage of the cost of having the Defect corrected, assessed as specified in the Contractor

21. Performance Guarantee

21.1. Within the time stipulated in the acceptance letter from the Procuring Agency, the successful Bidder shall furnish the Performance Guarantee in shape and amount **specified in SCC**.

21.2. The proceeds of the Performance Guarantee shall be payable to the Procuring agency as compensation for any loss resulting from the Supplier's failure to complete its obligations under the Contract.

21.3. The Performance Guarantee shall be denominated in the currency of the Contract, or in a freely convertible currency acceptable to the Procuring agency and shall be in the acceptable form as specified in **SCC**.

21.4. The Performance Guarantee will be discharged by the Procuring agency and returned to the Supplier not later than thirty (30) days following the date of completion of the Supplier's performance obligations under the Contract, including any warranty obligations, unless otherwise **specified in SCC**.

22. Sustainable Procurement

22.1. The Contractor shall conform to the sustainable procurement contractual provisions, if and as specified in the **SCC**.

D. Contractor's Personnel

23. Description of Personnel

23.1. The titles, agreed job descriptions, minimum qualifications, and estimated periods of engagement in the carrying out of the Services of the Contractor's Key Personnel. The Key Personnel listed by title as well as by name are hereby approved by the Procuring Agency.

24. Removal and / or Replacement of Personnel

24.1. Except as the Procuring Agency may otherwise agree, no changes shall be made in the Key Personnel. If, for any reason beyond the reasonable control of the Contractor, it becomes necessary to replace any of the Key Personnel, the Contractor shall provide as a replacement a person of equivalent or better qualifications.

24.2. If the Procuring Agency finds that any of the Personnel have (i) committed serious misconduct or have been charged with having committed a criminal action, or (ii) have reasonable cause to be dissatisfied with the performance of any of the Personnel, then the Contractor shall, at the Procuring Agency's written request specifying the grounds thereof, provide as a replacement a person with qualifications and experience acceptable to the Procuring Agency.

24.3. The Contractor shall have no claim for additional costs arising out of or incidental to any removal and/or replacement of Personnel.

E. Obligations of the Procuring Agency

25. Change in the Applicable Law

25.1. If, after the date of this Contract, there is any change in the Applicable Law with respect to taxes and duties which increases or decreases the cost of the Services rendered by the Contractor, then the remuneration and reimbursable expenses otherwise payable to the Contractor under this Contract shall be increased or decreased accordingly by agreement between the Parties, and corresponding adjustments shall be made to the amounts referred in the SCC.

26. Services and Facilities

26.1. The Procuring Agency shall make available to the Contractor and the Experts, for the purposes of the Services and free of any charge, the services, facilities and property described in the Terms of Reference, at the times and in the manner specified in the Terms of Reference.

26.2. In case that such services, facilities and property shall not be made available to the Contractor, the Parties shall agree on (i) any time extension that it may be appropriate to grant to the Contractor for the performance of the Services, (ii) the manner in which the Contractor shall procure any such services, facilities and property from other sources, and (iii) the additional payments, if any, to be made to the Contractor as a result thereof.

F. Payments to the Contractor

27. Contract Price

27.1. The price payable shall be in Pakistani Rupees unless otherwise specified in the SCC.

28. Terms and Conditions of Payment

28.1. Payments will be made to the Contractor according to the payment schedule stated in the SCC and as per actual invoice submitted by the Contractor.

28.2. Unless otherwise stated in the SCC, the advance payment shall be made against the provision by the Contractor of a bank guarantee for the same amount, and shall be valid for the period stated in the SCC. Any other payment shall be made after the conditions listed in the SCC for such payment have been met, and the Contractor have submitted an invoice to the Procuring Agency specifying the amount due.

29. Quality Control Identifying Defects

29.1. The principle and modalities of Inspection of the Services by the Procuring Agency shall be as indicated in the SCC. The Procuring Agency shall check the Contractor's performance and notify him of any Defects that are

found. Such checking shall not affect the Contractor's responsibilities. The Procuring Agency may instruct the Contractor to search for a Defect and to uncover and test any service that the Procuring Agency considers may have a Defect. Defect Liability Period is as defined in the SCC.

29.2. A {INSPECTION}

30. Correction of Defects, and Lack of Performance Penalty

30.1. The Procuring Agency shall give notice to the contractor of any Defects before the end of the Contract. The Defects liability period shall be extended for as long as Defects remain to be corrected.

30.2. Every time notice a Defect is given; the contractor shall correct the notified Defect within the length of time specified by the Procuring Agency's notice.

30.3. If the contractor has not corrected a Defect within the time specified in the Procuring Agency's notice, the Procuring Agency will assess the cost of having the Defect corrected, the contractor will pay this amount, and a Penalty for Lack of Performance.

31. Settlement of Disputes Amicable Settlement

31.1. The Parties shall use their best efforts to settle amicably all disputes arising out of or in connection with this Contract or its interpretation.

32. Dispute Settlement

32.1. Arbitration

If any dispute of any kind whatsoever shall arise between the procuring agency and the contractor in connection with or arising out of the Contract, including without prejudice to the generality of the foregoing, any question regarding its existence, validity or termination, or the execution of the contract, the parties shall seek to resolve any such dispute or difference by mutual consultation. If the parties fail to resolve such a dispute or difference even after negotiations or mediation, then the dispute shall be referred within fourteen (14) days in writing by either party to the Arbitrator, with a copy to the other party.

Any dispute in respect of which a notice of intention to commence arbitration has been given, in accordance with **GCC sub-clause 32.1**, shall be finally settled by arbitration. Arbitration may be commenced prior to or after completion of the Contract. Arbitration proceedings shall be conducted in accordance with Arbitration Act 1940. Notwithstanding any reference to arbitration herein, the parties shall continue to perform their respective obligations under the Contract unless otherwise agreed. The Procuring Agency shall continue to pay the Contractor any undisputed amounts due under the Contract during the resolution of any dispute.



Special Conditions of Contract

SECTION VIII. SPECIAL CONDITIONS OF CONTRACT

The following Special Conditions of Contract shall supplement the General Conditions of Contract. Whenever there is a conflict, the provisions herein shall prevail over those in the Conditions of Contract. The corresponding clause number of the GCC is indicated in parentheses.

Number of GC Clause

Amendments of, and Supplements to, Clauses in the General Conditions of Contract

Number of GC Clause 1

Definitions

The Procuring Agency is: ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA)), Divisional Engineer ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province).

The Supplier is:

The title of the subject procurement is: CRITICAL REQUIREMENT OF SECURITY EQUIPMENT AND OTHER PARAPHERNALIA AT VARIOUS AIRPORTS / LOCATIONS (CONSTRUCTION OF BARRACKS, JS APARTMENTS AND MOQs FOR ASF AT AIIAP LAHORE)

Number of GC Clause 2

Applicable/Governing Law:

The Contract shall be interpreted in accordance with the laws of Islamic Republic of Pakistan

Number of GC Clause 3

Language:

The language of the Contract, all correspondence and communications to be given, and all other documentation to be prepared and supplied under the Contract shall be in **English**.

Number of GC Clause 4

Notices:

The addresses for the notices are:

Procuring Agency:

ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA)), Divisional Engineer
ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province).

+92-345-567-2161

abراهيم161@gmail.com

Contractor/ Bidder:

[Name, address and telephone number]

The Contractor/ Bidder's Representative(s)

[Name, address, telephone number and e-mail address]

Number of GC Clause 6.1

The Authorized Representatives are:

For the Procuring Agency:

ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA)), Divisional Engineer

ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province).

+92-345-567-2161

abراهيم161@gmail.com

For the Bidder:

Name:

Designation:

Address:

Number of GC Clause 7

Effectiveness of the contract

The Contractor/Bidder shall be effective within days from the date of signature of the Contract by both parties

Number of GC Clause 8

Commencement of Contract:

The Contractor/Bidder shall provide Non-Consultancy Services from the effective date of contract.

Number of GC Clause 10.2

Expiration of Contract:

The time period shall be

Number of GC Clause 14

Termination

In the event of termination of the contract due to any reason as already defined in the General Conditions of Contract, the Bidder shall be responsible for providing to the Authority the Goods till the time of alternate arrangements.

Number of GC Clause 16

Conflict of Interest:

The Procuring Agency reserves the right to determine on a case-by-case basis whether the Bidder should be disqualified from providing goods or services due to a conflict of a nature described in Clause GCC 17.

Number of GC Clause 20**Liquidated Damages**

If the Bidder fails to provide services as required under the contract or in case of any data loss/data breach or any incident compromising the data security or other such failures related to any services, the Bidder shall pay to the Procuring Agency as Liquidated Damages at a rate of **0.05% to 10.00%** of the Contract value, in accordance with the extent of performance failure & the cost of investigating such incidents as judged by the Authority.

Number of GC Clause 21**Performance Guarantee:**

The amount of performance guarantee shall be **5.00%** of the contract price in acceptable form of **Pay Order, Banker's Cheque, Call at Deposit, Bank Guarantee**

Number of GC Clause 27**Currency of Payment:**

All the payment to be released to the contractor/Bidder shall be in Pakistani Rupees.

Number of GC Clause 28**Payment terms:**

Payment will be made to the Bidder against the procured Goods and services according to the actual invoice or running bills submitted by the Bidder against the services provided within the time given in the conditions of the contract.

Number of GC Clause 29**Identifying Defects:**

The Authority reserves the right at any time to inspect the premises of the provider to inspect the goods and monitor the goods being provided.

Inspections & Tests Requirements

For being Brand New, bearing relevant reference numbers of the equipment (Certificate from supplier)

For Physical Fitness having No Damages (Certificate from supplier)

For the Country of Origin as quoted by the Supplier (Certificate from manufacturer)

For conformance to specifications and performance parameters, through Prior to delivery inspection (Inspection Report by Procurement Committee / Inspection Team)

For successful operation at site after complete installation, testing and commissioning of the equipment (Installation, Testing and Commissioning Report by Procurement Committee / Inspection Team)

Delivery & Documents

Copies of the Supplier's invoice showing Goods' description, quantity, unit price, and total amount;

Original and two copies of the usual transport document (for example, a negotiable bill of lading, a non-negotiable sea waybill, an inland waterway document, an air waybill, a railway consignment note, a road consignment note, or a multimodal transport document) which the buyer may require to take the goods;

Copies of the packing list identifying contents of each package;

Insurance Certificate;

Manufacturer's or Supplier's Valid Warranty Certificate;

Inspection Certificate issued by the Nominated Inspection Agency (if any), and the Supplier's Factory Inspection Report;

Certificate of Origin.

The above documents would be required even if the equipment has already been imported and is available with the supplier ex-stock

Number of GC Clause 31

Following is the guidance for Dispute Resolution

- i. If any dispute of any kind whatsoever shall arise between the Authority and the Bidder in connection with or arising out of the Contract... (full clause unchanged)
- ii. At future of negotiation the dispute shall be resolved through mediation...
- iii. At failure of mediation, arbitration under Arbitration Act 1940...
- iv. Cost sharing equally...
- v. Proceedings may commence before/after completion...

Notwithstanding any reference to the arbitration herein, the parties shall continue to perform their respective obligations under the Contract.

Rules of procedure for arbitration proceedings:

Any dispute between the Authority and a Bidder shall be referred to arbitration under the laws of Pakistan including Arbitration Act 1940.

Place of Arbitration and Award:

The arbitration shall be conducted in English language and place shall be Islamabad. The award shall be final and binding.



Bid Securing Declaration

Form 9: Bid Securing Declaration

Date: *[insert date (as day, month and year)]*

Bid No.: **P72208**

To: **ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA)), Divisional Engineer ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province).**

We, the undersigned, declare that:

We understand that, according to your conditions, Bids must be supported by a Bid Securing Declaration.

We accept that we will be blacklisted and henceforth cross debarred for participating in respective category of public procurement proceedings for a period of (not more than) six months, if fail to abide with a bid securing declaration, however without indulging in corrupt and fraudulent practices, if we are in breach of our obligation(s) under the Bid conditions, because we:

1. have withdrawn or modified our Bid during the period of Bid Validity specified in the Form of Bid;
2. Disagreement to arithmetical correction made to the Bid price; or
3. having been notified of the acceptance of our Bid by the Procuring Agency during the period of Bid Validity, (i) failure to sign the contract if required by Procuring Agency to do so or (ii) fail or refuse to furnish the Performance Security or to comply with any other condition precedent to signing the contract specified in the Bidding Documents.

We understand this Bid Securing Declaration shall expire if we are not the successful

Bidder, upon the earlier of (i) our receipt of your notification to us of the name of the successful Bidder; or (ii) twenty-eight (28) days after the expiration of our Bid.



Contract Form

SECTION IX: CONTRACT FORMS

THIS AGREEMENT made the ____ day of _____ 20____ between **ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA)), Divisional Engineer ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province).**

(hereinafter called “the Procuring Agency”) of the one part and [name of Bidder] of [city and country of Bidder] (hereinafter called “the Bidder”) of the other part:

WHEREAS the Procuring Agency invited Bids for provision of goods, viz., **CRITICAL REQUIREMENT OF SECURITY EQUIPMENT AND OTHER PARAPHERNALIA AT VARIOUS AIRPORTS / LOCATIONS (CONSTRUCTION OF BARRACKS, JS APARTMENTS AND MOQs FOR ASF AT AIIAP LAHORE) (P72208)** and has accepted a Bids by the Bidder for the provision of Goods in the sum of [contract price in words and figures] (hereinafter called “the Contract Price”).

NOW THIS CONTRACT WITNESSETH AS FOLLOWS:

1. In this Contract words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract referred to.

2. The following documents shall be deemed to form and be read and construed as part of this Contract, In the event of any ambiguity or conflict between the Contract Documents listed below, the order of precedence shall be the order in which the Contract Documents are listed below:-

1. This form of Contract;
2. the Form of Bids and the Price Schedule submitted by the Bidder;
3. the Schedule of Requirements;
4. the Technical Specifications;
5. the Special Conditions of Contract;
6. the General Conditions of the Contract;
7. the Procuring Agency’s Letter of Acceptance; and
8. [add here: any other documents]

3. In consideration of the payments to be made by the Procuring Agency to the Bidder as hereinafter mentioned, the Bidder hereby covenants with the Procuring Agency to provide the Goods related services and to remedy defects therein in conformity in all respects with the provisions of the Contract.

4. The Procuring Agency hereby covenants to pay the Bidder in consideration of the provision of Goods and the remedying of defects therein, the Contract Price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.

IN WITNESS whereof the parties hereto have caused this Contract to be executed in accordance with their respective laws the day and year first above written.


Signed, sealed, delivered by _____ the _____ (for the Procuring Agency)

Witness to the signatures of the Procuring Agency:

.....

Signed, sealed, delivered by _____ the _____ (for the Procuring Agency)

Witness to the signatures of the Bidder:





Integrity Pact

Integrity Pact

DECLARATION OF FEES, COMMISSION AND BROKERAGE ETC. PAYABLE BY THE SUPPLIERS OF GOODS, SERVICES & WORKS IN CONTRACTS WORTH RS.10.00 MILLION OR MORE

Contract

Number: Contract

Value: Contract Title:

Dated:

[Name of Supplier] hereby declares that it has not obtained or induced the procurement of any contract, right, interest, privilege or other obligation or benefit from Government of Pakistan or any administrative subdivision or agency thereof or any other entity owned or controlled by it (GoP) through any corrupt business practice.

Without limiting the generality of the foregoing [Name of Supplier] represents and warrants that it has fully declared the brokerage, commission, fee etc. paid or payable to anyone and not given or agreed to give and shall not give or agree to give to anyone within or outside Pakistan either directly or indirectly through any natural or juridical person, including its affiliate, agent, associate, broker, consultant, director, promoter, shareholder, sponsor or subsidiary, any commission, gratification, bribe, finder's fee or kickback, whether described as consultations fee or otherwise, with the object of obtaining or inducing the procurement of a contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP, except that which has been expressly declared pursuant hereto.

[Name of Supplier] certifies that it has made and will make full disclosure of all agreements and arrangements with all persons in respect of or related to the transaction with GoP and has not taken any action or will not take any action to circumvent the above declaration, representative or warranty.

[Name of Supplier] accepts full responsibility and strict liability for making and false declaration, not making full disclosure, misrepresenting fact or taking any action likely to defeat the purpose of this declaration, representation and warranty. It agrees that any contract, right interest, privilege or other obligation or benefit obtained or procured as aforesaid shall, without prejudice to any other right and remedies available to GoP under any law, contract or other instrument, be voidable at the option of GoP.

Notwithstanding any rights and remedies exercised by GoP in this regard, [Name of Supplier] agrees to indemnify GoP for any loss or damage incurred by it on account of its corrupt business practices and further pay compensation to GoP in an amount equivalent to ten times the sum of any commission, gratification, bribe, finder's fee or kickback given by [Name of Supplier] as aforesaid for the purpose of obtaining or inducing the procurement of any contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP.



Performance Guarantee Form

Performance Guarantee Form

To: **ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY) (Pakistan Airports Authority (PAA)), Divisional Engineer ALLAMA IQBAL INTERNATIONAL AIRPORT (PAKISTAN AIRPORTS AUTHORITY), Lahore City, Lahore (District), Lahore Division (Division), Punjab (Province).**

WHEREAS *[name of Bidder]* (hereinafter called “the Bidder”) has undertaken, in pursuance of Contract No. *[reference number of the contract]* dated *[insert date]* for provision of Goods(hereinafter called “the Contract”).

AND WHEREAS it has been stipulated by you in the said Contract that the Bidder shall furnish you with a Bank Guarantee by a reputable bank for the sum specified therein as security for compliance with the Bidder’s performance obligations in accordance with the Contract.

AND WHEREAS we have agreed to give the Bidders guarantee:

THEREFORE, WE hereby affirm that we are Guarantors and responsible to you, on behalf of the Bidder, up to a total of *[amount of the guarantee in words and figures]*, and we undertake to pay you, upon your first written demand declaring the Bidder to be in default under the Contract and without cavil or argument, any sum or sums within the limits of *[amount of guarantee]* as aforesaid, without your needing to prove or to show grounds or reasons for your demand or the sum specified therein.

This guarantee is valid until the: *[insert date]*


Signature and seal of the Guarantors

[name of bank or financial institution]

[address]

[date]





Annexure

General Conditions of Contract

<p>These conditions supplement the default GCC of the SBD however, in case of any conflict, these will prevail.</p>

Information (Read-Only)

See Form Under Additional Forms and Documents: **General Conditions of Contract** (page number: 317)

Special Conditions of Contract (Civil works)

<p>These conditions supplement the default SCC of the SBD however, in case of any conflict, these will prevail.</p>

Information (Read-Only)

See Form Under Additional Forms and Documents: **Special Conditions of Contract (Civil works)** (page number: 334)

Special Conditions of Contract (E/M Works)

<p>These complement the SCC of the SBD however in case of any conflict, these will prevail</p>

Information (Read-Only)

See Form Under Additional Forms and Documents: **Special Conditions of Contract (E/M Works)** (page number: 341)

Drawings

<p>These drawings are preliminary and the contractor will have to formulate shop drawings as well as the As-Built Drawings of the complete facilities in accordance with the supplemented SCC (Civil Works)</p>

Information (Read-Only)

See Form Under Additional Forms and Documents: **Drawings** (page number: 342)

List of approved Manufacturers

Information (Read-Only)

See Form Under Additional Forms and Documents: **List of approved Manufacturers** (page number: 360)

List of approved Banks

Information (Read-Only)

See Form Under Additional Forms and Documents: **List of approved Banks** (page number: 363)

HSE Manual

<p>The instructions in the HSE Manual must be followed in entirety during execution</p>


Information (Read-Only)

See Form Under Additional Forms and Documents: **HSE Manual** (page number: 364)

Integrity Pact

Information (Read-Only)

See Form Under Additional Forms and Documents: **Integrity Pact** (page number: 379)





Procurement Forms

Past Construction Experiences

See Form Under Additional Forms and Documents: **Past Construction Experiences** (page number: 380)

Contractor's Key Personnel Representative and Their Schedules

See Form Under Additional Forms and Documents: **Contractor's Key Personnel Representative and Their Schedules** (page number: 386)

Historical Contract Non-Performance, and Pending Litigation and Litigation History

See Form Under Additional Forms and Documents: **Historical Contract Non-Performance, and Pending Litigation and Litigation History** (page number: 390)

Current Contracts and Their Progress

See Form Under Additional Forms and Documents: **Current Contracts and Their Progress** (page number: 392)

Financial Capacity and Net Worth Evaluation Form

See Form Under Additional Forms and Documents: **Financial Capacity and Net Worth Evaluation Form** (page number: 393)

Average Annual Turnover

See Form Under Additional Forms and Documents: **Average Annual Turnover** (page number: 395)





Additional Forms and Documents

GENERAL CONDITIONS OF CONTRACT

1 Definitions


In the Contract (as hereinafter defined) the following words and expressions shall have the meanings assigned to them except where the context otherwise requires:

- 1.1 **“PAA”** means Pakistan Airports Authority and includes its duly authorized agents, successors and assigns.
- 1.2 **“Competent authority”** means an officer of PAA under whose competence the acceptance of bid lies.
- 1.3 **“Contractor”** means the person or persons, firm or Company whose Bid (as hereinafter defined) has been accepted by PAA and includes the Contractor’s personal representatives, successors and permitted assigns, but does not include any sub-contractor.
- 1.4 **“Divisional Engineer”** means an Engineer duly authorized by the PAA for execution of work.
- 1.5 **“Representative of Divisional Engineer”** means any duly authorized officer or officers appointed by the PAA to perform the duties set forth.
- 1.6 The expression **“Works”** means all the works specified or set forth and required in and by the said specifications, drawings and schedule hereto or to be hereafter specified or required in such explanatory instructions and drawings and also in such additional Instructions and drawings as such from time to time, during the progress of the work hereby contracted for, be supplied by PAA.
- 1.7 **“Contract”** means the Conditions of Contract specifications, Drawings, priced schedule of Quantities, Bid and the Contract Agreement.
- 1.8 **“Contract Price”** means the amount / sum stated in the letter of Acceptance, subject to such additions thereto or deductions there from as may be made under the provisions hereinafter contained.
- 1.9 **“Construction Plant”** means all appliances, equipment or things of whatsoever nature required in or about the execution, completion or maintenance of the Works or Temporary works.
- 1.10 **“Temporary Works”** means all temporary works of every kind required in or about the execution completion or maintenance of the work.
- 1.11 **“Drawings”** means the drawings referred to in the Specifications and any modifications of such drawings approved in writing by the PAA and such other drawings as may from time to time be furnished or approved in writing by the Divisional Engineer.
- 1.12 **“Site”** means the lands and other places on, under, in, through which the works are to be executed or carried out and any other lands or places provided by the PAA for purposes of the Contract.
- 1.13 **“Approved”** means approved in writing including subsequent written confirmation of previous verbal approval and “Approval” means approved in writing including as aforesaid.




1.14 **“Bid”** means a tender, bid, or proposed remuneration, price, or cost submitted by a natural person, firm, corporation, or other legal entity in response to an invitation to bid, expressing the intent to undertake a specifically defined scope of works in conformity with the prescribed specifications, designs, drawings, instructions, and materials as stipulated under the Contract, and in compliance with all other applicable terms and conditions, including any and all annexures, schedules, or supplementary documents attached to or referenced in the offer.

- 2 Extent of Contract** The Contract comprises the construction, completion and maintenance of the Works and except in so far as the Contract otherwise provides, the provision of all labour, materials, construction plant, temporary works and everything whether of temporary or permanent nature required in and for such construction, completion and maintenance so far as the necessity for providing the same as specified in or reasonably to be inferred from the Contract.
- 3 Documents Mutually Explanatory** The several documents forming the Contract are to be taken as mutually explanatory of one another and in case of ambiguities or discrepancies, the same shall be explained by the Divisional Engineer whose explanation in this respect shall be final.
- 4 Sufficiency of Bid** The Contractor shall be deemed to have satisfied himself before bidding as to the correctness, completeness and sufficiency of his Bid for the works and of the rates and prices stated in the priced schedule of Quantities which rates and prices shall except in so far as otherwise provided in the Contract cover all his obligations under the Contract and all matters and things necessary for the proper completion and maintenance of the Works.
- 5 Inspection of Site** The Contractor shall inspect and examine the Site and its surroundings and shall satisfy himself before submitting the bid, as to the nature of ground and sub soil, the form and nature of the Site, the quantities and nature of the work and materials necessary for the completion of the works and the means of access of the Site, the accommodation he may require and in general shall himself obtain all necessary information as to risk, contingencies and other circumstances which may influence or affect his Bid.
- 6 Possession of Site** The Divisional Engineer, with the written order to commence the works will give to the Contractor possession of the Site as may be required to enable the Contractor to commence and proceed with the construction of the works in accordance with the program referred to in clause 10 hereof and otherwise in accordance with such reasonable proposals of the Contractor as he shall by notices in writing to the Divisional Engineer make and will from time to time as the works proceed give to the Contractor possession of such further portions of the Site as may be required to enable the Contractor to proceed with the construction of



Works with due diligence in accordance with the said programme or proposals (as the case may be).

- 7 Drawings** Three copies of each of the approved Drawings shall be furnished by PAA to the Contractor free of cost. The Contractor shall provide and make at his own expense any further copies required by him.
- 8 Drawings to be kept on Site** One copy of each of the Drawings furnished to the Contractor as aforesaid shall be kept by the Contractor on the Site and the same shall at all times be available for inspection and use by the Divisional Engineer the representative of the Divisional Engineer.
- 9 Further Drawing and Instructions** The Divisional Engineer shall have full power and authority to supply to the Contractor from time to time during the progress of the works such further Drawings and instructions as shall be necessary for the purpose of the proper and adequate execution and maintenance of the works and the Contractor shall carry out and be bound by the same.
- 10 Programme to be furnished** As soon as practicable after the acceptance of his Bid, the Contractor shall submit to the Divisional Engineer for his approval a programme showing the order of procedure and method in which he proposes to carry out the Work and shall furnish for his information, particulars in writing of the Contractor's arrangements for carrying out of the works and the constructional plant and temporary works which the Contractor intends to supply, use or construct, as the case may be. The submission to and approval by the Divisional Engineer or the Representative of the Divisional Engineer of such programme or the furnishing of such particulars shall not relieve Contractor of any of his duties or responsibilities under the Contract.
- 11 Commencement** The Contractor shall commence the Works on Site after the receipt by him of an order in writing to commence work from the Divisional Engineer and shall proceed for the same with due diligence (time being the essence of the Contract on the part of the Contractor).
- 12 Contractor's Superintendence** The Contractor shall give or provide all necessary superintendence during the execution of the Works and as long thereafter as the Divisional Engineer may consider necessary for the proper fulfilling of the Contractor's obligations under the Contract. The Contractor or his competent, qualified and authorized agent or representative approved by the Divisional Engineer in writing (which approval may at any time be withdrawn) is to be constantly on the Works and shall give his whole time to the superintendence of the same if such approval shall be withdrawn by the Divisional Engineer, the Contractor shall without any delay, after receiving written notice of such withdrawal, remove the Agent from the site and shall not thereafter the employ him again on the Site in any capacity and shall replace him by another agent approved by the Officer, Such authorized agent or representative shall receive, on behalf of the Contractor directions and instructions from the Divisional Engineer or the representative of the Divisional Engineer. The Contractor shall also



employ full time Engineer / Sub-Engineer, duly qualified in Civil / Electrical / Mechanical Engineering and having professional experience of at least three years for the purpose of execution of the proposed works and giving full time engineering / technical superintendence during all phases of execution and for receiving technical directions and instructions from the Divisional Engineer.

13 Contractor's Employees

The Contractor shall provide and employ on the Site in connection with the execution and maintenance of the Works:

13.1 Only such technical personnel as are skilled and experience in their respective fields and such sub-agents, foremen and leading hands as are competent to give proper supervision to the work they are required to supervise.

13.2 Such skilled and semi-skilled and unskilled labour as is necessary for the proper and timely execution and maintenance of the Works.

14 Removal of Contractor's Employees

The Divisional Engineer shall have the power to object in writing to and require the Contractor to remove forthwith from the Work any person employed by the Contractor in or about the execution or maintenance of the works who in the opinion of the Divisional Engineer is misconducting himself or is incompetent or negligent in the proper performance of his duties or whose employment is otherwise considered reasonably by the Divisional Engineer to be undesirable. Any person so removed from the works shall be replaced without delay by a competent substitute approved by the Divisional Engineer. The Contractor shall not demand the reasons from the Divisional Engineer for requiring the removal of any one of his employees.

15 Supply of Plant Materials and Labour

Except where otherwise expressly specified, the Contractor shall at his own expense supply and provide all the Constructional plants, work materials, both for temporary and for permanent works, labour (including the supervision thereof) transport to or from the site and in and about the works and other things of every kind required for the construction, completion and maintenance of the works.

16 Works to be executed in accordance with specifications drawings etc.

The Contractor shall execute the whole and every part of the work in the most substantial and workman-like manner and both as regards materials and otherwise in every respect in strict accordance with the specifications. The Works executed by the Contractor shall also conform exactly, fully and faithfully to the designs, drawings and instructions in writing relating to the work issued by the Divisional Engineer.

17 Action where no specification

In the case of any class of work for which there is no such specifications, such work shall be carried out in accordance with the written instructions, and requirements of the Divisional Engineer.

18 Quality of Material,

All materials and workmanship shall be of the respective kinds described in the Contract and in accordance with the instructions of the Divisional Engineer and shall be subjected from time to time to such tests as the

Workmanship and Tests

Divisional Engineer may direct at the place of manufacture or fabrication on the Site or at all or any of such places. The Contractor shall provide such assistance, instruments, machines, labour and materials as are normally required for examining, measuring and testing any work and the quality, weight or quantity of any materials used and shall supply samples of materials before incorporation in the works for testing as may be selected and required by the Divisional Engineer. All samples shall be supplied by the Contractor at his own cost. The cost of making all tests specified in the Contract shall be borne by the Contractor.

19 Delegation of Power to Divisional Engineer's Representatives.

The Divisional Engineer may from time to time in writing delegate to the representatives of the Divisional Engineer any of the powers and authorities vested in the Divisional Engineer. Any written instruction or approval given by the representative of the Divisional Engineer to the Contractor within the term of such delegation (but not otherwise) shall bind the Contractor and the PAA, as though it has been given by the Divisional Engineer provided as follow:

19.1 Failure of the representative of the Divisional Engineer to disapprove any work or materials shall not prejudice the power of the Divisional Engineer thereafter to disapprove such work or materials and to order the pulling down, removal or breaking up thereof.

19.2 If the Contractor shall be dissatisfied by reason of any decision of the representative of the Divisional Engineer he shall be entitled to refer the matter to the Divisional Engineer who shall thereupon confirm, reverse or vary or modify such decision, and whose decision shall be final.

19.3 The Agreement shall be rescinded by the PAA and the final measurements shall be recorded by the Divisional Engineer or his any authorized representative shall record the final measurement and Contractor will not claim for any item not recorded by the Divisional Engineer or his representative.

20 Access to Site


The Divisional Engineer and any person authorized by him shall at all times have access to the Works and to the Site and to all Workshops and places where work is being done or where materials, manufactured articles or machinery are being obtained for the Works and the Contractor shall afford every assistance in or obtaining the right to such access.

21 Way leave etc.

The Contractor shall bear all expenses and charges for special or temporary way leaves required by him in connection with access to the Site. The Contractor shall also provide with the written approval of Divisional Engineer at his own cost any reasonable additional accommodation at Site required by him for the purposes of the Works.

22 Rate of Progress and permission to work during Night.

The whole of the materials, plant and labour to be provided by the Contractor and the mode, manner and speed of execution and maintenance of the works are to be of a kind and conducted in a manner approved by the Divisional Engineer. Should the rate of progress of the Works or any



part thereof be at any time in the opinion of the Divisional Engineer too slow to ensure the completion, the Divisional Engineer shall so notify the Contractor in writing and the Contractor shall thereupon take such steps as may be necessary and the Divisional Engineer may approve to expedite progress so as to complete the Works by the prescribed time or extended time for completion. If the work is not being carried on by day and by night and the Contractor shall request permission to work by night as well as by day, then, if the Divisional Engineer shall grant such permission, the Contractor shall not be entitled to any additional payments. The contractor shall indemnify the PAA from and against all claims, liabilities, demands, proceedings, costs and expenses whatsoever in regard or in relation to such permission. All work at night shall be carried out without unreasonable noise and disturbance.

23 Time for Completion


Subject to any requirement in the Specification of any portion of the Works before completion of the whole of the works, the whole work shall be completed within the stipulated time.

24 Extension of time for completion

Should the amount of extra or additional work of any kind or other special circumstances of any kind whatsoever (acts of God and events beyond the control of PAA etc.) which may occur be such as fairly to entitle the Contractor to an extension of time for the completion of the work, the Divisional Engineer shall determine and grant such an extension of time. Provided that the Divisional Engineer is not bound to take into account any extra additional work or other special circumstances unless the Contractor has within fourteen (14) days after such work has been commenced or such circumstances have arisen, delivered to the representative of the Divisional Engineer full and detailed particulars of any claim for extension of time to which he may consider himself entitled in order that such claim may be investigated at the time.

25 Termination of Contract for slow progress

If in the opinion of the Divisional Engineer the progress of the Works is slow that it cannot be completed within the prescribed period or within the extended period granted to the Contractor, the Divisional Engineer shall give a notice in writing to the Contractor calling upon him to speed up the work by employing more labour and by increasing the rate of supply of material, equipment and plant to an extent to be mentioned in the notice. In case the Contractor fails to comply with the requirements of the notice within ten days from its issue, the Divisional Engineer shall have the power to have the works completed through any other agency at the risk and cost of the Contractor. In any such event, the work executed by the Contractor shall be measured up and all plant, machinery, equipment and material at Site will be taken over by the Divisional Engineer after preparing and inventory thereof, such stores to be used for the completion of the work will be at the cost of the Contractor. All payments due to the Contractor shall be withheld till the completion of the work and any loss suffered by the PAA or expenditure incurred in getting the works executed, shall be recovered from the Contractor.



26 Action and Compensation payable in case of works below specification

If it shall appear to the Divisional Engineer or his representative, that any work has been executed with unsound, imperfect or unskilled workmanship or with materials of any inferior description or that any materials or articles provided by him for the execution of the work are unsound or of a quality inferior to that contracted for or otherwise not in accordance with the contract, the Contractor shall on demand in writing from the Divisional Engineer specifying the work, materials or articles complained of notwithstanding that the same may have been inadvertently passed, certified and paid for, forth-with rectify, or remove and reconstruct the work so specified and provide other proper and suitable materials or articles at his own cost; and in the event of his failing to do so with in a period to be specified by the Divisional Engineer in his demand aforesaid, then the Contractor shall be liable to pay compensation at the rate of one percent on the total cost of work for every day not exceeding ten days apart from the cost of rectification, while his failure to do so, shall continue and in the case of any such failure the Divisional Engineer may rectify or remove, and re-execute the work which may include additional work necessary to strengthen or set right the unsound work carried out by the Contractor or remove and replace with others, the materials or articles complained of as the case may be at the risk and cost of the Contractor in all respect.

27 Security Deposits

The Contractor shall permit the PAA at the time of making any payment to him for work done under the contract to deduct such sum as will amount to be five per cent (5%) of all money so payable; such deductions to be held by PAA by way of security deposit. The sum five per cent (5%) of the amount of the bills including the earnest money held by the PAA by way of security deposit shall be paid back to the Contractor after the satisfactory expiration of Period of Maintenance as defined in the clause 49 hereof.

28 Forfeiture of Security deposit

28.1 In any case in which under any clause, or clauses of this agreement the Contractor shall have rendered himself liable to pay compensation amounting to the whole of his security deposit (whether paid in one sum or deduction by instalments) the PAA shall have the power in its own discretion to adopt any of the following courses, best suited to the interest of the PAA.

- a) To rescind the Contract (of which recession notice in writing by the Divisional Engineer to the Contractor shall be conclusive evidence) and in which case the security deposit of the Contractor as available with the PAA shall stand forfeited and be absolutely at the disposal of PAA.
- b) To employ labour paid by PAA and to supply materials to carry out the work or any part of the work debiting the Contractor with the cost of the labour and the price of the materials (of the amount of which cost and price a certificate of the Divisional Engineer shall be final and conclusive against the Contractor) and crediting him with the new value of the work done, in all respect in the same manner and at the same rates as if it had been



carried out by the Contractor under the terms of his Contract, the certificates of the Divisional Engineer as to the value of work done shall be final and conclusive against the Contractor.

- c) To measure up the work of the Contractor and to take such part thereof as shall be unexecuted out of his hand, and to give it to another contractor to complete, in which case any expenses which may be incurred in excess of the sum which would have been paid to the original Contractor, if the whole work had been executed by him (of the amount of which exceed, the certificate in writing to the Divisional Engineer shall be final and conclusive) shall be borne and paid by the original Contractor and may be deducted from any money due to him by the PAA under the contract or otherwise or from his security deposit, or the proceeds of sale thereof or a sufficient part thereof.

28.2 In the event of any of the above courses being adopted by the PAA, the Contractor shall have no claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials, or entered into any engagements or made any advance on account of or with a view to the execution of the work or the performance of the Contract. And, in case the Contract is rescinded under the aforesaid provisions, the Contractor shall not be entitled to recover or be paid any sum for any work therefore actually performed under this contract. Unless and until the Divisional Engineer will have certified in writing the performance of such work and the value payable in respect thereof, and he shall only be entitled to be paid the value so certified. Again, the Contractor will not in any manner hinder or prevent the owner or Divisional Engineer or any of the workmen and other employed by him from proceeding to complete the said buildings and works as aforesaid.

29 Liquidated damages for delay

If the Contractor fails to complete the works within the stipulated time for completion prescribed under the Contract, or any extended time allowed for completion in accordance with the Contract, then the Contractor shall pay to the PAA a sum equal to ten (10) per cent or less of the Contract Price as liquidated damages (and not as a penalty) for the delay beyond the time prescribed in the Contract or the extended time for completion, as the case may be. The said sum shall be payable by the sole fact of the delay without the need for any previous notice or any legal proceedings, or proof of damage, which shall in all cases be considered as ascertained. The PAA may, without prejudice to any other method of recovery, deduct the amount of such liquidated damages from any monies in its hands due or which may become due to the Contractor. The payment or deduction of such damages shall not relieve the Contractor from his obligation to complete the Works or from any other of his obligations and liabilities under the Contract.

30 Notice to be given before work is covered up

The Contractor shall give not less than five clear days' notice in writing to the Divisional Engineer or his representative before covering up or otherwise placing beyond the reach of measurement of any work, in order



that the same may be measured, and correct dimensions thereof be taken before the same is so covered up or placed beyond the reach of measurement without the consent in writing of the Divisional Engineer or his representative, and if any work shall be covered up or placed beyond the reach of measurement without such notice have been given or consent obtained the same shall be uncovered at the Contractor's expense, or in default thereof no payment or allowance shall be made for such work on the materials, with which the same was executed.

31 Suspension of work

The Contractor shall on the written order of the Divisional Engineer suspend the progress of the works or any part thereof for such time or times and in such manner as the Divisional Engineer may consider necessary and shall during such suspension properly protect and secure the work so far as is necessary in the opinion of the Divisional Engineer. The extra cost (if any) incurred by the Contractor in giving effect to the Divisional Engineer's instructions under this clause shall be borne by the Contractor, if such suspension is:

- a) as per the provision of the contract, or
- b) Necessary for the proper execution of the work or by reason of weather conditions affecting the safety or quality of the Works or by some default on the part of the Contractor, or
- c) Necessary for the safety of the works or any part thereof.

32 Care of works

From the commencement to the completion of the Works, the Contractor shall take full responsibility for the care thereof and of all temporary works, and in the event that any damage, loss or injury should happen to the Works or to any part thereof or to any temporary works from any cause whatsoever (save and except the "expected risk(s)" as defined in clause 33 hereof), the Contractor shall at his own cost repair and make good the same so that at completion, the works shall be in good order and condition and in conformity in every respect with the requirements of the contract and the Divisional Engineer's instructions. The Contractor shall also be liable for any damage to the Works occasioned by him in the course of any operations carried out by him for the purpose of complying with his obligations under Clause 50 hereof. The Contractor shall be fully responsible for the review of the Engineering design and details of the works and shall inform the PAA of any mistakes or incorrectness in such design and details which would affect the works.

33 Expected Risk

The "Expected Risk" are hostilities (where war be declared or not) invasion, act of foreign enemies, rebellion revolution insurrection or military or usurped power civil war or (otherwise than among the Contractor's own employees) riot, commotion or disorder or use by occupation by the PAA of any portion of the Works in respect of which a certificate of completion has been issued or any such operation of the forces of nature as reasonable foresight and ability on the part of the Contractor could not foresee or reasonably provide against (all of which are herein collectively referred as "the expected risk").

34 Damage to persons and property.

The Contractor shall (except if and so far as the Contract provides otherwise) indemnify and keep indemnified the PAA and its Employees from and against all suits, claims, demands, proceedings, and liability of any nature or kind, including costs and expenses, for injuries or damages to any person or any property whatsoever which may arise out of or in consequence of acts or omissions of the Contractor or its agents, employees, servants or subcontractors in the execution of the Contract.

35 Accident or injury to Workmen

The PAA shall not be liable for or in respect of any damages or compensation payable at law in respect or in consequence of any accident or injury to any workman or other persons in the employment of the Contractor or any sub-contractor. The Contractor shall indemnify and keep indemnified the PAA against all such damages, compensation and against all claims, demands, proceedings, cost charges and expenses whatsoever in respect thereof or in relation thereto.

36 Insurance

The Contractor shall obtain and keep in force policies in respect of Erection All Risks, Contractor's All Risks and Workmen's Compensation act, which shall apply specifically and solely to the Contractor and shall fulfil all Contractor's obligations for Insurance in connection with this Contract from an Insurance Company in Pakistan having at latest AA rating from PACRA / JCR-VIS.

37 Compliance with Statutes, Regulations etc.

The Contractor shall conform in all respects with any such Statutes, Ordinances, Laws, Regulations, Bye-laws or requirements of any such local or other authority / authorities which may be applicable to the Works or to any Temporary Works and shall keep the PAA indemnified against all penalties and liability of every kind for breach of any such Statutes, Ordinances, Laws, Regulations, Bye-laws or requirements.

38 Fossils etc.

All fossils, coins, article of value or antiquity and structures and other remains or things of geological or archaeological interest discovered on the site of the Works shall as between the PAA and the Contractor be deemed to be the absolute property of the PAA and the Contractor shall take reasonable precautions to prevent his workmen or any other persons from removing or damaging any such article or thing and shall immediately upon discovery thereof and before removal acquaint the PAA of such discovery.

39 Variation

The Divisional Engineer may introduce any variations to the form, quality or quantity of the work or any part thereof which he considers necessary and for that purpose or if for any other reasons it shall, in his opinion be desirable, he shall have power to order the Contractor to do and the Contractor shall do any of the following:

- a) increase or decrease the quantity of any work included in the Contract;
- b) omit any such work;
- c) change the character or quality or kind of any such work;

- d) change the levels, lines position and dimension of any part of the Works; and
- e) execute additional work of any kind necessary for the completion of the works.

and no such variation shall in any way vitiate or invalidate the Contract nor it will entitle the Contractor of any claims for compensation whatsoever, but the value (if any) of all such variations shall be taken into account in ascertaining the amount of the Contract Price.

40 Order for variation to be in writing

No such variation shall be made by the Contractor without an order in writing from the Divisional Engineer. Provided that, subject to the provisions of the Contract, no order in writing shall be required for any increase or decrease in the quantity of any work where such increase or decrease is not the result of an order given under this Clause but is the result of the quantities exceeding or being less than those stated in the Bill of Quantities. If for any reason, Divisional Engineer considers it desirable to give any such order verbally, the Contractor shall comply with such order but shall get it confirmed in writing from the Divisional Engineer within four days of the issue of such verbal order.

41 Valuation of Variation

41.1 The Divisional Engineer shall determine the amount (if any) to be added to or deducted from Contract Price in respect of any variation, addition, or omission made by his order. The valuation of any variation, addition or omission shall be calculated on the basis of the unit prices contained in the Bill of Quantities if in the opinion of the Divisional Engineer the same shall be applicable; if not then on the market rates.

41.2 No deviation from specifications stipulated in the Contract or additional items of work shall be carried out by the Contractor unless the rates of the substituted, extra, altered or additional item have been approved in writing by the competent authority failing which the PAA will not be bound to entertain any claim on this account.

42 Quantities

The quantities set out in the Bill of Quantities are the estimated quantities of the work but they are not to be taken as the actual and correct quantities of the works to be executed by the Contractor in fulfilment of his obligation under the Contract.

43 Work to be Measured

The Divisional Engineer shall except as otherwise stated ascertain and determine by measurement the value of work done in accordance with the Contract. The Divisional Engineer shall, when he requires any part or parts of the Works to be measured, give notice to the Contractor or the Contractor's authorized agent or representative who shall forthwith attend or send a qualified agent to assist the Divisional Engineer or his representative in making such measurement and shall furnish all particulars required by either of them. Should the Contractor not attend or neglect or fail to send such agent, then the measurement made by the Divisional Engineer or approved by him shall be taken to be the correct



measurement of the work. The purpose of measuring is to ascertain the volume of work executed by the Contractor and therefore determine the amount of the monthly payments.

44 Method of Measurement

The works shall be measured, notwithstanding any general or local custom except where otherwise specifically described or prescribed in the Contract.


45 Clearance of Site on Completion

On the completion of the Works, the Contractor at his own cost shall clear away and remove from the Site all Constructional plant, surplus materials, rubbish and Temporary Works of every kind and leave the whole of the Site and works clean and in a workman-like condition to the satisfaction of the Divisional Engineer, rubbish should be disposed of in the manner as directed by the Divisional Engineer or his representative.

46 Certificates for Completion of Works

46.1 When the whole of the Works have been substantially completed and have satisfactorily passed any test on completion as prescribed by the Contract, the Contractor may give a notice to that effect to the Divisional Engineer accompanied by an undertaking to finish any outstanding work during the Period of Maintenance. Such notice and undertaking shall be in writing and shall be deemed to be a request by the Contractor, for the Divisional Engineer to issue a Certificate of Substantial Completion in respect of the Works. The Divisional Engineer shall, within twenty-one (21) days of the date of delivery of such notice either issue to the Contractor a Certificate of Substantial Completion stating the date on which, in his opinion, the Works were substantially completed in accordance with the Contract or give instructions in writing to the Contractor specifying all the work which, in his opinion, are required to be done by the Contractor before the issuance of such Certificate. The Divisional Engineer shall also notify the Contractor of any defects in the Works affecting substantial completion that may appear after such instructions and before completion of the work specified therein. The Contractor shall be entitled to receive such Certificate of Substantial Completion within twenty-one (21) days of completion, to the satisfaction of the Divisional Engineer, of the work so specified and making good any defect so notified. Upon issuance of the Certificate of Substantial Completion of the Works, the Contractor shall be deemed to have undertaken to complete with due expedition any outstanding work during the Period of Maintenance.

46.2 Upon satisfactory completion of the work outstanding on the Works, the Divisional Engineer shall within twenty-eight (28) days of the expiration of the Period of Maintenance issue a Certificate of Final Completion to the Contractor. The Contract shall be deemed to be completed upon issuance of such Certificate, provided that the provisions of the Contract which remain unperformed shall remain in force for as long as is necessary to dispose of any outstanding matters or issues between the Parties.



47 Period of Maintenance

The "Period of Maintenance" shall be of one-hundred eighty (180) days duration unless otherwise specified in the Special Conditions of the Contract, calculated from the date of completion of the Works stated in the Certificate of Substantial Completion issued by the Divisional Engineer in accordance with the Clause 46 hereof or, in respect of any Section or part of the Works for which a separate Certificate of Substantial Completion has been issued, from the date of completion of that Section or part as stated in the relevant Certificate. The expression "the Works" shall, in respect of the "Period of Maintenance", be construed accordingly.

48 Completion of Outstanding Works and Remedying Defects etc.

During the Period of Maintenance, the Contractor shall finish the work, if any, outstanding at the date of the Certificate of Substantial Completion, and shall execute all such work of repair, amendment, reconstruction, rectification and making good defects, imperfections, shrinkages or other faults as may be required of the Contractor in writing by the Divisional Engineer during the Period of Maintenance and within fourteen (14) days after its expiration, as a result of an inspection made by or on behalf of the Divisional Engineer prior to expiration of the Period of Maintenance. To the intent that the works shall as soon as practicable after the expiry of the Period of Maintenance be delivered to the PAA in as good and perfect condition (fair wear and accepted tear) to the satisfaction of the Divisional Engineer as that in which they were at the commencement of the Period of Maintenance. All such outstanding work shall be carried out by the Contractor at his own expense if the necessity thereof shall, in the opinion of the Divisional Engineer, be due to the use of material or workmanship not in accordance with the Contract, or to neglect or failure on the part of the Contractor to comply with any obligation expressed or implied, on the Contractor's part under the Contract. In case the Contractor fails to comply with the requirements of the notice within ten days from its issue, the Divisional Engineer shall have the power to have the works completed through any other agency at the risk and cost of the Contractor.

49 Refund of Security Deposits

The Security Deposit shall not be refunded prior to six months after the completion of the whole work, unless and until a certificate is issued by the Divisional Engineer for successful and satisfactory passing of the Period of Maintenance with no other liability on the Contractor.

50 Contractor's Liability for Damage done

If the Contractor or his workmen or servants shall break, deface, injure or destroy any part of a building, in which they may be working or any building, road, road kerbs, runway, taxiway, apron, culverts, ducts, fence enclosure, water pipes, cables, drains, electric or telephone or wire poles, trees, grass or grassland or cultivated ground contiguous to the premises on which the work or any part of it is being executed, or if any damage shall happen to the work, while in progress from any cause whatsoever, or any imperfections become apparent in it within three (03) months after a certificate, final or otherwise of its completion shall have been given by the Divisional Engineer as aforesaid, the Contractor shall make the same good at his own expense, or in default, the Divisional Engineer may cause the same to be made good by other workmen, and deduct the expense (of



which the certificate of the Divisional Engineer shall be final) from any sums that may then, or at any time thereafter may become, due to the Contractor, or from his security deposit or the proceeds of the sale thereof, or a sufficient portion thereof.

51 Assignment & Sub-Letting

The Contractor shall not assign or sublet the Contract or any part thereof or any benefit or interest thereon or there under without the prior written consent of PAA. In case of failure, the Divisional Engineer shall by giving Notice in writing rescind the Contract and have the Works executed at the risk and cost of the Contractor.

52 Stores to be supplied by PAA


If the specification or estimate of the work provides for the use of any special description of materials to be supplied by PAA or if it is required that the Contractor shall use certain stores to be provided by the PAA (such materials and stores, and the prices to be charged therefore as hereinafter mentioned being so far as practicable for the convenience of the Contractor, but not so as in any way to control the meaning or effect of this Contract, specified in the schedule of memorandum hereto annexed). The Contractor shall be supplied with such materials and stores as required from time to time to be used by him for the purpose of the Contract only, and the value of the full quantity of materials and stores so supplied at the rates specified in the said schedule or memorandum may be set off or deducted from any sums then due, or thereafter to become due to the Contractor under the contract or otherwise or against or from the security deposit, or the proceeds of sale thereof. All materials supplied to the Contractor shall remain the absolute property of PAA and shall not on any account be removed from the Site of the work and shall at all times be open to inspection by Divisional Engineer. Any such material unused and in perfectly good condition at the time of the completion or termination of the Contract shall be returned to PAA; but the contractor shall not be entitled to return any such materials unless with such consent, and shall have no claim for compensation on account of any such materials so supplied to him, as aforesaid being unused by him, or for any wastage in or damage to any such materials.

53 Bills to be submitted monthly

A bill shall be submitted by the Contractor each month on or before the date fixed by the Divisional Engineer for all works executed in the previous month and the Divisional Engineer shall take or cause to be taken the requisite measurement for purposes of having the same verified, and the claim, as far as admissible, adjusted, if possible, before the expiry of ten days from the presentation of the bill. If the Contractor does not submit the bill within the time fixed as aforesaid, the Divisional Engineer may prepare a bill which shall be binding on the Contractor in all respects.

54 Completion drawings

The completion report of the work along with drawings on prescribed proforma shall be submitted by the Contractor in five copies along with the final bill. In case of failure to submit the completion report and completion drawings by the Contractor on the basis of which the work has been finally completed, the final bill shall be withheld till their submission. The completion report and drawings should be complete in all respects.



Works relating to maintenance do not come under the preview of this clause.

55 Final Bills

The final bill shall be submitted by the Contractor within one month from the date of completion of the Works otherwise the Divisional Engineer's certificate of the measurement and of the total amount payable for the work accordingly shall be final and binding on all parties, and will not be called in to question by anyone.

56 Urgent repair

If by reason of any accident or failure or other event occurring to or in connection with the Works or any part thereof during the execution of the Works or during the Period of Maintenance any remedial or other work on repair shall in the opinion of the Divisional Engineer or his representative be urgently necessary and the Contractor is unable or unwilling at once to do such work or repair, the Divisional Engineer may by his own or other workmen do such work or repair as the Divisional Engineer or his representative may consider necessary. If the work or repair so done by the Divisional Engineer is work which in the opinion of PAA the Contractor was liable to do at its own expense, under the Contract, then all costs and charges properly incurred by the PAA, in so doing shall on demand be paid by the Contractor to the PAA or may be deducted by PAA from any monies due or which may become due to the Contractor. Provided always that the Divisional Engineer shall as soon as after the occurrence of any such emergency as may be reasonably practicable notify the Contractor thereof in writing.

**57 Bribes,
Commission etc.**

Any bribe, commission gift or advantage given promised or offered by or on behalf of the Contractor or his partner, agent, or servant in relation to obtaining or to the execution of this or any other Contract with PAA, or given, promised, or offered by, or on behalf of, the Contractor, or his partner, agent, or servant, to any officer or person in the service or employment of PAA, who shall be in any way connected with the obtaining or the execution of this or any other Contract, shall in addition to any criminal liability, which he may incur subjects the Contractor to cancellation of this Contract, and also to payment of any loss resulting from any such cancellation. Any question or dispute to the commission of any offence under this Clause shall be settled by the PAA, in such manner as it deems fit and sufficient and its decision shall be final and conclusive.

**58 Law governing the
contract**

This Contract shall be governed by and construed in accordance with the laws of the Islamic Republic of Pakistan, and the obligations, rights and remedies of the parties hereunder shall be determined in accordance with such laws. Resort to litigation by either of the parties in respect of any disputes should be had only before a court of appropriate and competent jurisdiction.

**59 Increase or
Decrease of Cost.**


59.1 The Contractor is deemed to have quoted rates given in the Contract (Bill of Quantities) based on the prices of certain specified materials

prevalent in the month during which the last day of the submission of Bid fell.

- 59.2 No price adjustment shall be allowed under this clause except in respect of the materials specified in Appendix-A to Bidding Document which have actually been incorporated in the Permanent Works during the corresponding period of increase or decrease.
- 59.3 Adjustment shall be allowed for the specified materials according to the method prescribed in the Appendix-A to Bidding Document.
- 59.4 All claims for additional payments under this Clause shall be lodged by the Contractor with the Divisional Engineer within such reasonable time from the date of occurrence of the event which, according to the Contractor, entitles him to such additional payments by PAA, but in no case after the expiry of twenty-eight (28) days thereof, such claims shall invariably be supported with all relevant necessary details and particulars required for proper verification thereof and the Divisional Engineer shall be entitled to require the Contractor to provide such further details / information as may be required for due and effective verification of such claims.
- 59.5 The Divisional Engineer shall verify and certify for payment, if any, claims lodged by the Contractor under this Clause within a period not exceeding twenty-eight (28) days from the date on which the same are submitted by the Contractor as aforesaid.
- 59.6 In case the PAA is entitled to recover from the Contractor any sum or sums under this Clause arising from any decrease in the said prices for materials, the provisions of this Clause shall apply mutatis mutandis to such recoveries by the PAA.
- 59.7 If the Contractor fails to complete the works within the time for completion, adjustment of prices therefore until the date of completion of the works shall be made using either the indices or prices, whichever are more favourable to the PAA, provided that if extension of time is granted the above provision shall apply only to adjustments made up to the expiry of such extension of time.
- 59.8 No escalation shall be allowed to the Contractor in respect of the period extended for the completion of the work due to his own fault.

**60 Water Supply/
Power Supply etc.**

The Contractor should make his own arrangement for water and power supply required for execution of work and nothing will be paid for the same, by the PAA. Provided that in case water supply is allowed by the PAA to the Contractor from water mains passing through areas where the work is required to be carried out, the Contractor shall pay the cost of water to the department at one-half (1/2) per cent of the total cost of work for drinking purpose and one (01) per cent of the total cost of the items of work involving use of water (that is for constructional purposes). The Contractor shall bear full charges for laying its water lines of all length and size / dimensions from the mains to the site of his underground tanks as he may require and construct for storage purposes at its own cost.



- 61 Abandonment of work by PAA.** PAA shall have the power to abandon any work whether in progress or otherwise and in such an event, the Contractor shall have no claim for any compensation of any kind whatsoever from PAA except the actual cost of the work executed at the Site under the Contract for which the contract requires payment to be made.
- 62 Materials obtained from excavation & dismantling.** All materials (e.g. stone and other materials) obtained in the work of dismantling, excavation etc., will be considered PAA property and may be issued to Contractor (if they require the same for their own use) at rates approved by the Divisional Engineer. If these materials are not required by them, they will be disposed of as found fit by the PAA.
- 63 Danger Signs to be provided by Contractor** Lights for illumination, danger signs for warning, and information / cautionary signs in approved colours and sizes shall be provided by the Contractor wherever required at his own cost on the barriers as directed by the Divisional Engineer.

SPECIAL CONDITIONS OF CONTRACT

6 Possession of Site

(Substitute the clause 6 with following text)

- 6.1 The Divisional Engineer shall, together with the written order to commence the Works, grant the Contractor possession of such portions of the Site as are necessary to enable the Contractor to commence and carry out the Works in accordance with the programme referred to in Clause 10, subject to any sequencing or phasing requirements prescribed in the Contract.
- 6.2 Thereafter, and from time to time as the Works progress, the Divisional Engineer shall grant possession of further portions of the Site, as required for execution of the Works with due dispatch, provided such possession aligns with the Contractor's reasonable proposals as approved by the Divisional Engineer.
- 6.3 The Contractor shall submit any such proposals for staging of site possession in writing to the Divisional Engineer for review and approval, and no right to possession shall arise unless and until expressly granted by the Divisional Engineer.
- 6.4 PAA shall not be liable for any delay or claim arising from staged or partial possession of the Site, provided such staging is consistent with the Contract or approved programme.

10 Programme to be furnished

(For works with a contract price exceeding the financial limit prescribed for PEC Constructor Registration Category C-3, as revised from time to time, Clause 10 shall be substituted with the following text)

- 10.1 The Contractor shall, within fifteen (15) days of receiving the Letter of Acceptance, submit a detailed Programme of Works to the Divisional Engineer for approval. The Programme shall include all activities, including mobilization, and clearly identify critical path items using a computerized Critical Path Method (CPM) format. The Programme shall be updated monthly, incorporating a chart of forecasted principal activities, an updated cash flow schedule for payments, and any revisions necessary to reflect actual progress. It shall serve as the baseline for assessing progress and determining Liquidated Damages under Clause 29. Monthly progress reports shall include an up-to-date analysis of actual versus planned progress, identification of current or emerging critical items, and the Contractor's proposed measures for mitigation.

18 Quality of Material, Workmanship and Tests

- 18.2 Expenditure on account of laboratory testing to ascertain suitability of materials and all other required tests etc. shall be borne by the Contractor.

24 Extension of Time for Completion

(For works with a contract price exceeding the financial limit prescribed for PEC Constructor Registration Category C-3, as revised from time to time, Clause 24 shall be substituted with the following text)

- 24.1 In the event of:
 - (a) the amount or nature of extra or additional work,
 - (b) exceptionally adverse climatic conditions,
 - (c) any delay, impediment or prevention by the PAA, or
 - (d) other special circumstances which may occur, other than through a default of or breach of contract by the Contractor for which he is responsible, being such as fairly to entitle

the Contractor to an extension of the Time for Completion of the Works, or any Section or part thereof,

the Divisional Engineer shall, after due consultation with the Contractor, determine the amount of such extension and shall notify the Contractor accordingly. Provided that the Divisional Engineer is not bound to take into account any extra additional work or other special circumstances unless the Contractor has within fourteen (14) days after such work has been commenced or such circumstances have arisen, delivered to the representative of the Divisional Engineer full and detailed particulars of any claim for extension of time to which he may consider himself entitled in order that such claim may be investigated at the time.

25 Termination of Contract for slow progress

25.1 In the event of termination by the Divisional Engineer, the Contractor shall have the right to file an appeal before the Director General PAA, within seven (07) days from the receipt of such termination notice. The decision of the Director General PAA shall be final and binding.

29 Liquidated damages for delay

29.2 The amount of Liquidated Damages for each day of delay in completion of the whole of the Works, or if applicable for any Section thereof, shall be imposed at the rate of 0.05% of Contract Price as stated in Letter of Acceptance for each day of delay in completion of the Works. Provided that the amount of Liquidated Damages for delay shall not exceed ten (10) per cent of the Contract Price as stated in Letter of Acceptance in all cases.

29.3 In cases where liquidated damages have been imposed or have been proposed to be imposed, the amount to be retained in lieu of Security Deposit during the Maintenance Period shall be based on the cost of works executed, and not the reduced amount to be paid to the Contractor after imposition of liquidated damages.

29.4 Where a work has been delayed beyond the stipulated date of completion, the Contractor shall be required to extend the securities and insurances as per the revised dates at his own cost.

31 Suspension of Works

31.2 Partial / complete suspension in work is likely to take place during emergency operations and VIP movements etc. labour, equipment, and material, etc. shall be removed from the site of work during such suspension periods to a distance for essential security requirements. No compensation whatsoever on this account shall be claimed by the Contractor for those losses likely to occur. All such unforeseen disruptions during working hours may result in idleness of manpower and equipment and waste of material, etc. for which no compensation shall be paid to the Contractor.

31.3 No compensation is payable for interruption in the work due to any reason beyond the control of PAA.

32 Care of Works

32.2 The Construction materials should be stacked at a suitable place as per the direction of the Divisional Engineer or his representative.

32.3 The work shall be so arranged as not to cause any disturbance to the passengers / functionaries and other agencies working at the airport.

41 Valuation of Works

41.3 For works items described in the priced bill of quantities (BoQ), the valuation of works shall be made by applying the overall percentage (below / above) of the quoted bid to each item of the BOQ to work out rates for individual items , and



41.4 For work items not described in the priced bill of quantities (BoQ) but available in the Pak PWD Schedule of Rates (SoR) 2022, the valuation of works shall be made on pro rata basis, wherein the calculation for rates of individual items will be done in the same way as described in clause 41.3 and

41.5 For work items neither described in the priced bill of quantities (BoQ) nor available in the Pak PWD Schedule of Rates (SoR) 2022, the valuation of works shall be made on the basis of actual cost (market rates) plus a lumpsum of twenty-five per cent (25%) as overheads and profit.

47 Period of Maintenance

47.2 Period of Maintenance or Defects Liability Period shall be of 365 days duration.

59 Increase or Decrease of Cost

59.9 The Price Adjustment shall be applicable only for the Contracts having stipulated completion period of eighteen months or above and contract price exceeding financial limit of PEC Constructor's Registration Category C-3 as amended from time to time. Contracts having stipulated completion period less than eighteen months and value equal to or less than the above said limit will be considered as fixed price contracts. The price adjustment shall be done for the items mentioned in Appendix- A to SCC as per the conditions spelled out in Note (1) in the Appendix- A to SCC.

64 Settlement of Disputes

64.1 Any difference or dispute arising between the PAA and the Contractor regarding the interpretation, execution, or performance of any provision of this Contract shall be referred exclusively to the Director General PAA, whose decision shall be final, conclusive, and binding on both parties. The Contractor shall not initiate or pursue any legal proceedings or remedies in relation to such matters. This shall be without prejudice to the rights of the parties under the applicable laws.

65 Authenticity of Financial Instruments

65.1 Any financial instrument, submitted by the Contractor as Bid Security, and Performance Guarantee, if found fake or dishonoured by the issuing bank / financial institution at any pre- / post-contractual stage shall, in addition to any criminal liability, call for blacklisting of the Contractor.

66 Obligations of the Contractor


66.1 The Contractor, during the execution of works, shall be responsible for following the instructions and directions of the Divisional Engineer or his representative only.

66.2 The Contractor shall be responsible to provide and use quality construction material as per the specifications, and to the satisfaction of the Divisional Engineer.

66.3 The Contractor shall strictly adhere to all design requirements and technical specifications established by the Design Engineer and approved by PAA. The charges of which shall be borne by the Contractor, but the additional quantity of any materials used in executing the Works shall be paid as per Contractor's quoted rate.

66.4 The Contractor shall clean the existing rusty steel by approved means at his own cost and no compensation whatsoever shall be given to the Contractor.

66.5 The Contractor will be fully responsible to arrange security clearance of his workmen employed on the job in accordance with the rules requirements enforced at the time of



execution and shall not be entitled for any compensation whatsoever on account of wastage of time and labour due to any reason.

- 66.6 The Contractor shall enclose the work / site area as per direction of the Divisional Engineer or his representative at his own cost. He will also ensure safety of workers as well as passenger(s) and airport staff during and after the work hours.
- 66.7 The Contractor shall submit a list of fittings, fixtures, equipment etc. to be dismantled as approved by Engineer In charge accordingly.
- 66.8 Generally, the works will be carried in accordance with Electrical Act 1910 read with Electricity Rules 1937 and any amendments thereto, Pak PWD Specifications for Electrical Works & latest editions of I.E.E rules of Building Equipment.
- 66.9 All wires & Cables to be used for executions of work will be copper conductors.
- 66.10 Damages done by the contractor during execution of work will be made good by the Contractor as per Engineering specifications and to the complete satisfaction of the Engineer In charge.
- 66.11 The contractor will perform all types of tests as directed by E&M Engineer In charge after / before executions of his work & will submit test reports in this regard if required.
- 66.12 Cost of samples of materials will not be claimed & test charges for all required tests as instructed by the E&M Engineer from Govt. or other authorities will be borne by the contractor without any extra claim of this effect.
- 66.13 The Contractor will submit warranty / guarantees & literature of the Air-Conditioning equipment, Electrical equipment or Mechanical equipment etc. as desired by Engineer In charge.
- 66.14 The approved makes of materials, accessories & equipment are provided in Appendix-F. works shall be executed subject to approval of samples from Engineer In charge.
- 66.15 Any equipment / items during execution / testing / commissioning & during maintenance period if burnt out / malfunctioning or broken will be replaced by the contractor without any extra cost.
- 66.16 The contractor shall prepare / submit detailed shop drawings, level sheets (X-sections/ L-sections etc.) at his own cost and get approved by PAA before execution of work if, so required. The contractor shall provide complete As-built drawings of all the construction facilities without any extra cost
- 66.17 Afghan and suspected person holding old NIC will not be engaged by the contractor.
- 66.18 Provincial Sales Tax (PRA) is not applicable on PAA being a federal entity. In this regard Supreme Court Decision in favour of PAA under write petition No. SCMR 1344 of 2017 exists. Bidders are required to quote their rates excluding PRA Tax.
- 66.19 For works costing more than Rs. 65 Million, the Contractor may be given a Mobilization Advance of up to 10% of the bid cost by PAA on production of an irrevocable bank guarantee of an equivalent amount from Banks approved by PAA (as per the list provided in Appendix-E to Bidding Documents). Deduction shall be made at the amortization rate of 17.5 % of the value of the Works executed of each IPC as provided in paragraph (i) of Sub-Clause GCC 14.3, starting from 2nd IPC provided that the advance payment shall be completely repaid prior to the time when 90% of the Accepted Contract Amount less Provisional Sums has been certified for payment. It may be more than 17.5% in the last instalment to ensure full repayment. .
- 66.20 The contractor shall provide the following items without any extra cost as their cost shall be deemed to have been included in the price quoted by the Contractor for the works whereas Items mentioned at Sr. No. (i) to (v) upon expiry of contract period shall remain

the property of the PAA:-

- 04 Nos. File Rack / Steel Cabinet
 - 02 Nos. External Hard Disk (1 TB)
- 02 Nos. DESKTOP Computers with Motherboard supporting DDR5 RAM, 14th Generation processors, Core i5, 14th Generation i5 HX Processor, 8GB NVIDIA GeForce RTX 3050 GDDR6, 16GB RAM DDR5 & 512 GB / 1TB ROM SSD
 - 01 No. Canon Image Formula R40 Office Scanner
 - 01 No. Printer LaserJet Pro 400 1dn or equivalent
 - 01 No. Hiring of Hilux Double Cabin with POL and driver from start of work to 03 months after completion of work
 - 02 Nos. FIDIC Red Book Conditions of Contract for Construction (Second Edition) Published in 2017 (and reprinted with amendments in 2022)

SCHEDULE OF BASIC PRICES OF SPECIFIED MATERIALS

A) Basic Price Materials (To be filled by the Bidder)

We confirm herewith that the following prices were prevalent in the month during which the last day of the submission of bidder fell and have been taken as a basis for computing the prices governing our total bid cost.

Adjustment of increase / decrease in price shall only be admissible for the materials listed herein under:

S.No.	Materials	Unit	Basic Price Ex-Factory/Works	Remarks
1	2	3	4	5
1.	Cement i) Ordinary Portland Cement ii) Sulphate Resisting Cement	Bag (50 Kg)		The basis of the rate is the Monthly Statistical Bulletin issued by the Pakistan Bureau of Statistics. -- do --
2.	Steel i) Reinforcement Bars ii) M.S. Sections	Kg		-- do -- -- do --
3.	Bitumen i) Grade 60/70 ii) Grade 80/100 iii) Cutback Bitumen a) Medium Curing b) Rapid Curing	Tonne (1000Kg)		The basis of the rate is the Monthly Statistical Bulletin issued by the Pakistan Bureau of Statistics. If not available then basis would be National Refinery, Attock Refinery or from an approved equivalent source. -- do -- -- do -- -- do -- -- do --
4.	Bricks First class	Cft		The basis of the rate is the Monthly Statistical Bulletin issued by the Pakistan Bureau of Statistics.
5.	Coarse Aggregate	Cft		-- do --
6.	Paint	Sft		-- do --

Note:

(1) If the price paid by the Contractor for any of the Specified Materials shall differ from the basic thereof and shall cause an increase or decrease of cost to the extent of five (5) per cent or more to the Contractor in carrying out the Contract, the increase or decrease of such cost shall be adjusted in the Contract Price accordingly. The actual payments shall be made on the basis of quantities actually measured and certified for payment. Any fluctuation in the prices of materials other than the Specified Materials shall not be subject to adjustment of the Contract Price.

(2) The Bidders shall submit satisfactory documentary evidence (Price Bulletin from PBS etc.) in support of the rates and prices filled up in this Appendix.

We agree that price variation in the above listed basic prices during the currency of the Contract will be adjusted only to the extent as stipulated under the Conditions of Contract.

Authorized Signatures _____

Name _____

Seal _____

Date _____

For PAA



A-1

For Contractor

MATERIALS TO BE PROVIDED BY PAA

Schedule showing (approximately) materials to be supplied by the PAA under Clause 52 of the General Conditions of the Contract or for work contracted to be executed and the rates at which they are to be charged for

Particulars	Rate at which the material shall be charged to the Contractor		Place of Delivery
	Unit	Rs.	
	<i>NIL</i>		

Note: The person or firm submitting the Bid should see that the rates in the above schedule are filled up by the Divisional Engineer on the issue of the form prior to the submission of the Bid.

PAKISTAN AIRPORTS AUTHORITY
(Engineering Services E&M Works)


SPECIAL TERMS & CONDITIONS

Name of Work: **CRITICAL REQUIREMENTS OF SECURITY EQUIPMENT AND
OTHER PARAPHERNALIA**


1. The execution of all the items in BOQ is subject to the prior approval of Engineer In-charge before import / delivery of material / equipment at site.
2. The contractor shall arrange all tools and test equipment required for execution of work as laid down in the B.O.Q.
3. The contractor shall be responsible to coordinate with M/s LESCO for new electricity connection/load extension (as applicable) without any extra cost. This also include preparation of necessary documents and completion of formalities. However, the demand draft issued by M/s LESCO shall be paid by PAA in lieu of requisite work after thorough verification.
4. The contractor shall get the work executed through his trained staff and if any discrepancy is found during execution of work, he shall report the matter to the Engineer In-charge well in time and shall act as directed.
5. The contractor keep liaison with site engineer and with his staff and shall inform about the progress of the work on regular basis to avoid any hindrance in the progress of the work at site.
6. The contractor shall not claim any extra payment for wastage of manpower, suspension of work due to VIP/VVIP moments or any other operational reasons.
7. Security clearance of staff and labor shall be the responsibility of the contractor as required under the Airport Security Force (ASF) rules for obtaining airport entry pass, if the work is to be executed in the restricted areas of the aerodrome as well.
8. All watch and ward of equipment and material shall be the responsibility of the contractor during the execution of the work.
9. The import documents including but not limited to the purchase order, bill of lading etc must be submitted along with the material inspection request.
10. The amount of LD for each day of delay in completion of the whole of works, or if applicable for any section thereof, shall be or equal to 10% (Ten Percent) of the contract price stated in the letter of acceptance divided by the number of days specified as completion time.
 - i.
$$\frac{10\% \times CP \times N}{T}$$
 - ii. Where the contract completion period is more than 200 days = $0.05\% \times CP \times N$
{CP = Contract Price, T = Contract Completion Period, N= No. of days delayed}


(ENGR. IMRAN NASIM FARUKH)
Divisional Engineer ES E/M
PAA, AllAP, Lahore

DIVISIONAL ENGINEER E&M
PAA, AllAP, Lahore




PROJECT:	LAYOUT PLAN OF BERRACKS	PLOT SIZE:-	DESIGN BY:- Engr: AKbar Khan
TITLE:		SHEET NO:- A-001	VETTED BY:- ENGR: KAMRAN ULLAH




COLUMN LAYOUT PLAN

PROJECT:	COLUMN LAYOUT PLAN OF OFFICERS	PLOT SIZE:-	DESIGN BY:-
TITLE:	ACCOMODATION	SHEET NO:- A-001	Engr: AKbar Khan
			VETTED BY:- ENGR: KAMRAN ULLAH




EXCAVATION LAYOUT PLAN

PROJECT:	FOOTING LAYOUT PLAN OF OFFICERS ACCOMODATION	PLOT SIZE:-	DESIGN BY:- Engr: AKbar Khan
TITLE:		SHEET NO:- A-001	VETTED BY:- ENGR: KAMRAN ULLAH




EXCAVATION LAYOUT PLAN


PROJECT:	FOOTING LAYOUT PLAN OF OFFICERS	PLOT SIZE:-	DESIGN BY:- Engr: AKbar Khan	
TITLE:	ACCOMODATION	SHEET NO:- A-001	VETTED BY:- ENGR: KAMRAN ULLAH	




PROJECT:	ROOF BEAM PLAN OF OFFICERS ACCOMODATION	PLOT SIZE:-	DESIGN BY:- Engr: AKbar Khan
TITLE:		SHEET NO:- A-001	VETTED BY:- ENGR: KAMRAN ULLAH







PROJECT:	SLAB PLAN OF OFFICERS ACCOMODATION	PLOT SIZE:-	DESIGN BY:- Engr: AKbar Khan
TITLE:		SHEET NO:- A-001	VETTED BY:- ENGR: KAMRAN ULLAH




PROJECT:	BEAM REINFORCEMENT DETAIL	PLOT SIZE:-	DESIGN BY:- Engr: AKbar Khan
TITLE:	OF BERRACKS	SHEET NO:- A-001	VETTED BY:- ENGR: KAMRAN ULLAH





PROJECT:	ISOLATED FOOTING REINFORCEMENT DETAIL	PLOT SIZE:-	DESIGN BY:- Engr: AKbar Khan	
TITLE:	OF BERRACKS	SHEET NO:- A-001	VETTED BY:- ENGR: KAMRAN ULLAH	


DRAWING OF BARRACK FOR 192 PERSONNEL



G+2

CAPACITY OF ACCOMMODATION =192 PERSON
 GROUND FLOOR COVERED AREA =6395.23 SFT
 SUN SHED AREA 1/2 = 356.75 SFT
 TOTAL =6752.00 SFT

JS Apartment
(2 Bed)




MDS (3 Bed)

ANNEX-C



DRAWING OF 3 BED MOQS

ANNEX-C




WORKING DRAWING OF GROUND FLOOR


G+3

AREA ONE MOQs

GROUND FLOOR AREA COVERED = 4576.00 SFT

= 2242.00 SFT






FIRST FLOOR REINFORCEMENT PLAN (BOTTOM BARS)


FIRST FLOOR REINFORCEMENT PLAN (TOP BARS)

NOTES

- 1 - ALL SLABS ARE 5" THICK EXCEPTED NOTED OTHERWISE.
2 - BIDDING BARS FIGHT-IT UNLESS OTHERWISE REQUIRED.

[illegible]






LIST OF APPROVED MANUFACTURERS / SOURCES

This list of recommended manufactures / suppliers of different materials / equipment with brand names have been provided in order to establish a standard level of performance. The Contractor is supposed to provide and fix the materials / equipment of acceptable quality from the list or equivalent as approved by the Engineer. Whereas the preference of brand and model will be decided by the Engineer. Material from approved list shall stand rejected, if it fails in any of the specified tests or quality standards.

Sr. No.	Description	Manufacturer/Supplier/Source
Civil Works		
1	Cement (OPC, SR)	Lucky, Pioneer, Maple Leaf, Fauji, Askari, Power, Cherat, DG Khan, Dewan
2	Cement (White)	Kohat, Maple Leaf, Zealpak
3	Construction Chemicals & Sealants	Sika, Fosroc, BASF, Ultra, Fastchem, Vertex, MAPEI, KALON, Mitchell
4	Anchoring / Fixing Systems	Strong hold, Strong force, Hilti, Fischer
5	Sand	Bholari or from any other approved source as per Mix Design.
7	Aggregate	From approved source.
8	Steel Reinforcement	Amreli, FF Steel, AFCO, Ittehad, Ittefaq, Fazal, PECO, Razzaque, Metropolitan, Mughal, Pak Steel, Model Steel, Nizami Brothers, Moiz Steel, Poiner, Tayyaba Steel or approved equivalent.
9	Bitumen (Cold)	National Refinery, Attock Petroleum, PARCO
10	Bricks/Blocks	Local (Brand / source to be approved by the Engineer)
11	Ceramic Tiles	Shabbir, Master, Time Ceramic, National, or equivalent imported
12	Vinyl Tiles	Decora, Marflex, A.T.S. Synthetic
13	Wooden Flooring	Sarina, Firstfloor or equivalent
14	Textured Decorative Wall Coating	Rockwall, Wall Tec, Rock Shield, Sand Tec, Graffito, Jotun
15	Aluminium Doors / Windows	ALCOP, Pakistan Cables, Chawla, Prime, Ittehad Aluminium, Thermec, Eng: Co, Alhali Aluminum Co (Pvt) Ltd, Krudson, Lucky or equivalent
16	Aluminium Composite Panel	ALCOP, Chawla, Pakistan Safety Glass (Alucobond), AKB (EuroBond – Exterior. & DuBond – Interior)
17	Paint	ICI (Dulux, Paintex), Berger Robbialac, Brighto, Master, Kansai (Japan), Nippon, Jotun, Diamond, Buxly, Pakistan Phthalates Limited (Kalon Chemicals Company) or equivalent.
18	Powder Coating	Jotun or approved equivalent
19	Concrete Pavers	Tuff Tiles, Izhar, Envicrete, National Pavers, Banu Mukhtar, Magnacrete or equivalent
20	Insulation	Diamond (Jumbolon), Pakistan Insulations, Safe line, Insugreen



Sr. No.	Description	Manufacturer/Supplier/Source
21	Membranes for Roof and Basement walls	Polytec (Henkel Polybit), Hygrip, Roof Grip, A.T.S. Synthetic, Petro Seal, Bitumat (Saudi Arabia), Pakistan Phthalates Limited (Kalon Chemicals Company), Sika Raingard
22	uPVC Doors / Windows	Framez, Uniwin, Nasar Steel, U-Tech, Green Door, V-Make, Chawla
23	Steel Doors and windows	SECCO or any other approved equivalent
24	Termite Proofing	Agenda (Termidor), Biflex, Fiprokil, Mirage, Termicure, Ability
25	Terrazzo Tiles	As approved by Engineer
27	Pre-Engineered Steel Buildings	Zamil, Mammut, Mabani, Kirby, Banu Mukhtar, Izhar, SACHAL
28	Gypsum False Ceiling	Elephant, Lodhia (Arish), DFB, United
29	Glass	Pakistan Safety Glass, Ghani, Al-Fattah, Khawaja, Nowshera Prince or equivalent.
30	Door hardware	Kolf, Sitara Hardware, Jb.Saeed, IM Hardware (Yale), Alpha, Khas, Babar, or approved equivalent.
32	SS Railing	Dah Shi (Taiwan) or equivalent
33	Medium Density Fibreboard	Al-Noor, ZRK, Nuboard or equivalent.
34	High Density Fibreboard	Patex, Sonitex or equivalent
35	Plywood	Patex, Marineplex or equivalent.
PUBLIC HEALTH WORKS		
1	Sanitary Ware (WC Indian, WC European, Basin / Vanity, Urinal, Flushing Cistern)	Porta, Marachi, Master, ICL, Finecera, Karam, Cera and 3 Star or equivalent.
2	Bottle trap	Porta, Master, Faisal, Sonex, Asia and Super Asia or equivalent.
3	Bath / Kit. Fittings	Porta, Master, Faisal, Sonex or equivalent.
4	PPR-C Pipes & Fitting	Dadex, Beta, Master, Plasco, Turk Plast, Popular Pipe, Accufit, Minhas, Dura Built, IIL, Builtec, Euro Gulf, YAH Plastic Industry, Pelikan Pipe Industry (Civic)
5	uPVC Pipes & Fittings	Dadex, Shavyl, Galco, Beta, Turk Plast, Jamal, Fast Flow, Plasco, Popular Pipe, Master, Accufit, Dura Built, Builtec, Euro Gulf, YAH Plastic Industry, Newtech, Pelikan Pipe Industry (Civic), Prime Star Industries or approved equivalent.
6	RCC Pipe	Shalimar, Pakistan Pipes, National Pipe Industry
7	G.I. Pipes	International Industries Ltd. (IIL), Master Pipe, Jamal, Victory, Steelelex or equivalent
8	C.I. Pipes	C.I. Engineering / Corp: Teepu, Alpine, NPC and CME or equivalent.
9	Gate / Sluice Valves	KITZ (Star Corporation), Teepu, Anwer, Asia, Rehman Group, Sirajia Trading co.



Sr. No.	Description	Manufacturer/Supplier/Source
10	G.I. Fittings	KITZ (Star Corporation), Health Engineering (HE)
11	C.I. Fittings & Valves	Teepu, Alpine, Sirajia Trading co.
12	C.I. Manhole Cover	CME, Teepu, Alpine, Turk Plast
17	MS Seamless Pipe	Huffaz Industries, Jamal, KITZ, Sirajia Trading co., Master Pipes, Victory
18	PVC Water Stop	Fosroc, Sika, Decora, Marflex
19	HDPE pipe and Fittings	Dadex, Jamal, Plasco, Turk Plast, Beta, Popular Pipe, Accufit, IIL, DURA BUILT, Bultec, Fast Flow, YAH Plastic Industry, Newtech, Pelikan Pipe Industry (Pelikan), Prime Star Industries
21	Water Tank	Master, Super Tuff, Dura, Accufit, Prime Master
22	Kitchen Sink	Porta, Atlas, Asia or approved equivalent
ELECTRICAL & MECHANICAL WORKS		
1	Wires and Cables	Pakistan Cables, Fast, AGE, Newage, GM
2	Air Switch Breaker, Load brake switches, MCCB and MCB etc.	Terasaki Japan, Siemens, ABB, MG, Hager, Schneider Electric
3	Switches and Sockets	Schneider, Philips
4	Down Light/ Batten Lights	Sunlight, Pierlite, Future Technology, Orient
5	Flood Lights	Philips/ Signify, Osram, GE, Thorn
6	Fans Ceiling/Exhaust/Bracket	Pak, Royal, SK, Super Asia,
7	UPS	Huawei, Homage, Inverex, Goodwee, Crown, Fronius, APC
8	Tubular batteries	AGS, Phoenix, Osaka, Exide, Volta
9	AC Units	Gree, Haier, Orient, Green Air, Dawlance, PEL, Kenwood
10	Air Curtains	Gree, Haier, Orient, Green Air, Dawlance, PEL, Kenwood or Equivalent
11	PVC Conduits and Pipes	Polupar, Galco, Sheval, Adamjee, GM, Dadex
12	PVC Cable Trunk	Adamjee, Jeddah or equivalent
13	Termination Kit / Straight Jointing Kit	Raychem (Germany), 3M (USA), Elastimod (Egypt)
14	LV main distribution panel	Siemens, PEL, FICO, Schneider Electric, ABB, Sunbeams, Engineers & Engineering, Libra, Hussein & Co., BLS

LIST OF BANKS

Following is the list of approved schedule banks (financial institutions) acceptable to PAA for obtaining Bank Guarantee(s):

Public Sector

- 1) National Bank of Pakistan
- 2) Sindh Bank Limited
- 3) The Bank of Punjab

Private Sector

- 4) Allied Bank Limited
- 5) Askari Bank Limited
- 6) Bank Al Habib Ltd.
- 7) Faysal Bank Ltd.
- 8) Habib Bank Ltd.
- 9) Habib Metropolitan Bank Ltd.
- 10) JS Bank Ltd.
- 11) MCB Bank Ltd
- 12) Samba Bank Ltd.
- 13) Soneri Bank Ltd.
- 14) Standard Chartered Bank Ltd.
- 15) United Bank Ltd.
- 16) Industrial and Commercial Bank of China Ltd.

Islamic Banks

- 17) Al Baraka Bank (Pakistan) Limited
- 18) BankIslami Pakistan Limited
- 19) Dubai Islamic Bank (Pakistan) Limited
- 20) Meezan Bank Limited

Chapter 1

INTRODUCTION

1.1 INTRODUCTION

Integrated Management System comprising International Management System standards ISO 9001: 2008 (Quality Management System), ISO 14001: 2004 (Environmental Management System), OHSAS 18001: 2007 (Occupational Health and Safety Management System), and ICAO's SMS (Safety Management System) has been implemented in Pakistan CAA. These standards require adherence from all the stakeholders to fulfill their respective obligations towards vital aspects of Safety, Quality, Occupational Health and Environment. This HSE Manual outlines the responsibilities of contractors, suppliers and concessionaires working for CAA or on the areas under CAA's jurisdiction

1.2 CAA IMS POLICY

Top Management commitment is demonstrated in IMS Policy, attached as **Appendix-A** (English version) and **Appendix-B** (Urdu version).

1.3 RESPONSIBILITY & AUTHORITY

1.3.1 RESPONSIBILITY FOR HSE COMPLIANCE:

- 1.3.1.1 CAA shall require Contractors and/or Sub-contractors / Suppliers / Concessionaires to affirm that all supervisors are responsible for ensuring that the works / activities are performed in accordance with all applicable health, safety and environmental rules, regulations and good working practices with equal diligence being paid to the fulfillment of the contractual technical specifications. CAA will require Contractors and Sub-contractors to advise such personnel of their safety responsibilities. Contractors / Suppliers / Concessionaires shall also provide CAA with their organizational setup for a particular contract / subcontract / renewal / bid invitation document, where applicable, specifying the areas of safety responsibilities of their supervisors.
- 1.3.1.2 **All DDGs** shall ensure imparting necessary directions and establish requisite monitoring & evaluation mechanism in their respective area of responsibilities to fulfill the vision and the objectives contained in this manual.
- 1.3.1.3 **The concerned Directors / Additional Directors / Airport Managers / Chief Operations Officers / Location Heads / Sectional Heads**, involved / engaged in the purchase of materials, services and contracts (including sub-contracts, if any), shall ensure effective implementation of this manual. They shall also be responsible to designate **Contract Coordinators** where applicable especially on large scale projects.
- 1.3.1.4 **Contract Coordinator** (a designated CAA Employee) shall be responsible for the on-site implementation of HSE requirements by the contractors and their officials / workers. He shall also be responsible to record on-site management activities and meetings specific to the HSE issues.
- 1.3.1.5 **Deputy Management Representatives (DMRs)** shall be responsible to oversee the implementation and effectiveness of this manual at their respective Airports / ATS Units / Locations.
- 1.3.1.6 The concerned **Directors / Additional Directors / Airport Managers / Chief Operations Officers / Location Heads / Sectional Heads**, involved / engaged in the purchase of materials, services and contracts (including sub-contracts, if any), shall ensure incorporation of specific clause(s) on Safety, Health & Environment in the contract agreements or their renewals / bid invitation documents indicating the need for compliance with the detailed guidelines as outlined in this manual.



- 1.3.1.7 All Safety, Health and Environment requirements contained in this manual shall also be made part of the bid invitation documents / contracts.
- 1.3.1.8 Any specific requirements not covered in this manual and in the existing HSE clause of the contract / lease agreement may be specified in the contract / lease documents by the respective CAA functions, in consultation with Additional Director SQMS (REG/CF), Additional Director SQMS (ANS/APS) at HQCAA and concerned DMRs at Airports / ATS Units / Locations. These may include but not limited to:
- Working procedures
 - Risk / impact assessment of the job
 - Requirements of transporting carrier, machinery / equipment and tools
 - Handling / packaging identification requirements
 - Information about the product composition
 - Compliance to the related Safety, Health & Environment procedures for performing the activity
 - Usage of Personal Protective Equipment (PPE)
 - Competence / training requirements of workers
 - Handling and disposal of waste, etc
 - The need to obtain Permit To Work (PTW), where required
 - Emergency procedures
 - Accident / incident reporting
 - Legal requirements
- 1.3.1.9 The **concerned Directors / Additional Directors / Airport Managers / Chief Operations Officers / Location Heads / Sectional Heads** may ask the supplier / contractor / concessionaire to carry out a **risk assessment** before awarding a contract for high-risk tasks, where applicable.

1.3.2 **ONSITE MANAGEMENT OF CONTRACTORS FOR MEGA / MAJOR PROJECTS:**

- 1.3.2.1 The **concerned DDGs / Directors / Additional Directors / Airport Managers / Chief Operations Officers / Location Heads / Sectional Heads** shall ask the contractor / supplier / concessionaire to designate a **Safety Officer** wherever applicable, depending upon the quantum of contract, who shall be the focal person and responsible for on-site implementation of HSE requirements on part of contractors / suppliers / concessionaires. For Contracts / Agreements of smaller quantum, the contractor / supplier / concessionaire shall be directly responsible in this regard without having the need to designate such representatives.
- 1.3.2.2 The **concerned Directors / Additional Directors / Airport Managers / Chief Operations Officers / Location Heads / Sectional Heads** shall be responsible to nominate a representative (**Contract Coordinator**) for on-site management of contractors for mega / major projects. The contract coordinator / representative shall monitor the HSE compliance by the contractor / supplier. This includes monitoring of:
- Controls to prevent HSE risks
 - Contractor equipment for appropriateness
 - Compliance of work procedures
 - Waste Disposal & Record keeping



- e. Compliance of regulatory requirements, to this HSE Manual or their own HSE Manual(s) if exceeding the requirement stipulated by the CAA and PTW by contractors / suppliers / concessionaires
- 1.3.2.3 **Regular on-site meetings with the contractor** must be convened / held to discuss the HSE compliance and related aspects of the job. Records of such meetings and on-site management activities must be maintained by the Contract Coordinator.
- 1.3.2.4 **HSE audit or on-site inspections** shall be carried out randomly by the authorized Inspectors of SQMS Directorate in coordination with the concerned Directorate / Branch at HQCAA and concerned Section at airports / locations for checking HSE compliance. IAR (Improvement Action Report) on **CAAF-002-MSXX** shall be raised / generated in case any non-conformity is observed or if any corrective or preventive action is required. All proceedings of the audit or on-site inspections shall be documented by the respective inspectors.
- 1.3.2.5 All the works, purchase / supplies and services being carried out / rendered by Contractors / Suppliers / Concessionaires shall be liable to monitoring and supervision by CAA's authorized / designated official(s) to ensure their HSE-worthiness. Surprise inspection may be carried out at any time by SQMS Officials.
- 1.3.2.6 The monitoring / supervision so required shall be made under the relevant clause(s) of the contract. The performance monitoring data of contractors with regard to compliance to HSE manual and CAAO will be collected / maintained and documented on periodical basis by the respective DDGs as well as by SQMS Directorate / SQMS teams at locations, to develop necessary corrective / preventive actions accordingly. This significant data of a particular contractor / supplier / concessionaire, will be critically observed and be given due consideration at the time of awarding / continuation / renewals etc of any contract.
- 1.3.2.7 All potential Contractors, Suppliers and Concessionaires shall be informed about the availability of HSE manual which would require compliance from them. The latest version of this Manual shall be posted on the CAA's Official Website www.caapakistan.com.pk.
- 1.3.2.8 The concerned Directorate / Branch / Airport / Location shall provide the hard copy of the latest version of HSE Manual to the Contractors / Suppliers / Concessionaires at the time of signing of the Contract Agreements / License Agreements / Lease Deeds / Purchase Orders / Supply Orders, etc.
- a. No work be executed without supervision of concerned representation of OPI Section / Branch, especially at aerodrome.
- b. The representation of OPI section / function shall ensure implementation of preventive control measures during execution of work and corrective measures in case of any abnormal / emergency situation.
- c. All food concessionaires shall preferably be certified in Food Safety Management System ISO 22000: 2017.
- 1.3.2.9 In case of existence of any Contractor's, Supplier's and Concessionaire's HSE Manual having provisions more stringent to this HSE manual, those shall be applicable as far as the currency of that particular contract is concerned.
- 1.3.2.10 All the Contractors, Suppliers and Concessionaires shall be responsible to provide and update bare minimum training / awareness on HSE to their employees and subsequent implementation. Any breach / violation thereof by any of such employee(s) shall be construed upon to be on behalf of that very Contractor, Supplier and Concessionaire. Records pertaining to HSE related training / awareness shall be maintained and provided to concerned CAA official(s) designated by the OPI and/or Representative(s) of CAA's SQMS team.



DIVISIONAL
ENGINEER
CAA AIRAP LAHORE

1.3.2.11 The training / awareness described above shall include but not limited to the following: -

- a. Site acquaintance (i.e. Aerodrome / Building layout, Building Evacuation Procedure, etc).
- b. General aerodrome layout & hazards and handling of standard equipment.
- c. HSE related operational hazards / environmental aspects and risks / environmental impacts associated and related control measures with the particular contract / agreement.
- d. Basic First Aid and other corrective measures.
- e. Application of Permit to Work / Lock Out and Tag Out.
- f. Special MSDS, classification / composition of hazardous material for handling of hazardous material.
- g. Incident(s) / accident(s) including environmental incidents (spills, etc) reporting.
- h. Waste management.
- i. Basic Fire Fighting.
- j. Safe driving.
- k. Response in emergency.
- l. Personal Protective Equipment (PPE).



Chapter 2

GENERAL INFORMATION

2.1 BASIC SAFETY & SECURITY RESTRAINTS

2.1.1 The following are some basic safety & security restraints. In case of violation of any of these, Contractors / Suppliers / Concessionaire shall be dealt with in accordance with **Rule 91 (Section 10) of CARs 94:**

- 2.1.1.1 Possession or use of alcoholic beverages or illegal drugs.
- 2.1.1.2 Possession of un-authorized explosives, firearms, ammunition, and other weapons.
- 2.1.1.3 Violation of any safety or security rules or requirements as laid down in **Part VIII, Section 10 of CARs, 94 (Rule 92-110).**
- 2.1.1.4 Illegal dumping, handling, or disposal of hazardous materials.
- 2.1.1.5 Demolition or removal, without written permission, of any property belonging to CAA.
- 2.1.1.6 Intimidating, threatening, harassing, impeding or interfering with CAA employee(s) or designated representative(s).
- 2.1.1.7 Misuse of fire prevention and protection equipment.
- 2.1.1.8 Unauthorized removal or destruction of a safety barricade, handrail, guardrail, warning sign, fall protection, or other warning devices intended to protect employees or property.

2.2 SAFETY PERMITS

2.2.1 All CAA contractors, suppliers or concessionaires shall obtain prior approval for PTW from CAA's authorized / designated official(s) and follow all the safety requirements, precautions, controls of PPEs classified as PTW related tasks as any of the operations mentioned below may present a hazard to people, property and environment.

- 2.2.1.1 Performing burning, welding, cutting, soldering, or other hot work.
- 2.2.1.2 Working on fire protection / detection systems.
- 2.2.1.3 Working on electrical, steam, chilled water systems or other energized systems.
- 2.2.1.4 Installing a temporary electrical service
- 2.2.1.5 Working with hazardous chemicals (including solvents and paints).
- 2.2.1.6 Handling, transporting or generating hazardous wastes (including hospital biological waste, waste oil, chemicals, condensate, etc).
- 2.2.1.7 Using a gas, diesel, or LPG (such as Propane) powered engines.
- 2.2.1.8 Working on gas pipe lines or associated equipment.
- 2.2.1.9 Operating a power vehicle or self-propelled work platform.
- 2.2.1.10 Excavation / trenching.
- 2.2.1.11 Using radioactive sources or conducting field radiography (x-ray).
- 2.2.1.12 Working with asbestos & asbestos – containing materials.
- 2.2.1.13 Working on security systems.
- 2.2.1.14 Working with compressed air / gases.
- 2.2.1.15 Working on heating, ventilation, or air conditioning equipment.



- 2.2.1.16 Working with chemicals, polishing or grinding.
- 2.2.1.17 Working at heights of more than 06 feet or on roofs.
- 2.2.1.18 Entering or working in confined spaces like fuel tanks, trenches, service shafts, sewer system, etc.
- 2.2.1.19 Lifting or hoisting with cranes or hoists.
- 2.2.1.20 Blasting operations, etc.

2.3 **PERFORMANCE MONITORING**

- 2.3.1 The Contractors / Suppliers / Concessionaires shall monitor HSE performance of their employees and activities.
- 2.3.2 They shall in addition monitor all those performance monitoring actions agreed between CAA and the Contractors / Suppliers / Concessionaires.

2.4 **HOUSE KEEPING**

- 2.4.1 All Contractors / Suppliers / Concessionaires shall maintain good housekeeping by keeping work areas neat, clean, orderly, free of excess trash, debris and shall block walkways, stairs, exits, or create a tripping hazard. Poor housekeeping at a job site may lead to an increased potential for safety hazards and an increased frequency of accidents, falls, cuts, spills, leaks, fires or electrocution.
- 2.4.2 Tools, wires, materials shall not be left or haphazardly spread out at the work place.
- 2.4.3 Open holes, trenches, or excavations into which people may fall shall be identified, covered or provided with guardrails.
- 2.4.4 In order to protect the employees and environment, safety blinding shall be provided at all works execution sites, where necessary.

2.5 **REPORT OF ACCIDENT, INCIDENT, INJURY OR ILLNESS**

- 2.5.1 The area representatives of contractor shall inform fire, electrical, civil inquiries officials each day before start of work.
- 2.5.2 All work related accidents, incidents, fatalities, injuries, and illnesses must immediately be reported to the CAA authorized / designated officials.
- 2.5.3 Every incident / accident happened during execution of contractors work shall properly be analyzed as per **CAA0-015-MSXX** and if fall in Major / Catastrophic categories be published / mentioned in IOU report by the OPI Section / Branch.



Chapter 3

HAZARDOUS WASTE

3.1 HAZARDOUS WASTE MANAGEMENT

- 3.1.1 Hazardous waste generated by a Contractor / Supplier / Concessionaire as part of its work must be properly identified, stored and disposed in accordance with applicable laws / rules / regulations. The Contractor / Supplier / Concessionaire must coordinate with CAA representative(s) of relevant sections to provide a list of hazardous waste(s) which is / are likely to be generated during the project / activity, and to determine the location(s) for hazardous waste storage.
- 3.1.2 The Contractor / Supplier / Concessionaire must also ensure, at a minimum:
- 3.1.2.1 Proper labeling in terms of MSDS.
 - 3.1.2.2 Adequate secondary containment.
 - 3.1.2.3 Segregation of incompatible materials.
 - 3.1.2.4 Routine inspection of storage areas.
- 3.1.3 In addition, all hazardous waste containers shall be constructed of a material compatible with the waste, in sound condition, and kept securely closed to avoid spill or leakage.

3.2 WASTE DISPOSAL DOCUMENTS

The Contractors / Suppliers / Concessionaires shall be responsible for completing all waste disposal documents as per statutory / regulatory requirements, where applicable and as required by CAA. This may relate to CAA's own waste that is periodically removed for further disposal purposes, or waste created by Contractor / Supplier / Concessionaire while performing a task at CAA premises / areas under CAA's jurisdiction. OPI shall also ensure all normal wastes are also removed by the contracts.

3.3 TRAINING

Contractor / Supplier / Concessionaire must ensure that their employees are appropriately trained in hazardous waste management procedures. In the event a Contractor / Supplier Concessionaire encounters unidentified material that is reasonably believed to be hazardous (radioactive, volatile, corrosive, flammable, explosive, magnetic, infectious, toxic), the Contractor / Supplier / Concessionaire shall immediately stop work in the affected area and report the condition to the CAA's authorized / designated official(s). At no time shall such material be disposed in chutes, drains, pipes or in any other unauthorized manner.

3.4 TRANSPORTATION AND DISPOSAL OF HAZARDOUS MATERIALS

- 3.4.1 Transportation of hazardous materials on CAA property shall be conducted in accordance with CAA specified instructions. It shall not be disposed to burn or be used in a manner that is harmful to people or environment. While transporting hazardous materials, Contractor / Supplier / Concessionaire shall ensure that no harm is done to people or environment because of poor containers, packing, covering, lashing, fixing, loading, stacking or improper vehicle or mode of transport.
- 3.4.2 All transportation of dangerous / hazardous goods and materials by air shall be conducted strictly in accordance with provisions of Part XVI, Sections 1-3 and 5-6 of the Civil Aviation Rules, 1994.

3.5 SPILL PREVENTION AND CONTROL

- 3.5.1 Based on the inventory of oil and hazardous chemicals that will be brought on-site, the Contractor / Supplier / Concessionaire shall have available equipment (e.g., secondary containment pallets, absorbent pads, absorbent booms, speed-dry etc.) that is suitable and sufficient to control a potential spill / release.



- 3.5.2 The Contractor / Supplier / Concessionaire is responsible for identifying outlets to the environment (e.g., sumps, sewers, storm / floor drains, etc.) and adequately minimizing spill potential to these areas.
- 3.5.3 The Contractor / Supplier / Concessionaire is responsible for the proper storage of all flammable and combustible chemicals that are brought and/or stored on site to complete the work. Such storage may require the use of safety containers, safety cabinets, and/or secondary containment.
- 3.5.4 The Contractor / Supplier / Concessionaire shall also ensure that any incompatible chemicals are safely segregated. The Contractor / Supplier / Concessionaire is Responsible for maintaining and securing all chemical containers and all chemical storage-areas. This requires selecting locations and methods to minimize exposure to rainfall, surface water, and the ground surface or subsurface.
- 3.5.5 The Contractors / Suppliers / Concessionaires must ensure that their employees are adequately trained in spill control procedures and are aware of the use of spill control kits.
- 3.5.6 In the event of a release or spill, the Contractor / Supplier / Concessionaire must immediately inform CAA's authorized / designated official(s).

3.6 AIR EMISSIONS

- 3.6.1 Any conditions discovered which could result in an increase in air pollutant emissions must immediately be reported to the CAA's authorized / designated official(s).
- 3.6.2 Contractors / Suppliers / Concessionaires activities should not cause unacceptable level of emissions (emissions not meeting NEQS – National Environmental Quality Standards).
- 3.6.3 Contractors / Suppliers / Concessionaires shall immediately notify the CAA's authorized / designated official(s) whenever they become aware of any unintentional or intentional release of CFCs (Chloro-Fluoro Carbons), Halons etc.

3.7 WASTE WATER DISCHARGES

- 3.7.1 Waste water must NOT include any corrosive, flammable, or toxic substances / hazardous liquid, etc.
- 3.7.2 Contractor / Supplier / Concessionaire must ensure no waste water is discharged that violates NEQS.

3.8 BIOLOGICAL / CHEMICAL / RADIOACTIVE HAZARDS

- 3.8.1 Some CAA operations may involve the use of biological, chemical, or radioactive material that can be hazardous to persons or property, if not handled or disposed safely. Contractors / Suppliers / Concessionaire will mark the areas where work with biological, chemical, or radioactive materials is being performed with proper signs.
- 3.8.2 The Contractor / Supplier / Concessionaire shall not disturb damage or otherwise handle any suspected asbestos containing material.
- 3.8.3 The Contractor / Supplier / Concessionaire shall not sweep, dust, vacuum or mop dust / debris which are the product of a suspected asbestos containing material. The Contractor / Supplier / Concessionaire shall also not pick up or throw away any suspected asbestos-containing waste or trash.
- 3.8.4 Sand blasting, grinding, drilling, brazing, scraping, polishing of floors and other dust emitting surfaces will be done by persons wearing appropriate PPEs.

3.9 HAZARDOUS MATERIALS AND HAZARD COMMUNICATION

- 3.9.1 Hazardous materials shall not be handled or used by the Contractor / Supplier / Concessionaire without providing training to the concerned employees.



- 3.9.2 No solvents, paints, or similar flammable, toxic, or irritating materials shall be used in CAA premises / areas under the jurisdiction of CAA unless specifically authorized by CAA.
- 3.9.3 Adequate ventilation shall be maintained when paints or solvents are used.
- 3.9.4 Flammable solvents and materials shall be used with extreme caution.
- 3.9.5 It shall be ensured that flammable paints and solvents are isolated and stored in approved locations, if inside the building.
- 3.9.6 The Contractor / Supplier / Concessionaire shall submit an inventory of all hazardous chemicals / liquids / materials that are brought on-site or sold to CAA. These should be accompanied by MSDS.
- 3.9.7 The Contractor / Supplier / Concessionaire shall also ensure that all containers that are brought on site for the storage of hazardous chemicals (e.g., gas, paint, etc.) are labeled and inspected for correctness.
- 3.9.8 The Contractor / Supplier / Concessionaire shall remove at earliest all hazardous chemicals that it brings on-site when work involving a specific hazardous chemical has been completed.



Chapter 4

SPECIFIC SAFETY REQUIREMENTS

4.1 CONFINED SPACE ENTRY

- 4.1.1 Contractor / Supplier / Concessionaire will obtain Confined Space Entry Certificate before entering / working in confined spaces. If during the course of work, the Contractor / Supplier / Concessionaire encounters a confined space that has not been previously identified by the CAA, it must immediately bring the space to the attention of the CAA's authorized / designated official(s), and delays entry until the space is examined by the CAA's authorized / designated official
- 4.1.2 When CAA and Contractor / Supplier / Concessionaire personnel are working in or near confined spaces, the Contractor / Supplier / Concessionaire shall coordinate all operations, with likely-to-be-affected CAA personnel before entry.
- 4.1.3 Prior coordination shall also be required on entering a confined space with or without a CAA employee

4.2 LOCK-OUT / TAG-OUT (WHERE APPLICABLE)

- 4.2.1 As part of CAA's Electrical Isolation / De-Isolation permit requirement, standard locks and tags are used to control the start-up of equipment that is being serviced or maintained by its employees. At no time shall the Contractor / Supplier / Concessionaire or its employees override any locks or tags that they encounter during the performance of their work.
- 4.2.2 The Contractors / Suppliers / Concessionaires are responsible for developing, implementing and maintaining their own Lock-out / Tag-out Program.
- 4.2.3 The Contractor / Supplier / Concessionaire shall submit a copy of its Lock-out / Tag-out Program to the CAA's authorized / designated official(s) before the start of any work.

4.3 GENERAL ELECTRICAL SAFETY

- 4.3.1 Temporary electrical connection(s), where required, shall be obtained from CAA as per the prescribed procedure only.
- 4.3.2 Only qualified electricians are permitted to work on electrical systems and equipment that use or control electrical / power.
- 4.3.3 Electrical tools or equipment shall not be operated in wet areas or areas where potentially flammable dusts, vapors, gases, or liquids are present, unless specifically approved.
- 4.3.4 Should a circuit breaker or other protective device "trip," it is to be ensured that a qualified electrician checks the circuit and equipment and corrects problem before resetting the breaker. Moreover, there should always be a provision for safety isolation of the circuit where needed
- 4.3.5 Barriers and post warning signs shall be erected to ensure that the non-authorized personnel stay clear of the work area.
- 4.3.6 Hazards (lack of protective guards or covers, damaged equipment, etc.) shall be reported to the CAA's authorized / designated official(s) immediately.
- 4.3.7 Electrical boxes, switch gear, cabinets, or electrical rooms shall not be left open when not directly attended.
- 4.3.8 It shall be ensured to insulate energized parts when have been removed or doors are closed. Use of cardboard, plywood or other flammable to cover energized circuits is prohibited.
- 4.3.9 Proper grounding / earthing and arc quenching, where required, shall be ensured.



4.3.10 The size of the cable / conductor should match with the actual on-site requirement.

4.4 **COMPRESSED GAS CYLINDERS**

The following measures must be taken for the protection of persons and property:

- 4.4.1 All the cylinders brought in by the Contractors / Suppliers / Concessionaires shall have valid test certificates performed by a certified testing agency.
- 4.4.2 Pressure and leak testing shall invariably be carried out and documented in all jobs associated with compressed gas or liquid handling.
- 4.4.3 Valve protection caps must be in place when compressed gas cylinders are transported, moved, or stored.
- 4.4.4 Cylinder valves must be closed and valve covers must be replaced when work is complete and when cylinders are empty or moved.
- 4.4.5 Compressed gas cylinders must be secured in an upright position in a welding cart or to a solid object (using chains, straps, or a rigid retaining bar).
- 4.4.6 Compressed gas cylinders must be secured on an approved carrier while being transported.
- 4.4.7 Cylinders shall be kept at a safe distance or shielded from welding or cutting operations. Cylinders shall not be placed where they can contact an electrical circuit.
- 4.4.8 It shall be ensured to keep oxygen and flammable gas regulators in proper working order and a wrench in position on the acetylene valve when in use.
- 4.4.9 If a leak develops in a cylinder and it cannot be immediately corrected, the cylinder shall be moved to a safe location outside the building / away from the location of work.
- 4.4.10 Cylinders must not be taken into or stored in confined spaces.
- 4.4.11 Empty & filled cylinders must be kept separately.
- 4.4.12 Hoses and regulators must not be stored in unventilated or closed containers or areas.

4.5 **WELDING, CUTTING AND BRAZING**

The Contractors / Suppliers / Concessionaires shall ensure the following:

- 4.5.1 Obtain PTW.
- 4.5.2 Inform CAA's authorized / designated official(s) prior to the start of any welding / cutting / brazing work.
- 4.5.3 Remove combustible materials from the area before beginning work.
- 4.5.4 Install anti flashback (safety / check) valves in both the oxygen / acetylene hoses at the regulator.
- 4.5.5 Shield adjacent areas with welding partitions.
- 4.5.6 Persons involved are adequately trained in using portable fire extinguishers.
- 4.5.7 Have a second person trained in basic firefighting as standby with an approved fire extinguisher for welding and cutting operations.

4.6 **CRANES AND RIGGING**

- 4.6.1 Each crane or hoist brought onto CAA property must have a valid inspection testing performed by a certified testing agency.
- 4.6.2 The operator is responsible for the proper placement of the crane in relationship to the load to be handled and the landing area so as to obtain the best rated lift capacity, and the installation and maintenance of crane swing radius protection.
- 4.6.3 All operators must possess a valid crane / hoist operating / driving license as applicable.



4.7 **FITNESS**

- 4.7.1 Suppliers / Contractors / Concessionaires shall ensure that all their personnel working in CAA premises are medically fit to perform their assigned tasks.
- 4.7.2 If requested by CAA, Contractors / Suppliers / Concessionaires shall provide the fitness / health certificates of their employees.

4.8 **DRIVING**

- 4.8.1 All Contractors' / Suppliers' / Concessionaires' vehicles while in CAA premises or performing CAA duties shall adhere to speed limits (applicable in that particular zone), and also comply with all other traffic and road safety regulations of CAA.
- 4.8.2 The drivers should be in possession of valid driving license.
- 4.8.3 All Contractor / Supplier / Concessionaire vehicles should have:
 - 4.8.3.1 Standard seat belts. The seat belts should be neat and clean and in proper working condition.
 - 4.8.3.2 Standard fire extinguisher.
 - 4.8.3.3 Standard first aid box.

4.9 **INDEMNITY**

Suppliers / Contractors / Concessionaires shall keep harmless and indemnify Pakistan CAA against all losses, damages, injuries, death of any person, claims, actions, third party action arising out of acts and omissions by their employees/ personnel or non-compliance with the terms and conditions as stated herein and/or any applicable laws and regulation. Contractor shall take clearance with concerned offices before handing / taking over the area to be restored on the same condition(s) as was/were before start of work (as per contract agreement).



		CIVIL AVIATION AUTHORITY SUPPLIER'S / CONTRACTOR'S / CONCESSIONAIRE'S AUDIT		CAAF-017-XXMS-1.0
		(Name of Directorate/Branch/Airport/Location/MR/DMR)		
Contractor/Supplier/Concessionair Name _____			Date of Inspection _____	
Contractor Agreement for _____			Location _____	
S. No.	CHECKED FOLLOWING ISSUES	COMPLIANCE	REMARKS	
1	Are proper PPEs worn by Contractor / Contractor's staff?			
2	Is PTW taken and implemented?			
3	Was contractor briefed on Contractor /Supplier/Concessionaire HSE Manual?			
4	Check for Contractor's house keeping			
5	Check if waster disposal is safe and appropriate			
6	Does contractor have his own system to monitor / control HSE Performance of work			
7	Did you observe any other non-compliance unsafe practice being followed by contractor's staff?			
8	Are cranes/hoists and riggings accompanied by annual inspection test report of certified testing agency and operators of the same have valid crane / hoist operating / draiving license.			
9	Others (to be specified)			
Name of Auditor _____ Signature _____ Date of Audit _____				



		CIVIL AVIATION AUTHORITY WASTE DISPOSAL RECORD		CAAF-018-XXMS-1.0
		(Name of Directorate/Branch/Airport/Location/MR/DMR)		
Waste disposal record for the month _____ Location/Zone _____				
Symbol	Colour Code	Category of waste	Quantity/ Volume / Weight / size	Agency / Contractor who picked and disposed the waste.
PP	Blue	Paper		
M	Blue	Metal		
PL	Blue	Plastic		
R	Blue	Rubber (tyres / tubes etc.)		
W	Blue	Wood		
O	Red	Oil, greases, chemicals, paints, HAZARDOUS		
H	Red	Hospital related biological waste HAZARDOUS		
C	Red	Condensate HAZARDOUS		
Ensure HAZARDOUS waste is not mixed or disposed along with normal municipality waste. Ensure Hospital waste is Incinerated.				
Prepared By _____		Signature _____		Date _____



EPADS

ACRONYMS

CAA	CIVIL AVIATION AUTHORITY
CARs	CIVIL AVIATION RULES
EMS	ENVIRONMENTAL MANAGEMENT SYSTEM
HSE	HEALTH SAFETY AND ENVIRONMENT
IMS	INTEGRATED MANAGEMENT SYSTEM
ISO	INTERNATIONAL ORGANIZATION FOR STANDARDIZATION
LOTO	LOCK OUT TAG OUT
LPG	LIQUEFIED PETROLEUM GAS
MNL	MANUAL
MSDS	MATERIAL SAFETY DATA SHEET
NEQS	NATIONAL ENVIRONMENTAL QUALITY STANDARDS
OH&SMS	OCCUPATIONAL HEALTH AND SAFETY MANAGEMENT SYST
OPI	OFFICE OF PRIME INTEREST
PPE	PERSONAL PROTECTIVE EQUIPMENT
PTW	PERMIT TO WORK
QMS	QUALITY MANAGEMENT SYSTEM
SMS	ICAO SAFETY MANAGEMENT SYSTEM
TQM	TOTAL QUALITY MANAGEMENT



(INTEGRITY PACT)

DECLARATION OF FEES, COMMISSION AND BROKERAGE ETC.
PAYABLE BY THE SUPPLIERS OF GOODS, SERVICES & WORKS IN
CONTRACTS WORTH RS. 10.00 MILLION OR MORE

Contract No. _____ Dated _____
Contract Value: _____
Contract Title: _____

_____ hereby declares that it has not obtained or induced the procurement of any contract, right, interest, privilege or other obligation or benefit from Government of Pakistan (GoP) or any administrative subdivision or agency thereof or any other entity owned or controlled by GoP through any corrupt business practice. Without limiting the generality of the foregoing, _____ represents and warrants that it has fully declared the brokerage, commission, fees etc. paid or payable to anyone and not given or agreed to give and shall not give or agree to give to anyone within or outside Pakistan either directly or indirectly through any natural or juridical person, including its affiliate, agent, associate, broker, consultant, director, promoter, shareholder, sponsor or subsidiary, any commission, gratification, bribe, finder's fee or kickback, whether described as consultation fee or otherwise, with the object of obtaining or inducing the procurement of a contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP, except that which has been expressly declared pursuant hereto.

_____ certifies that it has made and will make full disclosure of all agreements and arrangements with all persons in respect of or related to the transaction with GoP and has not taken any action or will not take any action to circumvent the above declaration, representation or warranty.

_____ accepts full responsibility and strict liability for making any false declaration, not making full disclosure, misrepresenting facts or taking any action likely to defeat the purpose of this declaration, representation and warranty. It agrees that any contract, right, interest, privilege or other obligation or benefit obtained or procured as aforesaid shall, without prejudice to any other rights and remedies available to GoP under any law, contract or other instrument, be voidable at the option of GoP.

Notwithstanding any rights and remedies exercised by GoP in this regard, [name of Supplier] agrees to indemnify GoP for any loss or damage incurred by it on account of its corrupt business practices and further pay compensation to GoP in an amount equivalent to ten times the sum of any commission, gratification, bribe, finder's fee or kickback given by [name of Supplier] as aforesaid for the purpose of obtaining or inducing the procurement of any contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP.

Name of Buyer:	Name of Seller/Supplier:
Signature:	Signature:
[Seal]	[Seal]

CONSTRUCTION EXPERIENCE

Form EXP - 4.1 General Construction Experience

Bidder's Name: _____

Date: _____

JV Member's Name _____

Bid Reference No. (if any) and title: _____

Page _____ of _____ pages

Starting Year	Ending Year	Contract Identification	Role of Bidder
		Contract name: _____ Brief Description of the Works performed by the Bidder: _____ Amount of contract: _____ Name of EMPLOYER: _____ Address: _____	
		Contract name: _____ Brief Description of the Works performed by the Bidder: _____ Amount of contract: _____ Name of EMPLOYER: _____ Address: _____	
		Contract name: _____ Brief Description of the Works performed by the Bidder: _____ Amount of contract: _____ Name of EMPLOYER: _____ Address: _____	

Form EXP - 4.2(a)
Specific Construction and Contract Management Experience

Bidder's Name: _____

Date: _____

JV Member's Name _____

Bid Reference No. (if any) and title: _____

Page _____ of _____ pages

Similar Contract No.	Information			
Contract Identification				
Award date				
Completion date				
Role in Contract	Prime Contractor ☐	Member in JV ☐	Management Contractor ☐	Sub-contractor ☐
Total Contract Amount	PKR equivalent			
If member in a JV or sub-contractor, specify participation in total Contract amount				
EMPLOYER's Name:				
Address:				
Telephone/fax number				
E-mail:				

Form EXP - 4.2(a) (cont.)
Specific Construction and Contract Management Experience (cont.)

Similar Contract No.	Information
Description of the similarity in accordance with Sub-Factor 4.2(a) of Section III:	
1. Amount	
2. Physical size of required works items	
3. Complexity	
4. Methods/Technology	
5. Construction rate for key activities	
6. Other Characteristics	

Form EXP - 4.2(b)
Construction Experience in Key Activities

Bidder's Name: _____

Date: _____

Bidder's JV Member Name: _____

Sub-contractor's Name (if any): _____

Bid Reference No. (if any) and title: _____

Page _____ of _____ pages

All Sub-contractors for key activities must complete the information and Qualification Criteria and Requirements, Sub-Factor 4.2.

1. Key Activity No One: _____

Information				
Contract Identification				
Award date				
Completion date				
Role in Contract	Prime Contractor ☐	Member in JV ☐	Management Contractor ☐	Sub-contractor ☐
Total Contract Amount	PKR equivalent			
Quantity (Volume, number or rate of production, as applicable) performed under the contract per year or part of the year	Total quantity in the contract (i)	Percentage participation (ii)	Actual Quantity Performed (i) x (ii)	
Year 1				
Year 2				
Year 3				
Year 4				
EMPLOYER's Name:				
Address:				
Telephone/fax number				

	Information
E-mail:	

2. Activity No. Two

3.

	Information
Description of the key activities in accordance with Section III:	

Form EXP - 4.2 (c)
Specific Experience in Managing ES aspects

[The following table shall be filled in for contracts performed by the Bidder, and each member of a Joint Venture]

Bidder's Name: *[insert full name]*

Date: *[insert day, month, year]*

Joint Venture Member Name: *[insert full name]*

Bid Reference No. (if any) and title: *[insert ICB/NCB number and title]*

Page *[insert page number]* of *[insert total number]* pages

1. Key Requirement no 1 in accordance with 4.2 (c): _____

Contract Identification				
Award date				
Completion date				
Role in Contract	Prime Contractor ☐	Member in JV ☐	Management Contractor ☐	Subcontractor ☐
Total Contract Amount			PKR	
Details of relevant experience				

2. Key Requirement no 2 in accordance with 4.2 (c): _____
3. Key Requirement no 3 in accordance with 4.2 (c): _____
4. [PA define key requirements]

Contractor's Representative and Key Personnel Schedule

Bidders should provide the names and details of the suitably qualified Contractor's Representative and Key Personnel to perform the Contract. The data on their experience should be supplied using the Form PER-2 below for each candidate.

Contractor' Representative and Key Personnel

1.	Title of position:	
	Name of candidate:	
	Duration of appointment:	<i>[insert the whole period (start and end dates) for which this position will be engaged]</i>
	Time commitment: for this position:	<i>[insert the number of days/week/months/ that has been scheduled for this position]</i>
	Expected time schedule for this position:	<i>[insert the expected time schedule for this position (e.g. attach high level Gantt chart)]</i>
2.	Title of position:	
	Name of candidate:	
	Duration of appointment:	<i>[insert the whole period (start and end dates) for which this position will be engaged]</i>
	Time commitment: for this position:	<i>[insert the number of days/week/months/ that has been scheduled for this position]</i>
	Expected time schedule for this position:	<i>[insert the expected time schedule for this position (e.g. attach high level Gantt chart)]</i>
3.	Title of position:	
	Name of candidate:	
	Duration of appointment:	<i>[insert the whole period (start and end dates) for which this position will be engaged]</i>
	Time commitment: for this position:	<i>[insert the number of days/week/months/ that has been scheduled for this position]</i>
	Expected time schedule for this position:	<i>[insert the expected time schedule for this position (e.g. attach high level Gantt chart)]</i>
4.	Title of position:	
	Name of candidate:	
	Duration of appointment:	<i>[insert the whole period (start and end dates) for which this position will be engaged]</i>

	Time commitment: for this position:	<i>[insert the number of days/week/months/ that has been scheduled for this position]</i>
	Expected time schedule for this position:	<i>[insert the expected time schedule for this position (e.g. attach high level Gantt chart)]</i>
5.	Title of position:	
	Name of candidate	
	Duration of appointment:	<i>[insert the whole period (start and end dates) for which this position will be engaged]</i>
	Time commitment: for this position:	<i>[insert the number of days/week/months/ that has been scheduled for this position]</i>
	Expected time schedule for this position:	<i>[insert the expected time schedule for this position (e.g. attach high level Gantt chart)]</i>
6.	Title of position: <i>[insert title]</i>	
	Name of candidate	
	Duration of appointment:	<i>[insert the whole period (start and end dates) for which this position will be engaged]</i>
	Time commitment: for this position:	<i>[insert the number of days/week/months/ that has been scheduled for this position]</i>
	Expected time schedule for this position:	<i>[insert the expected time schedule for this position (e.g. attach high level Gantt chart)]</i>

**Form PER-2:
Resume and Declaration
Contractor's Representative and Key Personnel**

Name of Bidder

Position [#1]: <i>[title of position from Form PER-1]</i>		
Personnel information	Name:	Date of birth:
	Address:	E-mail:
	Professional qualifications:	
	Academic qualifications:	
	Language proficiency: <i>[language and levels of speaking, reading and writing skills]</i>	
details		
	Address of Employer:	
	Telephone:	Contact (manager / personnel officer):
	Fax:	
	Job title:	Years with present Employer:

Summarize professional experience in reverse chronological order. Indicate particular technical and managerial experience relevant to the project.

Project	Role	Duration of involvement	Relevant experience
<i>[main project details]</i>	<i>[role and responsibilities on the project]</i>	<i>[time in role]</i>	<i>[describe the experience relevant to this position]</i>

Declaration

I, the undersigned [insert either “Contractor’s Representative” or “Key Personnel” as applicable] , certify that to the best of my knowledge and belief, the information contained in this Form PER-2 correctly describes myself, my qualifications and my experience.

I confirm that I am available as certified in the following table and throughout the expected time schedule for this position as provided in the Bid:

Commitment	Details
Commitment to duration of contract:	[insert period (start and end dates) for which this Contractor’s Representative or Key Personnel is available to work on this contract]
Time commitment:	[insert period (start and end dates) for which this Contractor’s Representative or Key Personnel is available to work on this contract]

I understand that any misrepresentation or omission in this Form may:

- (a) be taken into consideration during Bid evaluation;
- (b) result in my disqualification from participating in the Bid;
- (c) result in my dismissal from the contract.

Name of Contractor’s Representative or Key Personnel: [insert name]

Signature: _____

Date: (day month year): _____

Countersignature of authorized representative of the Bidder:

Signature: _____

Date: (day/month/year): _____

Historical Contract Non-Performance, and Pending Litigation and Litigation History

[The following table shall be filled in for the Applicant and for each member of a Joint Venture]

Applicant's Name: *[insert full name]*

Date: *[insert day, month, year]*

Joint Venture Member Name: *[insert full name]*

IFP No. and title: *[insert IFP number and title]*

Page *[insert page number]* of *[insert total number]* pages

☐ Not debarred due to deviation from commitment of Bid Securing Declaration- ☐ Not debarred due to non-performance			
Year	Non-performed portion of contract	Contract Identification	Total Contract Amount (current value, currency, exchange rate and PKR equivalent)
<i>[insert year]</i>	<i>[insert amount and percentage]</i>	Contract Identification: <i>[indicate complete contract name/ number, and any other identification]</i> Name of Procuring Agency: <i>[insert full name]</i> Address of Procuring Agency: <i>[insert street/city/country]</i> Reason(s) for nonperformance: <i>[indicate main reason(s)]</i>	<i>[insert amount]</i>
Pending Litigation, in accordance with Section III, Qualification Criteria and Requirements			
☐ Pending litigation in accordance with Section III, Qualification Criteria and Requirements, Sub-Factor 2.3 as indicated below.			
Year of dispute	Amount in dispute (currency)	Contract Identification	Total Contract Amount (currency), US\$ PKR Equivalent (exchange rate)

<i>[insert year]</i>	<i>[insert amount]</i>	Contract Identification: [indicate complete contract name, number, and any other identification] Name of Procuring Agency: <i>[insert full name]</i> Address of Procuring Agency: <i>[insert street/city/country]</i> Matter in dispute: <i>[indicate main issues in dispute]</i> Party who initiated the dispute: <i>[indicate "Procuring Agency" or "Supplier"]</i> Status of dispute: <i>[Indicate if it is being treated by the Adjudicator, under Arbitration or being dealt with by the Judiciary]</i>	<i>[insert amount]</i>
☐ No consistent history of court/arbitral award decisions in accordance with Section III, Qualification Criteria and Requirements, Sub-Factor 2.4. ☐ Consistent history of court/arbitral award decisions in accordance with Section III, Qualification Criteria and Requirements, Sub-Factor 2.4 as indicated below.			
Year of award	Outcome as percentage of Net Worth	Contract Identification	Total Contract Amount (currency), PKR Equivalent (exchange rate)
<i>[insert year]</i>	<i>[insert percentage]</i>	Contract Identification: [indicate complete contract name, number, and any other identification] Name of Procuring Agency: <i>[insert full name]</i> Address of Procuring Agency: <i>[insert street/city/country]</i> Matter in dispute: <i>[indicate main issues in dispute]</i> Party who initiated the dispute: <i>[indicate "Procuring Agency" or "Supplier"]</i> Court/ arbitral award decision: <i>[Indicate if the award decision was against the Applicant or any member of a joint venture.]y]</i>	<i>[insert amount]</i>

Current Contract Commitments / Works in Progress

Bidders and each member to a JV should provide information on their current commitments on all contracts that have been awarded, or for which a letter of intent or acceptance has been received, or for contracts approaching completion, but for which an unqualified, full completion certificate has yet to be issued.

Current Contract Commitments					
No.	Name of Contract	Employer's Contact Address, Tel, Fax	Value of Outstanding Work [Current Eq. PKR]	Estimated Completion Date	Average Monthly Invoicing Over Last Six Months [Eq. PKR/month]
1					
2					
3					
4					
5					

Financial Situation and Performance

[The following table shall be filled in for the Applicant and for each member of a Joint Venture]

Applicant's Name: [insert full name]

Date: [insert day, month, year]

Joint Venture Member Name: [insert full name]

IFP No. and title: [insert IFP number and title]

Page [insert page number] of [insert total number] pages

1. Financial data

Type of Financial information in (currency)	Historic information for previous [insert number] years, [insert in words] (amount in currency, currency, exchange rate*, PKR equivalent)				
	Year 1	Year 2	Year 3		
Statement of Financial Position (Information from Balance Sheet)					
Total Assets (TA)					
Total Liabilities (TL)					
Total Equity/Net Worth (NW)					
Current Assets (CA)					
Current Liabilities (CL)					
Working Capital (WC)					
Information from Income Statement					
Total Revenue (TR)					
Profits Before Taxes (PBT)					
Cash Flow Information					
Cash Flow from Operating Activities					

* Refer ITA 14 for the exchange rate

3. Financial documents

The Applicant and in case of JV, members of JV shall provide copies of financial statements for [number] years pursuant Section III, Qualifications Criteria and Requirements. The financial statements shall:

- (a) reflect the financial situation of the Applicant or in case of JV member, and not an affiliated entity (such as parent company or group member).
 - (b) be independently audited or certified in accordance with local legislation.
 - (c) be complete, including all notes to the financial statements.
 - (d) correspond to accounting periods already completed and audited.
- ☐ Attached are copies of financial statements¹ for the [number] years required above; and complying with the requirements.

¹ If the most recent set of financial statements is for a period earlier than 12 months from the date of Application, the reason for this should be justified.

Average Annual Turnover (Annual Sales Value)

[The following table shall be filled in for the Applicant and for each member of a Joint Venture]

Applicant's Name: *[insert full name]*

Date: *[insert day, month, year]*

Joint Venture Member Name: *[insert full name]*

IFP No. and title: *[insert IFP number and title]*

Page *[insert page number]* of *[insert total number]* pages

Annual Turnover Data			
Year	Amount Currency	Exchange rate* (If applicable)	PKR equivalent
<i>[indicate calendar year]</i>	<i>[insert amount and indicate currency]</i>		
		Average Annual Turnover **	

* Refer ITA for date and source of exchange rate.

** Total PKR equivalent for all years divided by the total number of years. See Section III, Qualification Criteria and Requirements, ITA.